

TASK GROUP INSTRUCTION

AIM REV 20.11.4.0 (OCTOBER 2020)

TGI NO.:	COMPONENT NAME: CMPT 01-378-2-Q	TYPE: MS	PHASE: A	REPEAT: 0	CHANGE: 0
SHIP/HULL NO.:	SHIP/HULL NAME:	SYSTEM:	PROJ/WO NO:	CASREP CAT:	
DDG-115	USS RAFAEL PERALTA	15211	K61		
CU PHASE TITLE: F/O - INSPECT, REPAIR, AND PRESERVE IN IRS EDUCTOR SECONDARY AIR INLET TRUNK					
PREPARING ACTIVITY:					
PREPARED BY: MOTONORI HAYASHI	CODE 231B.	PHONE 315-243-6145	DATE 27-NOV-2025		
APPROVED BY: RYOUTA TAKAGI	CODE 231B.	PHONE 315-243-4502	DATE 27-NOV-2025		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
REASON FOR WORK/NEED FOR CHANGE:					
CHANGE INSTRUCTIONS:					
SPECIAL REQUIREMENTS: SURFMEPP, This work Affects a fire zone boundary. Fabrication and/or staging of a non-flammable closure is required.					

WORK CERTIFICATION SIGNATURES					
COMPLETION OF WORK REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
ACCEPTANCE OF COMPLETED WORK					
PHYSICAL INSPECTION REQUIRED: ☐ YES ☒ NO	PHYSICAL INSPECTION COMPLETED:	BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
RECORDS REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:



LIST OF EFFECTIVE PAGES									
SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.
1-5									
J-1									
M-1									

1. SCOPE/PURPOSE

1.1 Title: Inspection, Repair, and Preservation of IRS Eductor Secondary Air Inlet Trunk; accomplish

1.2 Location of Work:

1.2.1 IRS Eductor Secondary Air Inlet Trunk (01-378-2-Q)

1.3 Identification:

1.3.1 Quantity (One EA), IRS Eductor Secondary Air Inlet Trunk

1.4 Security Classification: None.

1.5 Initial Condition: None.

1.6 Contractor Work start date: 7/27/2026

1.7 Contractor Work completion date: 9/4/2026

2. REFERENCES:

REF. NO.	DOCUMENT /DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV	CHG NO.	COPY REQ'D (Y/N)	SOURCE DOC (Y/N)	PARA	SEC	PG	CHP
1	NSI FY-26	NAVSEA Standard Items	-	1	N					
2	LI FY-26	Local Standard Items	-	ORG	N					
3	DWG 100-7027658	UNIT STRUCTURAL ARR DWG-ASSY UNIT 3270	D		Y				SE E N O T E	
4	DWG 100-7026702	DDG-51 CLASS UNIT STRL ARR DWG ASSY UNIT3250	M		Y				SE E N O T E	
5	TM SYSTEMS & SPECIFICAT IONS	SSPC Painting Manual Volume 2	-		N					
6	TM T9074-AS-GIB-010/271	Requirements for Nondestructive Testing Methods	1		N					
7	TM S9086-DA-STM-010/CH-100	Hull Structures	4		N					
8	MIL MIL-STD-2035	Nondestructive Testing Acceptable Criteria	A		N					

3. APPENDICES:

2 TGI NO.:

SHIP:

CMPT 01-378-2-Q	MS	A	0
DDG-115	CHG/VER:		0/0

- 3.1 ~~Appendix "J" TGI Job Summary Information Sheet~~ 1/24/2026 C1209.2 K. YOSHIDA
 3.2 Appendix "M" TGI Material List
 3.3 Appendix "D" Deficiency Form

4. **GENERAL REQUIREMENTS:**

4.1 Not Applicable.

5. **PROCEDURE:**

5.1 Accomplish a visual inspection of the current ship condition, for the interior of each IRS eductor secondary air inlet trunk listed in 1.3.1, using 2.3 and 2.4 for guidance.

5.1.1 Inspect each vertical and horizontal stiffener, platform, bulkhead, steel channel, deck/bulkhead penetration, deck drain and hanger.

5.1.2 Mark each identified and designated area requiring repair.

5.1.3 Submit one legible copy, in hard copy or approved transferrable media, of a report listing results of the requirements of 5.1 to the SUPERVISOR.

5.2 Power tool clean to bare metal for each location reported in 5.1.3 to include each exposed vertical, and horizontal stiffener for up to 69 square feet. Accomplish each requirement of Surface Preparation Specification SSPC-SP 11 of 2.5, as designated by the SUPERVISOR.

5.3 Accomplish a visual inspection of each prepared surface in 5.2 for structural integrity deterioration, pitting, each crack and area of damage or distortion of each IRS eductor secondary air inlet trunk listed in 1.3.1, using 2.3 and 2.4 for guidance.

5.3.1 Mark each corroded, damaged and/or deteriorated area.

5.3.2 Submit one legible copy, in hard copy or approved transferable media, of a report with a sketch listing results of the requirements of 5.3 to the SUPERVISOR.

5.4 Accomplish each ultrasonic thickness measurement (UTM) in up to 10 locations in each location reported in 5.3.2 in accordance with Paragraph 6.7 of 2.6 and 2.7, as designated by the SUPERVISOR, using 2.3 and 2.4 for guidance. The acceptance criteria must be in accordance with 2.8.

5.4.1 Submit one legible copy, in hard copy or approved transferable media, of a report listing results of the requirements of 5.4 to the SUPERVISOR.

5.4.2 Ensure a sketch showing each location of each UTM reading, original material thickness, existing material thickness, and percentage of material thickness reduction.

5.5 Accomplish the following repairs reported in 5.1.3, 5.3.2 and 5.4.1 of each IRS eductor secondary air inlet trunk listed in 1.3.1, using 2.3 and 2.4 for guidance, as designated by the SUPERVISOR. See 5.8.4 and 5.8.5.

5.5.1 Base metal weld build-up for up to 30 square inches.

5.5.1.1 Ensure each base metal buildup area does not exceed 2 inches in diameter.

5.5.1.2 Estimate the base metal buildup repair to be one quarter inch thick for pricing purposes.

5.5.1.3 Fill each local pit and groove with metal prior to the application of each principle build-up layer.

5.5.1.4 Ensure each surface is ground smooth to metal.

CMPT 01-378-2-Q	MS	A	0
DDG-115	CHG/VER:	0/0	

- 5.5.2 Remove existing and install new up to 34 square feet of plate for each bulkhead, overhead, and deck plate.
- 5.5.3 Remove existing and install new up to 13 linear feet of longitudinal, vertical, and traverse stiffener.
- 5.5.4 Vee out and weld up to 5 linear feet of cracked, split, broken or damaged weld.
- 5.5.5 Chip and grind each surface flush in way of each repair.
- 5.5.6 Template exact size, configuration, and location from each existing shipboard condition, in way of each repair.
- 5.5.7 Accomplish the requirements of 009-012 of 2.1, including Table 2, Columns A, Lines One through 7.
- 5.5.8 Accomplish the requirements of 009-025 of 2.1 for a local air hose test of each new weld seam. Allowable leakage: None.
- 5.6 Accomplish the requirements of 009-032 of 2.1, including Table 3, Line(s) 22A, for coating removed in 5.2 and repaired 5.5 of IRS eductor secondary air inlet trunk listed in 1.3.1.
- 5.6.1 Power tool clean to bare metal for each area. Accomplish each requirement of Surface Preparation Specification SSPC-SP 11 of 2.5.
- 5.6.2 The preservation area must not exceed 10 square feet per one area.
- 5.7 Accomplish the requirements of 009-032 of 2.1 for each new and disturbed surface.
- 5.8 Notes:
- 5.8.1 Planner: Code 231B M. Hayashi, 243-6145
- 5.8.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-5419-0598
- 5.8.3 This TGI meets the intent of DDG CSWT File No. 259-101.
- 5.8.4 Removal and installation of interferences, and gas free operation, preservation of boundary spaces relating to front loading structure repair in 5.5 are not included in this TGI. They will be covered by a DL in the future based on Contractor submitted condition report.
- 5.8.5 Materials for structural members relating to front loading repair will be provided in the future as a DL based on Contractor submitted condition report.
- 5.8.6 Work per this instruction involves cutting an access (or removal of a door) through a fire zone bulkhead, through the hull of the ship above the turn of the bilge, through ventilation components (ducting, plenums, etc.), or through any air-tight, fume-tight or watertight bulkheads normally used to control air flow in the event of a shipboard fire. A nonflammable closure is required in accordance with COMNAVSEASYS COM MSG R 261400Z JUL 12. The closure, if not continuously in use, shall be staged near the access, readily visible and accessible, so that any emergency responder can install the closure to affect proper air flow onboard the ship.
- 5.8.7 WPC will copy the following pages in reference.
- REF. 2.3: Pages 5-1, 6-1, and 3-5
- REF. 2.4: Pages 3C, 3A-12, 5C-12, 6-12, 6A-12, and 7A-15
- 5.8.8 JCN EM02-ZAY9 is related to this TGI.
- 5.9 Government Furnished Material (GFM): None.

4 TGI NO.:

SHIP:

CMPT 01-378-2-Q	MS	A	0
DDG-115	CHG/VER:	0/0	

- 5.10 SRF-JRMC will provide the following service work: (TGI No. 38K6112321S02).
- 5.10.1 [C740] Crane and crane rigging service.
- 5.10.2 [X99E] Utility service, electrical.
- 5.10.3 [X99M] Utility service, including low pressure air supply, water supply, and steam supply.
- 5.10.4 [C106.1] Safety inspection for SRF-JRMC employees.
- 5.10.5 [C106.2] Gas free inspection for SRF-JRMC employees.
- 5.10.6 [C133] QA Inspection for (G) symbol(s).

5	TGI NO.:	CMPT 01-378-2-Q	MS	A	0
	SHIP:	DDG-115	CHG/VER:		0/0

APPENDIX “M”
TGI MATERIAL LIST

SYSTEM:	PLANT NO.:	COMPONENT NAME:	TYPE:	PHASE:	REPEAT:	CU PH VERSION:	CASREP CAT:
15211		CMPT 01-378-2-Q	MS	A	0	0	

CU PHASE TITLE:
F/O - INSPECT, REPAIR, AND PRESERVE IN IRS EDUCTOR SECONDARY AIR INLET TRUNK

MATERIAL REFERENCES			
REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV

JOB ORDER:	KEY OP:
38K6112321	A01

MATERIAL LIST

ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
-------------	-----------	------------	-------------	-------------	-----------------	-------------------------	-----	----	------------	------------	----------------------	----------------------

NOTES:

M-1

TGI NO.:	CMPT 01-378-2-Q	MS	A	0
SHIP:	DDG-115	CHG/VER:	0/0	

☐ NUCLEAR☐ NON-NUCLEAR

APPENDIX "D"

DEFICIENCY FORM

1. SHIP/HULL NO.:	2a. DL or DR No. (Circle One)	2b. REVISION:	3a. COMPONENT NAME:	3b. TYPE:	3c. PHASE:	3d. REPEAT:
DDG-115			CMPT 01-378-2-Q	MS	A	0
4a. ICN: 38K6112321		4b. KEY OP: A01	5. LOC SPACE/LVL:	FRAME:	P/S/C:	6. CAUSED BY:

7. DESCRIPTION:					
8. ORIGINATOR:	NAME:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:

9. CORRECTIVE ACTION:					
10. EVALUATOR:	NAME:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:

FOR NON-NUCLEAR USE ONLY

11. RFD/RFW REQ'D ☐	LAR REQ'D ☐	SRD/PLAN REV REQ'D ☐			
ILS MOD REQ'D ☐		DWG NO.: _____ S/A NO.: _____			
12. ISOLATION SATISFACTORY:	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.:

13. SUBSAFE OQE RECORD?	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.
YES ☐ NO ☐					
14. CORRECTIVE ACTION COMPLETE:	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.
15. INSPECTION REQ'D?	INSPECTION COMPLETE/SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.
:YES ☐ NO ☐					
16. RECORDS REVIEW COMPLETE (DR ONLY)	SIGN:	BADGE:	SHOP/CODE:	DATE:	PHONE NO.
DL's ISSUED (DR ONLY)					

