

CONTINUATION SHEET (Amendment 0010)**DRAWINGS:**

DELETE and **REPLACE** the following drawings as of March 20, 2026. These drawings accompany this Amendment:

SP101 – STRUCTURAL PROTECTION PART PLAN AND DETAILS
AE105 – SECOND FLOOR PLAN
AE121 – ROOF PART PLAN - WEST
AE401 – ENLARGED FIRST FLOOR TOILET ROOM AND INTERIOR ELEVATION
AE440 – ENLARGED STAIR PLANS 1
AE441 – ENLARGED STAIR PLANS 2
AE444 – STAIR DETAILS
AE511 – METAL PANEL DETAILS
AE601 – DOOR SCHEDULE AND DETAILS
AE640 – ROOM FINISH SCHEDULE
Q-601 – EQUIPMENT SCHEDULE (OPTION 2)
PD102 – FIRST FLOOR PLUMBING REMOVALS PLAN - EAST
P-101 – UNDERSLAB PLUMBING PLAN – EAST
P-102 – UNDERSLAB PLUMBING PLAN – WEST
P-103 – FIRST FLOOR PLUMBING PLAN – EAST
P-104 – FIRST FLOOR PLUMBING PLAN – WEST
P-105 – FIRST FLOOR MEZZANINE PLUMBING PLAN – EAST
P-106 – FIRST FLOOR MEZZANINE PLUMBING PLAN – WEST
P-107 – SECOND FLOOR PLUMBING PLAN
P-108 – SECOND FLOOR MEZZANINE PLUMBING PLAN
P-109 – ATTIC PLUMBING PLAN
P-401 – ENLARGED PLUMBING PART PLANS 1
P-402 – ENLARGED PLUMBING PART PLANS 2
P-403 – ENLARGED PLUMBING PART PLANS 3
P-601 – PLUMBING SCHEDULES AND DETAIL
P-701 – PLUMBING RISER DIAGRAM
MD102 – FIRST FLOOR MECHANICAL DUCTWORK REMOVALS PLAN – EAST
M-703 – MECHANICAL CONTROL DIAGRAMS 3
ET102 – FIRST FLOOR TECHNOLOGY AND SECURITY PART PLAN - WEST

The following DRAWINGS have been REVISED but NOT REISSUED:

Drawing	Detail	Summary of Revision	PPI Ref
G-004A and G-004B	General Construction Notes	Add note 25 that reads: “WORK IN ATTIC: ATTIC HAS A SINGULAR CATWALK DOWN THE CENTER OF THE BUILDING WITH OPEN CEILING JOISTS TO EITHER SIDE (REFER TO AE107). CONTRACTOR MUST PROVIDE TEMPORARY WORK SURFACES AND FALL PROTECTION FOR WORK IN THIS SPACE.”	NA

Drawing	Detail	Summary of Revision	PPI Ref
G-007	Sewer Sequence Notes	Delete Sewer Sequence Note 2	566
G-010	General Construction Barrier Notes	Revise Note 1 to read: "BARRIERS AND SIGNAGE MUST MEET THE REQUIREMENTS OF EM-385-1-1 AND AS SPECIFIED IN 01 50 00.00 22 TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS (PWD ME).	NA
AE411	KEYNOTES	Revise Keynote 2 to read: "PAINT (EPOXY) ELEVATOR PIT WALLS AND FLOOR. COLOR: GRAY"	NA
AE601	DOOR SCHEDULE NOTES	Note I: Add the following text to note: "Adjust existing man door hardware to provide operability and flush door closure."	595
AE640	COLOR KEY/MANUFACTURER GUIDE	SVT 1 and SVT 2: Revise size to 18"x36"	580

The following DRAWINGS have been ADDED:
None

The following DRAWINGS have been DELETED:
None

SPECIFICATIONS:

DOCUMENT 00 01 15 LIST OF DRAWINGS

1.2 CONTRACT DRAWINGS

DELETE and **REPLACE** the following drawings as of March 20, 2026. These drawings accompany this Amendment.

<u>VOL</u>	<u>SHEET NO.</u>	<u>DRAWING NO.</u>	<u>REV NO.</u>	<u>NAVFAC DWG NO.</u>	<u>DRAWING TITLE</u>	<u>PPI Ref</u>
1	74	SP101	1	-	STRUCTURAL PROTECTION PART PLAN AND DETAILS	544, 559
1	96	AE105	1	-	SECOND FLOOR PLAN	586
1	101	AE121	1	-	ROOF PART PLAN - WEST	NA
1	114	AE401	1	-	ENLARGED FIRST FLOOR TOILET ROOM AND INTERIOR ELEVATION	557
1	115	AE402	1	-	ENLARGED SECOND FLOOR TOILET ROOM PLANS AND INTERIOR ELEVATIONS	NA
1	119	AE440	1	-	ENLARGED STAIR PLANS 1	NA

<u>VOL</u>	<u>SHEET NO.</u>	<u>DRAWING NO.</u>	<u>REV NO.</u>	<u>NAVFAC DWG NO.</u>	<u>DRAWING TITLE</u>	<u>PPI Ref</u>
1	120	AE441	1	-	ENLARGED STAIR PLANS 2	493
1	123	AE444	1	-	STAIR DETAILS	671
1	126	AE511	1	-	METAL PANEL DETAILS	468
1	132	AE601	1	-	DOOR SCHEDULE AND DETAILS	592, 606, 607, 608, 634
1	138	AE640	1	-	ROOM FINISH SCHEDULE	386, 584
2	161	Q-601	2	-	EQUIPMENT SCHEDULE (OPTION 2)	406
2	164	PD102	1	-	FIRST FLOOR PLUMBING REMOVALS PLAN - EAST	NA
2	169	P-101	1	-	UNDERSLAB PLUMBING PLAN – EAST	NA
2	170	P-102	1	-	UNDERSLAB PLUMBING PLAN – WEST	NA
2	171	P-103	1	-	FIRST FLOOR PLUMBING PLAN – EAST	NA
2	172	P-104	1	-	FIRST FLOOR PLUMBING PLAN – WEST	NA
2	173	P-105	1	-	FIRST FLOOR MEZZANINE PLUMBING PLAN – EAST	NA
2	174	P-106	1	-	FIRST FLOOR MEZZANINE PLUMBING PLAN – WEST	NA
2	175	P-107	1	-	SECOND FLOOR PLUMBING PLAN	NA
2	176	P-108	1	-	SECOND FLOOR MEZZANINE PLUMBING PLAN	NA
2	177	P-109	1	-	ATTIC PLUMBING PLAN	NA
2	178	P-401	2	-	ENLARGED PLUMBING PART PLANS 1	NA
2	179	P-402	1	-	ENLARGED PLUMBING PART PLANS 2	NA
2	180	P-403	1	-	ENLARGED PLUMBING PART PLANS 3	NA
2	182	P-601	2	-	PLUMBING SCHEDULES AND DETAIL	NA
2	183	P-701	1	-	PLUMBING RISER DIAGRAM	NA
2	186	MD102	1	-	FIRST FLOOR MECHANICAL DUCTWORK REMOVALS PLAN – EAST	NA
2	222	M-703	1	-	MECHANICAL CONTROL DIAGRAMS 3	NA

<u>VOL</u>	<u>SHEET NO.</u>	<u>DRAWING NO.</u>	<u>REV NO.</u>	<u>NAVFAC DWG NO.</u>	<u>DRAWING TITLE</u>	<u>PPI Ref</u>
2	275	ET102	1	-	FIRST FLOOR TECHNOLOGY AND SECURITY PART PLAN - WEST	666

SPECIFICATION SECTION REVISIONS:

Spec No.	Part / Subpart / Paragraph	Summary of Revision	PPI Ref
01 11 00.00 22 Summary of Work (PWD- ME)	Entire Section	Delete and replace entire section.	479
01 14 00.00 22 Work Restrictions (PWD-ME)	1.5.5.a Outage Requirements	Fifth paragraph: revise “ 18 calendar days” to “21 calendar days”	NA
01 30 10.00 22 Coordination Procedures and Coordination Drawings (PWD -ME)	Entire section	Delete and replace entire section.	676
01 35 26.00 22 Governmental Safety Requirements	1.9.3.12 Site Safety and Health Plan	Delete paragraph 1.9.3.12	379
01 50 00.00 22 Temporary Construction Facilities and Controls (PWD- ME)	3.2.2.c	Delete last sentence beginning with: “Under no circumstances...”	516
02 41 00 Demolition and Deconstruction	1.6 Submittals	Delete SD-02 Jacking design drawings; G and SD-05 Jacking design calculations; G	NA
02 41 00 Demolition and Deconstruction	3.3 Wood Framing Jacking	Delete Paragraph 3.3 in its entirety	NA
02 41 00 Demolition and Deconstruction	3.1.14 Elevators and Hoists	Delete paragraph 3.1.14	530

Spec No.	Part / Subpart / Paragraph	Summary of Revision	PPI Ref
04 01 00.91 22 Restoration and Cleaning of Masonry in Historic Structures (PWD-ME)	3.4 Masonry Cleaning	Item k: Revise to read: “The work must provide for the complete cleaning of all affected exterior masonry surfaces of the structures, removing traces of moss, dirt, and other contaminants to allow determination of the masonry’s color and shades, finish and texture, and other properties.”	536
07 81 00 Spray Applied Fireproofing	1.6.2 Inspector Qualifications	Revise third sentence to read: “The inspector must be AMPP (Formerly NACE /SSPC) Certified Intumescent Coatings Inspector Level 2, be an ICC Fire Inspector 1 Certificate holder, or a Registered Fire Protection Engineer, who has passed the fire protection engineering written examination administered by the National Council of Examiners for Engineering and Surveying (NCEES).”	384
08 01 52 Operation and Maintenance of Wood Windows and Doors	2.3 Glass and Glazing	Revise paragraph 2.3 to read: “Reuse existing intact original glass. Reuse removed lights in their original frame and positions. New glass and glazing materials must conform to Section 08 81 00 GLAZING for Tempered Glass or must otherwise match existing glazing”	467
09 51 00 Acoustical Ceilings	1.7 Extra Materials	Delete Paragraph 1.7 Extra Materials	578
09 67 23.13 Resinous Flooring	3.1 Preparation	Fourth paragraph: Revise “maximum 75 percent relative humidity” to “ maximum 85% relative humidity”.	388, 534
09 67 23.13 Resinous Flooring	3.1 Preparation	Add the following paragraph after last paragraph: If concrete substrates are not within acceptable levels according to the manufacturer's written instructions, i.e., moisture-vapor emissions, anhydrous calcium chloride, and/or relative humidity, provide a fluid-applied, multi-component, moisture mitigation system, formulated for application on new and existing concrete substrates to reduce MVER to level required for installation of floor coverings indicated and acceptable to manufacturers of floor covering products indicated.	388, 534
09 68 00 Carpeting	3.7.1 Extra Materials	Delete Paragraph 3.7.1 Extra Materials	578
09 90 00 Paints and Coatings	3.13 Waste Management	Delete sentence: “Set aside extra paint for future color matches or reuse by the Government.”	578
09 90 00 Paints and Coatings	3.11 Coating Systems for Wood and Plywood	Item c: Revise beginning of first sentence to read: “Wood Floors to Receive Natural Finish to Match Existing: Apply all coatings at rate...”	549

Spec No.	Part / Subpart / Paragraph	Summary of Revision	PPI Ref
14 24 23 Hydraulic Passenger Elevators	Entire Section	Delete and replace entire section.	666
21 13 13 Wet Pipe Sprinkler Systems, Fire Protection	1.4.1 Preconstruction Submittals	Revise paragraph to read: "Within 45 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit SD-01 submittals for review and approval. Note that SD-02, SD-03, and SD-05 submittals received prior to the review and approval of the SD-01 (qualifications) submittals will be returned Disapproved Without Review."	660
28 31 76 Interior Fire Alarm and Mass Notification System, Addressable	1.8.1.1 Preconstruction Submittals	Revise first two sentence to read: "Within 45 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit SD-01 submittals for review and approval. Note that SD-02, SD-03, and SD-05 submittals received prior to the review and approval of the SD-01 (qualifications of the fire alarm subcontractor and QFPE) submittals will be returned Disapproved Without Review."	669

PROJECT DOCUMENTS:

DELETE and **REPLACE** the following PROJECT DOCUMENTS as of March 20, 2026. These documents accompany this Amendment.

Attachment T: PRICE SCHEDULE AMD 0010 rev5

--End of Amendment --