

TASK GROUP INSTRUCTION

AIM REV 20.11.4.0 (OCTOBER 2020)

TGI NO.:	COMPONENT NAME: FAS 02 LVL STBD	TYPE: AY	PHASE: A	REPEAT: 0	CHANGE: 1
SHIP/HULL NO.:	SHIP/HULL NAME:	SYSTEM:	PROJ/WO NO:	CASREP CAT:	
DDG-115	USS RAFAEL PERALTA		K61		
CU PHASE TITLE: F/O - REPLACE PANEL OF BLAST SHEILD & BNDG STRAP ASSY OF KINGPOST IN 02 LVL WEA					
PREPARING ACTIVITY:					
PREPARED BY: NORIYUKI TAKEUCHI	CODE 231B	PHONE 315-243-9983	DATE 21-NOV-2025		
APPROVED BY: RYOUTA TAKAGI	CODE 231B	PHONE 315-243-4502	DATE 21-NOV-2025		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
CONCURRED BY:	CODE	PHONE	DATE		
REASON FOR WORK/NEED FOR CHANGE: Paragraphs 1.3.4, 1.3.5, and 1.3.6 are incorrect.					
CHANGE INSTRUCTIONS: CH1: correct Paragraphs 1.3.4, 1.3.5, and 1.3.6. (11/28/2025)					
SPECIAL REQUIREMENTS: CLEANLINESS FOR PIPING SYSTEM/EQUIPMENT LEVEL II CLASS P-2 PIPING					

WORK CERTIFICATION SIGNATURES					
COMPLETION OF WORK REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
ACCEPTANCE OF COMPLETED WORK					
PHYSICAL INSPECTION REQUIRED: ☐ YES ☒ NO	PHYSICAL INSPECTION COMPLETED:	BADGE NO.:	SHOP/CODE:	PHONE:	DATE:
RECORDS REVIEW:		BADGE NO.:	SHOP/CODE:	PHONE:	DATE:



LIST OF EFFECTIVE PAGES									
SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.	SHT NO.	CHG NO.
1-5									
J1-2									
M1-3									
QA28 (1-2)									

1. SCOPE/PURPOSE

1.1 Title: Panel of Blast Shield and Bonding Assembly of Kingpost for Fueling At Sea (FAS) Station No. 7 in 02 Level Weather, Starboard (Stbd); replace

1.2 Location of Work:

1.2.1 02 Level Weather, Frames between 320 and 340, Stbd

1.2.2 Passage (01-314-01-L)

1.2.3 Stateroom (01-320-1-L)

1.2.4 Pressure Lock (01-330-3-L)

1.3 Identification:

1.3.1 Quantity (3 EA), Panel of Blast Shield for FAS Station No. 7 in 02 Level Weather, Frames between 334 and 340, Stbd

Remarks: See 2.4 for material and detail

1.3.2 Quantity (2 EA), Penetration Sleeve for Fuel Oil Gage Tubing and JP-5 Gage Tubing

Tube Size: 1/4 Inch OD

Material: Steel

Specification: 8100-2400-0033

1.3.3 Quantity (2 EA), Tube Hanger for Fuel Oil Gage Tubing and JP-5 Gage Tubing

Tube Size: 1/4 Inch OD

Material: Steel

Type: 35B

Specification: 810-4714432

1.3.4 Quantity (One Lot), Fuel Oil Gage Tubing, from outlet side union joint of valve (FT-V-19) to inlet side union joint of gage valve

Size: 1/4 Inch OD (0.250 OD X 0.065 WT)

Material: CRES 304L

Specification: MIL-P-24691/3

Gage No.: FT-GA-3

Note: Retain gage and gage valve until reinstallation for reuse

Remarks: See Sheet 5E9 (Zone 3-B) of 2.7 and Sheet 8A (DETAIL 8A-5F) of 2.8 for details

1.3.5 Quantity (One Lot), JP-5 Gage Tubing, from outlet side union joint of valve (JPT-V-13) to inlet side union joint of gage valve

Size: 1/4 Inch OD (0.250 OD X 0.058 WT)

Material: Cu-Ni 70/30

Specification: MIL-T-16420

Gage No.: JPT-GA-3

2 TGI NO.:

SHIP:

FAS 02 LVL STBD	AY	A	0
DDG-115	CHG/VER:	1/1	

Note: Retain gage and gage valve until reinstallation for reuse

Remarks: See Sheet 5E9 (Zone 3-B) of 2.7 and Sheet 7A (DETAIL 7A-7B) of 2.9 for details

1.3.6 Quantity (5 AY), Bonding Strap Assembly of Kingpost for FAS Station No. 7 in 02 Level Weather, Frames between 320 and 335, Stbd

Type I of MIL-STD-1310

Weld Joint Design: PT1S.1 of MIL-STD-22D

Fillet Weld Size: 1/8 Inch

Remarks: See 2.10 for material and detail

1.4 Security Classification: None.

1.5 Initial Condition:

1.5.1 Potential Asbestos Hazard

1.6 Contractor work start date: 7/27/2026

1.7 Contractor work completion date: 9/4/2026

2. REFERENCES:

REF. NO.	DOCUMENT /DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV	CHG NO.	COPY REQ'D (Y/N)	SOURCE DOC (Y/N)	PARA	SEC	PG	CHP
1	NSI FY-26	NAVSEA Standard Items	-	1	N					
2	LI FY-26	Local Standard Items	-	ORG	N					
3	DWG 600-7026502	HULL OUTFIT INSTALL ZONE 4720 FR 317-338	K		Y				4A, 3A, 12	
4	DWG 611-6221133	FAB OF MISC DK FTG - ZONE 4	AH		Y				SEE NOTE 6	
5	DWG 8100-2400-0033	PENETRATION-BHD & DECK CPRSN TYPE (INSUL) FOR CPRSN TYPE FERR AND NON IPS PIPE	P		Y					
6	DWG 810-4714432	STD Pipe Hangers Fabrication DETS & INSTL	L		N					
7	DWG 505-7027235	GAGE PIPING & GAGE BOARD INSTL-HOUSE AREA 01 TO 05 LVL FR 110-386	N		Y				5E 9	
8	DWG 541-6567419	FUEL TRANSFER SYS DIAGRAM	J		Y				8A	
9	DWG 542-6567439	JP-5 FILL, XFR, SVCE & STR SYSTEM DIAGRAM	J		Y				7A	
10	DWG 407-8436526	TOPSIDE ELECTROMAGNETIC CONTROL MEASURES DRAWING (DDG-115)	2		Y				SEE NOTE	
11	MIL MIL-STD-1310	Shipboard Bonding, Grounding, and Other Techniques for EMP Mitigation and Safety	H		N					
12	DWG 571-6220741	DDG51 CLASS FAB OF RAS/FAS FTS	AN		Y				SEE NOTE	

3 TGI NO.:

SHIP:

FAS 02 LVL STBD

AY

A

0

DDG-115

CHG/VER:

1/1

3. **APPENDICES:**

- 3.1 Appendix "J" TGI Job Summary Information Sheet 1/27/2026 C1209.2 K. YOSHIDA
 3.2 Appendix "M" TGI Material List
 3.3 Appendix "D" Deficiency Form

4. **GENERAL REQUIREMENTS:**

- 4.1 Not Applicable.

5. **PROCEDURE:**

- 5.1 Remove each existing panel listed in 1.3.1, using 2.3 and 2.4 for guidance.
- 5.2 Fabricate each new panel listed in 1.3.1 in accordance with 2.4.
- 5.2.1 Install each new penetration sleeve listed in 1.3.2 to the new panel listed in 1.3.1, using 2.4 and 2.5 for guidance.
- 5.2.2 Install each new tube hanger listed in 1.3.3 to the new panel listed in 1.3.1, using 2.4 and 2.6 for guidance.
- 5.2.3 Accomplish the requirements of 009-012 of 2.1, including Table 2, Column(s) A, Lines One through 7.
- 5.3 Accomplish the requirements of 009-032 of 2.1, including Table 5, Line(s) 23, for each new panel listed in 1.3.1.
- 5.4 Install each new panel listed in 1.3.1 in accordance with 2.3 and 2.4.
- 5.5 Remove existing, fabricate and install new each fuel oil gage tubing listed in 1.3.4 and JP-5 gage tubing listed in 1.3.5, using 2.7 through 2.9 for guidance.
- 5.5.1 Accomplish the requirements of 009-012 of 2.1, including Table One, Column(s) A, Lines One through 10.
- 5.5.2 Accomplish the requirements of 009-071 of 2.1 for hydrostatic test, using clean, fresh water at 270 PSIG, for new and disturbed fuel oil gage tubing listed in 1.3.4.
- 5.5.2.1 Document shop hydro test results on QA Form 28 Enclosure-01-1.
- 5.5.3 Accomplish the requirements of 009-071 of 2.1 for hydrostatic test, using clean, fresh water at 88 PSIG, for new and disturbed JP-5 gage tubing listed in 1.3.5.
- 5.5.3.1 Document shop hydro test results on QA Form 28 Enclosure-01-2.
- 5.6 Remove existing and install new each bonding strap assembly listed in 1.3.6 in accordance with 2.10 and 2.11, using 2.12 for guidance.
- 5.6.1 Drill hole(s) on existing center support leg and side support legs of kingpost located in 1.2.1.
- 5.6.2 Accomplish build up weld of remaining hole(s) on the center support leg and side support legs.
- 5.6.3 Accomplish the requirements of 009-012 of 2.1, including Table 2, Column(s) A and D, Lines One through 7.
- 5.7 Accomplish the requirements of 009-032 of 2.1 for each new and disturbed surface.
- 5.8 Notes:

4 TGI NO.:

SHIP:

FAS 02 LVL STBD	AY	A	0
DDG-115	CHG/VER:	1/1	

5.8.1 Planner: Code 231B N. Takeuchi, 243-9983
 Planner: Code 233 M. Takemura, 090-9350-1458
 Planner: Code 234 S. Yamashita, 070-7787-2035

5.8.2 Work Integration Manager (WIM): Code 333 T. Yaginuma, 080-6522-9560

5.8.3 WPC will copy the following pages in reference.

REF. 2.4: Pages 125A, 125B, 125D, and 125H

REF. 2.10: Pages 5-16, 15-2, and B-2

REF. 2.12: Pages 14A, 14B, 14C, 14D, 14E, 14F, 14G, 14H, 14J, 15A, 15B, and 15C

5.8.4 JCNs EB14-L021 and CE03-L017 are related to this TGI.

5.9 Government Furnished Material (GFM):

5.9.1 SRF-JRMC will provide GFM listed in Appendix "M".

5.10 SRF-JRMC will provide the following service work: (TGI No. 38K6154101S02).

5.10.1 [C740] Crane and crane rigging service.

5.10.2 [X99E] Utility service, electrical.

5.10.3 [X99M] Utility service, including low pressure air supply, water supply, and steam supply.

5.10.4 [C106.1] Safety inspection for SRF-JRMC employees.

5.10.5 [C106.2] Gas free inspection for SRF-JRMC employees.

5.10.6 [C133] QA inspection for (G) symbol(s).

FAS 02 LVL STBD	AY	A	0
DDG-115	CHG/VER:		1/1

APPENDIX "M"

TGI MATERIAL LIST

SYSTEM:	PLANT NO.:	COMPONENT NAME:	TYPE:	PHASE:	REPEAT:	CU PH VERSION:	CASREP CAT:
		FAS 02 LVL STBD	AY	A	0	1	

CU PHASE TITLE:

F/O - REPLACE PANEL OF BLAST SHEILD & BNDG STRAP ASSY OF KINGPOST IN 02 LVL WEA

MATERIAL REFERENCES

REF NO.	DOCUMENT/DRAWING NUMBER	DOCUMENT/DRAWING TITLE	REV
------------	----------------------------	------------------------	-----

JOB ORDER:

38K6154101

KEY OP:

A01

MATERIAL LIST

ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
001			M	PLATE,ME, 5FT X 6FT ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 9515 002243086		NA	4	N	53175818	30/SF	
002			M	STRIP,EL, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 5999 013438667		NA	4	N	53185044	5/EA	
003			M	SCREW,CA, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 5305 014535741		NA	4	N	53175182	10/EA	
004			M	NUT,SLEE, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 5310 014231667		NA	4	N	53185047	10/EA	
005			M	INSULATI, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9Q 5640 013713263		NA	4	N	53175119	3/SH	
006			M	INSULATI, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9Q 5640 013713262		NA	4	N	53175117	3/SH	
007			M	INSULATI, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9Q 5640 LL4823204		NA	4	N	53177517	1/SH	
008			M	TAPE,TEX, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 8315 002671632		NA	4	N	53185020	1/RO	

NOTES:

M-1

TGI NO.:	FAS 02 LVL STBD	AY	A	0
SHIP:	DDG-115	CHG/VER:	1/1	

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
009			M	ADHESIVE, ORIG: C231B N. TAKEUCHI 243-9983 ORDER FOR KTR	9B 8040 002738708		NA	4	Y	53185026	1/GL	
400			M	TUBE,METALLIC, OD 1/4" CU-NI 70/30, 0.058THK FOR JP-5 GAGE ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 4710 012344737		NA	4	N	53185048	15/FT	
401			M	TUBE,METALLIC, OD 1/4" CU-NI 70/30, 0.058THK FOR JP-5 GAGE ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 4710 012344737		NA	4	N	53185050	15/FT	
402			M	NUT,UNION, ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 4730 013148807		NA	4	N	53185053	2/EA	
403			M	UNION,TUBE, ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 4730 000610412		NA	4	N	53175815	10/EA	
404			M	TAILPIECE, UNION 1/4, TAILPIECE, UNION, SIZE: 1/4"OD, SW, MATL: CRES316L, 6000 PSI, SAE-AMS-QQ-S-763, NSN: 4730-01-175-6520 (NSN MATERIAL: COPPER ALLOY 715), NSN: 4730-01-270-9812 (NSN MATERIAL: COPPER ALLOY 706) ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	LL4903803		NA	4	N		1/EA	
405			M	TUBE,METAL, TUBE, METAL, CRES 304L,MIL-P-24691/3, TYPE 1 SEAMLESS, GRADE TP304L, 0.250"OD X 0.065" THICKNESS. ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	LL4805469		NA	4	N		15/FT	
406			M	TUBE,METAL, TUBE, METAL, CRES 304L,MIL-P-24691/3, TYPE 1 SEAMLESS, GRADE TP304L, 0.250"OD X 0.065" THICKNESS. ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	LL4805469		NA	4	N		15/FT	
407			M	TAILPIECE,UNION, OD1/4' CU-NI 70/30 FOR JP-5 GAGE ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 4730 011756520		NA	4	N	53175809	1/EA	
408			M	O-RING, ORIG: C234 S. YAMASHITA 070-7787-2035 ORDERED FOR KTR	9B 5331 001660980		NA	4	N	53175113	4/EA	

M-2

TGI NO.:	FAS 02 LVL STBD	AY	A	0
SHIP:	DDG-115	CHG/VER:	1/1	

MATERIAL LIST												
ITEM NO.	PC NO.	REF NO.	M / C	DESCRIPTION	STOCK NUMBER	GENERIC MATL TYPE	LVL	QA	HAZ MAT	DOC NO.	QTY REQD/ UNIT	QTY USED/ UNIT
409			M	PIPE HANGER, PIPE HANGER, SIZE: 1/4"OD, TY 35B, MATL: STEEL, WITH 2"LG WELDING STUD, NEOPRENE LINED TUBE HANGER, MODIFY: HANGER CLIP INCLUDE 2"LG WELDING STUD PREMIER COPPER P/N: PH35B004 MOD ORIG: C234 S. YAMASHITA 070-7787-2035 ODERED FOR KTR	LL9302967		NA	4	N		2/EA	
410			M	PENETRATION END, PENETRATION COMPRESSION END, STEEL 1/4" OD X 5" LG, WITH SLEEVES, NUTS, NEOPRENE GASKET AND O-RING 250 DEGREE F., MAX. BIW DRAWING: 1313-0801-0121. ORIG: C234 S. YAMASHITA 070-7787-2035 ODERED FOR KTR	LL9006154		NA	4	N		2/EA	
411			M	UNION,PIPE, 1/4" IPS SW CU-NI 70/30 ORIG: C234 S. YAMASHITA 070-7787-2035 ODERED FOR KTR	9B 4730 014213430		NA	4	N	53175803	1/EA	
412			M	BUSHING, 1/4"IPS X 1/4"OD, SW, CNA 70-30, 3000 PSI, INSERT(BUSHING) ORIG: C234 S. YAMASHITA 070-7787-2035 ODERED FOR KTR	9C 4730 LL4676524		NA	4	N	53177518	1/EA	

M-3

TGI NO.:	FAS 02 LVL STBD	AY	A	0
SHIP:	DDG-115	CHG/VER:	1/1	

☐ NUCLEAR☐ NON-NUCLEAR

APPENDIX "D"

DEFICIENCY FORM

1. SHIP/HULL NO.:	2a. DL or DR No. (Circle One)	2b. REVISION:	3a. COMPONENT NAME:	3b. TYPE:	3c. PHASE:	3d. REPEAT:
DDG-115			FAS 02 LVL STBD	AY	A	0
4a. ICN:		4b. KEY OP:	5. LOC SPACE/LVL:	FRAME:	P/S/C:	6. CAUSED BY:
38K6154101		A01				

7. DESCRIPTION:

8. ORIGINATOR:

NAME:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

9. CORRECTIVE ACTION:

10. EVALUATOR:

NAME:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

FOR NON-NUCLEAR USE ONLY

11. RFD/RFW REQ'D ☐LAR REQ'D ☐SRD/PLAN REV REQ'D ☐ILS MOD REQ'D ☐

DWG NO.: _____ S/A NO.: _____

12. ISOLATION

SATISFACTORY:

SIGN:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

13. SUBSAFE OQE RECORD?

YES ☐ NO ☐

SIGN:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

14. CORRECTIVE ACTION
COMPLETE:

SIGN:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

15. INSPECTION REQ'D?

:YES ☐ NO ☐

INSPECTION COMPLETE/SIGN:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

16. RECORDS REVIEW
COMPLETE (DR ONLY)

SIGN:

BADGE:

SHOP/CODE:

DATE:

PHONE NO.:

DL's ISSUED
(DR ONLY)

SHOP TEST RECORD

Page 1 of 1

QA FORM 28 Planning must fill in blocks identified by a ♦ prior to issuing

♦1. SHIP USS RAFAEL PERALTA		HULL NO. DDG115		♦2. JCN EB14-L021		♦3. LWC/SHOP KTR		♦4. CWP/REC SER NO. N/A		5. SYSTEM/COMPONENT/ROTATABLE POOL SER NO. Fuel Oil Gage Tubing					
♦6. REFERENCES: TEST REF (E.G., MS, TECH MAN) & OTHER REFS (E.G., VLV DWG)						7. TEST GAGE RANGE /INSTRUMENT USED		SERIAL NO.		CAL DUE DATE		8. RELIEF VLV SET POINT			
A.		S9086-RK-STM-010/CH-505 Rev. 6													
B.		DWG 541-6567419 BK Rev. H													
C.															
D.															
9. TEST REQUIREMENTS & RESULTS															
TEST TYPE KEY		H = STRENGTH AND POROSITY/ELEVATED PRESSURE TEST				J = MECHANICAL JOINT TIGHTNESS		ST = SEAT TIGHTNESS		OP = OPERATIONAL		O = OTHER (SPECIFY): _____			
♦ TEST TYPE (SEE KEY)	♦ PARAGRAPH DESCRIBING VALVE POSITION AND POINT OF ENTRY	♦ REF LTR	GAGE USED (LTR FROM BLK 7)	♦ REQUIRED MEDIUM	MEDIUM USED	♦ REQUIRED PRESSURE	ACTUAL PRESSURE	♦ MINIMUM DURATION	ACTUAL DURATION	♦ ALLOWED LEAKAGE	ACTUAL LEAKAGE	SAT/UNSAT	SIGNATURE, BADGE NO. & DATE		
H	5.5.2	A,B		Clean Fresh Water		270 PSIG		30 minutes		None					
10. REMARKS. (CRAFTSMAN/QAI SUBMIT A DF TO RESOLVE UNSAT DATA)															
11. QA INSPECTOR/SHOP SUPERVISOR SIGNATURE/BADGE NO. (RECORD REVIEWED FOR FINAL ACCEPTANCE)							DATE		12. QAS SIGNATURE/BADGE NO. (RECORD HAS BEEN REVIEWED FOR COMPLETENESS)					DATE	

38K6154101A01

ENCLOSURE-01-1

TOTAL 2

SHOP TEST RECORD

Page 1 of 1

QA FORM 28 Planning must fill in blocks identified by a ♦ prior to issuing

♦1. SHIP USS RAFAEL PERALTA		HULL NO. DDG115		♦2. JCN EB14-L021		♦3. LWC/SHOP KTR		♦4. CWP/REC SER NO. N/A		5. SYSTEM/COMPONENT/ROTATABLE POOL SER NO. JP-5 Gage Tubing					
♦6. REFERENCES: TEST REF (E.G., MS, TECH MAN) & OTHER REFS (E.G., VLV DWG)						7. TEST GAGE RANGE /INSTRUMENT USED		SERIAL NO.		CAL DUE DATE		8. RELIEF VLV SET POINT			
A.		S9086-RK-STM-010/CH-505 Rev. 6													
B.		DWG 542-6567439 BK Rev. J													
C.															
D.															
9. TEST REQUIREMENTS & RESULTS															
TEST TYPE KEY		H = STRENGTH AND POROSITY/ELEVATED PRESSURE TEST				J = MECHANICAL JOINT TIGHTNESS		ST = SEAT TIGHTNESS		OP = OPERATIONAL		O = OTHER (SPECIFY): _____			
♦ TEST TYPE (SEE KEY)	♦ PARAGRAPH DESCRIBING VALVE POSITION AND POINT OF ENTRY	♦ REF LTR	GAGE USED (LTR FROM BLK 7)	♦ REQUIRED MEDIUM	MEDIUM USED	♦ REQUIRED PRESSURE	ACTUAL PRESSURE	♦ MINIMUM DURATION	ACTUAL DURATION	♦ ALLOWED LEAKAGE	ACTUAL LEAKAGE	SAT/UNSAT	SIGNATURE, BADGE NO. & DATE		
H	5.5.3	A,B		Clean Fresh Water		88 PSIG		30 minutes		None					
10. REMARKS. (CRAFTSMAN/QAI SUBMIT A DF TO RESOLVE UNSAT DATA)															
11. QA INSPECTOR/SHOP SUPERVISOR SIGNATURE/BADGE NO. (RECORD REVIEWED FOR FINAL ACCEPTANCE)							DATE		12. QAS SIGNATURE/BADGE NO. (RECORD HAS BEEN REVIEWED FOR COMPLETENESS)					DATE	

38K6154101A01

ENCLOSURE-01-2

TOTAL 2