

PPI #	PPI	Government Answer
01	Ref. Solicitation Document: Page 1 gives 548 days to complete where schedule section on Page 15 only gives 414 days. Page 9 of Attachment T shows 1080 calendar days. Please clarify the duration for the seed project at B60.	Refer to Amendment 0002 0004 and revised Attachment T
02	Ref. Solicitation Document: Page 9 stipulates 40% Small Business participation where Page 16 only requires 20%. Please clarify the Small Business participation percentage for the seed project at B60.	There is no discrepancy. 40% is a component of the NAVFAC command-wide target for small business subcontracting. These targets are based on a percentage of total planned subcontract dollars. The 20% in Factor 3 applies to the total contract value.
03	Factor 1, Corporate Experience, requires that projects submitted were completed within (7) years of the proposal due date. Larger projects, particularly those with a final construction cost in excess of \$50M and those involving complex waterfront work span several years (3-4) thereby making the 7-year window short for a contractor involved in this work to have applicable projects. We request that this window be extended to 15-years to capture recent and relevant Corporate Experience.	Propose in accordance with the Solicitation
04	Factor 1, Corporate Experience, requires that projects submitted are complete. We request that projects at least 75% complete be accepted.	Propose in accordance with the Solicitation
05	Factor 1B calls for the submission of design firm experience. Please identify all design firms that NAVFAC deems ineligible to participate on the proposing contractors' teams, due to their direct contracting with NAVFAC.	The Government will not provide guidance in the development of proposals. Any concern of potential organizational conflicts of interest should be explained in offeror's proposals.
06	Ref. Solicitation Document Page 7 #3. Proposal Submission and Pre-proposal Inquiries. Section ends with 'Contractors should ensure that...' Please finish this sentence.	Refer to Amendment 0002
07	Ref. Solicitation Document Page 7 #3. Proposal Submission and Pre-proposal Inquiries. PPI are due by January 30, 2026 however proposals are due almost 5 weeks later. Please extend the due date for PPI to February to give bidders reasonable time to submit questions.	Refer to Amendment 0002
08	Ref. Solicitation Document Page 1. Proposals are due March 07, this is a Saturday. Please confirm this is correct.	Refer to Amendment 0002
09	Ref. Solicitation Document Page 32. Includes DFARS 252.7012, .7019, .7020 however none of the documents are labeled CUI or indicated to be controlled. Please confirm none of the contract is considered CUI.	Confirmed. The contract is not CUI.
10	Ref. 01 11 00.00 22 Par. 1.3.1 Indicates commencement of this contract is contingent on other ongoing projects. Please confirm what date the Government expects these contract(s)	Delete second sentence under paragraph 1.3 Period performance starting with "The mobilization date..". Replace paragraph 1.3.1 with the following: Contractor to mobilize no

	will be completing for material and labor pricing and schedule development for this proposal.	sooner than 45 calendar days after award and start construction activities no sooner than 90 calendar days after award. Pricing and schedule shall be developed accordingly.
11	Ref. 01 11 00.00 22 Par. 1.3.1 Describes a Post Award Meeting to review timelines and review proposed path forward. How does this meeting differ from the Preconstruction Meeting shown in 01 30 00.00 22?	Revise paragraph 1.3.1 as noted in response to PPI 10 (removes reference/requirement for Post Award Meeting). Also Delete "Post Award Kickoff (PAK)" from section 01 31 23.13 20 paragraph 1.6.8. Provide Preconstruction Meeting as indicated in specifications.
12	Ref. 01 33 29.00 22 Par. 1.5.3.2.a Prelim Sustainability eNotebook. Submit...at the first post award meeting in accordance with Section 01 30 00.00 22 ADMINISTRATIVE REQUIREMENTS (PWD ME). The Post Award Meeting is not detailed in 01 30 00.00 22. Please provide more information about this meeting.	Post Award Meeting is not required. Refer to responses to PPI 10 and 11. Prelim Sustainability eNotebook must be submitted at Preconstruction Meeting.
13	Ref 01 14 00.00 22 Par 1.2.a Tier 1 Infrastructure. Please provide the list of facilities that require additional work restrictions and procedures to be worked on or in the vicinity of. Please provide the restrictions and procedures. Please provide what constitutes in the vicinity of a Tier 1 Infrastructure.	a) Tier 1 Infrastructure includes: EW(12") Water line under building from Water Tower. Refer to revised sheets SB101 and SB102. b) Restrictions & procedures: Refer to spec 01 14 00.00 22 Paragraph 1.10 c) What constitutes 'within the vicinity of Tier 1 Infrastructure': Refer to spec 01 14 00.00 22 Paragraph 1.10 and see item 'a' above.
14	Ref 01 14 00.00 22 Par 1.4 Special Scheduling Requirements. It is unclear what is expected of the contractor in sub-paragraphs a & b. Par. b requires outages to be submitted 30 days prior to interruption where paragraph a only requires submission 15 days prior. Please clarify these requirements.	See revised specification section 01 14 00.00 22 for clarification.
15	Ref 01 14 00.00 22 Par 1.4.c Special Scheduling Requirements. ...See the Scope of Work to determine if the project limits include any security Island in or adjacent to the work area. Please confirm where this information is located in the contract documents.	See revised specification section 01 14 00.00 22 for clarification. Secure areas include work within Buildings 59, 13, and 86.
16	Ref 01 14 00.00 22 Par 1.4.d Special Scheduling Requirements. Coordinate the work with the sequencing/phasing requirements outlined in the Scope of Work Memo and as outline in the Construction Drawings. Please confirm where the Scope of Work Memo is located.	See revised specification section 01 14 00.00 22 for clarification. Section has been updated to reference construction drawings and specifications. See also <i>general sequencing info on Sheet G-007</i> .

17	Ref 01 14 00.00 22 Par 1.5.5.a Outage Requirements ...Outages involving Tier 1 Shipyard Infrastructure require a specific Risk Analysis and Risk Mitigation Plan as outlined in Paragraph herein entitled TIER 1 SHIPYARD INFRASTRUCTURE REQUIREMENTS. Please confirm where this paragraph is in the specifications.	Outages involving Tier 1 Infrastructure require a specific Risk Analysis and Risk Mitigation Plan as outlined in Section 01 35 26, paragraph 3.9.4, titled Excavating with Hazardous or Tier 1 Utilities Within the Excavation Area and under Section 01 14 00.00 22 paragraph 1.10 titled TIER 1 INFRASTRUCTURE RISK ANALYSIS (RA) AND RISK MITIGATION PLAN (RMP). Refer to revised specification section 01 14 00.00 22 for additional information
18	Ref 01 14 00.00 22 Par 1.5.5.a Outage Requirements ...Any Outage requests denied due to incomplete stakeholder alignment or information required to support the requested outages, will not be justification for a delay claim. The denial of an outage for alignment of stakeholders is not in the control of the contractor. Please confirm if the contractor submits the (9) items listed lower in the paragraph in advance of the outage it will satisfy the requirements for outages.	Confirmed. See revised specification section 01 14 00.00 22 for clarification. Text has been updated to reflect that if the required items contain "incomplete information" denial will not be justification for a delay claim.
19	Ref 01 14 00.00 22 Par 1.8.9 and 1.8.10 None of the contract documents have been labeled or designated CUI. These paragraphs limit the information to the Contractor's organization only but dissemination to subcontractors and vendors is necessary for this proposal. Please confirm the contract documents can be shared with other entities to support this proposal.	Refer to PPI 9 response - The contract is not CUI and documents can be distributed accordingly.
20	Factor 1, Corporate Experience, notes that projects submitted for the Offeror shall have been completed within the previous (7) years of the proposal due date for this RFP. The RFP seems to indicate that projects of large scale may be contemplated. Large projects generally have durations of 4 – 8 years. As such, very few large projects would qualify with a only a 7 year reach-back period. For such large project solicitations, it is common for the Government to allow a reach-back period of 15 years. In order to show a company's true capabilities, we request that the 7 year completion requirement be revised to 15 years.	Propose in accordance with the Solicitation
21	Factor 1 also requires projects be completed to qualify as relevant. Please consider allowing completed projects or projects that are at least 75% complete; or consider allowing projects in which the associated relevant portion of the work has been complete if the project is still ongoing.	Propose in accordance with the Solicitation
22	The RFP is silent on whether or not any Design Firms would be prohibited in participating on a team due to a conflict of interest. If the Government foresees any Designers not being	The Government will not provide guidance in the development of proposals. Any concern of potential organizational conflicts of interest

	eligible for participation on a team in response to the RFP, please provide the names of those conflicted out.	should be explained in offeror's proposals
23	Page 1 and page 30 of the RFP solicitation calls for a 548 day contract duration where Schedule section on page 15 calls for 414 days. Please clarify which duration applies to the overall contract period.	Refer to the changes included in Amendment 0004.
24	Factor 1 (1B) Design Experience instructs the offeror to use the "Construction & Design Experience Project Data Sheet (Attachment A)" for design experience. However, the Attachment A provided with the solicitation "Construction Experience Project Data Sheet" is only for construction projects, does not identify DES 1 to DES 5 at the top row, and does not include Block 8 that is usually reserved for design project information. a) Please clarify and provide the relevant Construction & Design Experience Project Data Sheet (Attachment A) that is mandatory to be used for both the design and the construction projects.	Please refer to the revised Attachment A provided with Amendment 0004.
25	The page limitation for each construction project is defined as 4 pages, whereas the page limitation for each design project is defined as 2 pages. Please confirm the page limitation for each Construction Project and each Design Project presented in Factor 1.	Confirmed. The page limitations are as stated in the Solicitation.
26	RFP page 8 states "information is not required to be completed under Section 00 10 00 - Solicitation Contract Form in SF 1442." a) Shall the offeror still include the Section 00 10 00 - Solicitation Contract Forms in the proposal, but enter "Not Applicable" in the cells for Unit Rate and Amount of the Base and Option periods? b) Alternatively, shall the offeror only provide the completed Attachment T Price Schedule form in this section?	Propose in accordance with the Solicitation
27	Item (vii) of the Price submission requirements identifies the Small Business Subcontracting Plan is required, but refers to details under the "ADDITIONAL INFORMATION TO BE SUBMITTED WITH PRICE PROPOSAL PACKAGE." Please confirm the Small Business Subcontracting Plan shall be presented under "Additional Information for Responsibility Determination" and not under item (vii)	Confirmed.
28	Factor 1, RFP page 11, Para 5 states "Offerors proposing as a JV shall submit a signed JV agreement." a) In which Factor and section shall the executed JV agreement be provided? b) Please confirm the JV agreement is not page counted.	Offerors should submit the executed JV agreement with the non-price proposal. It will not count towards the page limitations.
29	Para 1 states "... Offeror is required to identify the design firm (Architect/Engineering firm) to be utilized as Designer of Record (DOR) on anticipated future projects. Provide the full name of the firm, address, Unique Entity Identifier (UEI), and	a) Factor 1 b) Factor 1

	CAGE code. The Offeror must provide supporting documentation (such as a signed joint venture agreement, partnership agreement, teaming agreement, or letter of commitment on the proposed DOR's letterhead) demonstrating agreement by the proposed design firm to perform as DOR for the duration of this MACC." a) In which Factor and section shall the offeror place the executed agreement or letter of commitment for its proposed DOR? b) In which Factor and section shall the DOR's name, address, UEI, and CAGE code be presented? c) Please confirm the DOR agreement and the DOR company information are not page counted.	c) Confirmed.
30	The primary solicitation PDF and each Amendment 0001 and 0002 PDFs issued so far are of a secured nature such that they do not allow the offeror to find key words or to copy information, potentially impacting proposal compliance. Since the contract is not CUI, as clarified in Amendment 02, will the Government remove the security setting for any future amendment files?	Propose in accordance with the Solicitation.
31	when the original sources sought attached to this solicitation was issued in June 2025 under N6247024R0057rev1 the qualifying \$ amount for a single project was \$20mil. Would the Government entertain lowering the new single project requirement of \$50mil to \$25mil to allow those whom showed interest in this MACC originally to qualify? Although there appears to be a strong SB % requirement it does appear that this solicitation is favoring large business due to this new threshold.	Propose in accordance with the Solicitation.
32	Will NAVFAC consider providing a design stipend at 1% of the estimated construction cost, to offset proposal development burdens and encourage robust industry competition. Currently the US Army Corps of Engineers, and the Baltimore District in particular, are offering a 1% design stipend for design build type solicitations.	Propose in accordance with the Solicitation.
33	Please provide solicitation documents with text searchable content for ease of solicitation review and proposal development.	Propose in accordance with the Solicitation.
34	Please confirm that two PDF documents should be submitted as part of this proposal and named accordingly as listed below: 1.) Price Proposal 2.) Non-Price Technical Proposal	Propose in accordance with the Solicitation.
35	Paragraph 2 is missing from section 5.	Please refer to the changes included in Amendment 0004.
36	Please clarify what specific data should be included for projects listed in the Price Proposal under "Other offeror's work presently under contract".	Offerors shall provide a list of ongoing projects, to include the final value, duration, and geographical location of each project.
37	Please consider allowing projects substantially completed at 90% or greater to be included in past performance experience	Propose in accordance with the Solicitation.

	submissions to provide the Government with the most recent project experience that is relevant to the solicitation.	
38	Please identify what Factor or section an Offeror's JV agreement should be provided in the proposal.	An offeror's JV agreement should be provided with the non-price proposal.
39	(1A) Construction Experience states Attachment A is limited to two (2) double-sided pages (or four (4) single-sided pages) (1B) Design Experience states Attachment A is limited to one (1) double-sided pages (or two (2) single-sided pages) The page limitations for Attachment A differ as listed above. Please clarify the correct page limitations for Attachment A is two (2) double-sided pages (or four (4) single-sided pages) for Construction and Design experience.	Please refer to the revised Attachment A provided with Amendment 0004.
40	Please clarify the TRC rate calculation should be Number of TCR Incidents x 200,000 / Total Number of Employee Labor Hours Worked. The division operation appears to have been left out of the calculation equation.	Confirmed. Please refer to the revisions included in Amendment 0004.
41	Please increase the Factor 3 Management Approach page limitations to 10 single-sided pages to allow offerors the capability to fully describe our understanding of the requirements and management approach.	Please refer to the revisions included in Amendment 0004.
42	Will NAVFAC consider allowing offerors to only submit a PDF of the P6 schedule and remove the requirement for the native .xer file?	Please refer to the revisions included in Amendment 0004.
43	"The solicitation states ""the Offeror may receive a deficiency if firm commitments with subcontractors are not provided..."" Please clarify if Offerors required to include a copy of the commitment letter within Factor 5 for each subcontractor company listed in the SBPCD in order to demonstrate firm commitments?"	Offerors are not required to provide copies of their firm written commitment documents for each of the small business subcontractors identified on Attachment E, Small Business Participation Commitment Document (SBPCD). Please refer to the revised Attachment E provided with Amendment 0004.
44	Attachment A, Box 7 & 8 The instructions above Box 7 indicate that box 7 is to be completed for construction projects and box 8 is completed for design projects. Please clarify that Box 7 and 8 is required for both Construction and Design projects.	Please refer to the revised Attachment A provided with Amendment 0004.
45	Attachment A, Project No. Box: This section only provides boxes for Construction projects and does not provide a way to identify Design projects #1-#5.	Please refer to the revised Attachment A provided with Amendment 0004.
46	Please identify the anticipated total contract value offerors should utilize in the Small Business Subcontracting Plan for the Base Period, Option Period 1 and Option Period 2.	The value of the base and option periods should reflect the associated percentage of the total contract value.

47	Please clarify that there is no Option Period 3 or Option Period 4 on this MACC which is listed on page 13 of Attachment E.	Please refer to the revised Attachment F provided with Amendment 0003.
48	On page 7 of the RFP, it states that "proposals are to be submitted via the PIEE Solicitation Module." We are not able to locate this solicitation on PIEE. Will the Government please provide the PIEE link to the solicitation?	The PIEE link is now available and will remain available for proposal submission within the PIEE Solicitation Module
49	"Factor 5 - Small Business Participation and Utilization under item 1 states, ""Each project submitted under Factor 1, Corporate Experience, shall be included on Attachment D."" Typically such subcontracting information is only requested for the Construction Experience portion of the factor (not Design) since the Construction Experience represents the Offeror responsible for the management of the subcontracting program. Please confirm that Attachment D is only required for Construction Experience projects."	Please refer to the changes included in Amendment 0004 and to the revised Attachment D provided with Amendment 0004.
50	If an Offeror files VETS 4212 reports for multiple hiring regions, please confirm if all report confirmations should be included in the proposal, or only the report confirmation which corresponds to the region of the project.	Propose in accordance with the Solicitation.
51	On page 12 of the RFP, it states that Attachment A is required for response to Factor 1. Within Attachment A it states, "Complete Box 8 for Design Projects." Box 8 contains the detailed description of the project and the relevancy to the project requirements for both construction and design experience. Please clarify if there is a box missing.	Please refer to the revised Attachment A provided with Amendment 0004.
52	Attachment D instructions at the top of page one states <i>"supporting information for the evaluation of Factor 3"</i> . Factor 3 is Management Approach. Please clarify that Att D supports the evaluation of Factor 6, Small Business Utilization and Participation.	Please see the revised Attachment D included in Amendment 0004. Attachment D supports the evaluation of Factor 5, Small Business Utilization and Participation
53	The period of performance listed in the specifications is 608 calendar days. However the Amendment 2 solicitation, under Factor 4, states the POP is 548 calendar days. Please clarify.	Please refer to the changes included in Amendment 0004.
54	Factor 3, Management Approach (ii) Basis of Evaluation states <i>"An Offeror's <u>narrative work plan</u> that identifies risks for the seed project and provide potential mitigation solutions may be considered more favorably than those that do not."</i> Factor 3 instructions do not ask for Offeror's to provide a narrative work plan. Please clarify that this sentence applies to Factor 4, Schedule where risks and mitigations are discussed.	Please refer to the changes included in Amendment 0004.
55	Page 1 of the Solicitation - Section 13 states "Sealed offers in original and 1 copies to perform the work required are due at the place specified in Item 8....." Item 8 is currently left blank.	Item 8 is intentionally blank, as offers will be received electronically. Confirmed. Hard copy submissions will not be accepted. Please submit proposals in accordance with the

	Page 7 of the Solicitation 00 21 00 - Section 3 states "Proposals are to be submitted via the PIEE Solicitation Module. Hard Copy Delivery or facsimile submission will not be accepted." Please confirm hard copy of originals/ copies are not required and response shall be submitted electronically.	Solicitation revisions included in Amendment 0004.
56	Please advise if a date/ time for site visit been established?	Refer to Amendment 0003.
57	Factor 1B - Please confirm that we are allowed to have more than one Designer of Record on our team for this very large, very diverse MACC pursuit.	Confirmed. Please refer to the changes included in Amendment 0004.
58	Specification states: "Base Bid: the Government has estimated that the onsite contract work contingent upon the completion of current ongoing projects which have an estimated completion time of late summer 2026. Please confirm this specification section is intended to state 548 in accordance with the updates made in Amendment 0002.	See response to PPI #1
59	Specification states to provide coating inspector and protective coatings specialists for 09 97 13. 16 Interior coating of welded steel water tanks and 09 97 13.27 High performance coating for steel structures. The referenced specifications are not included for this project. Please confirm coating inspector and protective coating specialists are not required as it is not applicable for this project.	Confirmed. Protective costing specialists indicated for sections 09 97 13.16 and 09 97 13.27 are not applicable to this project.
60	Specification section 01 14 00.00 22 states "a. Do not release to anyone outside the Contractor's organization any unclassified information, regardless of medium (e.g., hard copies, computer files, film, tape, document), pertaining to any part of this Contract or any program related to this Contract, unless the Contracting Officer has given prior written approval. b. Requests for approval under paragraph (a) must identify the specific information to be released, the medium to be used, and the purpose for the release. Submit the request to the Contracting Officer at least 10 business days before the proposed date for release. c. The Contractor agrees to include a similar requirement, including this paragraph (c), in each subcontract under this Contract. Subcontractors must submit requests for authorization to release through the Prime Contractor to the Contracting Officer." Please confirm it is acceptable that all documents publicly available can be shared outside of Contractors organization for bidding purposes. Please also confirm all subcontractors can	Confirmed. The contract is not CUI.

	release publicly available information to sub-tier vendors and suppliers for bidding purposes.	
61	Specification states "Identify all activities in the Baseline NAS with its respective Drawing Code. The Drawing Code is the Sheet Number on the primary project drawing which indicates work to be performed. If an activity does not have an applicable Drawing Code (e.g., Mobilize), the code must be "0000"." Please advise if drawing codes are required for the schedule which will be submitted with the solicitation response.	Drawing codes are not required for the schedule which will be submitted with the solicitation response.
62	The documents included within the solicitation do not seem to provide order of precedence for the documents in the event of a conflict. Please provide an order of precedence.	Propose in accordance with the Solicitation.
63	Drawings do not indicate spray foam. Specifications not "stud work, attic, and eave as indicated." Please confirm where spray polyurethane foam work will take place.	Spray foam insulation will be limited to ancillary work for sealing openings, penetrations, etc. as part of insulated metal panel work.
64	• On sheet SP101 it shows the columns, and beams rated for 1HR of protection. • In the 07 81 00 spec section 1.4.2 it says 2HR rating. • On sheet G-100 it lists the building as a Type IIIB building which doesn't require fireproofing. Please clarify the fireproofing scope of work.	Provide fireproofing as indicated on sheet SP101. This includes 1-HR fireproofing at the new columns and beams supporting the fire pump room and existing steel beams and portion of wood joists at the existing northeast stair. Revise specification 07 81 00 Fire Rating Schedule to indicate 1-Hr rating. Note: Provide fireproofing, sealing, and firestopping as required at fire rated partitions that are indicated in contract drawings and specifications.
65	This specification section notes the requirement for complex systems. It also provided examples of equipment meeting and not meeting the Complex System Definition. Packaged Terminal Air-Conditioners are noted as not being complex systems. Are we to assume Split System Air conditioner is not a complex system, and thus would not need to be commissioned?	The ductless split system does need to be commissioned, being part of the HVAC systems.
66	On Sheet P-102, it shows Sanitary Vent piping being installed inside Elevator Machine (001A) that does not serve Elevator Machine (001A) or Elev (001). Please confirm this piping is allowed per Maine Elevator Code.	Sanitary line is to be installed within the stud wall cavity and not within the Elevator Machine Room. Applicable elevator code is ASME A17.1 as referenced in Specification 14 24 23.
67	Under (1B) Design Experience on page 12 of 63 of the solicitation, it is indicated that the DOR is to use the Attachment A for their Previous Experience however Attachment A is only for the Construction Experience. Please provide another attachment for the Designers Previous Experiences. thank you	Please refer to the revised Attachment A provided with Amendment 0004.

68	Please confirm if copies of the written, firm commitments with the small businesses are to be included with our proposal and in Factor 5. thank you	Offerors are not required to provide copies of their firm written commitment documents for each of the small business subcontractors identified on Attachment E, Small Business Participation Commitment Document (SBPCD). Please refer to the revised Attachment E provided with Amendment 0004.
69	Under Factor 1, Corporate Experience, Construction Experience it reads that projects submitted "shall have been completed within the previous seven (7) years of the proposal due date for this RFP. If discussions are required, the initial proposal submission date will be the date used to determine if projects were completed within the previous seven (7) years of the proposal due date of this RFP. and not any revised proposal due date." Please confirm that even if the proposal due date moves via Amendment, the original proposal due date listed on the RFP is the date used.	The due date of initial proposals, subject to any extensions issued via amendment, is the relevant date.
70	Factor 1, Corporate Experience requires the Construction Experience projects to be completed in the previous seven (7) years of the proposal due date for this RFP while the Design Experience requires design to be completed within the previous eight (8) years. Please confirm that the Construction Experience and Design Experience have different recency requirements versus both being 7 or 8 years.	Confirmed. Propose in accordance with the Solicitation.
71	Factor 1 Corporate Experience for Construction Experience reads that Construction Experience Project Data Sheets are not to exceed 4 single-sided pages, and the Design Experience Project Data Sheets are not to exceed 2 single-sided pages. Please confirm that the Construction and Design Project Data Sheet page limits are different and remain 4 single-sided pages for construction and 2 single-sided pages for design.	Confirmed. Propose in accordance with the Solicitation.
72	Factor 4, Schedule requires submission of the native (.xer) files with the proposal. These cannot be submitted via PIII. Please confirm that we are to email this file to the contracting officer.	Please refer to the changes included in Amendment 0004.
73	Factor 5, Small Business Utilization reads to submit Attachment D for each project submitted under Factor 1. Please confirm that this is for only the projects submitted under Construction Experience only.	Please refer to the changes included in Amendment 0004 and to the revised Attachment D provided with Amendment 0004.
74	Factor 6, Past Performance reads that if no completed CPARS is available a PPQ is to be submitted. Please confirm that a "completed" CPARS can be an Interim CPARS if the project is completed and used for its final intended purpose but a final CPARS is not yet available.	Confirmed. Interim CPARS are acceptable if the final is not yet available
75	The latest three complete fiscal year financial statements are required in the Price Volume. It reads "Offerors are not required to submit financial information as detailed in the price submission instructions via PIII. However, if this is the case, the submitted copies in the hard copy proposal must be received	Confirmed. Please refer to the changes included in Amendment 0004.

	no later than the established due date and time". Please confirm that hard copies are the Price and Non-Price proposals are not required.	
76	Section 00 21 00 says that "Proposals are to be submitted via the PEE Solicitation Module." When this solicitation is searched within PEE, it returns no results. Please confirm that this Solicitation is to be submitted via PEE and that the project page will be active at time of submittal.	The PEE link is now available and will remain available for proposal submission within the PEE Solicitation Module
77	For Design Experience it reads "Projects submitted for the DOR shall have had design completed within the previous eight (8) years of the proposal due date for this RFP. Please confirm that for Design Experience, only Design needs to be fully complete, and that construction can still be in progress.	Confirmed. Regarding projects submitted for design experience, only design needs to be fully complete, and construction can still be in progress.
78	In the Solicitation under [00 70 00] both FAR 52.225-9 - Buy American-Construction Materials and 52.225-11 Buy American-Construction Materials under Trade Agreements are incorporated by Full Text, but these are alternate clauses. Please confirm FAR 52.225-11 applies to the SEED Project Contract.	FAR 52.225-11 is incorporated and applies to the Seed Project.
79	Would you consider lowering th mininun of 1 project final; condtruction cost from \$50,000,000 to \$35,000,000 Our largest completed project to date had a final cost of \$34,194,441 this was N4008520C0025, DBB BQ 488, NAVALSUBMARINE BASE, NEW LONDON, CT which was awarded to us in May 15, 2020 we feel counting for the high increase costs in construction this same project if bid today would have a cost of way over \$50,000,000. This Building was 109,442 Gross SF this would be roughly \$330 per SF We are currently performing another Navy awarded in August 17, 2023 for \$36,246,142 this building is only 78,000 gross sf or roughly \$465 per SF these buildings are similar to each other. This would be an increase in SF costs of \$45 per sf for each of the 3 years between awards. So if I was to follow the \$45 increase per sf cost for 6 years it would be \$270 or a total of \$600 per sf so or 2020 project if bid today would be roughly \$65,000,000 We ask you to consider this as we would not be eligible to bid on this program without some consideration, we are currently working at PNSY and have finished other projects on that base and believe we are well liked by that construction office	Propose in accordance with the Solicitation.
80	The solicitation indicates that proposals are to be submitted via the PEE Solicitation Module. The solicitation cannot be found in PEE. Please confirm when the solicitation will be posted to PEE and if future amendments will be posted to PEE and/or SAM.gov.	The PEE link is now available and will remain available for proposal submission within the PEE Solicitation Module. All updates / amendments to the solicitation will be posted to SAM.gov.

81	An organized site visit is projected to be scheduled for the seed project and <i>"to be provided via amendment"</i> per the solicitation. Given the uncertainty of the site visit date and pending amendment, please consider extending the RFI closing period to be 3 business days following the date of the site visit to allow post site visit questions to be submitted.	Refer to Amendment 0003
82	Ref. Solicitation PPI Due Date: With the sitewalk scheduled for February 5, bidders and participating small businesses will need at least two weeks after the site visit to submit effective PPI. Currently the due date is February 6. Please extend the due date for PPI to accommodate the questions generated from the site visit.	Please refer to the changes included in Amendment 0004.
83	Ref. Solicitation Proposal Due Date: Due to the complexity of the seed project and the vastly differing corporate experience and past performance requirements, bidders must balance the complicated estimates with minor small business participation to date all with formulating the non-pricing factors. Also, there are important PPI still not answered that will change the pricing and schedule narrative. Please extend the proposal due date to April 7 to afford bidders the opportunity to gain more small business participation, assemble corporate experience and receive outstanding PPI responses to incorporate into the bid pricing.	Propose in accordance with the Solicitation.
84	Factor 3 Management Approach narrative is limited to only 4 pages. More space is warranted for the offeror to fully and effectively address the required four elements defined in item (i) and meet item (ii) basis of evaluation to demonstrate best value. As a reference, NAVFAC Solicitation N4008525R2507 (DB/DBB MACC MCI East AOR) allocates ten pages to address just three of the four elements required in this RFP, which affords ample space to fulfill each item. Will the Government follow the same approach by increasing the page count for the Factor 3 narrative from four pages to ten pages, allowing the offeror to effectively feature its management approach for this solicitation?	Please refer to the changes included in Amendment 0004.
85	(ii) Basis of Evaluation, para 2 states "An Offeror's narrative work plan that identifies risks for the seed project and provides potential mitigation solutions may be considered more favorably than those that do not." Should this statement be moved to the basis of evaluation for Factor 4, Schedule, where this topic applies? Please clarify.	Please refer to the changes included in Amendment 0004.
86	Box 1. in Attachment A requests the offeror to provide its DUNS Number for each Experience. The DUNS Number is no longer used. Other parts of the proposal require the offeror's Unique Entity Identifier (UEI), including the Executed SF1442. a) Will the Government replace "DUNS number" to "UEI" on	Please refer to the changes included in Amendment 0004.

	Attachment A? b) Shall the offeror enter the UEI instead of DUNS on Attachment A?	
87	RFP page 16 of 63, item 2., 3rd para/bullet states "To demonstrate maximum practicable participation of small businesses, identify (in terms of dollar value and percentage of the total contract value) the offeror's proposed small business participation." a) Please confirm that all dollars values and percentages detailed in Attachment E SBPCD, including Item 3.a) and Table on page 2 are based on a Total contract value (TCV)(including options) of \$4,000,000,000, which is the TCV of this solicitation. b) If the Attachment E SBPCD is required to be completed for the Seed Project value, then the contractor will only be able to provide accurate values if the Attachment E if it is due several days after the proposal is submitted. This practice is consistent with a variety of NAVFAC MACC and SIOP solicitations, such as NAVFAC Northwest N4425525RF014, RM25-4869 Seismic Repair Dry Dock 4, B704 PSNS, WA. Will the Government revise the due date such that the Factor 5 Attachment E SBPCD may be submitted within three business days after the main proposal due date?	a) Confirmed. b) Propose in accordance with the Solicitation.
88	a) Please confirm that all dollars values and percentages detailed in Attachment F Individual Small Business Subcontracting Plan, including Item 1.a) [Page 4 and Page 13] are based on a Total contract value (TCV)(including options) of \$4,000,000,000, which is the TCV of this solicitation. b) RFP Section 00 10 00 table indicates the MACC consists of a Three-Year Base Period (CLIN 0001) and two one-year Option Periods (Option Line Item 0002 and 0003). Please confirm the first five columns on Page 13 of Attachment F should be revised to Base Period 1 - Base Period 3, Option Period 1 - Option Period 2.	a.) Confirmed. b.) Please refer to the revised Attachment F included in Amendment 0004.
89	The deadline for submitting questions (6 February 2026) is only one day after the site visit. To provide offers to fully evaluate the site walk information for developing the technical solution and best value pricing, will the Government extend the deadline for pre-proposal inquiries to 20 February 2026, which leaves 14 days prior to the proposal due date?	Please refer to the changes included in Amendment 0004.
90	Will offerors be required to propose on every MACC Task Order?	No. Please refer to the changes included in Amendment 0004.
91	Congress recognized the unique financial risks faced by contractors working in locations with aged infrastructure and many unknown and unforeseen challenges when it included Section 2816 in the recently passed National Defense Authorization Act for Fiscal Year 2026. This section authorizes the use of Cost-Plus-Incentive-Fee (CPIF) contracts for certain	Propose in accordance with the Solicitation.

	military construction projects at all four public shipyards. This update has the effect of expanding the number of contractors allowed by their shareholders to bid on SIOP military construction projects, increasing competition and benefiting the Navy. Question: Would NAVFAC be amenable to including a CLIN allowing for CPIF contracts to be awarded under this MACC?	
92	Attachment A - Construction & Design Experience Project Data Sheets provided with the solicitation only include check boxes for Construction projects 1-5. Can the Government provide a revised Attachment A form that includes corresponding check boxes for projects submitted for Factor 1B – Design Experience?	Please refer to the revised Attachment A included with Amendment 0004.
93	Page 13 of the solicitation states that five years of safety data must be submitted: 2020, 2021, 2022, 2023, 2024. Should 2025 data also be submitted?	Propose in accordance with the Solicitation.
94	Line Item 3A on the pricing schedule shows a Government Estimated price of \$1,695,370. Please confirm this estimated price only accounts for procurement and installation of the new industrial equipment.	Confirmed. See PPI 119 response and see amended Price Schedule.
95	Amendment 0002 extended the Pre-Proposal Inquiry (PPI) deadline to 06 February 2026. We respectfully request that the PPI deadline be extended to 15 business days prior to the submission date for a revised date of 13 February 2026 to ensure that both the prime and subcontracting community has sufficient time to submit technical PPI's related to the Seed Project.	Please refer to the changes included in Amendment 0004.
96	Amendment 0003 included Site Walk Information instructing visitors needing passes to make an appointment at Pass & ID through the QLESS app. As many prime and subcontractors who plan to attend the Site Walk will not be local to Kittery and will be traveling in for the Site Walk and as there is extremely limited appointment availability on 4 February 2026 and the morning of 5 February 2026, please confirm there will be sufficient walk-in access to support the visitor pass needs of the Site Walk contractors the morning of 5 February 2026.	Offerors are responsible for compliance with the requirements detailed within Amendment 0003.
97	Will the Government please allow the use of an 11x17 size page for the presentation of the Factor 3 Organizational Chart?	Yes. Please refer to the changes included within Amendment 0007.
98	Please confirm that the Government is not expecting a full project schedule with the submission of Factor 4, and that a milestone schedule containing items A through E (on page 15) is sufficient.	Propose in accordance with the Solicitation.
99	FX400, note 11 states 8" incoming from underground supply but the drawing does not indicate how much of this piping is existing for reuse. Please confirm we are to cut at the nearest flange at the wall and start from that location.	The 8" pipe entering the building will be new. See sheet G-100 for approximate location of the start of the new pipe and refer to the exterior utility work outlined on CS101.

100	Please provide as-built drawings of the current fire protection system that requires removal.	There are no as-built drawings available. Entire existing sprinkler system will be demolished throughout the building under this contract per Fire Sprinkler Note 3 on FX001. Sheet FX001 is hereby amended, see continuation sheet.
101	Keynote 8 on Drawing AE102 states to refinish wood plank flooring per Option 8 but the limits of this keynote are unclear. Please provide a quantity for this work or clearly define the extent of the keynote.	Refer to amended sheet AE102 with dimensions.
102	Sign Type K Detail on AE131 calls for 12 signs associated with 12 Fire extinguishers on the project, but there are 14 fire extinguishers in the FFE plans. Please confirm the GC is to provide 14 fire extinguishers and 14 Type K signs.	Provide 15 fire extinguishers and associated type K signs. See amended FF&E Package and Sheet AE804.
103	Specification 104416 calls for surface mounted fire extinguisher cabinets where shown, but all fire extinguishers on the FFE plans are bracket mounted. Please confirm no Fire extinguisher cabinets are required.	Confirmed that fire extinguisher cabinets are not required. Section 10 44 16 is hereby amended to delete the requirement.
104	MD102: Under Keynotes, "CLIN002" is referenced. Per the new Price Schedule this is Option 1: FF&E. Please verify all work on this drawing sheet should fall under CLIN 01D. Please also see sheet MD106 where CLIN 002 is referenced.	Items indicated on MD102 and MD106 with CLIN 002 tags pertain to the existing industrial equipment removals included in CLIN 002. Items identified in construction documents as "CLIN 002" must be priced under item 1H in the Price Schedule. Refer to amended Price Schedule and amended sheets MD103, MD106, MD108, and MD109.
105	MP101: Keynote 1 appears under the Keynotes section with no text. Please provide the description for this keynote or confirm it is not used.	Sheet MP101 is hereby amended at Keynote 1 to read "LOCATE THERMOSTAT 48" ABOVE FINISHED FLOOR" and add appropriate keynote tags.
106	MP102: Keynote 7 appears under the Keynotes section with no text. Please provide the description for this keynote or confirm it is not used.	Sheet MP102 is hereby amended at keynote 7 to read "NOT USED".

107	MP107: Keynote 2 states that HWS/R piping is to be on stanchions secured to continuous structural channel rails running from HWS/R risers to Attic Unit Heater 3-1. The structural channel rail does not appear on the mechanical or structural sheets. Please provide a detail of this and show the structural channel on the plan.	Refer to amended drawings MP107, SF105, and SF506 for support detail information.
108	23 05 93-1.6 requires a Workmanship and performance warranty for the DALT and TAB system Work for 2 years and a Contractor installation warranty of 2 years. Please confirm "Contractor" in this case refers to the installing mechanical contractor.	The required 2-year installation Warranty is to be provided by the General Contractor.
109	The Schedule of Fire Protection Systems Inspections by FPQC Specialist after Specification 014500.0022 does not have boxes checked showing which tasks to perform. Please indicate which of these tasks are required inspections that the FPQC must provide.	Specification Section 01 45 00.00 22 is hereby amended for the checklist attachment to reflect the required actions.
110	Keynote 3 on SF102 says to reference notes on sheet G-003. Please confirm the correct reference is to sheet G-004A.	On Sheet SF102, Keynote 3 is hereby amended, deleting reference to "G-003". Replace to read "G-004A"
111	Keynote 3 on SF102 says "base bid on 60 lf of total crack repair between all (3) locations". However, there are 5 different locations where keynote 3 comes up on SF102. Please confirm that 60lf is still the correct qty to include in the base bid.	Bid per solicitation. There are only three locations tagged for "Keynotes" (3) showing new work, which is different from Existing Keynotes number (3) showing existing conditions.
112	Please confirm if quantities provided under "Approximate Masonry Restoration Quantities (Project Totals)" section on AE202 are the only items we are to include pricing on for exterior masonry repairs. Please confirm quantities provided on AE202 also include any patch/repair work required that are shown on AD201-AD203 as well.	Sheet AE202 is hereby amended to clarify that the quantities indicated under Approximate Masonry Restoration Quantities (Project Totals)" include masonry repairs on Sheets AE202-AE204. Additional quantities for work associated with removals per Removals Keynotes on sheets AD201 through AD203 are not included in the Approximate Masonry Restoration Quantities but must also be included in Base Bid pricing.
113	Rooms 201 and 206 show an existing beadboard ceiling but the Finish Schedule does not list any paint requirements. Please advise if we are to provide a P4 finish in these rooms similar to other rooms with existing beadboard ceiling.	Bid per solicitation. Per Keynote 5, Sheet AE704, " IN AREAS WHERE BEADBOARD CEILING HAS TRANSPARENT, CLEAR COAT FINISH, REMOVE DUST, DIRT OIL, AND GREASE, RINSE THOROUGHLY. [OPTION 8]" Most of the existing beadboard ceiling has

		been painted, but in areas where it hasn't (rooms 201 and 206) the original unpainted finish is to be preserved.
114	Section 014500.0022 Part 1.6 states that the FPQC cannot serve as the Special Inspector for fireproofing or firestopping which is not typical for NAVFAC projects. Please revise this section to allow the FPQC to serve these roles if they meet the qualifications for those inspections.	Bid per solicitation, Section 1.6.7.2 does not prohibit the FPQC from being the fire stopping inspector.
115	The Offeror has a strong history performing Department of Defense federal construction work, with primary experience in vertical construction projects. The Offeror is currently engaged in active DoD work within the region and is highly interested in competing for the referenced Multiple Award Construction Contract (MACC). The RFP solicitation includes resume and past performance requirements that reference work types such as wharf and dry dock construction, which are not services typically performed by all general contractors pursuing vertical construction work under this MACC. Please clarify whether an Offeror that does not meet the specific resume requirements associated with wharf and dry dock work would be eliminated from consideration for award under this MACC. The Offeror intends to pursue this MACC for vertical construction task orders and requests clarification to confirm eligibility and proposal expectations.	Propose in accordance with the Solicitation
116	Can additional geotechnical and boring information be provided? Based on the specification sections referenced, it seems additional information is available at it states: "The data are available for examination by prospective bidders in the office of the Contracting Officer." Additional information regarding the top of rock elevation is needed in order to understand the full scope of the micropiling requirements.	Drawings include the available Geotech and boring information. Specification 00 01 15 is hereby amended to delete paragraphs 1.3 BORING LOGS and 1.4 SUBSURFACE DATA.
117	Please see page SB401 Details A1, A2, B2, and C3. The steel pipe micropiles are called out to be galvanized but there is no reference to this in the specifications. What exactly is to be galvanized? Please provide clarification.	Sheet SB401 is hereby amended to delete the requirement to galvanize the steel casings since they are required to be designed with an extra 1/16-inch wall thickness to account for corrosion loss.
118	The price schedule (attachment T - Item 1AA) is indicating micropiles to be bid at 60 LF for 36 piles meaning each pile is less than 2ft in length. Is this correct?	The linear foot quantity of micropiles must be determined from the contract drawings based on the information provided (embedment length into ledge, height from the indicated ledge elevation to bottom of pile cap elevation, and embedment length into

		the pile cap). This total would be the base bid quantity to be carried in line item 1B. Line Item 1AA is no longer applicable. See updated Price Schedule.
119	Attachment T - Please advise if option 3A and 3B are flipped, and that the Government estimated price is for "...including installation of government procured and provided equipment and associated utilities.." and that the contractor is to provide an estimate for "...procurement/installation of new equipment..."	Item 3A must include provisions for the procurement and installation of new industrial equipment. Item 3B must include provisions for installation of government procured and existing industrial equipment as well as utilities associated with new and existing industrial equipment.
120	Please clarify if the roof being removed at the annex is ACM?	The Government's Hazardous Materials Survey Report, dated November 21, 2024, is included with the RFP documents and details the inspection, sampling, and testing of the Annex roof, which was conducted in accordance with MEDEP Chapter 425. Laboratory analysis of collected samples did not identify the presence of asbestos. For bidding purposes, the Annex roof shall be considered non-asbestos containing material. The Contractor remains responsible for all environmental sampling and work practices as required by the contract documents and all applicable regulations.
121	Sheet FA001 Note 9 notes that existing fire alarm system shall be maintained until the new fire alarm system has been installed, tested and accepted by NAVFAC Fire Protection Engineer and Engineer of Record. Since the building will be unoccupied during the course of the renovation, can this note be removed?	Sheet FA001 is hereby amended, revising Note 9 to read: "Provide NFPA 241 plan for fire alarm and fire protection measures during construction prior to the removal of existing systems"
122	Please confirm if this project is tax-exempt in the State of Maine?	Propose in accordance with the Solicitation. Offerors are responsible for their own compliance with any applicable taxes.
123	On the Equipment Removal Schedule 2 Sheet equipment tags Number 555 and 556 are listed as "Composite Pallets". Please	Items 556 and 557 on Sheet QD602 are identified as Composite Pallets. For bidding purposes assume removal

	list any materials or equipment on these pallets that will need to be removed and disposed of .	of pallets without additional equipment or materials.
124	Cold Formed Metal Framing is not specified as delegated design but requires specific drawing requirements. Will the CFMF shop drawings be required to be stamped by a PE and complete as a delegated design?	Requested information is within the documents. Price per solicitation. The cold-formed metal framing is not a delegated design. Shop drawings are required to be submitted to reflect the 05 40 00 structural cold-formed metal framing shown on the contract drawings but are not required to be stamped.
125	Metal panels are to be attached to existing structure. Please confirm all imposed loads by the metal panels onto the existing structure have been reviewed by the EOR and no further structural reinforcement of the existing structure is required.	Requested information is within the documents. Price per solicitation. The existing structure can support the imposed wind loads. No reinforcement of the existing steel framing is required, beyond the structural work shown in the documents for other purposes.
126	Please see key note #5 on HM102. Abatement and removal based on this directive is not quantifiable to an abatement contractor. In order for a complete bid a fixed quantity should be assumed. Can a quantity be provided to be included within the bid?	Requested information is within the documents. Price per solicitation. On sheet HM604 refer to schedule "SUMMARY OF ACM TO BE REMOVED" for quantities.
127	Drawing CS101 key note 22 identifies ductbank connection to AC801. Detail B4 - C502 depicts a general connection into the manhole. Has the existing conditions within the manhole been investigated? Can the new ductbank penetrations fit within this manhole. Is there existing infrastructure or racking that requires relocation to support the new infrastructure?	Requested information is within the documents. Price per solicitation. Existing manhole AC801 was investigated, and record documentation was reviewed to generate the elevations on Detail B4/C502. There is nothing on this manhole face that requires relocation.
128	Please clarify/ locate what exterior elements that contribute to base security, supervision, and access which must remain active.	Requested information is within the documents. Price per solicitation. Maintain access routes as indicated on Sheet G-006 as well as exterior site lighting unless otherwise provided by temporary security lighting that meets the requirements of the construction documents.

129	Pricing schedule items 1K, 1L, 1M, 1N, 1O, 1P, 1Q, 1R, 1S, 1T, 1X, 1Y, 1AA, 1BB, 1CC, 1DD, 1EE, 1FF, 1GG, identifies varies lines items with assigned quantities: 1) Will these items will be tracked as unit prices to the assigned quantities. 2) Shall the bid only include the quantities listed within the pricing schedule, or are these additional quantities, beyond what is identified in the documents? Please clarify the intention of the quantities and unit prices within the pricing sheet.	1. Yes, items 1K through 1GG will be tracked as unit prices. 2. These quantities as noted on updated drawings are for additional scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. See revised Price Schedule and revised sheets HM604, CS101, SD101, SD102, SF502, AE105, and AE704.
130	Please confirm if B-1 of the boring log located on B-001 represents the conditions where the micropiles are to be installed.	Refer to specification 31 63 29, paragraph 1.6, borings are representative of the area in which the boring was conducted and is not representative of other areas. Refer to the response to PPI 116 for additional rock/ledge information.
131	Att. S FFE Package and the Building 60 Equipment Schedule found on Q-601 do not align with each other. There are 27 “contractor purchased and installed equipment” but 25 are listed in Att. S. Items are missing on the equipment schedule that are in the Att. S file and vice versa. Please advise which list to follow when bidding out the contractor purchased and installed equipment.	•Provide (16) Cable Protector ramps as indicated in updated FF&E attachment. See updated Equipment Schedule Sheet Q601. •Provide (2) Haz Mat cabinets (MS108A) as indicated in updated Equipment schedule Q-601. See updated FF&E attachment. •Delete Equipment item SP103D as it is included with the purchase of the CNC Cutter (EQ105A). See updated Equipment schedule sheet Q-601. •Delete Equipment item WT100A. See updated FF&E attachment.
132	Drawing G004A - list CLIN's 001 - 004 and 11 option line items (1-11). Pricing schedule Attachment T does not seem to include CLIN 002-003. Please clarify and update the documents accordingly.	Sheets G-004A and G-004B are hereby amended. Refer to continuation sheet and updated Price Schedule.
133	Solicitation Amendment 0004, Section 00 21 00, Para 2.(a)(1) Price Submittal Requirements; Section 00 10 00 - CLIN Schedule; Attachment T - Price Schedule AMD 0004 Amendment 0004 states the offeror is required to submit a complete Price Proposal Form that includes completion of all	No pricing is required in section 00 10 00.

	contract line-item numbers (CLINs), and that pricing information is not required to be completed under Section 00 10 00. Amendment 0004 revised the descriptions for CLIN 0001 (Base Period), Option Line Item 0002 (Option Period One), and Option Line Item 0003 (Option Period Two) to identical language but removed the associated period dates. Attachment T (Price Schedule AMD 0004) only includes CLINs for the B60 seed project. Please clarify what pricing, if any, is required to be submitted for CLIN 0001, Option Line Item 0002, and Option Line Item 0003 under Section 00 10 00, given that Attachment T addresses only the seed project.	
134	Solicitation Amendment 0004; Attachment F - Individual Small Business Subcontracting Plan AMD 0004, Attachment 1. Attachment 1 of the Small Business Subcontracting Plan (Attachment F) requires a breakdown of subcontracting goals by Base Period, Option Period 1, and Option Period 2. Since this is an IDIQ contract with no guaranteed dollar values per period beyond the \$10,000 minimum guarantee, please clarify how offerors should complete the dollar values and percentage goals in Attachment 1 for each contract period. Should offerors estimate projected contract values per period, use the B60 seed project value for the Base Period and leave option periods blank, or apply another methodology?	Refer to PPI #46
135	Can the Government please provide a Geotechnical report for this project?	See PPI 116 response.
136	The solicitation states: Responsibility Determination Information - In order to be eligible for award, the offeror must be determined responsible in accordance with FAR Part 9, specifically 9.104-1, General Standards. FAR Part 9, 9.104-1 General Standards includes: To be determined responsible, a prospective contractor must- (a) Have adequate financial resources to perform the contract, or the ability to obtain them (see 9.104-3(a)); (b) Be able to comply with the required or proposed delivery or performance schedule, taking into consideration all existing commercial and governmental business commitments; (c) Have a satisfactory performance record (see 9.104-3 (b) and subpart 42.15). A prospective contractor shall not be determined responsible or nonresponsible solely on the basis of a lack of relevant performance history, except as provided in 9.104-2; (d) Have a satisfactory record of integrity and business ethics (for example, see subpart 42.15); (e) Have the necessary organization, experience, accounting and operational controls, and technical skills, or the ability to obtain them (including, as appropriate, such elements as production control procedures, property control systems, quality assurance measures, and safety programs applicable to materials to be produced or services to be performed by the prospective contractor and subcontractors). (See 9.104-3(a).) (f) Have the necessary production, construction, and technical equipment and facilities, or the ability to obtain them (see 9.104-3(a)); and	Confirmed.

	(g) Be otherwise qualified and eligible to receive an award under applicable laws and regulations (see also inverted domestic corporation prohibition at 9.108). Please confirm that a response to all items in FAR Part 9, 9.104-1 (a) - (g) are not required and that the Government only requires Offerors to provide items 1-5 listed in the solicitation.	
137	Factor 3, Management Approach, the solicitation submittal requirements include the Organizational Structure in both narrative and chart form. It is understood that Offeror shall detail the Organizational Structure for the overall MACC program. However, it is unclear if the Organizational Structure for the Seed project shall also be included. Please confirm the intent is for the Offeror to provide details on the Organizational Structure for the overall MACC program and not the Seed project.	Confirmed. See Amendment 0004.
138	The paragraph states that a bid bond is required to be submitted equal to 20% of the total price or \$3 million dollars, whichever is less. Please confirm that the bid bond is for the Seed project only and that no other security is required for the overall MACC program. Also, please confirm the intent is for a bid bond to be supplied as part of each individual task order of the program.	The bid bond is for the Seed project only. If required, the requirement for bid bonds will be delineated in the RFP for individual task orders.
139	The RFP specifies a 10-point font minimum for Factor 3, Management Approach, and Factor 4, Schedule. Will NAVFAC permit a smaller font size for graphics including the organizational structure chart, tables, and other graphic figures?	Offerors may use a smaller font size for graphics, including the organizational structure chart, tables, and other graphic features.
140	For Factor 2, the RFP specifies a limit of two single-sided pages for the Technical Approach to Safety Narrative. Please confirm whether the DART and TCR rates do not count toward the two page limit for Safety Technical Approach and can be provided on a separate sheet.	Confirmed.
141	Bid documents and Seed project do not provide any indication that PLA's are anticipated on any of the task orders for this MACC. Please confirm that is the intent for this project. Project approach, interest, and teaming are all predicated on status of PLA's for various pursuits, and the assumption would be that the requirements would be consistent on the entire MACC based on the indication in the RFP and the associated Seed project.	The inclusion of PLAs will be determined on a task order basis.
142	We request a follow up pre-bid meeting focused on what projects and task orders are anticipated under this MACC. This would help inform our approach to teaming, the seed project, and the overall program as a whole.	The Government does not intend to hold a pre-bid meeting. Propose in accordance with the Solicitation.
143	The Specification Table of Contents indicates that sections 23 23 00 and 23 81 29 are "(Under Development)". Section 23 23 00 was included in Att J, but Section 23 81 29 was not included. Please confirm that the provided version of Section 23 23 00 is the final version for this solicitation. Please provide the missing Section 23 81 29 or remove from the table of contents.	The specification section 23 23 00 included in the documents is the final version (and not "under development"). Specification Section 23 81 29 is not applicable and is hereby deleted. Refer to revisions to Specification Table of Contents.

144	In Attachment T of AMD 04, General Bid Note B states that Line Items 6 through 12 (Options 5 through 11) can be awarded up to 365 calendar days after contract award. Please confirm when Line Items 2 to 5 (Options 1 to 4) will be awarded relative to contract award.	Please refer to the revised attachment T included with Amendment 0009.
145	If the Government elects to exercise any options to this contract, will it be done at one time or will they be exercised individually prior to the 365 calendar days after contract award deadline.	Please refer to the revised attachment T included with Amendment 0009.
146	The current proposal due date aligns with other NAVFAC solicitations, which is hindering subcontractors and small business's ability to properly respond to each solicitation. We request a four week extension to the proposal due date to allow adequate time to respond to this solicitation.	Please refer to the revised proposal due date included in Amendment 0006.
147	Please provide additional site visit(s) to allow access to boring logs and subsurface data referenced as only available at the station in the office of the Contracting Officer. Please define a date and time, along with procedures to offer firms enough time to resurvey and regain site access.	See response to PPI 116.
148	Please define how the Government distinguishes "maximum practicable opportunity" in small business Factor 5 to clarify the basis of evaluation for Offeror's to potentially be rated higher.	The Government will evaluate proposals in accordance with the criteria established in the solicitation for Factor 5.
149	Under Small Business Factor 5, does exceeding the minimum small business participation requirement—when supported by a reasonable demonstration and commitment—constitute providing "maximum practicable opportunity" defined in the evaluation criteria?	The Government will evaluate proposals in accordance with the criteria established in the solicitation for Factor 5.
150	Will the Government provide current, approved photographs of the project (interior and exterior) to assist Offerors in accurately pricing the seed project?	No, propose based on documents provided with the Solicitation.
151	Given the complexity and magnitude of the seed project, will the Government adjust the proposal due date to ensure at least three weeks between the release of responses to RFIs and the proposal submission deadline, allowing Offerors sufficient time to incorporate clarifications into their proposals?	Please refer to the revised proposal due date included in Amendment 0006.
152	Given the extensive amount of equipment within the facility, will the Government provide current, approved photographs and a comprehensive list of all industrial equipment that contractors are required to remove for bidding purposes?	No. Photographs are not available. Price per solicitation.
153	Drawing FA001 Notes ask us for a complete new fire alarm/mass notification system but fire alarm floor plan drawings only show sprinkler supervision monitoring devices. Please advise us of the complete scope of work for the fire alarm/mass notification system. Are we to provide only what is shown on the floor plans? Are there existing-to-remain system components? Or is this a design-build project with	The scope of the fire alarm / mass notification includes all devices shown on the drawing and all devices required by the specification. The specification is a performance specification that requires the contractor to provide shop drawings

	respect to the fire alarm system? If design-build, does the contractor have to engage the services of a registered Fire Protection Engineer (FPE) to do the design work?	to be prepared by the fire alarm designer (NICET III or IV) and reviewed and stamped by the QFPE, who is required to be a licensed FPE. The entire existing fire alarm system is required to be removed as part of this project, however, portions of the fire alarm may be required to remain temporarily as part of an NFPA 241 plan for construction period fire safety. This plan is required to be developed by the contractor to address all fire safety concerns during the construction including the periods of time without a fully functioning fire alarm or sprinkler system.
154	Will building be occupied during the renovation?	No.
155	Request photos of the interior and exterior of the building.	Photographs will not be provided.
157	Drawing FA001 Notes ask us for a complete new fire alarm/mass notification system but fire alarm floor plan drawings only show sprinkler supervision monitoring devices. Please advise us of the complete scope of work for the fire alarm/mass notification system. Are we to provide only what is shown on the floor plans? Are there existing-to-remain system components?	See response to PPI 153.
158	Please provide domestic water and compressed air riser diagrams.	Riser diagrams for domestic water and the Compressed air piping are not available.
159	Specification 102113 includes Urinal Screens but none are shown on the plans. Please confirm no urinal screens are required on the project.	Confirmed, there are no urinal screens in the project.
160	No Exterior signage specifications were provided and none is shown on the plans. Please confirm no exterior signage is required on the project.	Confirmed, there is no exterior signage included in this project.

161	Custodial Closets 107 and 202 are shown on AE401 and AE402 to receive mop and broom holders but there is no such designation for Custodial M104. Please confirm M104 also receives a mop and broom holder.	Confirmed, provide mop and broom holder for Custodial M104. Sheet AE104 is hereby amended, see continuation sheet.
162	The Toilet Room Accessory Schedule on AE401 lists Solid Plastic Locker Benches but none are shown in enlarged bathroom plans or locker room. Please confirm locker benches are not required on the project.	Confirmed, locker benches are not required on this project.
164	Specification 142423 Part 2.1.1.1.a calls for in-ground direct plunger type elevator. This design is no longer standard industry practice. Please confirm a holeless elevator type is an acceptable alternative.	A telescoping plunger is not permitted per UFC 3-490-06. Therefore given the travel distance and limited pit depth, a hole-less elevator would not work for B60.
165	Drawing Q-601 notes that equipment marked "NEW" is to be contractor purchased and installed. CLIN 3A on the Price Schedule shows a description of "procurement/installation of new equipment." Please confirm the equipment tagged "NEW" on Q-601 is included in this CLIN 3A item.	Confirmed. Refer to PPI response 119.
166	Drawing Q-601 notes that equipment marked "EXIST" is government relocated equipment to be contractor installed. Please confirm this work should be priced under CLIN 3B on the Price Schedule.	Confirmed. Refer to PPI response 119.
167	Please indicate the location where the contractor will take possession of the government relocated equipment that requires contractor installation.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of overhead door 101A.
168	Please confirm if the Government will allow for the 2025 filling cycle of Veterans' Employment and Training (VETS-4212), rather than the 2023/2024 filing cycle as stated in the RFP.	Confirmed. Please refer to the changes included in Amendment 0007.
169	Specifications Volume 1, Section 01 91 00.15 22 Total Building Commissioning, sub-section 1.1 states the the Government has hired an independent Commissioning Firm for this project. Could the Government please confirm that all commissioning elements as described in the 01 91 00.15 22 Total Building Commissioning as well as the 23 08 00 Commissioning of Mechanical and Plumbing Systems will be executed by the Government hired Commissioning Firm?	Commissioning is a process that must be accomplished as a Team. Commissioning activities required of each member of the Cx Team (including the KTR, the Government hired Cx provider, the DOR and the Government's technical representatives) are assigned in UFGS 01 91 00.15 22 Total Building Commissioning. The Contractor, and

		relevant subcontractors, are required to actively participate, support, and coordinate with the Government Cx provider to execute the Commissioning process.
171	Specifications Volume 2, Section 07 84 00.00 Firestopping, sub section 1.5.1 states that a single qualified installer/subcontractor is to be used for the entire project in regards to the firestopping work. For clarification, please confirm this single subcontractor requirement will be on all firestopping scope of work for all trades and their systems including but not limited to mechanical, electrical, plumbings, and drywall.	Confirmed. One company will do all fire stopping for the entire project.
172	On sheet P-104, keynote 4 shows the locations of the 3/8" Compressed Air Hose and Electrical Power Extension Chords from the Retractable Reels which will be supplied by equipment packages per keynote 3 on sheet P-106 at 9 locations. The drawings on sheet P-104 show two locations for the compressed air service/electrical power extension chords at multiple locations in shop 111. Could the Government confirm that a total of 9 drops are required for this associated equipment with a single air service and single electrical power extension at each piece of equipment, and that the intent is not to have a double compressed air service at each piece of equipment?	On sheet P-104, Keynote 4 is used to identify a total of nine (9) sets of compressed air hose reel / electrical power cord reel drops. Each pair of small circles with leaders from a keynote 4 tag represents one air service drop and one electrical service drop.
173	Detail B1/P-501 shows an expansion tank EXT-P1 for the electric water heater EWH-1. The expansion tank schedule located on sheet P-601 only shows EXT-P1 which is located in room Mech M106. The detail A3/P-601 doesn't show any expansion tank for EWH-2. Will EWH-2 and EWH-3 require expansion tanks?	Expansion tank is required for electric water heater EWH-2. Sheets P-401 and P-601 are hereby amended. Refer to continuation sheet.
174	Offerors are told to assume removal of 1,000 linear feet of copper cable between load center 4 vault and building 60 for bidding purposes. If a quantity of cable larger than the amount stated is determined to be removed, please confirm this will be considered as an unforeseen condition and treated as a change.	Propose in accordance with the solicitation.
175	Please confirm that Offerors are responsible for all costs associated with the delegated design of the lightning protection system.	Confirmed.
177	Will the Government be responsible for maintaining the utility markings throughout the contract period?	Requested information is within the documents. Price per solicitation. Refer to specification 01 35 26.00 22 for utility locating requirements

178	On the DDC architecture drawing, AHU-1 is shown as having a BACnet interface for a controller. Should it be assumed that the instrumentation is included with the AHU and the I&C contractor should exclude from their bid for procurement?	Requested information is within the documents. Price per solicitation.
179	DDC System architecture shows "Control Unit-xx" on the drawing. It is assumed that these are the control panels that are required on-site. Control Unit-02 thru Control Unit-04 indicate that the equipment that should be included is BCU-x/CH-x. There are no chillers on the control drawings so it is unclear what equipment should be tied to which control panel. Please clarify which equipment is to be tied to the control panel.	See updated drawing M-701 for typographical corrections for blower coil unit/condensing unit pairs.
180	Will the Government be open to other ground improvement methods if the design parameters are met?	Propose in accordance with the solicitation.
181	(Att. P. 01 45 35a) The document states: "< Designated Seismic Systems APPLY to this project." However, all DSS tables (Electrical, Mechanical/Plumbing, and Other) are marked "N/A," and the Final Walk Down Inspection section states: "< Does not apply – no Designated Seismic Systems." (1) Please confirm whether Designated Seismic Systems do or don't apply to this project. (2) If they do not apply, please revise the document to remove the contradictory "APPLY" statement for consistency.	The document referenced in this PPI does not state that Designated Seismic Systems APPLY to this project. As stated at the bottom of Page 2 of this document, Designated Seismic Systems does NOT apply. No changes to this document will be issued.
182	Please clarify whether the ductwork is to be lined per the General Note #2 or externally insulated per Keynote #9.	For ductwork that is indicated as lined and includes Keynote 9, provide lined insulation (see General Note 2) inside the ductwork for acoustic sound dampening, and provide insulation on the exterior of the ductwork for thermal isolation.
183	Please confirm that Line Item 1DD "Replace damaged wood strip flooring (2nd floor)" on the Price Schedule is pertaining to Note 10 on sheet AE105 for 300SF.	Refer to updated sheet AE105. Unit Price Item 1DD is for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. Scope associated with Note 10 on Sheet AE105 is to be

		included in Line Item 1B for architectural work.
184	Option Item 8 states "Price for providing work associated with Additional Finishes". Note 8 on sheet AE102 states to Refinish Wood Plank Flooring on the First Floor. Please clarify how much of Corridor 103 should be Refinished.	Refer to PPI 101 response
185	Please provide a Manufacturer Model/Type for the Wood Strip Flooring.	Wood strip flooring is existing to be refinished. See Room Finish Schedule Note 6.
186	Please clarify if one of the existing panels can be used for temp power during the construction phase.	Yes, provided the existing panel is in safe, operational condition, it may be used for temp power during the construction phase.
187	Drawing SB401 shows the locations where to install the micropiles. The Price Schedule Line Item 1AA is for 60 LF of micropiles. It is unclear if Line Item 1AA is to include the micropiles shown on SB401 or if Line Item 1AA is additional micropiles above and beyond SB401. Please clarify if the micropiles shown on SB401 are to be included within Line Item 1AA or Line Item 1B (Structural/Architectural) on the Price Schedule.	Please refer to response provided for PPI 118.
188	Drawing SB401 shows the locations of where to install the micropiles. The Price Schedule Line Item 1CC is for 4 CY of drilling spoils generated with micropile installation. It is unclear if Line Item 1CC is to include the drilling spoils of micropiles shown on SB401 or if Line Item 1CC is additional drilling spoils of micropiles above and beyond SB401. Please clarify if the drilling spoils of micropiles shown on SB401 are to be included within Line Item 1CC or Line Item 1B (Structural/Architectural) on the Price Schedule.	The cubic yard quantity of drilling spoils must be determined from the contract drawings based on the information provided. This total must be the quantity included in Line Item 1B. The unit price (Line Item 1CC) is no longer applicable. Refer to updated Price Schedule.
189	Line Item 1Z on the Price Schedule Form is to provide a price for 1 Day of the Industrial Hygienist. Please clarify if Line Item 1Z is for Industrial Hygienist costs in addition to what is required in other Base Bid Line Items 1H & 1I.	Unit Price Item 1Z is no longer applicable. Refer to updated Price Schedule.
190	Please confirm that Line Item 1H on the Price Schedule is to include all scope identified as CLIN 002 on the drawings.	Confirmed. Refer to revised Price Schedule

191	Please confirm that Line Item 1I on the Price Schedule is to include all scope identified as CLIN 003 on the drawings.	Confirmed. Refer to revised Price Schedule
192	Please confirm that Line Item 1J on the Price Schedule is to include all scope identified as CLIN 004 on the drawings.	Confirmed. Refer to revised Price Schedule
193	Drawing AE622 states Bid Option 6 for the Window and Door Restoration. However, the Price Schedule states that Bid Option 6 is not applicable. Please confirm that all references to Bid Option 6 on AE622 should state Bid Option 5.	Confirmed. Sheet AE622 is hereby amended to reflect that the work is in "Bid Option 5".
194	Drawing AE704 identifies areas of existing wood bead board ceilings to be replaced on the 2nd Floor. On the Price Schedule form, Line Item 1EE is to provide a price to replace 120 SF of damaged wood bead board ceiling (2nd Floor). Please clarify if the wood bead board ceilings to be replaced on AE704 are to be included within Line Item 1EE or Line Item 1B (Structural/Architectural) on the Price Schedule.	The quantity indicated on drawings must be included in Line Item 1B. Unit Price Item 1EE is no longer applicable. See updated Price Schedule and sheet AE704.
195	Specification Section 01 11 00.00 22 1.3 states that the performance period is 608 days. However, the Amendment 0004 Price Schedule states the duration is 622 calendar days plus 40 days if Option 3 is exercised bringing a total duration to 662 calendar days. Please confirm that 662 days is the correct period of performance if all Options are exercised.	Performance Period is 622 Calendar days. If Option 3 is executed then the performance period would extend 40 calendar days, for a total of 662 calendar days. See amended Price Schedule. Confirmed. 662 calendar days is the correct period of performance if all Options are exercised.
196	On Drawing Q-601 Building 60 Equipment Schedule, it specifies many items as "NEW" to be Contractor Purchased and Installed Equipment. Please clarify that all equipment items listed as "NEW" are included within Line Item 3A (Option 2) Industrial Equipment FF&E.	Confirmed. See also response to PPI 119.
197	On Drawing Q-601 Building 60 Equipment Schedule, it specifies many items as "EXIST" to be Government Relocated Equipment, Contractor Installed. Please clarify that all equipment items listed as "EXIST" are included within Line Item 3B (Option 2) Industrial Equipment.	Confirmed. See also response to PPI 119.
198	Drawing Q-601 states that the Existing Equipment is located Off Site. Please clarify the current location of this Existing Equipment and the distance from Building 60.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of overhead door.

199	Line Item 1FF on the Price Schedule Form is to provide a price for 50 LF of Masonry Crack Repair. However, Drawing AE202 states to assume 30 LF of Crack Repair. (1) Please clarify the assumed quantity of Masonry Crack Repair to be included. (2) Please confirm that all Masonry Crack Repair is to be included in Line Item 1FF.	1. The quantity indicated on AE202 (30 LF) must be included in line item 1B. 2. Item 1FF quantities are indicated on updated sheet SF502 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation. Note that the repairs in 1FF should be for work similar to repairs indicated in detail C1/SF502.
200	Specification Section 01 30 00.00 22 1.6 states that the Environmental Manager may be combined with the QC Manager. However, Section 01 57 19.00 22 1.5.4 states the Environmental Manager cannot perform the duties of the Quality Control Manager. Please confirm that the QC Manager can also be the Environmental Manager.	Environmental manager cannot perform the duties of the Quality Control Manager. Specification section 01 30 00.00 22 section 1.6 is hereby amended: Delete "May be combined with the QC Manager" from the Environmental Manager Responsibility/Restrictions column.
201	Specification Section 01 78 00.00 22 3.2 makes reference to Record Drawings and Record Model deliverables. As customary on a Design-Bid-Build delivery model, please confirm the DOR will be producing the record drawings and record BIM model, utilizing Contractor's as-built drawings. Since the DOR owns the complete set of electronic drawings required to produce the record drawings/model (including all backgrounds and "add-ons" which are often proprietary information), having the DOR produce these documents would be the most practical and efficient method. Please confirm the DOR will be providing the record drawings and record model for this Design-Bid-Build project.	Contractor is responsible for producing the Record Drawings in accordance with Specification 01 78 00.00 22.
202	Please confirm that all construction activities on this project must be performed by U.S. citizens.	Confirmed
203	Line Item 1I on the Price Schedule Form states to provide the management/abatement and removal of hazardous materials (identified as 003). However, the drawings do not identify 003 scope. Please confirm if all abatement and removal of hazardous materials within the drawings is to be included within Line Item 1I.	Abatement and removal of hazardous material is to be included under line item 1I unless noted otherwise (refer to industrial equipment related hazardous material which will be included in line item 1H). Refer to revised Price Schedule.

204	Specification Section 23 05 48.00 40 1.2 states that within ten working days of Contract Award, submit equipment and performance data for vibration isolator systems. This timeframe of ten working days after Contract Award is extremely quick to provide this information. Please confirm that the vibrator isolator systems equipment and performance data do not need to be submitted within ten working days of Contract Award.	In Specification Section 23 05 48.00 40, Part 1.2, first sentence; Delete “Within ten working days of Contract Award,” and capitalize “submit” to read as follows: "Submit equipment and performance data for vibration isolation systems..."
205	Multiple items throughout the drawings indicate to be removed, salvaged, and stored for reinstallation. Please clarify if the Offeror is required to provide an onsite storage location for the items to be salvaged and reinstalled, or if the Government will provide a storage location.	On-site storage is required. Refer to specification 01 11 00.00 22 for additional information and salvage plan requirements.
206	Drawing HM604 identifies the removal of 3,300 SF of ACM Floor Tile. However, Line Item 1R on the Price Schedule Form provides a removal quantity of 50 SF of ACM floor tile and mastic. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1R quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1R quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
207	Drawing HM604 identifies the removal of ACM Brown Duct Sealant, Gray Sealant, and Black Sealant for a total of 140 LF. However, Line Item 1Q on the Price Schedule Form provides a removal quantity of 50 LF of ACM Sealants. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1Q quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1Q quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
208	Drawing HM604 identifies the removal of 1,000 LF of ACM Pipe Insulation. However, Line Item 1N on the Price Schedule Form provides a removal quantity of 50 LF of ACM Pipe Insulation. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1N quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1N quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
209	Drawing HM604 identifies the removal of ACM Unused Control Circuit Wiring. However, no quantities are provided. For bidding purposes, please provide a quantity of ACM unused Control Circuit Wiring that is to be removed.	On Sheet HM604 SUMMARY OF ACM TO BE REMOVED schedule, revise quantity for UNUSED CONTROL CIRCUIT WIRE to be 100LF.

210	Drawing HM604 identifies the removal of 1,400 SF of ACM Debris. However, Line Item 1S on the Price Schedule Form provides a removal quantity of 50 LF of ACM Debris. (1) Please clarify what quantity is to be included within the project scope. (2) Is the Line Item 1S quantity in addition to what is shown on the drawings?	1. The quantity indicated on drawings must be included under line item 1I. 2. Item 1S quantities are indicated on updated sheet HM604 and are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
211	Please confirm this project is not located within the Controlled Industrial Area (CIA).	Building 60 is not located within the CIA. Some communication routing work is located within the CIA.
212	Please confirm that all privately owned vehicles must park at the Jamaica Island Parking lot.	Confirmed per Specification 01 50 00.00 22, paragraph 1.7 EMPLOYEE PARKING PLAN.
213	Building 60 currently has a considerable amount of tools, material office supplies, FF&E, etc to support current operations. Since pictures were not allowed at the site visit, please confirm the Government will remove all items not shown on the drawings prior to construction starting.	See response to PPI 156
214	Please clarify what days and times heavy equipment delivery will be allowed to the project site.	Deliveries are to be scheduled during regular working hours except when approved by the Contracting Officer in accordance with Specification 01 14 00.00 22, paragraph 1.5 CONTRACTOR ACCESS AND USE OF PREMISES (PNSY) and paragraph 1.6 WORKING HOURS (PNSY).
215	Drawing G-006 identifies areas for Contractor construction staging and storage. Please clarify if there is another location for the Contractor's temporary construction office trailer.	No. Location of construction trailer/office must be coordinated with staging areas indicated or set up within Building 60.
216	(HM001; Drawings; 1. Haz. Survey) Can the collection of the additional samples A - E be done during two consecutive days or one mobilization, or will they need to be sequenced?	The Contractor is solely responsible for the sequencing and duration of all sampling activities. All sampling must be conducted in strict accordance with UFGS Sections 01 57 19, 02 82 00.00 22, and 02 83 00.00 22, as well as all applicable local, state, federal, and PNSY-specific instructions. The Contractor is responsible for submitting a sampling plan for approval that includes coordination with the government's representative/COR and to schedule the required government witnessing for each sampling event. Performing the sampling during two consecutive days or one mobilization will be dependent on the Contractor's approved plan and coordination efforts

217	(HM001; Drawings; 4. Haz. Survey) Can the collection of the additional 30 - 40 dust wipe samples A - E be done during two consecutive days or one mobilization, or will they need to be sequenced?	The Contractor is solely responsible for the sequencing and duration of all sampling activities. All sampling must be conducted in strict accordance with UFGS Sections 01 57 19 and 02 83 00.00 22, as well as all applicable local, state, federal, and PNSY-specific instructions. The Contractor is responsible for submitting a sampling plan for approval that includes coordination with the government's representative/COR and to schedule the required government witnessing for each sampling event. Performing the sampling during two consecutive days or one mobilization will be dependent on the Contractor's approved plan and coordination efforts.
218	Will the abatement of the loose and peeling paint require full containment?	The Government cannot dictate the contractor's means and methods. The specific level of containment and engineering controls is dependent on the paint mitigation activities proposed by the contractor. However, any chosen method must prevent the release of lead-containing dust, debris, and fumes from the immediate work area and comply with the strict performance requirements of UFGS Section 02 83 00.00 22, EM 385-1-1, and all applicable OSHA regulations (e.g., 29 CFR 1926.62, 1926.1126, & 1926.1127). The contractor is required to submit a detailed, site-specific LCC Compliance Plan outlining their proposed means, methods, and the engineering controls they will use to meet these performance standards. This plan requires review and approval by the Government's representative/COR before work can commence.
219	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	The requirement for post-mitigation clearance, including the conditions under which dust wipe sampling is mandatory, is governed by the performance criteria detailed in UFGS Section 02 83 00.00 22. The Contractor is responsible for including a detailed, site-specific clearance plan within their overall Lead Abatement Plan. This clearance

		plan must describe the methodology the contractor will use to demonstrate that the work area meets the cleanliness criteria outlined in the UFGS specification for the chosen abatement strategy. This plan is subject to Government approval before work begins.
220	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	Requirements for air sampling for work on asbestos-containing materials (ACM) are governed by UFGS Section 02 82 00.00 22 and MEDEP Chapter 425. If the contractor's chosen means and methods have the potential to render the ACM friable, then post-abatement final clearance air sampling is mandatory per MEDEP Chapter 425 before containment can be dismantled. The contractor's site-specific Work Plan, submitted for Government approval, must detail the full air sampling strategy (personal, area, and clearance) to ensure compliance
221	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	Dust wipe sampling for industrial equipment is not generally needed as long as a visual inspection of the cleaned equipment shows no accumulation of dust or debris. There are no clearance standards applicable in this situation. The litmus test is a visual inspection to ensure that the equipment can be taken out of the building without disseminating contaminated dust or debris in the process.
222	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures?	Post-mitigation dust wipe sampling is not required for equipment designated for disposal. The Contractor's approved LCC Compliance Plan must detail the decontamination procedure, which shall include a final visual inspection to ensure equipment is free of all visible dust and debris before being removed from the work area.
223	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI Question 218.
224	The Specification Section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and is not the latest version of this section. Is this version the applicable version to be utilized for this project?	No. Section 02 83 00 hereby amended, see continuation sheet.

225	Will the Government consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval?	Propose in accordance with the solicitation.
226	This seed project has considerable interest as demonstrated by the high turnout at the site walk. We are receiving a significant number of questions from subcontractors and vendors. There is a large volume of detailed information required to submit at the prime level. There are also several other Federal projects bidding in early March that are spreading resources thin at multiple levels of the supply chain. As the Government requires time to prepare detailed responses to all RFIs, adequate time is also needed for the contractors to integrate the RFI responses issued into our proposals and pricing to ensure best value compliant proposals with ample competition. As such, will the Government please extend the proposal due date by 4 weeks to April 3, 2026?	Refer to Amendment 0006.
227	To effectively and clearly present the offeror's organization for the broad range of the scope of this solicitation, will the Government please allow the organization chart to be placed on an 11x17 size sheet?	Refer to PPI #97.
228	Please confirm the elevator does not have a stop at the second floor mezzanine.	Confirmed. Elevator has three stops (first floor, first floor mezzanine, and second floor)
229	Detail A1 and A2 on sheet AE111 conflict; Detail A1 appears to show elevator opening slotted to the right side, while A2 shows a left side opening. Please confirm which detail to follow.	Both plan and section show door opening in same direction. Section A2 is looking back at interior of door.
230	Please confirm space above proposed elevator shaft is clear to top of roof deck.	Provide 1-HR shaft ceiling at top of elevator shaft, refer to keynote 9 on AE411.
232	Can Site Quality Control Manager dual hat as Environmental Manager?	No. Propose in accordance with the solicitation.
233	The RFP states the Contractor's Interior Designer must have "completed a program accredited by the Council for Interior Design Accreditation (CIDA) or equal accreditation program of academic training in Interior Design," in addition to attaining NCIDQ certification and applicable state licensure, certification, or registration. To ensure compliance and consistent evaluation of qualifications, what academic programs or accreditation bodies does the Government consider acceptable as an "equal accreditation program" to CIDA? Specifically, please confirm the below programs are considered	Provided that the Designer has passed the NCIDQ, programs listed are acceptable.

	acceptable, provided the Interior Designer has attained NCIDQ certification and state licensure, certification, or registration: * Interior Design or Interior Architecture degrees from institutions accredited by the National Association of Schools of Art and Design (NASAD); * Interior Design or Interior Architecture degrees from regionally accredited colleges or universities whose programs meet NCIDQ eligibility requirements; and/or * Other nationally or regionally accredited academic programs that support eligibility for NCIDQ certification.	
234	Is it permissible for the FF&E scope to be performed by a team of Interior Designers? One with the CIDA Design Accreditation and one with the NCIDQ certification.	Refer to Response for PPI #233
235	Specialty CEQ Package Requirements: The RFP states that the project “may also include a Specialty CEQ Package” and that, if required, the same requirements identified for the FF&E Package would apply, or as outlined by project-specific UFC or the requiring Agency. Please confirm there is no Specialty CEQ Package scope, and that there is no pricing, design, procurement, or installation of a Specialty CEQ Package associated with this solicitation. Otherwise, please identify the locations in the RFP or Price Schedule where it is defined and shall be incorporated.	Confirmed. There is no Specialty CEQ Package in the project.
237	Att. I) Specifications Volume 2, Section 12 00 01.00 20 - Furniture, Fixtures and Equipment (FF&E) Package, Page 514 of 543, ¶3.1.1 states: The FF&E or CEQ Concept Design Package submittal (approximately 35 percent), as prepared by the A/E's Interior Designer, was sufficiently developed to fully integrate with the building systems (e.g., electrical, mechanical) to include product sizes and communications, data, and electrical requirements. Given the seed project is defined as a Design-Bid-Build (DBB) procurement, and the AE 800-Series (FF&E) drawings, the Q-Series (Equipment) drawings and Att. S) FFE Package are stamped and sealed and identified as “FINAL SUBMISSION.” please confirm the referenced “approximately 35 percent” FF&E / CEQ Concept Design reflects the current and complete level of design for bidding purposes, such that no further design development by the Contractor is anticipated beyond standard coordination and submittal review.	Contractor is responsible for providing Interior Design services and completing the FF&E package design, procurement, installation, and related requirements in accordance with the specifications. See Spec section 12 00 01.00 20, Part 3 Execution, Paragraph 3.1.1 System Description: Contractor's Interior Design Services.
238	Please confirm the stamped and sealed AE 800-Series and Q-Series drawings represent the final contract documents for FF&E and equipment scope, including all required sizes,	The stamped and sealed AE800-Series and Q-Series drawings are not the final design. The Contractor must hire a different Interior Designer to

	utilities, communications, data, and electrical requirements necessary for procurement and installation.	validate the FF&E Concept Design Package requirements with the Activity or End User and NAVFAC Interior Designer and make any necessary revisions. Refer to project documents and bid per solicitation.
240	Att. I) Specifications Volume 2, Section 12 00 01.00 20 - Furniture, Fixtures and Equipment (FF&E) Package, Page 507 of 543. Is Section 12 00 01.00 20, Furniture, Fixtures, and Equipment (FF&E) intended to apply to the Option 2 Industrial Equipment scope of work as well? If not, please identify the specification section(s) that govern the Industrial Equipment requirements for Option 2.	Section 12 00 01.00 20, Furniture, Fixtures, and Equipment (FF&E) applies to the Option 2 Industrial Equipment scope of work as well
241	For Line Item 2, Option Item No. 1. Please confirm the Contractor is only required to provide the HAR percentage (%) and to calculate the corresponding HAR Subtotal and Total based on the Government Estimated Price for the FF&E scope.	Confirmed. Contractor must input HAR Subtotal and Total.
242	For Line Item 3A, Option Item No. 2. Please confirm the Contractor is only required to provide the HAR percentage (%) and to calculate the corresponding HAR Subtotal and Total based on the Government Estimated Price for the FF&E scope.	Confirmed. Contractor must input HAR Subtotal and Total.
243	Line Item 3B Option Item 2 states: ...for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities... It is unclear what specific equipment should be included in pricing for Line Item 3B as the same nomenclature, i.e. 'government procured and provided equipment' is not utilized in the provided drawings. Drawing Q-601, Equipment Schedule (Option 2), identifies the status of equipment as: NEW, EXIST, SHIPYARD. What Government procured and provided equipment is associated with Line Item 3B?	See response to PPI 119
244	Line Item 3B Option Item 2 states: ...for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities... It is unclear what scope or 'entire work' is to be included for the installation of government procured and provided equipment in the pricing for Line Item 3B. Which of the following specific scope elements (or add others) shall be included in the pricing for the installation of Government-procured and provided equipment under Line Item	See response to PPI 119. The list indicated in the question is an accurate general scope related to 3B work. Note 3A will only include the procurement and installation of "NEW" industrial equipment. See response to PPIs 119 and 254. List indicated is accurate general scope related to 3B work. Note 3A will only include the procurement and

	3B? *Equipment handling, off-loading, staging, and setting *Final placement, anchorage, and alignment *Electrical, mechanical, plumbing, controls, data, and other utility connections *Modifications to building systems or infrastructure required for installation *Testing, start-up, and coordination support *Any demolition, removals, or temporary work associated with installation	installation of "NEW" industrial equipment.
245	For Line Item 1G it states: Subtotal of Base Price for the entire Building Removals/Demolition work complete, in accordance with the drawings and specifications. Shall the scope associated with the QD "Equipment Removal Plans" be included in the pricing for Line Item 1G? If not, under which line item it should be priced?	Industrial equipment removal (work indicated as CLIN 002) must be included in line item 1H. See revised Price Schedule.
246	Please confirm all infrastructure and utility systems required to support the FF&E have been fully designed by the Designer of Record (DOR) for this Design-Bid-Build (DBB) seed project, including but not limited to: *Structural support and anchorage *Electrical power, grounding, and communications *Mechanical systems (HVAC, exhaust, process piping, etc.) *DDC/BAS/controls and related integration *Fire protection and life safety interfaces	Contractor design requirements are outlined in specification 12 00 01.00 20. Price per solicitation.
247	Please confirm the Contractor's responsibility is limited to installation and coordination in accordance with the contract documents, and that no additional design development or engineering coordination effort is required beyond standard construction coordination.	See response to PPI 246
248	Key Note 8. states: 8. PROVIDE FOR REMOVAL OF (3)-20 CY DUMPSTERS WORTH OF MISCELLANEOUS MATERIALS/ EQUIPMENT LEFT IN SPACE BEYOND THE EQUIPMENT INDICATED. Under which Line Item # shall this pricing be included?	Line item 1H
249	Key Note 1. states: PROVIDE UTILITIES FOR AND INSTALLATION OF INDUSTRIAL EQUIPMENT. SEE EQUIPMENT SCHEDULE ON SHEET Q-601. For this Design-Bid-Build (DBB) seed project, please confirm all infrastructure and utility systems required to support the industrial equipment have been fully designed by the Designer	Requested information is within the documents. Price per solicitation. See response to PPI 246

	of Record (DOR), including but not limited to: *Structural support and anchorage *Electrical power, grounding, and communications *Mechanical systems (HVAC, exhaust, process piping, etc.) *DDC/BAS/controls and related integration *Fire protection and life safety interfaces Please also confirm that the Contractor's responsibility is limited to installation and coordination in accordance with the contract documents, and that no additional design development or engineering coordination effort beyond standard construction coordination is required of the Contractor.	
251	(Att. M) This states: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLING THE INDUSTRIAL EQUIPMENT AS INDICATED AND IS RESPONSIBLE FOR COORDINATING THE RELOCATION OF EXISTING EQUIPMENT BY THE GOVERNMENT. Note 8. states: INSTALL EQUIPMENT STATUS MARKED "EXIST" (EQUIPMENT TO BE RELOCATED BY THE GOVERNMENT). Equip Schedule Remarks Notes, Note A. states: INSTALL EQUIPMENT AT FINAL LOCATION IN BUILDING 60. What is the intended extent of the Government-performed relocation of existing equipment? Please confirm the division of responsibility between the Government and the Contractor so that pricing and logistics assumptions may be aligned.	Government provided/relocated industrial equipment will be delivered to Building 60 outside of the west side overhead door. Contractor must coordinate the scheduling of this effort with the Contracting Officer. The Contractor will be responsible for final placement, installation, and coordination of testing.
252	(Att. M) Does the Government's relocation responsibility include moving the equipment to the final installed location shown on the drawings, or only to a temporary or intermediate location (e.g., building entrance, loading area)?	No. Refer to response to PPI 251
253	Will any equipment handling, rigging, internal movement, positioning, or setting in place be required to be performed by the Contractor following Government relocation?	Yes. Refer to response to PPI 251
254	Att. M)_Drawings_Volume_2a, Q-601, Equipment Schedule General Notes, Note 6. states: COORDINATE TESTING OF EXISTING EQUIPMENT TO BE RELOCATED TO CONFIRM WORKING CONDITION BEFORE AND AFTER RELOCATION. TESTS MUST BE WITNESSED BY SHOP REPRESENTATIVE AND COORDINATED WITH THE CONTRACTING OFFICER. The clarification is needed to	Government personnel will be responsible for the testing of the existing equipment before and after relocation. Contractor is responsible for coordinating and witnessing the testing.

	assist the offeror appropriately allocate scope, schedule, and pricing assumptions. Testing Responsibility: Who is responsible for performing the testing of the existing equipment before and after relocation (i.e., Government personnel, shop representative, equipment manufacturer/vendor, or the Contractor)? If the Contractor is expected to perform or subcontract the testing, please confirm the extent of this responsibility.	
255	Witnessing vs. Performing: Please confirm the Contractor is responsible for coordination and witnessing of testing, but not for executing the tests.	Confirmed. See response to PPI 254.
257	Att. _M_ Drawings_ Volume 2a, Q-601, Equipment Schedule General Notes, Note 6. states: COORDINATE TESTING OF EXISTING EQUIPMENT TO BE RELOCATED TO CONFIRM WORKING CONDITION BEFORE AND AFTER RELOCATION. TESTS MUST BE WITNESSED BY SHOP REPRESENTATIVE AND COORDINATED WITH THE CONTRACTING OFFICER The clarification is needed to assist the oferor in appropriately allocating scope, schedule, and pricing assumptions. Testing Responsibility: Who is responsible for performing the testing of the existing equipment before and after relocation (i.e., Government personnel, shop representative, equipment manufacturer/vendor, or the Contractor)? If the Contractor is expected to perform or subcontract the testing, please coeconfirm the extent of this responsibility.	See response to PPI 254.
258	Witnessing vs. Performing: Please confirm the Contractor's role is limited to coordination and witnessing of testing, and not for executing the tests.	See response to PPI 255
259	Maintenance Records: Please provide any existing equipment maintenance, service, or testing records available for review to establish baseline operating condition prior to relocation.	See response to PPI 226.
260	Paragraph 1.3.1.c. states that the FF&E Option Item must be awarded a minimum of six (6) months prior to the contract completion date to avoid schedule impacts, while Section 1.3b. identifies Option 2 – Industrial Equipment as having a 365-calendar-day onsite performance period, concurrent with the Base Bid. The clarification is requested to ensure consistent schedule logic and pricing assumptions.	1) Correct 2) No 3) Provide per solicitation

	How does the six-month minimum award timing requirement in paragraph c. apply to Option 2, given its defined 365-day concurrent performance period? Specifically, please confirm whether: 1. The six-month award timing requirement applies only to the FF&E option and not to Option 2 – Industrial Equipment; or 2. Option 2 is also subject to the six-month minimum award requirement; and 3. How proposers should align scheduling and pricing assumptions for Option 2 in the event the option is awarded later in the Base Bid period.	
261	The QD drawings are identified as “Equipment Removals.” However, the extent of the Contractor’s responsibility related to removal, disposal, and potential salvage is not clearly defined. The clarification is requested to ensure proper allocation of scope, logistics, and pricing assumptions. Is the Contractor responsible for the disposal of removed equipment?	Yes.
267	During the site visit, it was observed that the existing bridge crane on first floor level was obstructed by miscellaneous electrical conduits and piping. Will the Government remove obstacles in the path of bridge crane for contractor to gain access? Or is the contractor responsible for removing these items?	The contractor is responsible for removing these items.
268	Please confirm the contractor is not responsible for testing and certifying the bridge crane since the contractor is reusing the existing bridge crane provided with building.	Confirmed. Contractor will not be certifying or operating bridge cranes. Contractor must coordinate with the Contracting Officer to schedule the Government to relocate cranes.
269	Will electric and water utilities consumption cost for course of construction usage be provided at no cost to the General Contractor?	Refer to the changes included in Amendment 0009.
270	Detail A4 presents a Fire Alarm riser diagram with FA devices shown. There are no plans that show device locations within the building. Will fire alarm device layout drawings be provided?	See PPI 153 response.
274	Can the Contractor arrange the collection of the additional samples A. - E. during two consecutive days or one mobilization; or will they need to be sequenced ?	See response to PPI 216
275	Can the Contractor arrange the collection of the additional 30 - 40 dust wipe samples A. - E. during two consecutive days or one mobilization; or will they need to be sequenced?	See response to PPI 217

276	Are the pipes covered with asbestos insulation scheduled to be removed or stay?	Pipes covered with asbestos insulation are scheduled to be removed.
277	Will the abatement of the loose and peeling paint require full containment?	See response to PPI 218.
278	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	See response to PPI 219.
279	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	See response to 220.
280	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	See response to PPI 221.
281	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	See response to PPI 222.
282	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI 223.
283	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this latest version applicable for this project ?	See response to PPI 224.
284	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what documentation/plans need to be submitted for review and approval?	See response to PPI 225
285	Note 4 directs the contractor to remove the existing exterior receptacle servicing trailer #2 and salvage it. The "existing keynotes" instructs this receptacle is to remain and be reused. Which is the correct direction?	The existing receptacle is to be removed, salvaged, and reinstalled in a new location. Refer to Keynote 4, Sheet ED101 and Keynote 1, Sheet EP101. The existing duraline connection/cable is existing to remain and must be disconnected from the receptacle at its existing location and plugged back into the receptacle at its new location. Refer to Existing Keynote 2, Sheet ED101 and Keynote 4, EP501.
286	Shows the power feed to trailer #2 and there are notes that indicate we need to temporarily feed trailer #2 and trailer #1. Can you tell us where the existing feed to trailer #1 is shown on the drawings?	Refer to Keynote 2, Sheet ED102. Refer to transformer in Storage 104, Sheet ED102. Refer to Keynote 12, Sheet EP501.

287	Can the existing building service be utilized for temporary power to trailers 1 and 2?	Refer to Keynote 6, Sheet ES101 and Sheet G-008, Electrical
288	Can the existing building service be utilized for construction power?	Refer to Keynote 6, Sheet ES101 and Sheet G-008, Electrical
289	The electrical demolition drawings indicate that the equipment will be removed and only disconnect switches will be left behind for removal under this scope of work. Is this a correct understanding?	No. Refer to the General Sheet Notes on the electrical demolition sheets for a description of what needs to be removed, in addition to the disconnect switches.
290	Do the existing emergency lights contain lead acid batteries that will require special disposal?	Refer to General Hazardous Materials Notes 6 on G-004A.
291	Existing network connection and telephone punchdown blocks are located in a different room from the future networking room. Do the existing data and telephone connections enter through the new network room or will these connection points need to be modified?	Existing telephone enters through the new network room. [Base Bid] Network N does not enter through the new network room. Refer to Keynote 7, Sheet ET501. One fiber optic cable serving Network P does not enter through the new network room. Refer to Keynote 9, Sheet ET501. The new Network P cable, indicated via Keynote 13, Sheet ET501, will enter the new network room. [Option 11] The new Network N and Network P outside plant fiber optic cables will enter the new network room. Refer to Keynotes 16 & 17, Sheet ET501. For reference, the ductbank indicated at Keynote 8, Sheet ES101, between B59 & B60, enters the new network room.
292	On drawing ED105 Note 4 indicates we are to disconnect power to existing attic exhaust fans. There are 4 locations where we see this indicated. Is it a correct understanding that there are only four attic exhaust fans?	There are 4 fans indicated with Keynote 4, Sheet ED105 and 2 additional fans called out on Sheet ED105 as "EF-E" and "EF60-2", with the "remove line type" that must be removed, as well.
293	Note 3 indicates we are to perform fusion splices to a 6mm network P cable. How many fibers are involved and will require splicing? Can the owner provide a length of cable necessary to perform this splicing as the location within building 59 is not indicated on the plans?	Refer to Keynote 2, Sheet ET106, this is the room within Building 59 that contains the existing fiber that must be spliced. This sheet also indicates the proposed pathway through Building 59. Provide splice to all 6-

		strands of fiber. Additionally, refer to Keynote 13, Sheet ET501.
294	ES101 note 5 indicates network cables for network P and network N are rooted to building 59 from building 60. This note is connected to a duck bank that connects 2 manholes and does not appear to enter building 59 or 60. How do these network cables connect to the two buildings and what length of cable will be required to make this connection?	This ductbank enters both Building 59 and Building 60 via pits located within each building. The location of the pit within Building 59 is indicated by Existing Keynote 1, Sheet ET106. The location of the pit within Building 60 is indicated by Keynote 7, Sheet ET102. Between these two sheets, and Sheet ES101 the cable lengths can be determined.
295	Note #8 indicates to seal conduits. Can the government clarify what they are asking for at this location?	Refer to General Note 17, Sheet E-001. The interior of the existing ducts entering into the pits within Building 59 and 60 must be sealed after new cables are installed. The interior of conduits entering into Building 60 must also be sealed. Additionally, refer to Specification 33 71 02, 2.1.4 & 3.4.8.
297	Indicates a vertical fire rated chase will be required around the fire pump feeder. What rating should this chase have? Will the fire pump feeder be required to be fireproofed the length of its run back to the service?	The chase must be rated for 2-hours. Refer to Detail A4/AE501. Refer to Keynote 1, Sheet EP501 and Keynote 15, Sheet EP102. The concrete encased ductbank provides the required fire rating between the fire pump room and the service.
298	Indicates to provide a copper ground bar the length of the exterior wall as shown in detail A4 on drawing EP 502. The detail on drawing EP 502 shows individual ground bars but does not indicate a length or size. Is it the intent of the drawings that this should be a continuous copper ground bar or will individual ground bars at each piece of equipment with cable connections be acceptable?	Individual ground bars for each piece of equipment must be provided. A separate ground wire run from each ground bus must be provided back to the service ground ("star pattern"). Refer to amended sheet EP102
299	Must a separate ground wire be run from each ground buss back to the service ground or can the ground buss on each wall be chained together and a cable run back to the service ground?	A separate ground wire run from each ground bus must be provided back to the service ground ("star pattern").
301	Indicates we are to reuse one set of existing conductors to provide temporary power for trailers. Will the government be adjusting the trip setting on the circuit breaker feeding these conductors?	The contractor must coordinate with the Government and the contractor must adjust the trip settings.
302	Shows a floor box with both power and data contained within it. Will the government permit both power and data within the same enclosure or will separate boxes be required?	Refer to Detail A1/EP505, Note 12. Divided compartments for power and

		communications are permitted within one poke through enclosure.
303	In corridor 102 there are two motion sensors shown. Do these motion sensors control all of the lights in the space or just the lights in the general area of the motion sensor?	The two motion sensors control all of the lights in the space: the (6) Type D1 fixtures in Corridor 102 located between columns J and N.
304	In vestibule 101 there are two motion sensors do these control the individual lights adjacent to them or do they operate the entire space? If a single motion sensor in this space will covered the area can the number of motion sensors be reduced?	"The two motion sensors operate the entire space. Yes, if a single motion sensor can be shown to provide complete coverage of the space, one sensor is acceptable. Ceiling height and potential obstructions from coiling doors must be considered.
305	On the security and technology plans there are RFID device stations indicated. There does not appear to be a coordinating power outlet at this location. Will power be required for the RFID equipment? If so how will this equipment be powered?	No, power is not required. The RFID are POE (power over ethernet) devices.
306	At what height will the RFID device stations be located?	Refer to Detail B4/ET502, Detail Note 7.
307	At what height will the TV outlets for the data system be located?	Refer to Detail C1/ET502.
308	Is it a correct understanding according to detail C1 on drawing EY 501 that security is only provided on exterior doors and there are no interior security islands?	No, that is not correct. Refer to the second floor of Detail C1/EY501 and associated Sheet ET105.
309	Please identify the NAVFAC Interior Design Representative and the NAVFAC Industrial Design Representative (if applicable) who will be responsible for review, coordination, and approval of the FF&E and/or Industrial Equipment scope.	Contractor to price their scope of work in accordance with the solicitation inclusive of Government review where required by the specifications.
316	"The contract documents do not appear to provide sufficient specificity regarding demolition and restoration requirements associated with equipment removal and reinstallation. This clarification is requested to ensure proper scope allocation and alignment of pricing assumptions. Housekeeping Pad Demolition – Is demolition of existing housekeeping pads required as part of the equipment removal scope? If so, please identify the applicable locations and extent of demolition."	Pad/slab removals are indicated on structural drawings.
317	Slab Restoration Standard – Following equipment removal and/or pad demolition, what is the required slab restoration standard (e.g., flush patch repair, structural repair, finish restoration to match adjacent slab, or full-depth structural replacement)? Please identify the governing specification section, if applicable.	Refer to General note 7 on QD101 for treatment at anchorage locations.

318	“Reinstallation Materials and Criteria – For equipment reinstallation, please confirm responsibility for providing anchors, epoxy, grout, and required torque values. Additionally, please confirm whether anchorage details and torque specifications are to be provided by the Designer of Record (DOR), the OEM, or determined by the Contractor.”	Unless noted otherwise, anchorage is to be provided by the contractor in coordination with OEM requirements.
323	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 216.
324	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced?	See response to PPI 217.
325	Are the pipes covered with asbestos insulation scheduled to be removed or stay?	See response to PPI 276
326	Will the abatement of the loose and peeling paint require full containment?	See response to PPI 218.
327	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling?	See response to PPI 219.
328	Will the abatement of the loose and peeling asbestos containing paint require post air sampling?	See response to PPI 220.
329	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal?	See response to PPI 221.
330	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures?	See response to PPI 222.
331	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures?	See response to PPI 223.
332	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project?	See response to PPI 224.
333	Page 5 of section 01 11 00.00 22 states Contractor must provide commissioning specialist from a 3rd party. However, Part 1 General 1.1 Summary states “The Government has hired an independent Commissioning Firm.” Please advise on if the contractor should price commissioning.	Building Envelope Commissioning is a process that is conducted by the Commissioning Team, which includes the government's CxB as well as the KTR's testing and verification company. Specification 01 91 19 describes the KTR's requirements. 01 11 00.00 22 is hereby amended.
334	Section 01 57 19 22 1.5.4 - Does the Environmental Manager need to be on-site 100% of the time?	The Environmental Manager must provide the required oversight of applicable programs as dictated in the project specifications. The presence of the Environmental Manager on-site

		would depend on the construction activities on that particular workday/week.
335	Section 01 57 19 22 3.1.2 – Understood that Environmental plans (SWPPP, etc.) need stamped by a Maine PE, however, do inspections need carried out by a PE or can they be done by a qualified inspector?	Inspections should be completed by a qualified inspector per State - Maine Certification in Erosion Control Practices (01 57 19.00 22)
336	Can excavation, foundation and pipe spoils remain on site?	Refer to specification Section 31 00 00.00 22 paragraph 1.4. Reuse of excavated soil as backfill is allowed given project specifications are met. Excess soils need to be disposed of in accordance with project specifications.
337	Is the contractor required to have a cultural resource manager or will this be provided by the Government?	Cultural Resources Manager is a Government entity that the Contractor must coordinate with where indicated.
339	There is no requirement for the contractor to have a geotechnical engineer for the job however there is a requirement for the geotechnical engineer to be at the excavation meeting on site in specification section 01 30 00 – is a geotechnical engineer required of the contractor or is a testing agency enough?	Geotechnical engineer is required. Refer to specification Section 31 00 00.00 22 paragraph 1.6 for Quality Control requirements.
340	Specification 01 30 00.00 22 1.19.1 part f. Can follow-on partnering sessions be virtual?	No.
341	Will Contractor be required to provide a trailer for the government near the jobsite?	No.
342	Specification Section 01 91 00.15 3.1.3 refers to Design phase Commissioning Plan – this project is Design-Bid-Build and there is no design phase, please confirm.	Design Phase Commissioning is not the responsibility of the KTR. Specification 01 91 00.15 22 is hereby amended.
343	Would the government consider reducing the government review period to 7 days to facilitate full use of the period of performance?	No.
344	Should the contractor price commission separately for all options?	Contractor price each Line Item individually as applicable.
345	"Please provide latest geotechnical report for the project (boring logs previously provided in drawings)	Bid per solicitation. See response to PPI 116. Refer to unit price line items in the Price Schedule.
346	Will the government provide the radios for communicating with the fire department or will the contractor need to coordinate? If the contractor provides the radio for fire department and emergency services, who will program the radio?	The radio transmitter must be provided by the KTR. KTR to install

		and program the radio with GOV guidance.
348	Is there any additional laydown space that can be provided to the contractor for trailers?	No.
350	Option 06 is listed as not applicable in the specifications however, option 06 is listed on drawing AE622 Window and Door Restoration Schedule. This seems to be option 05. Please clarify	See response to PPI 193
351	Please clarify what industrial equipment needs replaced in base bid versus option 2	Industrial Equipment must be included is Option 2. Note that the "(OPTION 2)" tag in Sheet titles indicates entire sheet is considered part of that option unless noted otherwise.
352	Please clarify if the ½" compressed air branch service with isolation valve as seen on P-106 is part of the base bid or option 2	Compressed air branch connection requirements are part of the base bid.
353	P109 – Key Note 1 – is the government to assume this is not needed if Option 3 is not awarded?	P109 Keynote 1 identifies base bid requirements, regardless of whether the government awards Option 3 (radon exhaust fans).
354	Who is responsible for testing for elevated Radon levels?	The Contractor
355	Please indicate what mechanical equipment needs removed by the contractor and what will be removed by the government.	Unless noted otherwise all mechanical equipment indicated for removal must be removed by the Contractor.
356	Please confirm anything that cannot be lifted by 2 people will be removed by the government.	Unless noted otherwise all mechanical equipment indicated for removal must be removed by the Contractor.
357	Please send approved pictures of mechanical equipment to be moved so the contractors can properly price removals	Pictures are not available.
359	Are their fencing requirements for the laydown area?	Requested information is within the documents. Price per solicitation.
367	Are government trailers required on this project? If so, what are the contractor requirements?	No.
368	Are Office trailer 1 and Office trailer 2 currently occupied by NAVFAC, or can contractor use office trailers as field offices?	No. No.

369	The current submission timeline presents challenges in coordinating with specialty subcontractors and suppliers necessary to develop accurate and competitive pricing, Will the Government consider extending the proposal submission deadline by twenty-one (21) calendar days from current due date. We believe a modest extension would benefit the Government by increasing the quality and number of competitive proposals received, ultimately supporting best value to the Government.	Refer to Amendment 0006.
370	Does this note extend to Shop 119 and 120, or is it limited exclusively to 118?	Keynote extends to Shop 119. Add keynote 2 in room 119.
371	Where do the bridge crane wheel stop get relocated? What is the scope?	Existing Keynote 6 shows its existing location on the bridge crane. Keynote 6 with the text "(REVISED LOCATION)" is the new proposed location from the wheel stop. The Contractor must disconnect the crane wheel stop at its current location and re-attach it to the bridge crane rail in its new location. Price per solicitation.
372	Reference to "off-site equipment to building 60: 60 days". Coordinate construction schedule and sequence with the contracting officer for scheduling industrial equipment relocations. Duration is 60 days. What is being moved? Where is it being moved from? And, when will the equipment be ready to be relocated?	Contractor must inform Government when equipment delivery is desired and Government will deliver equipment indicated as EXIST from current locations to the overhead door at B60 within 60 days of request. Price per solicitation.
373	Par.1.3 states 608 calendar days. Solicitation Amd 0004 Factor 4 identifies 622 calendar days. Please identify the governing contract duration - 608 or 622 calendar days - and confirm whether a specification revision will be issued.	Refer to Amendment 0008. The correct duration is 622 days.
374	Tier 1 Infrastructure list referenced but not provided in bid documents. Provide the Tier 1 Shipyard Infrastructure list for the B60 project scope per Par.1.2(a), including all utilities, structures, and systems classified as Tier 1.	Refer to Amendment 004 documents.
375	Confirm whether finalized versions of Sections 23 23 00 and 23 81 29 will be issued by addendum prior to proposal due date, or whether bidders should price based on drawings only.	See response to PPI 143
377	GFE per Equipment (Q) sheets with 45 CD advance notification only. No Government delivery commitment or schedule provided. Cannot establish delivery dates for P6 schedule. Provide anticipated delivery dates or windows for all GFE industrial equipment identified on Equipment (Q) sheets.	See response to PPI 372
378	Option 9: Government may exercise within 365 days of award. 186 CD concurrent with base bid. Cannot schedule, procure materials, or reserve subcontractors without exercise date. Provide anticipated timeline for Option 9 exercise decision, and confirm whether late exercise extends base contract duration.	Refer to amended Price Schedule and amended specification 01 11 00.00 22. Government will exercise Option 9 within 90 days of award. Date of exercise does not extend base contract duration.

380	"SF105 General Note #1 states ""DO NOT STORE/STAGE MATERIAL ON ATTIC FLOOR FRAMING. PROVIDE TEMPORARY SHORING (WITH APPROVED ENGINEERED DESIGN) IF STORING/STAGING MATERIALS ON ATTIC FLOOR IS NECESSARY."" Based on the MEP work identified on P109, MH105, MP107, FX105, EP107, EL107, there will be permanent loads added to the attic. Please confirm no additional structural reinforcement is required for the new additional MEP loads and please confirm shoring is not required to install the permanent systems."	Requested information is within the documents. Price per solicitation.
381	Can you please provide the existing door hardware manufacturer?	Requested information is within the documents. Price per solicitation.
382	Section 01 91 00.15, paragraph 3.2.3.1.f requires the commissioning activities to include "Perform inspections, measurements, and testing of building envelope and roofing systems specified in Sections 07 42 13 METAL WALL PANELS and 07 42 63 METAL WALL PANEL ASSEMBLIES. In both of the referenced Sections the testing is specified as follows: "Leakage Tests: Finished application of metal wall panels are to be subject to inspection and test for leakage by request of the Contracting Officer, Architect/Engineer. Conduct inspection and tests at no cost to the Government." No test standard is included, and no scope of testing is identified. Please provide clarification.	Specification 01 91 00.15 22 is hereby amended. Refer to continuation sheet.
385	"Specification states ""Provide complete manufacturer's standard vision panels assembly consisting of clear acrylic glazing panels or fire-rated glass as required for the type door."" Drawing AE 601 - Door tags 101A and 101B for the overhead doors denotes ""N"" in the glazing column. Please confirm vision lites are not required for the overhead doors."	Confirmed - vision lites are not required
387	On drawing AD102, between grid lines K & J/ e4 & e6, it notes 1 - existing wood planks on concrete floor. The new finish plans (AE640), identify corridor 103 to have concrete floor.	There is an area of existing strip wood flooring, original to the building, which is to remain. Under option 8, it

	Please confirm the existing wood plank floor shall be removed in this location based on the proposed finish plans.	is to be refinished. It's location and quantity is delineated on revised sheet AE102. Refer to amendment 008.
389	For option 10, resinous flooring, please confirm resinous integral base is not required. Wall base would remain as indicated with the base bid option.	Integral resinous base is not required with resinous flooring. See finish schedule for specified wall base.
390	Details throughout this page identify "expansion joints". Do any of these conditions require firestopping and/ or be a fire rated assembly? Currently only detail A1 references firestopping.	Expansion joints must be smoke rated. Provide fire rated at locations indicated in details. Refer to updated sheets AE530 and AE531 and specification 07 95 00.
391	Specifications indicate wood siding, but not shown on drawings. Please indicate location.	Wood siding is not required on this project.
392	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	Refer to PPI 216.
293	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	Refer to PPI 217.
394	Are the pipes covered with asbestos insulation scheduled to be removed or stay	Refer to PPI 276.
395	Will the abatement of the loose and peeling paint require full containment	Refer to PPI 218.
396	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling	Refer to PPI 219.
397	Will the abatement of the loose and peeling asbestos containing paint require post air sampling	Refer to PPI 220.
398	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal	Refer to PPI 221.
399	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	Refer to PPI 222.
400	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures	Refer to PPI 223.
401	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project	Refer to PPI 224.

402	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval	Refer to PPI 225.
403	The price schedule states for line item 3A - "Subtotal of Option Item 2 for the entire work associated with Industrial Equipment: procurement/installation of new equipment (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3B and 4 - 12. " There is Government estimated price for this line item. For clarification, please confirm this estimated value is for all items listed as "New" on drawing Q-601.	Confirmed. See also response to PPI 119 and 244
404	The price schedule states for line item 3A - "Subtotal of Option Item 2 for the entire work associated with Industrial Equipment: procurement/installation of new equipment (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3B and 4 - 12. " There is Government estimated price for this line item. For clarification, clarify if this includes the final MEP connections to the equipment..	See response to PPIs 119 and 244
405	The price schedule states for line item 3B - "Subtotal of Option Item 2 for the entire work associated with industrial equipment, including installation of government procured and provided equipment and associated utilities (identified as Option Item 2), but excluding work provided described in Line Item 1 – 2, 3A and 4 - 12." There is no Government estimated price for this line item. For clarification, please clarify if this line item is to include all items listed as "EXIST" on drawing Q601.	See response to PPIs 119 and 244
408	Please confirm Option 5 in the price schedule / option is the same as Option 6 found on drawing page AE622.	See response to PPI 193

409	"Note 10 states ""ALL PIPING IN AREAS WITH SUSPENDED CEILINGS MUST BE CONCEALED ABOVE CEILINGS. ALL EXPOSED PIPE MUST BE PAINTED AND/OR LABELED IN ACCORDANCE WITH THE SPECIFICATION. ALL EXISTING PIPING THAT IS EXPOSED AND CURRENTLY NOT PAINTED, MUST BE PAINTED. ANY PIPING OBSERVED TO BE CORRODED THAT IS NOT IDENTIFIED FOR REPLACEMENT MUST BE BROUGHT TO THE ATTENTION OF THE CONTRACTING OFFICER. "" Please provide locations of existing piping that requires to be painted."	All existing pipe will be removed. Revise note 10 to read: "ALL PIPING IN AREAS WITH SUSPENDED CEILINGS MUST BE CONCEALED ABOVE CEILINGS. ALL EXPOSED PIPE MUST BE PAINTED AND/OR LABELED IN ACCORDANCE WITH THE SPECIFICATION."
410	Sheet FA001 Note 9 notes that existing fire alarm system shall be maintained until the new fire alarm system has been installed, tested and accepted by NAVFAC Fire Protection Engineer and Engineer of Record. Can the existing FA as-builts be provided?	The as-builts for the existing fire alarm system are not available. NFPA 241 requires KTR personnel to be notified during an emergency. This can be accomplished with a temporary FA system or using the existing FA system. The plan developed per NFPA 241 is required to be approved by the GOV. Also see response to PPI 121.
411	Specification 01 45 00.00 22 requires Fire Protection Quality Control Specialist (QFPE) to "perform construction surveillance in accordance with the Schedule of Fire Protection System Inspections." The schedule included at the end of this specification section does not appear to have been edited for this project (all boxes unchecked). Please clarify scope of QFPE responsibility.	See response to PPI 109
412	The Statement of Special Inspections included at the end of Specification 01 45 35.00 22 identifies project seismic design category (SDC) as C, for which ASCE 7 typically specifies seismic design for architectural, mechanical, and electrical components (including fire sprinkler systems). Bid drawing S-002 identifies SDC as B. Please verify SDC and confirm whether seismic design requirements apply.	Sheet S-002 incorrectly identifies the building Seismic Design Category. The correct Seismic Design Category (SDC) is "C".
413	Bid drawing FA001, General Note #9, requires existing fire alarm system to remain operational until new system is installed, tested, and accepted. G-007, Construction Sequence Strategy, indicates existing fire alarm system will be removed	See response to PPI 121

	before installation of new system. Please clarify extent to which existing fire alarm and fire sprinkler systems must remain operational during construction.	
414	FA-series bid drawings appear to generally omit fire alarm/mass notification system (FAMNS) notification appliance and initiating device layouts. FC 1-300-09N §7-11 requires design drawings to include this information. Please provide FAMNS device layouts to facilitate bidder cost estimates.	See response to PPI 153
415	Bid drawings FX001 and FX101 require fire sprinkler branch lines in “the annex” to be provided with threaded outlets for future ESFR sprinklers. Please specify maximum protection area and spacing of outlets (as determined by NFPA 13 Chapter 14) throughout annex.	10x10 spacing of 1-inch outlets.
417	Please identify all concealed spaces where fire sprinkler protection is required. For example, section A1 on bid drawing AE221 appears to depict an interstitial space between ACT system in rooms 209, 210, and 211, and combustible mezzanine structure above.	All combustible concealed spaces are required to be provided with upright sprinklers.
420	Bid drawing FX400 shows the 8-inch fire service main entering the building through an exterior wall then changing direction to the backflow preventer suction. Please confirm whether fire service main must be restrained against movement at this location, and provide details of restraint.	Backflow preventor will be relocated. Refer to attached FX400 drawing modification.
421	Specification 21 30 00 §2.4.4.5 requires a “suction pressure regulating valve” in the fire pump assembly. This valve doesn’t appear to be shown on bid drawings; please confirm requirement.	Not all valves are shown on the drawings. Suction pressure regulating valve is required.
422	Specification 21 30 00 §2.13 requires fire pump assembly “to permit flow meter to discharge to pump suction and to discharge through test header.” Bid drawing FX400 shows flow meter discharging to pump suction but not directly to test header. Please confirm whether any modifications are required to the flow meter and test header configurations shown on FX400.	The discharge from the flow meter must connect to the test header. Refer to revised sheet FX400.
423	Specification 28 31 76 §2.13.3 requires mass notification text signs to display “EVACUATE” or “ANNOUNCEMENT”; this paragraph also refers to “scrolling text displays”. Please confirm whether mass notification signs limited to “EVACUATE” and “ANNOUNCEMENT” displays are sufficient, or whether scrolling text displays are required.	28 31 76 §2.13.3.g requires the date and time to be displayed when in non-emergency status.
425	Factor 1, Corporate Experience, requires that projects submitted were completed within (7) years of the proposal date for construction experience. We request that the 7 year completion requirement be revised to 10 years.	Propose in accordance with the Solicitation.

426	In Attachment T issued with Amendment 0004, bid line item 3 (“Option Item No. 2...”) appears to function as an offset to the Government’s estimate for FF&E associated with bid line item 2 (“Option Item No. 1...”). For clarity and consistency, should bid line item 2 be renumbered as “2A” and bid line item 3 as “2B,” and should the description currently labeled “Option Item No. 2” be revised to “Option Item No. 1”? Please confirm whether NAVFAC intends a numbering correction or whether the line items should remain as issued.	Price per solicitation. Bid line item 2 should not be renumbered. Bid line item 3 should not be renumbered.
427	Will the Government permit offerors to include a separate Assumptions and Clarifications document as part of the proposal submission? Box 2 of the SF-1442 identifies this procurement as “Negotiated,” and paragraph 3.2 states that the Government reserves the right to conduct discussions “except clarifications as described in FAR 15.306(a).” We believe that providing a concise Assumptions and Clarifications document would assist the Government in its evaluation and bid-conditioning process. Please confirm whether submitting such a document would be acceptable and not render the proposal unacceptable.	Propose in accordance with the Solicitation.
428	Referring to Attachment T issued with Amendment 0004, the Government has populated certain cells with its own estimated values. Please confirm that offerors should enter the same values in those cells, and that the brackets are not intended to indicate that offerors should provide negative dollar amounts.	Offerors should use the Government estimates where provided. Brackets do not indicate negative dollar amounts.
429	Please confirm that Attachments E and F are intended to reflect projected SBE participation for the MACC scope, and that Attachment D is to document historical SBE performance. Accordingly, please verify that no SBE exhibit or attachment is required with the bid for the Seed project.	Propose in accordance with the Solicitation, Attachment instructions, and PPI response #46.
430	Please confirm the Seed project price is subject to federal, state, and local taxes pursuant to the cited FAR clause 52.229-3 Federal, State, and Local Taxes and it is NOT tax exempt.	Propose in accordance with the Solicitation. Offerors are responsible for their own compliance with any applicable taxes.
431	Please provide the geotechnical report.	See response to PPI 116
432	"Quantities discrepancy between the ""Summary of ACM identified"" and ""Summary ACM to be removed"". Please clarify & confirm the removal quantities for the items below: a. Ceiling textured surfacing: 13,500 sqft indentified / 400 sqft to be removed b. Transite Panels: 160 sqft indentified / 0 sqft to be removed"	Items will remain in place unless indicated or required to be removed by project scope. Bidder to account for removal of quantities indicated "to be removed". Refer also to additional quantities indicated in the Price Schedule for unit prices.
434	Please identify/provide the location/area that require seeding & landscape construction maintenance.	Construction staging and storage areas may require repairs if disturbed by Contractor operations. See sheets G-006.
435	Under Factor 1B - Design Experience, the solicitation states, "For the purpose of evaluating Design Experience, a project is defined as a complete design effort performed under a single task order or stand-alone contract or subcontract." Will the	No. Propose in accordance with the Solicitation.

	Government accept projects involving multiple phases (i.e., Preliminary Design Authority [PDA]/preliminary or conceptual design, final design, Post Construction Award Services [PCAS]) of the same project awarded across different task orders, as a single project?	
436	The Door Schedule indicates no glazing for doors 101A and 101B. Part 2.2.1.4 indicates that Coiling Overhead Doors are to be provided with the manufacturer's standard vision panels consisting of clear acrylic glazing panels or fire-rated glass. This conflicts with the Door Schedule notes. Are doors 101A and 101B to be supplied with vision panels and/or fire rated glass?	See response to PPI 385
438	Please provide photographs typical of flooring areas to be repaired per Key Notes 4 & 7 on drawing AE105.	Photographs are not available. Keynote 4 indicates an area where there is existing racquetball court flooring over an existing wood strip flooring. The racquetball court flooring is scheduled to be removed. The wood strip flooring is not intended for refinishing but needs to be prepared to receive carpet tile. Keynote 7 indicates areas where plywood has been fastened to existing wood strip flooring. The plywood is scheduled to be removed and wood strip flooring to be refinished.
440	There does not appear to be a waste receptacle included for the Expressing Rm 205. Please confirm this is correct.	A smaller waste receptacle is scheduled for that room in the FF&E package. See AE804.
441	Please confirm that there is no solid plastic locker bench item (J) included in the locker room or restrooms.	See response to PPI 162
443	Can the collection of the additional samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 216
444	Can the collection of the additional 30 - 40 dust wipe samples A. - E. be done during two consecutive days or one mobilization or will they need to be sequenced	See response to PPI 217
445	Are the pipes covered with asbestos insulation scheduled to be removed or stay	See response to PPI 276
446	Will the abatement of the loose and peeling paint require full containment	See response to PPI 218
447	Will the abatement of the loose and peeling paint require post LCC dust wipe sampling	See response to PPI 219
448	Will the abatement of the loose and peeling asbestos containing paint require post air sampling	See response to PPI 220.

449	Will heavy metals dust cleaning on equipment require dust wipe verification sampling prior to removal and disposal	See response to PPI 221.
450	Will brush/scrape paint removal on walls and architectural features require full negative pressure enclosures	See response to PPI 222.
451	Will brush/scrape paint removal on wood flooring require full negative pressure enclosures	See response to PPI 223
452	The specification section 02 83 00 Management of Lead, Cadmium, and Chromium (VI) is dated 10/23 and are not the latest version of this section. Is this version the applicable version to be utilized for this project	See response to PPI 224.
453	Will NAVFAC consider modifying the frequency of area air sampling for Chromium (IV) for large or long duration tasks and what needs to be submitted for review, consideration and approval	See response to PPI 225.
454	What area will be made available for material laydown outside the building? If possible, it would be convenient if the parking lot on the west side of the building could be used for storage.	Refer to sheet G-006 - SITE CONSTRAINTS AND REQUIREMENTS PLAN
456	There is a gantry crane inside the building running above the proposed micropiles. Will this crane be made available to move materials within the building?	No. Contractor will not be able to use bridge cranes.
457	Prior to mobilization for the drilled micropiles, will the entire slab within the working area be removed or will there only be localized removals at proposed footing locations?	The Contractor must determine the means and methods of installing the piles. The Contractor must coordinate this work with their subcontractors.
458	A minimum of 15' of headroom is required for low headroom micropiles. Please confirm this will be the case throughout the working area.	Yes, upon completion of the demolition of the existing north mezzanine.
460	Will photos be permitted during construction for record keeping purposes?	Refer to 01 14 00.00 22
462	Is there a plan for ventilation of equipment exhaust?	Equipment exhausting must comply with EM 385-1-1.
463	Due to the significant size and complexity of reference projects anticipated to be submitted under Factor 1B – Design Experience, can the Government increase the total allowable page count for each design project data sheet to no more than two (2) double-sided pages (or four (4) single-sided pages)? This will enable offerors to provide more details about relevant features, which will help reduce ambiguity during the review process.	Propose in accordance with the Solicitation.
465	The contract documents indicate rehabilitation of existing windows, doors, and masonry at B60; however, the contractor was prohibited from taking photographs during the site walk due to shipyard security restrictions. Please provide Government-approved photo documentation of existing conditions sufficient to evaluate and price the rehabilitation scope.	Pictures are not available. Provide repairs and restorations indicated on AE622 and window survey per Window and Door Repair and Restoration General Notes 5.

466	Specification section 14 24 23 part 2.4.4 indicates an “in-ground direct plunger type hydraulic elevator” is to be provided. Please confirm that a plunger type elevator is required	See response to PPI 164
470	General Note 12 on AE622 references 20 sashes stored in the attic. Are these sashes from B60 mechanical intrusions and can they be used to infill the same locations in 60W1C, 60W1F, 60W1G, 601SA, and 60PN1A that currently are missing sashes?	It is unclear where the window sashes were removed from and may not match sizes of missing sashes.
471	Removal keynote 3 on AD203 references Window grills to be removed referencing historic restoration requirements. Are these grills to be retained and restored for future use?	No. Metal grills are to be removed and disposed of.
472	Removal keynote 3 on AD203 references Window grills. Do the window sashes exist currently behind the metal grills?	Yes, unless noted otherwise
477	Please clarify Key Note 7 (PATCH AND REPAIR WOOD FLOOR WHERE PLYWOOD WAS REMOVED. REFINISH WOOD FLOOR.) on Drawing AE105. Does the wood floor refinishing extend beyond the limits of the plywood is removed? If so, please define.	There are currently sheets of plywood (see AD104 for locations) fastened to wood strip flooring (which is throughout the majority of the 2nd floor). Once the plywood is removed, the entirety of the wood strip flooring (including areas that had no plywood over it) is scheduled to be refinished.
478	Amendment 0004 revises Factor 3 – Management Approach and removes the statement regarding consideration of seed project risks and mitigation. Please confirm that Factor 3 is intended to address the offeror’s management approach for execution of the MACC overall, and not the seed project specifically.	Confirmed.
480	Can a press system be used for the domestic water system?	No.
481	Can a copper press system be used for the compressed air system?	No.
482	Can a press system be used for the heating hot water heating system?	No.
483	Can type L copper piping be used for hot water heating system?	Yes.
484	Detail C1 on Drawing C-502 shows the bituminous concrete pavement detail and the limits are defined on CR-101 and CS-101. Please confirm the intent is to only remove the existing wear and binder courses in these areas, leaving the base course intact.	See detail C1/C-502 Note 1 for related requirements. Note that if the gravel beneath the pavement is disturbed or quality degraded due to construction activities 18” base course shall be installed. Also, see General Sheet Note 8 on sheets CR101 and CS101 for other related requirements. Price per solicitation.

486	KEYNOTE 2/SF104 - Option 7: Regarding recoating previously coated existing steel with (ASTM) A780 Cold Applied Galv Paint as indicated, the note indicates to remove loose and flaking paint. Is the intention to scrape loose paint from surface with hand tools or will power tool cleaning to SP11 or abrasive blast be required. Note: many of the high zinc coating manufacturers are likely to require there be no residual coatings and to provide abrasive blast surface prep, although a power tool clean to SP11 may be sufficient. Other products may be more surface tolerant than zincs and could be considered.	The SSPC surface preparation method must be in accordance with the cold-applied galvanizing paint manufacturer's requirements. Price per solicitation.
487	Spec 05 12 00 with regard to GC steel design responsibilities: a. Para 2.1 – SYSTEM DESCRIPTION notes "...including design...". Please confirm that no structural steel design is to be provided by the GC on the seed project?	Structural steel design is not required except for the items specified to be a delegated design (i.e. stair framing and railings). Price per solicitation.
488	Spec 05 12 00 with regard to GC steel design responsibilities: b. Para 3.2 – CONNECTIONS notes "Except as modified....design connections...". Connections appear to be designed in the contract drawings. Please confirm that no structural steel connection design is to be provided by the GC on the seed project?	Structural steel connection design is not required except for the items specified to be a delegated design (i.e. stair framing and railings connections).
490	Stair in C4/AE440 is identified as M110. In C1/AE442 this stair is identified as M107. Please clarify correct stair number.	Stair is for M110. Revise detail C1/AE442 title to read: "STAIR M110 SECTION"
491	Keynote 12/SF102 indicates stringers for Stair 002 and Stair M110 are to be C12s. Please provide stringer weight/LF, or member size to selected by designer?	The stringer size must be 12-inches deep, but the final stringer channel size will be determined by the delegated designer.
492	Stair 005 as shown in C3/SF101 and C1/SF504 indicates (2) stringers to be MC12x10.6. Does this stringer size apply to the others in Stair 005, or is member size to be selected by designer?	The stairs inside Fire Pump room M107 are not part of Stair 005. Stair 005 is outside of the Fire Pump room and is a delegated design. The stairs within the Fire Pump room have been designed as part of this project. Detail C1/SF504 is only applicable to the stair within the Fire Pump room.
494	Regarding Stair 004, Keynote 1/AE441 indicates to replace riser and patch hole in stringer. Please provide details for these repairs.	Detailing to match existing stair and is similar to A3/AE444.
495	Keynote 8/AE105 indicates to provide guardrails at existing windows. We noted that the (4) northmost windows along Grid e4 and the (1) eastmost window along Grid p appear to have guardrails drawn, but do not have a Keynote 8 note. Please clarify if these windows require guardrails.	Windows 60E2I, 60E2H, 60E2G, and 60E2F do not require the guardrails.
496	From AE104, section A1/AE223 is cut (near e6 from p to f). In that section where the MECH MEZZ (M110) is shown, it appears the guardrail (small amount shown behind equipment) is 4-line fall protection rail per D1/AE445. Please confirm that is the type of rail required around the unprotected edges of this mezzanine.	Confirmed. Refer to detail D1/AE445. Confirmed, railing is to be provided at unprotected edges. Refer to updated sheet AE104 for locations.
497	Are the guardrails provided for window protection (A4/AE626) and fall protection at Mechanical Mezzanines (D1/AE445) to be included as part the delegated design responsibility/scope for pans stairs, guardrail, handrail, etc.? If not, please provide	Yes, railings at mech mezz and window protection railings are to be included in delegated design.

	missing details for rail fabrication and installation (material, welds, fasteners, etc.).	
498	Is there a specific wage determination general decision applicable to the project?	Refer to Amendment 0007.
499	Please provide clarification on the scope of the Government's Independent Commissioning firm. The specification states that "The Government has hired an independent Commissioning Firm. This Section specifies the scope of work for the entire Commissioning Team which includes the scope of work for the Lead Commissioning Specialist, Commissioning Specialists, Designers of Record, Installing Contractors, and Equipment Suppliers." Are the CxC, CxS-M and CxS-E provided by the Government?	Lead Commissioning Specialist (CxC) and Technical Commissioning Specialists (CxM-H (HVAC), CxM-P (Plumbing), Cx-B (Building Envelope), and Cx-E (Electrical)) are hired by the government.
500	Please extend PPI deadline by 2-weeks to allow bidders sufficient time to address scope needing clarification. Again, the current proposal due date aligns with other NAVFAC solicitations, which is hindering subcontractors and small business's ability to properly respond to each solicitation.	Propose in accordance with the Solicitation. Please refer to Amendment 0006 for the revised proposal due date.
502	The specification states groundwater is estimated at "mean high water level" but subsequently mandates dewatering be planned for the "elevation of the highest tide." Drawing general notes indicate the highest observed tide is El. 8.1' while Mean Higher High Water is El. 4.2'. There is a 4-foot difference in hydraulic head between these two standards. Please clarify if the dewatering system design must account for continuous operations at Elevation 8.1' (Highest Tide) or if the system can be designed for Mean High Water with temporary suspension protocols during extreme tide events.	The elevations provided on the drawings are data points. The work may be phased with the tide cycles. Provide necessary controls required to manage dewatering activities required to complete the work within the specified contract time. Submit dewatering work plan prepared by a Professional Geotechnical Engineer licensed in the State of Maine.
503	Will rock removal be paid via a Unit Price schedule, or is the Contractor responsible for all rock removal as incidental to the Base Bid regardless of actual quantity encountered?	Contractor is responsible for calculating required rock removal based on information provided in documents and must be included in this quantity in the base bid CLIN 001 work. Item 1K quantities are for scope not otherwise indicated in the plans, specifications or reports provided with the solicitation.
504	Section 31 00 00.00 22 states "Testing results used for geotechnical analysis cannot also be used for waste characterization." Since the Government-provided environmental test results (Sheet B-005) identify contaminants (Arsenic, Lead, PAHs), can the Contractor rely on this data for bidding disposal costs, or must the Contractor carry the cost to re-sample and characterize 100% of the soil for off-site disposal prior to excavation?	Criteria for bidding is in specification section 31 00 00.00 22 paragraph 1.4. The tests provided are for bidding purposes. The Contractor is also required to provide testing of soils as indicated in specifications.
511	Solicitation Excerpt; Clause: "Prohibition on Contracting for Certain Telecommunications... (Huawei/ZTE)". ◦ Issue: The solicitation enforces FAR 52.204-24/25/26, strictly prohibiting equipment from Huawei, ZTE, Hytera, Hikvision, and Dahua. This project includes Option 4: Electronic Security Systems (ESS) and Option 11: Communication Service Routing.	Offerors are responsible for their own compliance with applicable clauses.

	◦ Inquiry: Given the ubiquity of chipset components from these manufacturers in "off-the-shelf" security cameras and communication devices, does the Government require the Contractor to provide "Representation" (proof of non-use) down to the internal chip/board level for all ESS and Comm equipment, or only for the end-unit manufacturer? This impacts the selection of the ESS integrator and equipment lead times.	
519	Drawing HM-001, General Hazardous Materials Note 1 requires the Contractor to inspect for "unidentified" materials and includes a requirement to collect and analyze a specific quantity of new samples (30 Asbestos, 10 PCB, 15 Heavy Metals, 10 TCLP). Question: General Hazardous Materials Note 1 on HM-001 requires the Contractor to perform a survey and include costs for additional sampling (30 Asbestos, 10 PCB, etc.). If this post-award survey identifies hazardous materials not currently shown on the HM drawings, how will the abatement of those newly discovered materials be paid? Should the Contractor carry a unit price allowance for abatement of unknown materials?	Results of post-award survey will be evaluated based on findings at that time. Unit Prices are included in the pricing sheet for anticipated hazardous materials. Price per solicitation.
639	Please identify the wage rate determination documentation for this project.	Propose in accordance with the Solicitation and Amendment 0007. Wage determinations under this IDIQ will be included at the task order level.
640	Please identify any labor agreements that may be in place or affect this project, in lieu of Davis Bacon wages / wage rate determinations.	Propose in accordance with the Solicitation and Amendment 0007.
642	Please distinguish the Buy American (BAA) or Build America Buy America (BABA) requirements for this project.	Propose in accordance with the Solicitation.
656	Please confirm if there is a minimum requirement of work to be self-performed by awarded GC.	Propose in accordance with the Solicitation.
657	Due to magnitude, critical scope and vast complexity of the project we requests that the due date for proposals be extended until 4/3/26 to give potential bidders a reasonable opportunity to respond to the RFP.	Refer to Amendment 0006.
658	Due to magnitude, critical scope and vast complexity of the project we requests that the due date for PPIs be extended until 3/20/26 to give potential bidders a reasonable opportunity to respond to the RFP.	Propose in accordance with the Solicitation.