


- A. REFER TO SHEETS E-001 THROUGH E-004 FOR ADDITIONAL ELECTRICAL INFORMATION.
- B. PROVIDE CLASS 1 LIGHTNING PROTECTION SYSTEM. PROVIDE #2/0AWG BARE COPPER CONDUCTOR WITH STRANDS NOT LESS THAN #17AWG FOR MAIN ROOF LPS AND DOWN CONDUCTORS.
- C. EXTERIOR CONDUCTORS WITHIN 8 FEET OF PAVEMENT MUST BE PROTECTED IN 1" SCHEDULE 80 PVC CONDUIT.

1. PROVIDE #2/0 AWG BARE COPPER GROUND LOOP CONDUCTOR INSTALLED AT APPROXIMATELY 3'-0" OUT FROM THE EXTERIOR WALL AT 36" BELOW GRADE.
2. PROVIDE GROUND ROD WITH TEST PIT ENCLOSURE WITH MECHANICAL HIGH STRENGTH CABLE CONNECTORS FOR SYSTEM TESTING.
3. BOND THE BUILDING REBAR TO SECONDARY GROUND LOOP WITH A #2/0 AWG BARE COPPER BONDING CONDUCTOR.
4. PROVIDE MAIN ROOF CONDUCTOR INTERCONNECTING THE AIR TERMINALS.
5. PROVIDE DOWN CONDUCTOR FROM AIR TERMINAL IN A 1" SCHEDULE 80 PVC CONDUIT DOWN TO 18" BELOW GRADE TO THE TEST WELL SHOWN ON THIS SHEET.
6. PROVIDE #2/0 AWG BARE COPPER BONDING CONDUCTOR FROM GROUND BAR TO SECONDARY GROUND LOOP.
7. NEC REQUIRED SERVICE GROUND ROD.
8. BOND PLUMBING VENT TO LPS.




APPROVED				AE INFO	
FOR COMMANDER NAVFAC					
ACTIVITY					
APPROVED BY LCDR ELIZABETH					
OLOKODE NAVFAC NLON FEAD					
DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE				05/27/2025	
ES	JHP	DRW	JHP	CHK	KB
WDM				SMS/CV	
BRANCH MANAGER				WF	
CHIEF ENGINEER				JV	
RE PROTECTION				HF	

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
MID-ATLANTIC
NAVAL SUBMARINE BASE NEW LONDON
GROTON, CONNECTICUT
NAVAL STATION - NORFOLK, VA
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

ELECTRICAL GROUNDING AND LIGHTNING PROTECTION PLAN

SCALE: AS NOTED			
PROJECT NO.:		1667770	
CONSTR. CONTR. NO.			
AVFAC DRAWING NO.		12894135	
SHEET	47	OF	65




A3 GROUND LEVEL - GROUNDING PLAN
1/4" = 1'-0"

A. REFER TO SHEETS E-001 THROUGH E-004 FOR ADDITIONAL ELECTRICAL INFORMATION.

B. REFER TO LIGHTING FIXTURE AND CONTROLS SCHEDULE ON SHEET E-703 FOR ADDITIONAL INFORMATION.

C. PROVIDE UNSWITCHED HOT LEG TO EXIT SIGNS.



1. PROVIDE PHOTOCCELL MOUNTED ON ROOF FACING NORTHERN SKY FOR CONTROL OF EXTERIOR WALLPACKS.
2. PROVIDE PHOTOCCELL MOUNTED ON ROOF FACING NORTHERN SKY FOR CONTROL OF MAGAZINE AREA POLE LIGHTS. REFER TO SITE PACKAGE FOR POLE LIGHT LOCATIONS AND LIGHTING CONTROL SEQUENCE OF OPERATION.



APPROVED			
FOR COMMANDER NAVFAC			
ACTIVITY			
APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT			
SUSPECTORY TO DATE		05/27/2025	
DES	JHP	DRW	JHP
PM/DM		CHK	KB
BRANCH MANAGER		SMS/CW	
CHIEF PROTECTION		WR	
FIRE PROTECTION		HPI	

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
 NAVAL SUBMARINE BASE NEW LONDON
 GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

SCALE:	AS NOTED		
EPROJECT NO.:	1667770		
CONSTR. CONTR. NO.			
NAVFAC DRAWING NO.	12894136		
SHEET	48	OF	65




GENERAL SHEET NOTES

A. REFER TO SHEETS E-001 THROUGH E-004 FOR ADDITIONAL ELECTRICAL INFORMATION.


B. REFER TO EQUIPMENT CONNECTION SCHEDULE ON THIS SHEET FOR ADDITIONAL CIRCUITING AND DISCONNECTING MEANS INFORMATION.

SHEET KEYNOTES

1. UNIT IS POWERED BY CORRESPONDING OUTDOOR UNIT. PROVIDE WIRING FROM OUTDOOR UNIT TO INDOOR UNIT AS RECOMMENDED BY EQUIPMENT MANUFACTURER. PROVIDE 30A NON-FUSED DISCONNECT SWITCH IN NEMA 1 ENCLOSURE.
2. PROVIDE JUNCTION BOX AND HARDWIRED CIRCUIT FOR SENSOR OPERATED CONTROLS FOR EVERY PLUMBING FIXTURE LOCATED IN RESTROOM.
3. PROVIDE 120V HARDWIRED CIRCUIT FOR ELECTRONIC TRAP PRIMER.
4. PROVIDE NEMA L6-30R FOR TELECOM RACK POWER. PROVIDE 2#10 + 1#10G IN 3/4".
5. PROVIDE 120V HARDWIRED CIRCUIT FOR SECURITY PANEL POWER.
6. SWITCHBOARD WIDTH MUST NOT EXCEED 6'-0".
7. PROVIDE RECEPTACLE FOR REMOTE WATER METER DISPLAY.
8. PROVIDE GENERATOR ANNUNCIATOR PANEL.
9. PROVIDE DEDICATED QUAD RECEPTACLE FOR TELECOM RACK POWER.
10. COORDINATE FINAL LOCATION OF MANUFACTURER PROVIDED DISCONNECT SWITCH. MAINTAIN NEC CLEARANCES.
11. COORDINATE FINAL LOCATION OF CEILING MOUNTED RECEPTACLE FOR ERV-1 WITH EQUIPMENT SUPPLIER.
12. LOCATE DISCONNECT SWITCH FOR DHWH-1 BELOW SINK.



A3 POWER PLAN
1/4" = 1'-0"



SWITCHBOARD: MDP

LOCATION: ELECTRICAL 003
SUPPLY FROM: T-UTILITY-SB
MOUNTING: Surface
ENCLOSURE: Type 1


VOLTAGE: 480/277V,3P,4W,60Hz
BUS AMPS: 1600A
MCB FRAME / MCB TRIP: 1600 A / 1600 A

INTERRUPTING RATING (kA SYMMETRICAL): 35 kA
GROUND BUS: EQUIP. ONLY
NEUTRAL BUS RATING: 100%
ACCESSORY LUGS: NONE

NOTES	LOAD CLASS	DESCRIPTIONS	FRAME	TRIP AMPS	POLES	CKT NO.	A	B	C	A	B	C	CKT NO.	POLES	TRIP AMPS	FRAME	DESCRIPTIONS	LOAD CLASS	NOTES
	Spare; LTG; REC;...	MDP-SB VIA ATS-1	1200 A	1200 A	3	1	288.076			24.833			2	3	125 A	200 A	BOX H MAGAZINE	Other	
3							284.129			24.833	4								
5								285.811			24.833	6							
	Other	BOX G#1 MAGAZINE	200 A	125 A	3	7	19.867			19.867			8	3	125 A	200 A	BOX G#2 MAGAZINE	Other	
9							19.867			19.867	10								
11								19.867			19.867	12							
	Other	EX. A113 MAGAZINE	100 A	70 A	2	13	5.67			11.2			14	3	150 A	225 A	EX. A114 MK-48 MAGAZINE	Other	
15							5.67			11.2	16								
17								0			11.2	18							
	--	SPARE	100 A	100 A	3	19	0			--			20	3	--	--	SPACE	--	
21							0			--	22								
23										--	24								
						25							26						
						27							28						
						29							30						

TOTAL CONNECTED LOAD / PHASE:				369.513 kVA	365.566 kVA	361.577 kVA				
LOAD CLASSIFICATIONS		CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND		TOTAL LOAD SUMMARY				
Other		238.64 kVA	100.00%	238.64 kVA		LOAD (kVA)		CURRENT (AMPS)		
LTG		2.992 kVA	100.00%	2.992 kVA		CONNECTED LOAD:		1096.656 kVA	CONNECTED CURRENT:	
REC		2.88 kVA	100.00%	2.88 kVA		ESTIMATED DEMAND LOAD:		957.979 kVA	1319.1 A	
EQC		15.194 kVA	100.00%	15.194 kVA		ESTIMATED DEMAND FACTOR:		87.35%	ESTIMATED DEMAND CURRENT:	
EQN		6.55 kVA	100.00%	6.55 kVA		SPARE CAPACITY:		15%	1152.3 A	
CLWS		830.4 kVA	83.30%	691.723 kVA						
						ESTIMATED LOAD WITH SPARE:		1101.676 kVA	ESTIMATED DEMAND CURRENT W/ SPARE:	
									1325 A	

6/20/2025 9:14:58 AM
\\b1c1v6s01\eng\p1\FDZ\EL628\TELECOM\BLOG-166770-T-101\SENTRY.rvt



5

GENERAL SHEET NOTES

- A REFER TO SHEET T-001 FOR TELECOM SYMBOLS AND ABBREVIATIONS.
- B BOND CABLE TRAY SECTIONS TOGETHER AND GROUND THE SYSTEM TO THE PBB/SBB.
- C ALL TELECOMMUNICATIONS RACKS AND/OR CABINETS MUST BE BONDED TO THE PBB/SBB
- D ALL TELECOMMUNICATIONS CONDUITS MUST BE BONDED TO THE PBB/SBB OR TO THE NEAREST CABLE TRAY OUTSIDE THE TR.
- E PROVIDE INFRASTRUCTURE FOR GOVERNMENT FURNISHED GOVERNMENT INSTALLED SECURITY INTRUSION DETECTION SYSTEM AND ACCESS CONTROL SYSTEM. PROVIDE JUNCTION BOXES AND CONDUIT WITH PULL STRINGS.
- F MAIN TAIN SEPARATION BETWEEN ALL CLASSIFIED AND UNCLASSIFIED CABLING IN ACCORDANCE WITH CNSSAM TEPMEST/1-13.

SHEET KEYNOTES

- 213 PROVIDE CATEGORY 6 WALL MOUNTED DATA OUTLETS FOR ESS EQUIPMENT. COORDINATE ROUGH IN HEIGHT WITH ESS PROVIDER.
- 577 PROVIDE DEDICATED 1 INCH CONDUIT FROM TELECOM RACK FOR CATEGORY 6 METERING CONNECTION. COORDINATE FINAL PLACEMENT WITH EQUIPMENT PRIOR TO ROUGH IN. INCLUDE PATCH CORDS AS NEEDED.



Jacobs

1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1600
FAX: 571.218.1600

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY APPROVED BY LCDR ELIZABETH
CLOKODE NAVFAC NLON FEAD
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES RR DRW RR CHK SA

PMIDM SMS/CWJ

BRANCH MANAGER WRB

CHIEF ENGINEER JWJ

FIRE PROTECTION HPN

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC

NAVAL STATION - NORFOLK, VA

NAVAL SUBMARINE BASE NEW LONDON

GROTON, CONNECTICUT

P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

SENTRY

TELECOMMUNICATIONS FLOOR PLAN

SCALE: AS NOTED

EPROJECT NO.: 1667770

CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894145

SHEET 57 OF 65

T-101

0 2' 4' 8' 12'

1/4" = 1'-0"




$$1/2'' = 1'-0''$$
$$1/2'' = 1'-0'$$


TELECOM ISO VIEW


T-401

A



A

6/20/2025 9:11:52 AM
\\bct1vso1\l6697\FDZ\EL628\TELE\BLOG-16677D-T-8M\SENTRY.rvt



B1 SECURITY FLOOR PLAN - OVERALL SENTRY BUILDING
1/4" = 1'-0"

GENERAL SHEET NOTES

1. REFER TO SHEET TY001 FOR SECURITY SYMBOLS AND ABBREVIATIONS
2. PROVIDE SEPERATE AND INDEPENDANT PATHWAYS FOR SECURITY CABLING.

SHEET KEYNOTES

- 672 WALL SPACE ALLOCATED FOR TELECOMMUNICATIONS AND SECURITY WIRING, TERMINATIONS AND EQUIPMENT. REFERENCE T-401 FOR ADDITIONAL INFORMATION.
- 673 PROVIDE NEW CCTV CAMERAS AND MOUNT FROM GUARD BOOTH TO SENTRY BUILDING B AND MOUNT AT 9-0 FT AFF. COORDINATE VIEW AND ANGLE WITH OWNER.




Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY: APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE: 05/27/2025					
DES	MG	DRW	LA	CHK	RR
PMIDM				SMS/CWJ	
BRANCH MANAGER				WRB	
CHIEF ENGINEER				JWJ	
FIRE PROTECTION				HPN	

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
SECURITY FLOOR PLAN

SCALE: AS NOTED	
EPROJECT NO.:	1667770
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	12894150
SHEET 63 OF 65	
TY101	

6/20/2025 9:11:54 AM
\\bcs1ty501\eng\proj\FDZE1628\TELEBLOG-166770-T-BIN\SENTRY.rvt



SYM	DESCRIPTION	DATE	APPR



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY					
APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE				05/27/2025	
DES	MG	DRW	LA	CHK	RR
PM/DM				SMS/CWJ	
BRANCH MANAGER				WRB	
CHIEF ENGINEER				JWJ	
FIRE PROTECTION				HPN	

DEPARTMENT OF THE NAVY	NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC	NAVAL STATION - NORFOLK, VA
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC	NAVAL SUBMARINE BASE NEW LONDON	GROTON, CONNECTICUT
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC	P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY	SENTRY
SCALE:	AS NOTED	
PROJECT NO.:	1667770	
CONSTR. CONTR. NO.		
NAVFAC DRAWING NO.	12894151	
SHEET	64	OF 65
TY501		

