

PERFORMANCE WORK STATEMENT (PWS)

FOR

UK-WIDE INTEGRATED WASTE MANAGEMENT SERVICES (IWMS)

14 January 2026

1.0 DESCRIPTION OF SERVICES. The Contractor shall provide all personnel, equipment, containers, tools, materials, vehicles, supervision, and other items and services necessary to perform the integrated waste management services (IWMS) described in this performance work statement (PWS) at U.S. Visiting Forces (USVF) locations across the United Kingdom (U.K.). IWMS consists of solid (to include recycling), non-hazardous and hazardous liquid waste collections and removal. As of the date of this PWS, USVF locations include Royal Air Force (RAF) Lakenheath, Feltwell, Mildenhall, Alconbury, Blenheim Crescent, Det 6, Croughton, Fairford, Molesworth and Welford. The Contractor shall perform to the standards in the contract, as well as all applicable United Kingdom laws and regulations, international agreements, Status of Forces Agreements (SOFA) and appropriate Final Governing Standards (FGS) or in their absence, the Overseas Environmental Baseline Guidance Document (OEBGD). Estimated workload factors can be found in Appendix A of this document. Collection areas can be found in Appendix B of this document.

The offer sheet will be submitted with the proposal. The pricing schedule will be filled out later with the awardee's information.

To minimize any decrease in service and to prevent possible negative impacts on additional services, the contractor shall have personnel on board during the 60-day Mobilization period. The Mobilization Period shall consist of providing the equipment and costs associated with getting both personnel and equipment in place to begin work at the start of the contract period of performance. The contractor shall also become familiar with performance requirements in order to become fully operational and assume complete contract responsibility on the contract start date. The Mobilization Period may include, but is not limited to, obtaining necessary clearances, hiring and training personnel, becoming familiar with work sites, meeting with Government staff members, acquiring equipment and transitioning with the outgoing contractor.

Service requirements outlined in this PWS apply to all USVF locations, unless otherwise specified.

1.1 COLLECTION REQUIREMENTS

1.1.1 Main Base

1.1.1.1 Municipal Solid Waste (MSW). The Contractor shall provide all containers. Contractor shall empty refuse containers in accordance with Appendix B. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the Contracting Officer's Representative

(COR) and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container. Site weights and Tip-Site Tickets shall be provided to the COR the next working day. A written description of the waste including the European Union List of Waste or European Waste Catalogue (EWC) code shall be provided when disposing of MSW that is treated, recovered, or separated for recycling or recovery.

1.1.1.1.1 UK Regulations – Waste Services. The Contractor shall perform all waste management services in accordance with (IAW) applicable UK regulations and governing standards. These include:

Table 1: Applicable Waste Management Regulations	
Regulation / Standard	Reference / Date
The Waste (England and Wales) Regulations	UK SI 2012/0811; amended by UK SI 2014/1771
Duty of Care Regulations	SI 1991/2839
The Environmental Protection Act	1990
The Separation of Waste (England) Regulations	2025 (Effective)
Final Governing Standards – United Kingdom, Chapter 15 (Solid Waste)	Jun-24
Final Governing Standards – United Kingdom, Chapter 16 (Hazardous Waste & Duty of Care Code of Practice)	Jun-24

1.1.1.1.2 Environmental Permitting Regulations. The Contractor shall demonstrate that all prime and subcontractor performing work is in possession of UK Environmental Agency (EA) permits and is registered with the EA public register to transport and dispose of all types of waste covered by this contract. The contract cannot be awarded to an organization that cannot demonstrate that they or their applicable partners or subcontractors are in possession of the relevant permits and licenses to operate. Permits for all facilities (e.g., Landfill sites, incinerators, material recovery, processing/treatment) for each type of waste covered by this contract shall be IAW UK's EA Standards. Copies shall be forwarded to each installation's Environmental Office no later than 5 working days prior to the start of the contract.

1.1.1.1.3 In-flight bladder relief device (Piddle Packs) – RAF Lakenheath. The Contractor shall provide all containers. The Contractor shall empty containers used to dispose of Air Crew

Piddle Packs in accordance with Appendix B in order to maintain a healthy and sanitary environment. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. This waste stream shall be removed by the Contractor to an offsite location for incineration. Piddle Pack containers and pickup schedule are identified in Appendix B. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day.

1.1.1.2 Food Waste. The Contractor shall provide containers for the collection of food waste. The contractor shall empty containers used to dispose of food waste as necessary to maintain a healthy, vector-free environment on days when the serviced facility is in operation. Food Waste containers and pickup days are identified in Appendix B. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. All containers shall be clearly labelled with the waste stream. A written description of the waste, including the EWC code shall be provided when disposing of MSW that has been treated, recovered, or separated for recycling or recovery. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR. Contaminated waste shall be treated and disposed of as general waste, with associated costs factored into the monthly line-item cost, at no additional cost to the Government.

1.1.1.2.1 International Food Waste (CAT 1). The contractor shall provide all containers for the collection of CAT 1 waste. CAT I waste streams shall be removed by the Contractor and transported to an offsite location authorized for CAT 1 incineration IAW UK and EU regulations. The Contractor shall supply each facility with the appropriate clearly marked containers specifically designated for the disposal of CAT 1 waste. Estimated workload factors and collection areas are identified in Appendix B. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR.

1.1.1.2.2 Food Waste Including Animal By-Products (CAT 3). The Contractor shall provide all containers for the collection of CAT 3 waste. CAT 3 waste shall be removed by the Contractor and transported to an offsite location authorized for CAT 3 disposal and processing IAW UK and EU regulations. The Contractor shall supply each facility with the appropriate clearly marked containers specifically designated for the disposal of CAT 3 waste. Estimated workload factors and collection areas are identified in Appendix B. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR.

1.1.1.3 Recycling - RAF Fairford / Welford. The Contractor shall supply appropriate containers to designated Recycling Areas at RAF Fairford and Welford for the collection of Dry Mixed Recycling (DMR), glass and bulk scrap wood. Recyclable materials include, but are not limited to, metal beverage containers, glass (clear, brown, green), office paper, newspaper, corrugated Fiberboard/cardboard/paperboard, plastics. Pickup shall be accomplished in accordance with Appendix B. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the Contracting Officer's Representative (COR) and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.1.4 RAF Blenheim Crescent DMR (Dry Mixed Recycling) Only. The Contractor shall provide all containers for the collection of DMR. The Contractor shall empty DMR containers based on the Appendix B. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the COR and Contractor shall monitor container fill capacities during the first 30 days of performance and one additional mutually agreed-upon within the same performance period. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.1.5 RAF Croughton Glass Bottle Bank. The Contractor shall be required to empty the glass bottle bank at RAF Croughton IAW Appendix B. The COR will request emptying, and the Contractor shall respond and complete collection within 5 working days of notification.

1.1.1.6 Sewage Screening/Rag. RAF Fairford. The Contractor shall supply appropriate watertight containers suitable for the collection of pretreated Sewage Screening/Rag. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and

CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the COR and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval.

1.1.2 MILITARY FAMILY HOUSING (MFH) COLLECTION REQUIREMENTS

1.1.2.1 Municipal Solid Waste. The Contractor shall provide all containers for each MFH domestic property. MSW containers to be placed at curbside by MFH occupants on scheduled pickup days. The Contractor shall provide containers which match the color of the local Council Authority where the installation is located and be clearly labelled to identify the waste stream. Pickup shall be accomplished IAW Appendix B. Initial vehicle routes and collection schedules shall be submitted to the COR no later than five calendar days prior to the start of contract performance. The Contractor shall be responsible for cleaning any spills, debris, etc. while collecting MSW at each location. Installations requiring MFH collections are RAF Alconbury, RAF Croughton, RAF Fairford Site weight tickets and Landfill site tip tickets shall be provided to the COR, no later than the next working day. A written description of the waste, including the EWC code shall be provided when disposing of MSW that has been treated, recovered, or separated for recycling or recovery. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.2.2 Food waste. The Contractor shall provide all containers for each MFH domestic property. Food waste containers will be placed at curbside by MFH occupants on scheduled pickup days. The Contractor shall provide containers which match the color of the local Council Authority where the installation is located and be clearly labelled to identify the waste stream. Pickup shall be accomplished IAW with Appendix B. Initial vehicle routes and collection schedules shall be submitted to the COR no later than five calendar days prior to the start of contract performance. Food Waste container location and pickup days are identified in Appendix B. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. A written description of the waste, including the EWC code shall be provided when disposing of food waste that has been treated, recovered, or separated for recycling or recovery. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.2.3 Recycling. The Contractor shall provide all containers for each MFH domestic property. Recycling containers will be placed at curbside by MFH occupants on scheduled pickup days. The Contractor shall provide containers which match the color of the local Council Authority where the installation is located and be clearly labelled to identify the waste stream. Pickup shall be accomplished IAW Appendix B. Initial vehicle routes and collection schedules shall be submitted to the COR no later than five calendar days prior to the start of contract performance. Recyclable materials include, but are not limited to, industrial scrap material, metal beverage containers, glass (clear, brown, green), office paper, newspaper, corrugated fiberboard/cardboard/paperboard, plastics, and rags/textile waste. The Contractor may request approval to recycle additional materials not listed above with prior coordination with the COR. All recyclable items shall be stored, transported and disposed of IAW with UK laws and regulations. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.2.4 Green Waste. The Contractor shall provide all containers for each MFH domestic property. Green waste containers will be placed at the curbside by MFH occupants on the scheduled pickup date. The Contractor shall provide containers which match the color of the local Council Authority where the installation is located and be clearly labelled to identify the waste stream. Pickups shall be accomplished IAW Appendix B. Initial vehicle routes and collection schedules shall be submitted to the COR no later than five calendar days prior to the start of contract performance. Green Waste will include, but is not limited to, grass, branches/twigs, leaves, flower cuttings, hedge trimmings, mulch, sod, dirt, small trees/shrubs and vegetable waste. Waste Transfer consignment notes shall be provided to the COR, no later than the next working day. Missed collections shall be recovered and collections performed no later than the next working day following notification from the CO or COR. When the Contractor completes service at a location, the Contractor shall ensure there is no litter, waste, or recyclable material on the ground within a 10-foot radius of the container.

1.1.2.5 Bulk Item Pickup – RESERVED.

1.1.3 OVER AND ABOVE REQUIREMENTS. The following services shall be separately priced IAW the cost contained in the Attachment 2 – Pricing Schedule. The Contractor shall be compensated IAW the price specified on the price schedule for the applicable period when these services are authorized by the CO. Over and Above services shall not be performed without prior written approval from the CO.

1.1.3.1 Unscheduled Pickup and Special Events. In addition to the regularly scheduled solid waste collections, the CO or COR may request the Contractor perform unscheduled collections and disposals. For unscheduled events, the Contractor shall respond within one business day of notification from the CO or COR. For special events, the Contractor shall also provide (or re-

position as directed) solid waste containers. These containers shall be placed in locations for a length of time designated by the CO or COR. The COR shall notify the Contractor in writing at least seven days in advance of the special event date. See Appendix A for workload data related to unscheduled and special event support.

1.1.3.2. Construction and Demolition Debris (C&D). When requested by the CO or COR, the Contractor shall provide containers for collection of C&D. The Contractor shall place containers at the designated site within one business day of notification by the CO or COR. The Contractor shall recycle or dispose of all C&D at a permitted recycling facility or permitted landfill IAW applicable UK and EU regulations. The Contractor shall provide weight tickets for all roll containers to the COR. A written description of the waste including the EWC code shall be provided when disposing of C&D that has been treated, recovered, or separated for recycling or recovery. Landfill site tip tickets shall be provided to the COR, no later than the next working day following disposal.

1.1.3.3 Public/Common Use MSW Receptacles – RESERVED.

1.1.3.4. Public/Common Use Recycling Receptacles – RESERVED.

1.1.3.5 Ash Collection – RESERVED.

1.1.3.6 Additional Pickups. In the event unusual conditions cause a container to require pickup before its scheduled service time, the CO or COR may request an additional pickup in writing. Upon receipt of a written request, the Contractor shall perform the pickup within 24 hours, and the Contractor shall be compensated at the unit rate specified in the Pricing Schedule, based on the container size.

1.1.3.7 Container Relocations. The CO or COR may request relocation of containers in writing, and the Contractor shall complete the relocation within 72 hours. Container relocations within the same installation shall be at no additional cost. Container locations beyond the installation perimeter shall be charged at the unit rate specified in the Pricing Schedule. The specific relocation site shall be designated by the CO or COR.

1.1.3.8 Additional Front-End Loading (FEL)/Waste Container Requirements. In addition to the data supplied in Appendix A, the Government may require additional FEL or waste containers to support any new facilities or meet increased service demand. The Contractor shall coordinate with the CO and COR to assess placement locations, service frequency, and integration into existing collection routes.

1.1.3.9 Bulk Glass Disposal. When requested by the CO or COR, the Contractor shall provide a bulk skip container for the collection and disposal of clean sheet glass, container glass, and approved furniture glass. The COR shall request the service on an ad hoc basis. The Contractor shall place the container at a designated site within one business day of notification and shall

ensure all collected glass is transported to an appropriate recycling facility. The Contractor must provide weight tickets for all bulk glass containers to the COR.

1.1.4 Inclement Weather Schedule. The Contractor shall continue to collect solid waste, and non-hazardous and hazardous liquid waste during periods of inclement weather. In cases of severe weather that create unsafe or impractical conditions for service, the CO or COR may authorize exceptions to normal collection requirements. When exceptions are granted, all missed collections shall be performed within 24 hours after the severe weather has terminated, unless otherwise authorized by the CO or COR.

1.1.5 Route Parameters. The Contractor shall propose collection routes for each service location and submit them to the COR for review and acceptance. Hours of access are between the hours of 0500 – 1700 Monday through Saturday. Collection outside these hours shall require prior coordination and written approval from the CO or COR. Escorted collection shall be IAW paragraph 4.7.4.2.

1.1.6 Points of Collection. Collection stations for MSW and recyclable materials are identified in Appendix A. The Contractor shall position bulk containers for customer ease of use in depositing MSW. The Contractor shall also position containers to minimize interference with adjacent parking areas, pavements, roadways, overhead utilities, trees, and other potential obstructions. Container placement shall also comply with any U.S. Air Forces Europe (USAFE) directives during periods of increased security, or as otherwise directed by the CO or COR.

1.1.7 Cubic Yard Capacity. Proposed capacity of containers is indicated in Appendix A. The Contractor is encouraged to recommend changes to the capacity of containers and/or pickup frequency that may improve the overall efficiency of MSW and recycling removal. All proposed changes shall be submitted in writing to the CO or COR. No changes shall be made until the proposed change is coordinated by the CO or COR.

1.1.8 Government-Approved Containers. Collection of MSW and recyclable materials in all non-residential areas shall be from Contractor-provided, CO or COR accepted containers. Containers shall meet the base architectural and appearance standards. The Contractor shall provide residential containers for RAF Croughton and RAF Alconbury housing area which match the color of the local Council Authority where the installation is located, and be clearly labelled to identify the waste stream

1.1.9 Maintaining Containers and Collection Area. The Contractor shall return all MSW and recycling containers to their original location after servicing, in an upright position with the lids securely in place (closed). The Contractor is responsible for cleaning up any spills, debris, etc., on the ground within ten feet of the container when servicing a location. The Contractor shall collect debris placed at collection stations; for example, tree branches, sacks, cartons, boxes, cans, tied bundles, or other containers. It is intended that most debris will be placed in containers. However, the Contractor shall notify the COR of locations where debris is frequently placed

outside of containers so the COR may notify facility managers and, if necessary, the Contractor can adjust the container size or pickup frequency with CO or COR approval. The Contractor shall also notify the COR if it is discovered that a particular receptacle is being utilized for the wrong material.

1.1.10 Vehicle Weighing. All vehicles used to collect MSW, C&D, organics and recyclable commodities shall be weighed on certified public scales/weight station, either on- or off-base or an onboard weight system. When use of off-base scales is the only option, a predetermined public certified scale/weight station will be identified for use. The COR may be present at the public scale for empty and loaded weighing with no notice to the Contractor. All weight discrepancies will be resolved prior to submission of monthly report. The Contractor and COR (if present) shall sign all weight tickets. The Contractor shall submit a monthly report (IAW para 1.7) that includes copies of all weight tickets and shall identify the disposed tonnage, disposal date, vehicle type and landfill tipping fee cost.

Weighbridge Locations:

- RAF Mildenhall – Weighbridge – Bldg. 599
- RAF Fairford – Weighbridge – Bldg. 56
- RAF Alconbury – Weighbridge – Bldg. 560

See Appendix B for further details

1.1.10.1 Locations with a Weigh Station. The Contractor is responsible for reporting accurate waste material weights. Weight tickets (empty and full) from Weighbridge Station will satisfy this requirement. If the collection vehicle is empty upon arrival at UK/US base, the Contractor may proceed onto the installation without first obtaining an empty weight. This is subject to verification by Government personnel upon request. Upon completion of the collection route, the Contractor shall proceed directly to the Weighbridge and obtain a full weight ticket. Should the Weighbridge Station be inoperable the Contractor shall notify the COR and receive approval to follow paragraph 1.1.10.2. Upon arrival on base, proceed directly to the on-base Weighbridge outlined above and obtain an empty/starting weight ticket. Upon completion of the route, proceed directly to the Weighbridge and obtain a full weight ticket.

1.1.10.2 Locations without a Weigh Station. The Contractor is responsible for reporting accurate waste material weights and providing a solution to weighing vehicles at locations without weighbridge stations. Any proposed solutions must be approved by the CO and COR. Calibrated, industry standard onboard weighing systems are authorized, but shall be fully operational from entering to exiting each installation. If using an onboard weighing system, the Contractor shall be required to provide current calibration certificates for each truck for their respective base, when requested by the COR. Upon departure from each installation, the Contractor must provide accurate weight details of all waste collected and compare them to the weight of their vehicles from when they entered the installation to departure weights and record times to ensure material weight accuracy.

1.1.11 Schedules. The Contractor shall establish initial vehicle routes and collection schedules upon contract award IAW Appendix B. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The only difference from this is for Military Family Housing (MFH) waste. For MFH, details on container size, routes, and pickup frequencies shall be submitted to the CO no later than five calendar days prior to start of contract performance. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the COR and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A.

1.2 RECYCLABLE MATERIALS PROCESSING – RESERVED

1.3 DISPOSAL

1.3.1 Off-Base MSW Disposal. The Contractor shall transport and dispose of all MSW at a permitted off-base disposal site. A copy of each landfill(s) operating permit that material is transported to shall be provided to the CO or COR for verification with the appropriate installation’s Environmental Office within ten calendar days of performance start. The Contractor shall transport separately collected MSW and non-hazardous Liquid waste (for recycling and/or reuse) recyclable commodities to an off-based material recovery facility (as required). A written description of the waste, including the EWC code shall be provided when disposing of MSW that has been treated, recovered, or separated for recycling or recovery. The Contractor is responsible for ensuring disposal is IAW existing UK regulations.

The Contractor shall also transport separately collected MSW, biosolids/sewage sludge, and non-hazardous liquid waste intended for recycling or reuse to an off-base material recovery facility, as required. Where pre-treatment is not feasible, these waste streams shall not be landfilled or incinerated, except in cases where landfilling or incineration results in the most environmentally friendly outcome IAW the waste management hierarchy.

1.3.1.1 UK Specific Regulations. The Contractor must perform services in accordance with the following regulations/codes/practices:

Table 2: Applicable Waste Management Regulations	
Regulation / Standard	Reference / Date
The Waste (England and Wales) Regulations	UK SI 2012/0811; amended by UK SI 2014/1771

Duty of Care Regulations	SI 1991/2839
The Environmental Protection Act	1990
The Separation of Waste (England) Regulations	2025 (Effective)
Final Governing Standards – United Kingdom, Chapter 15 (Solid Waste)	Jun-24
Final Governing Standards – United Kingdom, Chapter 16 (Hazardous Waste & Duty of Care Code of Practice)	Jun-24

1.3.1.2. Disposal of Non-marketable Materials. RESERVED

1.4 EQUIPMENT MAINTENANCE. The Contractor shall provide all containers which match the architectural and appearance standards of the base. Current base standards do not have a specific color scheme required for containers, only that they be uniform in color. For MFH housing, the containers shall match the color of the local Council Authority where the installation is located and be clearly labelled to identify the waste stream. Additional re-painting must match the approved color scheme. The Contractor shall maintain all containers ensuring they have a professional appearance and are free of unpleasant odors, dirt, debris, and pests. All containers must remain in good, workable condition, with no leaks. They must remain easily accessible to customers. The Contractor shall perform all cleaning, painting, repair, and other maintenance tasks of vehicles and equipment off-base. Equipment and vehicles shall be kept in good repair, free of odor, dirt, debris and pests, and shall not have any waste or equipment leaks such as oil or hydraulic fluid. Should any Contractor vehicles or equipment have any leaks, the Contractor is responsible for cleanup within 4 hours of the spill. When oil is leaked or spilt the Contractor shall contact the COR immediately.

1.5 LIQUID WASTE MANAGEMENT.

1.5.1 Description of Services. The Contractor shall provide cleaning, removal, transportation, and/or disposal of liquid waste (to include but not limited to sewage sludge, liquid sewage, fuel, oil, grease, waste water and/or any combination thereof) from sewage works, septic tanks, cesspits, lift stations, pumping stations, catch pits, oil water separators, fuel interceptors, sludge pits, silt pits, gullies, drainage channels, grease traps, scum wells, lagoon walls, maintenance facilities and any other catchment or disposal management facilities IAW applicable UK laws and regulations. The Contractor shall clean, empty, wash, transport, and/or remove/dispose of hazardous liquid waste. Hazardous and non-hazardous waste streams shall not be comingled.

1.5.1.1 Liquid Waste Transfer Notes and Reports. The Contractor shall provide waste transfer notes stating the nature and quantity of the material being removed, the relevant establishment Premise Code, and the applicable HW Consignment Code in respect to each load or part thereof before removal from each installation. The CO, COR, and/or respective installation's Environmental Office must sign each transfer note. The Contractor shall also provide abstract summaries of waste types disposed of on a Waste Material Notification

Schedule and reports monthly to the CO, COR, and/or each respective installation's Environmental Office no later than 10 business days from the end of the reporting month. Beginning in 2026, all waste streams shall be tracked electronically. The CO or COR will provide the Contractor with the email addresses required to receive the information.

1.5.1.2 Testing/Sampling/Analyzing. The Contractor shall schedule, coordinate, and collect testing, sampling, and/or analyzing of chemical content for each new liquid waste stream at each installation before emptying and transporting or disposal off base. Existing liquid waste streams should only need to be sampled if they change. Liquid waste streams which are treated, recovered, or separated for recycling/recovery require further sampling IAW UK and installation regulations. This is not necessary if being transported to on-Base treatment. The COR reserves the right to request random sampling semi-annually. The Contractor must respond to the COR's request within 2 business days and provide a sampling date to the CO, COR, and respective installation's Environmental Office 5 business days prior to the month being scheduled. The Contractor shall return all analytical results within 10 business days of the COR's original request to sample. Hazardous and non-hazardous waste shall not be co-mingled.

1.5.1.3 Schedules. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the COR and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A.

1.5.1.4 Emergency Collections. There may be occasions, to include but not limited to lift station failure, sewage treatment work shutdown, pump station failure, pipe breakages, mains water pipe breaks, and fuel spills where emergency liquid waste tasks IAW para 1.5.1 may be required from various locations on each UK/US RAF Installation on a 24/7 basis. The Contractor shall also provide to the CO the names and phone numbers of Contractor POCs for after business hours including nights, weekends, and holidays. The Contractor shall respond to the site within four hours of the notification from the CO or COR.

1.5.1.5 UK Regulations – Liquid Waste – The Contractor must perform services in accordance with the following regulations/codes/practices:

Table 3: Applicable Waste Management Regulations

Regulation / Standard	Reference / Date
The Waste (England and Wales) Regulations	UK SI 2012/0811; amended by UK SI 2014/1771
Duty of Care Regulations	SI 1991/2839
The Environmental Protection Act	1990
The Separation of Waste (England) Regulations	2025 (Effective)
Final Governing Standards – United Kingdom, Chapter 15 (Solid Waste)	Jun-24
Final Governing Standards – United Kingdom, Chapter 16 (Hazardous Waste & Duty of Care Code of Practice)	Jun-24

1.5.1.6 US Regulations – Liquid Waste – The Contractor must perform services in accordance with the following regulations/codes/practices: UFC 3-600 Series (Fire Protection).

1.5.1.7 Aqueous Film-Forming Foam (AFFF) - Foam waste effluents shall not be released to the environment nor released to any sanitary waste stream. Fluorine surfactant-based foam such as commercial or Military Specification AFFF concentrate, or solution waste must be disposed of through incineration.

1.5.2 Canine Septic Tank: The Contractor shall dispose of canine septic tank waste at RAF Fairford and RAF Mildenhall. At RAF Mildenhall, the tank shall be emptied twice a month. At RAF Fairford, the tank shall be emptied no more than 3 times per year.

1.5.2.1 Uniform wash tank: The Contractor shall dispose of the wastewater from the tank at RAF Mildenhall, building 814 on an ad hoc basis, when instructed by the CO/COR.

1.5.2.1.1 The contractor shall transport the wastewater to an off-base treatment facility.

1.5.2.1.2 The Contractor shall provide waste transfer notes stating the nature and quantity of the material being removed, the relevant establishment Premise Code, and the applicable HW Consignment Code in respect to each load or part thereof before removal from each installation. The CO, COR, and/or respective installation's Environmental Office must sign each transfer note. The Contractor shall also provide abstract summaries of waste types disposed of on a Waste Material Notification Schedule and reports monthly to the CO, COR, and/or each respective installation's Environmental Office no later than 10 business days from the end of the reporting month. Beginning in 2026, all waste streams shall be tracked electronically. The CO or COR will provide the Contractor with the email addresses required to receive the information.

1.5.2.1.3 The Contractor shall provide the CO/COR the tanker wash out certificate for each service performed.

1.5.3 Non-Hazardous Liquid Waste Management. The Contractor shall clean, empty, wash, transport, and/or remove/dispose of liquid waste to include, but not limited to sewage sludge, liquid sewage, grease, wastewater, and/or any combination thereof. This will be removed from sewage works, septic tanks, cesspits, pumping stations, catch pits, oil water separators, fuel interceptors, hanger waste tanks, sludge pits, silt pits, gullies, drainage

channels, grease traps, scum wells, lagoon walls, maintenance facilities, and any other catchment or disposal management facilities IAW this PWS and any applicable UK laws and regulations.

Sewage sludge that has been properly treated/processed into bio-solids and can be applied to agricultural land for beneficial reuse, must meet pollutant limits, pathogen reduction requirements, and vector attraction reduction requirements before land application. Agricultural lands in which bio-solids are applied must be tested prior to the first application and every five years thereafter. Testing and sampling analysis for bio-solids applied to agricultural land must be submitted to the CO/COR for verification with the appropriate installation's Environmental Office within 10 business days.

1.5.4 Hazardous Liquid Waste Management. Clean, empty, wash, transport, and/or remove/dispose of hazardous waste, to include fuel & water mix, oil & water mix, Aqueous Film Forming Foam (AFFF), Polyfluoroalkyl Substances (PFAS) grouped chemicals, White Spirit, exterior aircraft cleaning solvent, and any other combination thereof. This will be removed from sewage works, septic tanks, cesspits, pumping stations, catch pits, oil water separators, fuel interceptors, hanger waste tanks, sludge pits, silt pits, gullies, drainage channels, grease traps, scum wells, lagoon walls, maintenance facilities, and any other catchment or disposal management facilities IAW this PWS and any applicable UK laws and regulations. PFAS containing materials must be disposed of in accordance with DoD regulations and instructions which are subject to updates during the term of contract.

1.5.5 RAF Fairford Site Specific Liquid Waste.

1.5.5.1 Sewage. At RAF Fairford, sewage is treated at the on base treatment plant, however, the Contractor shall collect from all cesspits, septic and sludge pits/tanks and deliver to the treatment plant. The Contractor shall provide delivery volumes to the COR for accountability.

1.6 HAZARDOUS WASTE MANAGEMENT

1.6.1 Description of Services. The Contractor shall transport, remove, and/or dispose of solid hazardous waste. This waste will include, but not limited to, contaminated soil, contaminated road sweepings, paint chippings, or wood as requested by the CO or COR. Hazardous and non-hazardous waste streams shall not be comingled. Hazardous waste will be sampled and analyzed for chemical content to determine proper disposal route. Hazardous waste must be disposed of in

accordance with this PWS and any applicable UK laws and regulations. The Contractor shall provide analysis results to the Government, if requested.

1.6.2 Schedules. The Contractor shall establish initial vehicle routes and collection schedules upon contract award. Within 30 days after start of award, the contractor shall provide a pickup schedule to the CO and CORs based on the Appendix B. Whereas Appendix B specifies the frequency of pickups, the contractor shall specify which day of the week pickup will be made. The Contractor may propose adjustments to the schedule at any time; however, at a minimum, the COR and Contractor shall monitor container fill capacities during the first 30 days of performance. The purpose of this monitoring is to determine if adjustments to container size, routes, or pickup frequency are necessary to maintain a healthy, vector free environment and prevent waste container overflow. No changes are allowed to the schedule or haul routes without prior CO or COR coordination and approval. Historical frequency tables are located at Appendix A.

1.6.3 UK Regulations – Hazardous Waste – The Contractor must perform services in accordance with the following regulations/codes/practices:

Table 4: Applicable Waste Management Regulations	
Regulation / Standard	Reference / Date
The Waste (England and Wales) Regulations	UK SI 2012/0811; amended by UK SI 2014/1771
Duty of Care Regulations	SI 1991/2839
The Environmental Protection Act	1990
The Separation of Waste (England) Regulations	2025 (Effective)
Final Governing Standards – United Kingdom, Chapter 15 (Solid Waste)	Jun-24
Final Governing Standards – United Kingdom, Chapter 16 (Hazardous Waste & Duty of Care Code of Practice)	Jun-24

1.6.4 Persistent Organic Pollutants (PoPs). In addition to the data supplied in Appendix A, the Government may require additional Bulk/ Roll on Roll Off containers for the collection of items containing Persistent Organic Pollutants. The Government may require ad-hoc pick-ups of contaminated items as directed by the COR. This may occur when existing containers are inappropriately contaminated and require immediate removal to prevent environmental or safety hazards. The COR will provide specific instructions regarding the nature, quantity, and location of the waste requiring ad-hoc removal. Disposal of this waste stream shall be performed IAW UK Environmental Agency guidance: Regulation (EU) 2019/1021 of the European Parliament and of the Council of 21 May 2025 on persistent organic pollutants. The COR shall request the

service on an Ad hoc schedule. Landfill site tip tickets shall be provided to the COR, no later than the next working day.

1.6.5 Hazardous Wood/ Amber Wood waste. The Contractor shall provide containers at each UK/US Air Force Installation in 24 hours from the request of the Installation COR or CO for the collection and disposal of hazardous treated waste timber, from heavy industrial installations including but not limited to structural timbers, tile battens, external joinery, fence posts, sleepers, and decking. The Contractor is responsible for ensuring disposal is IAW existing UK regulations. Disposal site tickets shall be provided to the COR no later than the next working day.

1.6.6 Waste Electrical and Electronic Equipment (WEEE). The Contractor shall provide containers at each UK/US Installation in 24 hours from the request of the Installation COR or CO for the collection and disposal of waste electrical and electronic equipment. The Contractor is responsible for ensuring disposal is IAW existing UK regulations. Disposal site tickets shall be provided to the COR no later than the next working day.

1.7 REPORTS AND RECORDS. The Contractor shall provide a monthly report, submitted electronically, by the fifth working day of the month, detailing the previous month's total disposal activities. These reports shall include at a minimum: IWMS overall and each waste stream's monthly costs, the IWMS overall and each waste stream's monthly weights (tonnage/liters/UK gallons), each waste stream's monthly percentage, waste hierarchy (Reuse/recycling/recovery/disposal), category monthly tonnage, and waste hierarchy, category monthly percentage and costs reflecting the above, and the overall calculated net costs per ton. The format for these monthly reports shall be coordinated by the CO or COR. Beginning in 2026, all waste streams shall be tracked electronically. The CO or COR will provide the Contractor with the email addresses required to receive the information. Disposal of waste from installations to landfills/disposal sites is exempted from the UK's landfill tax. Installation Environmental personnel require detailed monthly consignment notes and invoices in order to validate the tonnage sent to landfills. This in turn allows USAFE-UK/JA to issue a memorandum that can be used by the Contractor to recover landfill taxes for each year of the contract.

2.0 SERVICE SUMMARY. The contract service requirements are summarized in performance objectives that relate directly to mission essential items. The performance threshold briefly describes the minimally acceptable levels of service required for each requirement. The Services Summary (SS) and the Contractor's Quality Control Plan provide information on contract requirements, the expected level of Contractor performance, and the expected method of Government validation and confirmation of services provided. These thresholds are critical to mission success. Procedures set forth FAR 52.212-4(a), Contract Terms and Conditions – Commercial Items, Inspection/Acceptance, will be used to remedy all deficiencies. During the first initial 30 days of the contract, two additional errors on each Performance Objective shall be allowed in an effort to identify normal phase-in problems.

Performance Objective	PWS para	Performance Threshold (Per Installation)	Remedy
Collect Main Base Solid Waste in accordance with the established schedule.	1.1.1	No more than 2 validated customer complaints per month.	Missed collections shall be collected within 24 hours of identification.
Collect MFH Solid Waste in accordance with the established schedule.	1.1.2	No more than 2 validated customer complaints per month.	Missed collections shall be collected within 24 hours of identification.
Collect Liquid Waste in accordance with waste in accordance with the established schedule.	1.5	No more than 2 validated customer complaints per month.	Missed collections shall be collected within 24 hours of identification.
Collect Hazardous Waste in accordance with the established schedule.	1.1.3.9 & 1.6	No more than 2 validated customer complaints per month.	Missed collections shall be collected within 24 hours of identification.
Dispose of Solid, Liquid, and Hazardous waste in accordance with the established governing directives.	1.3, 1.6, 1.7	No more than 2 validated customer complaints per month	Missed collections shall be collected within 24 hours of identification.
Collect Food Waste in accordance with the established schedule.	1.1.1.1.3, 1.1.1.2, 1.1.1.2.1, 1.1.1.2.2, 1.1.2.2	No more than 2 validated customer complaints per month	Missed collections shall be collected within 24 hours of identification.
Collect Piddle packs, CAT 1, and CAT 3 waste in accordance with the established schedule.	1.1.1.1.3, 1.1.1.2, 1.1.1.2.1, 1.1.1.2.2, 1.1.2.2	No more than 2 validated customer complaints per month	Missed collections shall be collected within 24 hours of identification.
Perform unscheduled collections required by the contracting officer in accordance with paragraph 1.1.3.	1.1.3.1	No more than 1 validated customer complaints per month	Missed collections shall be collected within 24 hours of identification.
Perform Emergency liquid waste collection in accordance with paragraph 1.5.1.4	1.5.1.4	No more than 1 deficiency permitted.	Missed collections shall be collected within 4 hours of identification.

Produce/maintain reports and records by the fifth working day of the month.	1.7	No more than 1 deficiency permitted.	All discrepancies and/or inaccuracies shall be corrected within 2 working days.
---	-----	--------------------------------------	---

2.1 QUALITY CONTROL. The Contractor shall develop and maintain a quality program to ensure Integrated Waste Management is performed in accordance with commonly accepted commercial practices. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. As a minimum the Contractor shall develop quality control procedures addressing the areas identified in paragraph 9, Service Summary.

2.2. QUALITY ASSURANCE. The Government may inspect and evaluate the Contractor's performance to ensure services are received in accordance with requirements set forth in this PWS. The Contractor shall provide work schedules to the COR in accordance with paragraph 4.4 of this PWS. The COR shall inspect by validating actual work performance, physically checking an attribute of the completed task, checking a management information report, investigating customer complaints, conferring with facility managers or otherwise inspecting the task or its results to determine whether performance meets the standards contained in this PWS. The COR will use the Contractor's work schedule or modified version thereof, to record validation results. The results of the validation then become the official Air Force record of the Contractor's performance. When a performance threshold had not been met or Contractor performance has not been accomplished, the COR will initiate and provide the CO and Contract Discrepancy Report (CDR) DD Form 2772 for issuance to the Contractor. The Contractor shall respond to the CDR IAW instructions provided and return it to the CO within ten calendar days or receipt.

2.3. PERFORMANCE ASSESSMENT

2.3.1 Periodic Validations. This method requires the COR to employ a "spot check" style of evaluation based on the Contractor's schedule. Periodic valuations will be conducted on a scheduled basis (daily, weekly, monthly, quarterly, semi-annual or annually) and may be adjusted, based on quality trends.

2.3.2 Unsatisfactory Performance. Any unsatisfactory inspection (defect) result shall be recorded, and the Contractor shall re-perform the service after notification by the COR. Failing to meet the performance threshold as outlined in the SS of these performance objectives in any combination for any two, or more consecutive or non-consecutive months during a contract period shall constitute an immediate Progress Meeting with the Multi-functional Team. All remedies shall be in accordance with FAR 52.212-4(a), Contract Terms and Conditions – Commercial Items, Inspection/Acceptance.

2.4 PERIODIC PROGRESS MEETINGS

2.4.1 Meetings. The CO, Functional Commander, COR, QRP Manager and/or Solid Waste Manager, other Government personnel as appropriate, and the Contractor shall periodically meet to discuss the Contractor's performance. The following issues shall be discussed: opportunities to improve the contract, required contract modification(s), unsatisfactory inspections and trends against each performance objective observed, positive performance and steps taken by the Contractor to prevent unsatisfactory occurrences in the future. The Contractor shall provide a summation of unsatisfactory inspections and customer complaints and provide insight into any identified trends.

2.4.2 Meeting Minutes. The minutes of these meetings will be reduced to writing and distributed to the functional area and the Contractor. Should the Contractor not concur with the minutes, the Contractor shall provide a written notification to the CO identifying areas of non-concurrence for resolution.

3.0 GOVERNMENT FURNISHED PROPERTY AND SERVICES - RESERVED.

4.0 GENERAL INFORMATION

4.1 HOURS OF OPERATION. Perform integrated waste management services during normal duty hours (see Para 1.1.5) and be available (by phone or e mail) during COR normal duty hours (0730 to 1600) Monday through Friday and for after-hours response to refuse problems or emergencies. This excludes US Federal Holidays and UK Holidays, unless otherwise required in the contract or approved by the CO. There may be situations where the Contractor is required to work at times outside of normal duty hours to perform emergency response for Liquid waste collection. Any costs for work outside of normal duty hours shall be factored into the monthly line-item pricing and not be at an additional cost to the Government.

4.2 HOLIDAYS & CLOSURES.

4.2.1 Recognized US Federal Holidays. There may be US federal holidays when the Contractor is not required to perform service, except in emergency situations or to support specific mission needs. The US holidays are:

- New Year's Day – 1 January
- Martin Luther King Day – 3rd Monday in January
- Washington's Birthday – 3rd Monday in February
- Memorial Day – last Monday in May
- Juneteenth – 19 June
- Independence Day – 4 July
- Labor Day – 1st Monday in September
- Columbus Day – 2nd Monday in October
- Veteran's Day – 11 November

Thanksgiving Day – 4th Thursday in November
Christmas Day – 25 December

If a holiday falls on a Saturday, the preceding Friday will be observed. If a holiday falls on Sunday, the following Monday will be observed. If a holiday falls on a scheduled service day, the Contractor shall be responsible for rescheduling services for the first day after the holiday observance in addition to performing the regular scheduled duties.

4.2.2 Recognized UK Holidays. There may be UK holidays when the Contractor is not required to perform service, except in emergency situations or to support specific mission needs. The UK holidays are:

New Year's Day
Good Friday
Easter Monday
Early May Bank Holiday
Late May Bank Holiday
Summer Bank Holiday
Christmas Day
Boxing Day

If a holiday falls on a scheduled service day, the Contractor shall be responsible for rescheduling services for the first day after the holiday observance.

4.2.3 Base Closures. Work scheduled but not accomplished because of base closure due to weather, exercises, or actual alert, shall be accomplished as soon as possible after reopening the base. The CO or COR will notify the Contractor of any anticipated base closures in advance. A schedule of 'catch up' work shall be provided to the COR(s) for the base/task order before work commences. Notification of elevated force protection levels will be provided to the Contractor's management.

4.3 PERFORMANCE OF SERVICE DURING CRISIS OR HEIGHTENED SECURITY

The services under this contract are not mission essential for performance during crisis. The CO will determine circumstances which constitute a crisis based on direction from Security Forces and base leadership.

4.4 CONTRACTOR WORK SCHEDULE

4.4.1 Schedule Submission and Approval. The Contractor shall submit a schedule for all services described in this PWS and Appendices to the CO for approval at the post-award conference. Within the first 30 days after award, the contractor may adjust the schedule to better meet the needs of the government. This final schedule is due to the CO for approval 30 days after award. The exception to this is Military Family Housing, that final schedule must be submitted

for approval at the post-award conference. The schedule shall include routes, pickup points, times, and days that pickups will occur. The Contractor shall not deviate from the approved schedule without prior approval from the CO or COR. Permanent changes to the schedule must be submitted 10 days before implementation and receive CO approval before the Government will allow the proposed changes. The schedule must be submitted electronically using a file format compatible with Government software.

4.4.2 Schedule Changes. Occurrence-based (non-permanent) schedule changes due to customer requests or base exercises shall be submitted to the COR and do not require CO approval.

4.5 CONTRACT PERSONNEL

4.5.1 Contract Manager. The Contractor shall establish and maintain an office through which the contract manager or alternate(s) can be contacted during work hours. The contract manager or alternate shall be available during normal duty hours to meet on the installation or via teleconference within 1 hour of the request, with the Government personnel designated by the CO and/or COR to discuss problem areas. The Contractor shall provide the CO telephone number(s) where validation results and complaints can be reported. The Contractor shall also provide to the CO the names and phone numbers of Contractor POCs for after business hours including nights, weekends, and holidays. This information will be kept updated by the Contractor whenever personnel changes occur. The Contract Manager or alternate shall have full authority to act for the Contractor on all Contract matters relating to the daily operation of this Contract.

4.5.2 Personnel. Contractor personnel shall present a neat appearance. Contractor personnel shall be easily recognizable while on the installation in conjunction with this contract. This shall be accomplished through the wear of distinctive clothing, overcoats, or hats, bearing the company name or logo. The coloring or design of the items selected should be such that identifies personnel easily and quickly for reasons of safety and personal protection.

4.5.3 Employee Restrictions. The Government is authorized to restrict performance under the contract of any Contractor employee or prospective Contractor employee who is identified as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.5.4 Transfer of Undertakings (Protection of Employment) Regulations 2006 (TUPE).

4.5.4.1 Definition. The United Kingdom's Transfer of Undertakings (Protection of Employment) Regulations 2006 (TUPE) is the main piece of legislation governing the transfer of an undertaking, or part of one, to another. The regulations are designed to protect the rights of employees in a transfer situation.

4.5.4.2 TUPE Information. The U.S. Government does not have access to specific TUPE information nor becomes involved with related TUPE processes and associated liabilities (to include indemnification) that may transpire during pre-award or post-award phases between transferor and transferee. The responsibility to provide TUPE-information rests solely with the transferor; governed by Regulation 11 of the Transfer of Undertakings (Protection of Employees) Regulations 2006 (TUPE). As the transferor need only provide TUPE information to the transferee prior to the transfer, the U.S. Government will provide the name of the current incumbent Contractor(s) with associated points of contact upon request. The U.S. Government is not responsible for determination of TUPE applicability; the responsibility lies solely with the transferor.

4.6 SERVICE CONTRACT REPORTING. Section 2330a of title 10, United States Code (10 USC 2330a), requires the Secretary of Defense to submit to Congress an annual inventory of contracts for services performed during the prior fiscal year for, or on behalf of the Department of Defense (DoD) by 31 Oct. The Contractor shall report ALL contractor labor hours (including subcontractor labor hours) provided under this contract by generating a Service Contract Report (SCR) at <https://www.sam.gov>. The inventory shall include the number of Contractor employees using direct labor hours and associated cost data. Information from the secure website is considered to be proprietary in nature when the contract number and contractor identity are associated with the direct labor hours and direct labor dollars. At no time will any data be released to the public with the Contractor's name and contract number associated with the data. Contractors for other than Army components can visit https://www.fsd.gov/gsafsd_sp?id=kb_article_view&sysparm_article=KB0029921 to review the user guide and understand the data fields included in the reporting structure.

4.7 SECURITY REQUIREMENTS. Contractor employees shall comply with the installation's security requirements always imposed by the Installation Commander for each Installation while on the premises. The Contractor shall obtain all necessary passes, decals, badges, or other items required for access to perform contract services at each installation. The Contractor shall be responsible for acquiring and maintaining Flight Line Driving Permits as required to access sites each installation. The Contractor is responsible for accountability of all such media, which shall be surrendered to the Security Forces Squadron Pass and Registration Section upon completion or termination of the contract or upon termination of an individual's employment for the Contractor. The Contractor shall comply with all policies regarding entry to each installation, rules of the road, contingency operations compliance, and photography prohibitions. Contractor employees are authorized entry to each installation for the purpose of work under this contract only and are not authorized in other facilities or areas without prior Government authorization.

4.7.1 Base Access.

The Contractor shall be aware that entry requirements are subject to change due to installation and world situations. All employees may be subject to a background check through the appropriate US and/or host nation agency checks to include but not limited to SFMIS, MODLO, FBI, and/or other MOD agency for base access.

4.7.2 Main Base Access. Current security access procedures require all Contractor vehicles to enter through each installation as indicated below only. Contractor vehicles may be subject to search prior to gaining base entry. The Contractor should plan and allow for delays as a result of increased and ever-changing security procedures. The driver and any passengers must present a valid (Base issued) Contractors ID Card. On occasions the Search Barns at each installation may have the doors closed, this is due to vehicle searches taking place. Contractors should check with the Visitors center (VCC) personal to gain access.

RAF Lakenheath – Gate 8 (Contractor’s Gate) Mon – Fri 0600 – 1730. When Gate 8 is closed, the Contractor may use the Main Gate (Gate 1).

RAF Feltwell – Main Gate.

RAF Mildenhall – Gate 15 or Main Gate.

RAF Alconbury – LVIS Gate on Mon – Fri during 0700 – 1400. If the LVIS Gate is closed, the Contractor may use the Main Gate.

RAF Molesworth – Main Gate.

RAF Croughton – Main Gate.

RAF Welford – Main Gate.

RAF Fairford – Main Gate.

4.7.2.1 Pass & Registration Locations. The Security Forces Pass & Registration office hours of operation are typically 0700 - 1600 and locations are at each installation’s Main Gate apart from the bases indicated below. All offices are closed on US Federal Holidays, Wing and family down days. During normal duty hours all base access and vehicle passes must be obtained at this office prior to entering the base. After hours passes may be obtained from the gate personnel.

RAF Lakenheath – building 977, Monday – Wednesday 0730 – 1600; Thursday 0930 – 1600; Friday 0730 – 1530

RAF Mildenhall – building 438, Monday thru Friday from 0800 - 1500.

RAF Alconbury and RAF Molesworth – located in building 334 on RAF Molesworth, Monday thru Friday from 0830- 1530.

RAF Croughton – Main Gate until 1300 Monday thru Friday. Gate House from 1300.

RAF Fairford – building 478, Monday thru Friday from 0700 – 1600 (closed for lunch 1200 – 1300).

RAF Welford – No pass and identification office.

4.7.2.2 Requirements for Contractor Credentials.

4.7.2.2.1 Identification. Must present a current state or Government issued identification card or driver’s license issued by their state of residence or an alien card (green card), or local United Kingdom/host nation license requirements if outside the continental United States.

4.7.2.2.2 DD FORM 2583: Unescorted Entry Authorization Certificate, and USAFE Form 79 must be filled out completely prior to proceeding to the Pass & Registration office. The Contractor shall complete Blocks 1-3, 5-14 on DD Form 2583 and sections 1-4 down to the Approving Official on the USAFE Form 79 (once complete, the Pass and Registration office will fill out section 5). The contract will then sign a Receipt of Acknowledgement after the issuance of a pass.

4.7.2.2.3 Access to Multiple Installations. For access to multiple installations, the Contractor must follow procedures identified in AFMAN 331-113 USAFESUP-O. The sponsoring official will route a memorandum request through each installation to justify access and acquire approval. The sponsoring installation will be responsible for performing all components of the background/Host Agency Check and/or equivalent and providing copies of the results to other installations upon request.

4.7.3 Security Manager. Upon contract award, the Contractor shall designate, in writing to the CO, a Security Manager for each USVF location who shall be the Contractor's point of contact for all security matters. Within five working days of contract award, the Contractor's Security Manager shall contact the respective Civil Engineer Squadron (CES) Security Manager and/or COR for assistance on accomplishing Contractor personnel security requirements.

4.7.3.1 Security Training. The Contractor shall schedule initial and annual refresher training (for all assigned Contractor personnel) through the CES Security Manager. Initial training shall be scheduled within 30 days from date of contract award. All Contractor personnel shall be thoroughly briefed by the CES Security Manager on established security requirements and procedures as stipulated by Air Force Policy Directive (AFPD) 31-1, Integrated Defense.

4.7.3.2 Security Authority. The Contractor shall brief all employees that they shall *immediately leave any area* upon notification by the CO, COR, constituted authority, Security Forces, or when directed as occasional operational requirements, real world activities, or emergencies dictate.

4.7.4 Restricted/Controlled Areas. Contractor performance within all restricted and/ or controlled areas shall require Contractor compliance with various levels of security and established personnel security entry control procedures. The Contractor shall ensure all Contractor employees performing services in secured areas are processed for a controlled area, limited access, or visitor badge by the Entry Controller of the restricted/controlled area. Outside contents to include but not limited to bags, containers, vehicles, etc. are subject to inspection prior to entering and leaving a restricted/controlled area and prohibited and/or misappropriated items will be confiscated

4.7.4.1 Access Coordination. The facility manager/user/occupant/requester for each installation's building will be responsible for providing access, escorts, or temporary visitor access badges for Contractor personnel while performing ISWM duties. The Contractor shall be

responsible for *scheduling* access/escorts/badges by contacting the facility manager/requester no less than 14 calendar days prior to the date requiring access to the Entry Control Point of the restricted/controlled area.

4.7.4.2 Escorts. At all times while in any restricted/controlled areas, Contractor employees shall be under direct surveillance of a person from that facility who is cleared to wear a controlled area badge and perform escort duties. Visitor badges shall be returned to the Entry Controller each time the employee completes the duties and leaves the area. This requirement is waived for Contractor personnel who have unescorted access privileges and display a controlled area badge for the restricted/controlled areas. Escorts for entering the main base will only be provided with prior coordination with the COR at the respective installation. Requests for escorts must be coordinated and approved a minimum of 14 calendar days prior to the date needed.

4.7.5 Employee Background Checks. All Contractor employees who do not have a current security investigation acceptable to the Security Forces, and who require a Host Agency Check (HAC) for the performance of their duties, shall complete an AF Form 2583, USAFE IMT 19, a Basic Check Verification Record and MODLO Proforma. Once all forms are filled out, they are routed through the Ministry of Defense Liaison's Office to the Defense Vetting Agency.

4.7.5.1 Pre-Approval Coordination. The CES Security Manager at each installation is the source for the necessary forms and will provide instructions for receiving, preparing, and processing these forms. The Contractor shall coordinate with all required facilities to process all necessary paperwork. After forms have been properly completed, the CES Security Manager at each installation will make an appointment for Contractor employee(s) to go to the Security Forces for submittal of paperwork and fingerprinting into IACS database. Appointments will be scheduled within two weeks of request.

4.7.5.2 Badge Issuance. A minimum of 180 days is required to process Contractor employee's applications through HAC. Additional time will be required if results are unfavorable and may result in denial of entry to any escorted/unescorted restricted/controlled areas and/or the installation. The CES Security Manager will notify the Contractor of any HAC results. After completion of a favorable HAC, each eligible employee shall report to the CES Security Manager for processing of AF Form 2586. The CES Security Manager or designate at each installation, will schedule appointments for the issuance of badges.

4.7.5.3 Access Revocation. Each installation's Commander or equivalent reserves the right to deny restricted area entry to any Contractor employee whose HAC is unfavorable, and the right to terminate the entry of any employee upon disclosure of information indicating the individual's continued entry to a secure area is not in the best interest of national security.

4.7.5.4 Badge Validity. Controlled area badges will be valid only for the actual period of employment or the term of the contract, whichever occurs first. Contractor employees must display the controlled area badge on their outer garment above waist level, and must, upon

request, surrender the badge to any DoD member for identification verification. Violations or deviations from established security procedures by Contractor employees may result in confiscation of controlled area badges and denial of future entry to restricted areas.

4.7.5.5 Contract Personnel Requirements. The Contractor shall not employ persons for work on this contract who are identified to the Contractor by the CO as a potential threat to the health, safety, security, general well-being, or operational mission of the installation and its population.

4.7.6 Prohibited Items. All offensive weapons as dictated in UK Criminal Justice Acts and Prevention of Crime Acts are prohibited on all installation. Any weapon made or adapted for use for causing an injury to another person or intended by the person having it with him for such use will be apprehended and charged under applicable UK laws.

4.7.7 Contractor Vehicles. Contractor vehicles must be legally compliant and always maintained in a safe and operational condition while on each installation.

4.7.8 Reporting Requirements. Contractor personnel shall report to an appropriate authority any information or circumstances of which they are aware may pose a threat to the security or well-being of DoD personnel, Contractor personnel, resources, and classified or unclassified defense information.

4.7.9 Physical Security. The Contractor shall be responsible for safeguarding all Government property and controlled forms provided for Contractor use. At the end of each work period, all Government facilities, equipment, and materials shall be secured.

4.7.10 Key Control. The Contractor shall establish and implement methods of making sure all keys/combinations issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. The Contractor shall not duplicate any keys issued by the Government. The Contractor shall immediately report to the COR or CO any occurrences of lost or duplicated keys. In the event keys other than master keys are lost or duplicated, the Contractor may be required, upon written direction of the CO, to re-key or replace the affected lock or locks without cost to the Government. The Government may, however, at its option, replace the affected lock or locks or perform re-keying and deduct the cost of such from the monthly payment due the Contractor. In the event a master key is lost or duplicated, the Government may replace all locks and keys for that system, and the total cost will be deducted from the monthly payment due the Contractor.

4.8 SAFETY REQUIREMENTS AND REPORTS. The Contractor shall perform work in a safe manner as required by UK Health and Safety Requirements. Provide a verbal report to the CO as soon as possible of each occurrence of damage to Government property or an accident resulting in death, injury, occupational disease, or adverse environmental impact. Provide a completed copy of the required Accident Investigation Reports to the CO within five calendar days of each occurrence.

4.9 SPECIAL QUALIFICATIONS. All Contractor personnel who transport dangerous goods must be done under the regulations of the European Agreement concerning the International Carriage of Dangerous Goods by Road (ADR), as set out in ADR 2017 and possess a valid Waste Carriers License issued by the Environmental Agency. Dangerous Goods include Flammable, toxic and compressed gases, flammable liquids, flammable solids, spontaneously combustible materials and materials that are dangerous when wet, oxidizing agents and organic peroxides, toxic substances and infectious substances, and corrosives.

4.10 CONTRACTING OFFICER & CONTRACTING OFFICER REPRESENTATIVE. (QUALITY ASSURANCE PERSONNEL) The CO will appoint a primary and alternate representative for management of the day-to-day activities of the contract. The identity, title, and authority of this representative will be provided in writing to the Contractor after contract award.

4.11 MULTI-FUNCTIONAL TEAM. The Senior Leadership may require a multi-functional team established between the Government and the Contractor to ensure cooperation and a sound customer focus of all parties involved in the execution of this contract.

4.12 DAMAGES TO GOVERNMENT BUILDINGS, EQUIPMENT OR VEGETATION. Damages to Government buildings, equipment, or vegetation are addressed in FAR 52.237-2, Protection of Government Buildings, Equipment and Vegetation.

4.13 GOVERNMENT FURNISHED TRAINING

4.13.1 Level 1 Anti-terrorism Training: Contractor employees performing under this contract shall complete Level 1 Anti-terrorism training located at <https://jkodirect.jten.mil/Atlas2/page/login/Login.jsf> and present certificates upon request by the COR.

4.13.2 Operational Security (OPSEC) Training: All on-site Contractor employees shall complete Center for the Development of Security Excellence OPSEC Awareness, Unauthorized Disclosure of Classified Information for DoD and Industry, Insider Threat Awareness, and Introduction to Information Security courses or authorized DoD Component equivalents. Training will be provided by the host unit and shall be completed by the Contractor within 30 days of contract award, and for each new Contractor employee thereafter.

5.0 APPENDICES.

A. To be determined