

SCOPE OF WORK

Medium Intensity Approach Lighting System with Rail (MALSR), Houma-Terrebonne Airport Demolition and Installation

The existing MALSR for Runway 18 at Houma-Terrebonne Airport will be removed in its entirety and replaced with a new Patriot MALSR system. The proposed scope of work includes the following:

- Demolition of the existing HUM MALSR system, including demolition of the existing shelter, all light stations/foundations, and the existing MALSR access road.
 - Includes removal of:
 - Existing primary power feed cables
 - Existing Direct Earth Buried (DEB) cables
 - Existing Quazite boxes
 - Existing power and control racks
- Installation of new MALS Light stations, including reinforced concrete foundations, concrete maintenance pads, light fixtures, new mounting hardware (frangible connections where required), and Earth Electrode System (EES).
- Installation of new Runway Alignment Indicator Lights (RAIL) stations, including reinforced concrete foundations, concrete maintenance pads, light fixtures, mounting hardware, junction boxes/Individual Control Cabinets (ICCs), maintenance stands, EES, and security fence.
- Installation of new primary power duct, transformer pad, and utility-provided transformer.
 - Primary cables furnished, installed, and terminated by the utility company
- Installation of new concrete-encased power and control ducts throughout the new MALSR system, complete with conduit, cabling, handholes, warning tape, and guard wires/ground rods.
 - Includes new power and power/control racks
 - Includes bores under Aviation Road, State Route 24, and Bayou Terrebonne.
- Installation of a new 10' x 16' Dupont fiberglass shelter outside the Runway Object Free Area (ROFA), including a new reinforced concrete foundation, EES, and lightning protection system.
 - The shelter will be complete with a new pre-installed Patriot MALSR equipment system

- Installation of new asphalt paved access roads, including turnarounds and culvert pipes with concrete endwalls.
- Site restoration – The contractor is responsible for restoring worksite areas disturbed by construction activities.
- Government Furnished Equipment
 - Patriot MALSR System
 - 10' x 16' Dupont Fiberglass Shelter
- Deliverables
 - Drawing Redlines
 - Technical Reference Data Records
 - Functional Checkout
 - Site Acceptance Testing
 - An approved Safety Plan Compliance Document in compliance with the Construction Safety Phasing Plan