

MT PRAIRIE 2016(3), Milwaukee Bridge Resurfacing and Rehabilitation

Prairie County, Montana

This work consists of replacement of existing timber decking with metal grid bridge deck, replacement of existing timber railing with metal bridge rail, performing scour remediation and concrete repair, and grading and resurfacing of the roadway adjacent to the bridge.

Project Location: This project is located approximately 5 Miles west of Terry City, Prairie County, Montana State.

Project Length: 0.348 Mile

Estimated Price Range: Between \$5,000,000 and \$10,000,000

Tentative Solicitation Date: Spring/ Summer 2026

Tentative Fixed Completion Date: Fall/ Winter 2026

**DESCRIPTION OF WORK in US CUSTOMARY UNITS
USING FP-14 SPECS**

	One Schedule Sch Name A
DIVISION 150 – Project Requirements	
152 Construction Survey & Staking (yes/no)	Yes
153 Contractor Quality Control and Assurance (yes/no)	Yes
154 Contractor Sampling & Testing (yes/no)	Yes
155 Schedules for Construction Contracts (construction schedules) (yes/no)	Yes

	One Schedule Sch Name A
157 Soil Erosion & Sediment Control (<i>erosion control devices</i>) - Temporary Soil Tackifier - Fiber Roll	0.9 ACRE 1800 LNFT
158 Watering for Dust Control	LPSM
DIVISION 200 – Earthwork	
201 Clearing & Grubbing	0.4 ACRE
202 Additional Clearing & Grubbing (<i>clearing & grubbing</i>)	---
203 Removal of Structures & Obstructions - Removal of Sign/Marker - Removal of Sign - Removal of bridge rail - Removal of bridge deck	4 EA 2 EA 2160 LNFT 1520 SQYD
204 Excavation & Embankment - Roadway excavation - Subexcavation - Unclassified borrow	100 CUYD 2000 CUYD 600 CUYD
DIVISION 250 – Slope Reinforcement and Retaining Walls	
251 Placed Riprap, Method A, Class 5	2000 CUYD
DIVISION 300 – Aggregate and Base Courses	
302 Minor Crushed Aggregate	680 CUYD
DIVISION 550 – Bridge Construction	
555 Steel Structures (<i>structures, steel</i>)	382,000 LB
556 Bridge Railing	2170 LNFT

	One Schedule Sch Name A
563 Painting (<i>structures, painting</i>) - <i>Containment system and worker protection plan</i>	LPSM
575 Minor Bridge Work - <i>Work Platform</i>	LPSM
DIVISION 600 – Incidental Construction	
619 Fences, Gates, Cattle Guards & Bollard Posts - <i>Remove and reset fence</i>	60 LNFT
621 Monuments & Markers (<i>construction survey & staking</i>) (yes/no)	No
622 Rental Equipment (yes/no)	Yes
623 General Labor (yes/no)	Yes
624 Topsoil (<i>landscaping & related items</i>)	0.3 ACRE
625 Turf Establishment <i>(indicate seeding or mulching separately)</i>	0.4 ACRE
633 Permanent Traffic Control (traffic control devices) - <i>Sign system</i> - <i>Object markers</i> - <i>Delineators</i>	40 SQFT 4 EACH 4 EACH
635 Temporary Traffic Control – <u>Flagger</u>	16 HOUR
635 Temporary Traffic Control – <u>Construction signs</u>	200 SQFT
635 Temporary Traffic Control – Barricade	7 EACH
635 Temporary Traffic Control – Drum	22 EACH

