

D

D

C



100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
71.218.1000
FAX: 571.218.1600

U.S. GPO: 1980-0-290-000

B



COMMANDER NAVFAC

APPROVED BY LCDR ELIZABETH
OLOKODE NAVFAC NLON FEAD
RECTOR NEW LONDON, GROTON, CT

FACTORY TO DATE		05/27/2025	
PS	DRW	PS	CHK WS

PG	DATE	PG	DATE	PG	DATE
					SMS/CWJ

CH MANAGER	NEK
ENG/ARCH	JWJ

PROTECTION		HPN
1	1	

C
LK, VFA
TICUT
ITY

ANIT
CORFO
NECT
CIL

MAIL
ON - N
CONN
S FA

10

PROTIC

IANL	NA	G	PER.
------	----	---	------

OF

SC
NCE
HEET

EMC	ONAL	ER SH
-----	------	-------

COVER	CONTENTS	ORDERS	SYNOPSIS
-------	----------	--------	----------

ING S	IN	E & (	SE	RAL (
-------	----	-------	----	-------

ENERG

GAZ

MA

BASE	IONS
------	------

APC

FAC	MAR	WEA	
-----	-----	-----	--

WAL	
ANTIC	
SUB	
102	

NA	VAL	P-11
----	-----	------

MI	NA	
AS NOTED		

PROJECT NO.:	1667770
--------------	---------

STR. CONTR. NO.

FAC DRAWING NO.
 12004000

12894089

ET 1 OF 65

G-001

6/20/2025 8:54:47 AM
\\act19501\engineering\FDZ\1628\STR\BLDG-1667770-S-BIM_V21_SENTRY.rvt

A

B

C

D

DELEGATED DESIGN

- FOUNDATION SUBGRADE IMPROVEMENT SYSTEM
- EXCAVATION DEWATERING AND EARTH RETENTION SYSTEM
- SUPPLEMENTARY FRAMING TO SUPPORT PIPES, DUCTS, MECHANICAL EQUIPMENT, ELECTRICAL EQUIPMENT, ETC.
- TEMPORARY SHORING AND BRACING
- STRUCTURAL STEEL CONNECTIONS
- BLAST RESISTANT STOREFRONT SYSTEM

CONSTRUCTION REQUIREMENTS

- REVIEW AND VERIFY EXISTING CONDITIONS AND DIMENSIONS PRIOR TO SUBMISSION OF SHOP DRAWINGS AND BEGINNING CONSTRUCTION.
- CONFIRM ACTUAL EQUIPMENT DIMENSIONS USING APPROVED MANUFACTURER/ VENDOR DRAWINGS PRIOR TO SUBMISSION OF SHOP DRAWINGS.
- DETERMINE AND COORDINATE THE SIZE & LOCATION OF CHASES, INSERTS, OPENINGS, SLEEVES, FINISHES, DEPRESSIONS, HOUSEKEEPING PADS, AND EQUIPMENT SUPPORTS (INCLUDING FOUNDATIONS) BEFORE SUBMITTING SHOP DRAWINGS.
- SUBMIT DIMENSIONED SHOP DRAWINGS SHOWING THE LOCATION OF SLEEVES AND OPENINGS THROUGH MASONRY WALLS, STRUCTURAL STEEL MEMBERS AND CONCRETE ELEMENTS. OPENINGS THROUGH A STRUCTURAL MEMBER MUST BE SHOWN ON THE SAME DRAWING. DRAWINGS ORGANIZED BY DISCIPLINE OR SUB-CONTRACTOR ARE NOT ACCEPTABLE. OPENINGS NOT SHOWN ON THE SHOP DRAWINGS REQUIRE THE WRITTEN APPROVAL OF THE COR BEFORE INSTALLATION.
- DO NOT FIELD CUT OR DRILL OPENINGS IN STRUCTURAL MEMBERS UNLESS INDICATED ON THE ACCEPTED SHOP DRAWINGS OR APPROVED BY THE COR.
- REFER TO THE ARCHITECTURAL DRAWINGS FOR DETAILED INFORMATION REGARDING FINISHES, WATERPROOFING, NON-BEARING MASONRY PARTITIONS, ETC.
- DO NOT SCALE DRAWINGS FOR THE PURPOSE OF ESTABLISHING DIMENSIONS.
- DO NOT CHANGE THE SIZE, DIMENSION OR POSITION OF STRUCTURAL ELEMENTS WITHOUT THE WRITTEN APPROVAL OF THE COR.
- DO NOT STORE OR STACK CONSTRUCTION MATERIALS ON FLOORS OR ROOFS IN EXCESS OF 80 PERCENT OF INDICATED LIVE LOAD.
- THE STRUCTURE IS DESIGNED TO BE STABLE IN THE COMPLETED CONDITION. PROVIDE BRACING AND SHORING TO MAINTAIN THE STABILITY OF THE STRUCTURE AND TO AVOID OVER-LOADING THE STRUCTURE DURING CONSTRUCTION. RETAIN A REGISTERED PROFESSIONAL OR STRUCTURAL ENGINEER TO DESIGN THE TEMPORARY SUPPORT SYSTEM AND ADVISE ON TEMPORARY LOADING CONDITIONS.

CODES AND STANDARDS

- THE FOLLOWING CODES AND STANDARDS, AS MODIFIED BY THE REFERENCED UFC PUBLICATIONS, APPLY TO THE DESIGN AND CONSTRUCTION OF THIS PROJECT:
- UFC 1-200-01, *DOD BUILDING CODE*, 1 SEPTEMBER 2022
 - UFC 3-301-01, *STRUCTURAL ENGINEERING*, CHANGE, 04 FEBRUARY 2022
 - ASCE 7-16, *MINIMUM DESIGN LOADS AND ASSOCIATED CRITERIA FOR BUILDINGS AND OTHER STRUCTURES*
 - IBC 2021, *INTERNATIONAL BUILDING CODE*
 - ACI 318-19, *BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE*
 - AISC 303-16, *CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES*
 - AISC 360-16, *SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS*
 - RCSC 2020, *SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS*
 - AWS D1.1-2020, *STRUCTURAL WELDING CODE - STEEL*
 - SDI C-2017, *STANDARD FOR COMPOSITE STEEL FLOOR DECK - SLABS*
 - NAVSEA OP5, *AMMUNITION AND EXPLOSIVES ASHORE SAFETY REGULATIONS FOR HANDLING, STORAGE, PRODUCTION, RENOVATION, & SHIPPING*

GENERAL NOTES

- ELEVATIONS NOTED ON THE STRUCTURAL DRAWINGS ARE RELATIVE TO TOP OF THE FIRST/GROUND FLOOR SLAB. SEE CIVIL DRAWINGS FOR THE ELEVATION OF THE FIRST/GROUND FLOOR RELATIVE TO MEAN SEA LEVEL.
- DETAILS LABELED "TYPICAL DETAILS" OR DETAILS ON SHEETS WHERE THE TITLE INCLUDES "TYPICAL DETAILS" APPLY TO SITUATIONS THAT ARE THE SAME OR SIMILAR TO THOSE SPECIFICALLY DETAILED. SUCH DETAILS AND DIMENSIONS APPLY WHETHER OR NOT DETAILS ARE REFERENCED AT EACH LOCATION.
- DETAILS NOT LABELED AS "TYPICAL" APPLY AT THE SPECIFIC LOCATIONS INDICATED AND OTHER SIMILAR CONDITIONS.
- SLOPING DECK PLANES ARE USUALLY DEFINED BY A WORK POINT ELEVATION AND A SLOPE OR A HIGH AND LOW POINT ELEVATION. STEEL MEMBERS SUPPORTING A SLOPING DECK PLANE HAVE THEIR TOP OF STEEL COINCIDENT WITH THE BOTTOM OF DECK, UON.
- DO NOT REPRODUCE THE STRUCTURAL DRAWINGS FOR USE AS SHOP DRAWINGS. SHOP DRAWINGS PREPARED IN SUCH A MANNER WILL BE REJECTED AND RETURNED WITHOUT REVIEW.

ABBREVIATIONS

ABV ABOVE
ACI AMERICAN CONCRETE INSTITUTE
ADDL ADDITIONAL
ADJ ADJACENT
AE AIR ENTRAINED
AFF ABOVE FINISHED FLOOR
AISC AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ALT ALTERNATE
ANSI AMERICAN NATIONAL STANDARDS INSTITUTE
APPROX APPROXIMATE
AR ANCHOR ROD
ARCH ARCHITECT or ARCHITECTURAL
ASCE AMERICAN SOCIETY OF CIVIL ENGINEERS
ASTM AMERICAN SOCIETY FOR TESTING & MATERIALS
AWS AMERICAN WELDING SOCIETY

B/ or BOT BOTTOM
BF BOTH FACES
BLDG BUILDING
BM BEAM
BOS BOTTOM OF STEEL
BP BEARING PLATE
BPL BASE PLATE
BRDG BRIDGING
BRG BEARING
BS BOTH SIDES
BTWN BETWEEN

¢ CENTERLINE
C/C CENTER TO CENTER
CANT CANTILEVER
CF CUBIC FEET
CFMF COLD-FORMED METAL FRAMING
CFRP CARBON FIBER REINFORCED POLYMER
CIP CAST-IN-PLACE
CJ CONTRACTION / CONTROL JOINT
CJP COMPLETE JOINT PENETRATION
CLR CLEAR
CMU CONCRETE MASONRY UNIT
CO CLEAN OUT
COL COLUMN
CONC CONCRETE
CONT CONTINUOUS
COORD COORDINATE
COR CONTRACTING OFFICER'S REPRESENTATIVE
CY CUBIC YARD

D DEPTH
db REINF BAR DIAMETER
DBA DEFORMED BAR ANCHOR
DEMO DEMOLITION
DIA or Ø DIAMETER
DIAG DIAGONAL
DIM DIMENSION
DL DEAD LOAD
DN DOWN
DWG(S) DRAWING(S)

(E) EXISTING
EA EACH
EE EACH END
EF EACH FACE
EJ EXPANSION JOINT
EL ELEVATION
ELEC ELECTRIC or ELECTRICAL
ELEV ELEVATOR
EMBED EMBEDMENT
EOD EDGE OF DECK
EOR ENGINEER OF RECORD
EOS EDGE OF SLAB
EQ EQUAL
EQUIP EQUIPMENT
ES EACH SIDE
EW EACH WAY
EXIST EXISTING
EXP EXPANSION
EXT EXTERIOR

FA FALL ARREST ANCHOR
FD FLOOR DRAIN
FDN FOUNDATION
FIN FINISH or FINISHED
FLG FLANGE
FLR FLOOR
FOW FACE OF WALL
FP FIRE PROTECTION
FRP FIBER REINFORCED POLYMER
FT FOOT or FEET
FTG FOOTING

GA GAGE or GAUGE
GALV GALVANIZED
GC GENERAL CONTRACTOR

H HIGH OR HORIZONTAL
HK HOOK
HORIZ HORIZONTAL
HP HIGH POINT
HS HIGH STRENGTH
HT HEIGHT

I INSIDE DIAMETER
IF INSIDE FACE
IN INCH
INCL INCLUDED
INFO INFORMATION
INT INTERIOR
IP INFLECTION POINT

J JOINT
JST JOIST

K KIPS (1000 POUNDS)
KB KNEE BRACE
KSF KIPS PER SQUARE FOOT
KSI KIPS PER SQUARE INCH

L POUND(S)
Ld REINF BAR DEVELOPMENT LENGTH
LE LEFT END
LL LIVE LOAD
LLH LONG LEG HORIZONTAL
LLV LONG LEG VERTICAL
LP LOW POINT
LTWT LIGHT WEIGHT

M MAXIMUM
MC MOMENT CONNECTION
MECH MECHANICAL
MEP MECHANICAL, ELECTRICAL AND PLUMBING
MID MIDDLE
MIN MINIMUM
MISC MISCELLANEOUS
MO MASONRY OPENING
MTL METAL
MWFRS MAIN WIND FORCE RESISTING SYSTEM

N NOT IN CONTRACT
NLWT NORMAL WEIGHT
NOM NOMINAL
NUMBER NUMBER
NTS NOT TO SCALE

O ON CENTER
OD OUTSIDE DIAMETER
OF OUTSIDE FACE
OPENING OPENING
OPP OPPOSITE OR OPPOSITE HAND

P POUNDS PER CUBIC FOOT
PEN PENETRATION
PJP PARTIAL JOINT PENETRATION
PL PLATE
PLUMB PLUMBING
PROJ PROJECTION
PS PRESTRESSED
PSF POUNDS PER SQUARE FOOT
PSI POUNDS PER SQUARE INCH

R RISER OR RADIUS
RE RIGHT END
REBAR REINFORCING STEEL BARS
REINF REINFORCEMENT or REINFORCING
RTU ROOF TOP UNIT

S SLIP CRITICAL
SCHEDULE SCHEDULE
SDI STEEL DECK INSTITUTE
SDL SUPERIMPOSED DEAD LOAD
SHT SHEET
SIM SIMILAR
SJI STEEL JOIST INSTITUTE
SFRS SEISMIC FORCE RESISTING SYSTEM
SOG SLAB-ON-GROUND
SQ SQUARE
SS STAINLESS STEEL
STD STANDARD
STL STEEL
STRUCT STRUCTURAL


T TREAD
T/ TOP
TEMP TEMPORARY
THK THICK or THICKNESS
TMS THE MASONRY SOCIETY
TOS TOP OF STEEL
TYP TYPICAL

U UNLESS OTHERWISE NOTED

V VERTICAL
VERT VERTICAL
VIF VERIFY IN FIELD

W WIDTH
W/ WITH
W/CM WATER-CEMENTITIOUS MATERIAL RATIO
W/O WITHOUT
WD WOOD
WP WORK POINT
WT WEIGHT
WWR WELDED WIRE REINFORCING

GRAPHIC LEGEND



SCALE: AS NOTED
EPROJECT NO.: 1667770
CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894091
SHEET 3 OF 65

S-001

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
GENERAL NOTES, ABBREVIATIONS & LEGEND

FOR COMMANDER NAVFAC
ACTIVITY APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT
SATISFACTORY TO DATE 05/27/2025
DES JH DRW JT CHK LP
PMID SMS/CWJ
BRANCH MANAGER NEK
CHIEF ENGINEER JMJ
FIRE PROTECTION HPN

Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600



SYN	DESCRIPTION	DATE	APPR

A

B

C

D

D

C

B

A

DESIGN CRITERIA & LOADS				
SUPERIMPOSED DEAD & LIVE LOADS (UNFACTORED - PSF)	ROOF ABOVE ELECTRIC ROOM			
	ROOF ABOVE SENTRY & TOILET ROOMS			
	ELECTRIC ROOM FLOOR			
	SENTRY & TOILET ROOM FLOOR			
ROOF MEMBRANE & INSULATION	5	5	----	----
CONCRETE ALLOWANCE FOR DECK DEFLECTION	5	5	----	----
MEP	10	5	----	----
CEILING	----	5	----	----
CONCRETE HOUSEKEEPING PAD (4" MINIMUM)	----	----	50	----
1. TOTAL SUPERIMPOSED DEAD LOAD	20	20	25	0
2. LIVE LOAD	20	20	125	75
3. BUILDING RISK CATEGORY	II			
4. SNOW				
a. SNOW IMPORTANCE FACTOR, Is	1.0			
b. GROUND SNOW LOAD, Pg	30 PSF			
c. TERRAIN ROUGHNESS	C			
d. ROOF EXPOSURE FACTOR, Ce	1.0 PARTIALLY EXPOSED			
e. THERMAL FACTOR, Ct	1.0			
f. ROOF SLOPE FACTOR, Cs	1.0			
g. FLAT-ROOF SNOW LOAD, Pf	21 PSF			
h. MINIMUM UNIFORM SNOW LOAD, Pm	20 PSF			
i. MAXIMUM DRIFT SURCHARGE	19 PSF			
j. TOTAL UNIFORM SNOW W/ DRIFT	39 PSF			
5. RAIN				
a. INTENSITY, i	2.75 IN/HOUR			
6. WIND				
a. ULTIMATE DESIGN WIND SPEED, V:	128 MPH			
b. ALLOWABLE STRESS WIND SPEED, Vasd:	99 MPH			
c. WIND EXPOSURE:	C			
d. INTERNAL PRESSURE COEF, GCpi	±0.18			
e. MAIN WIND-FORCE RESISTING SYSTEM				
• 0 FT - ROOF	31 PSF			
• PARAPET	70 PSF			
f. COMPONENTS & CLADDING	REFER TO TABLE 1			
7. EARTHQUAKE				
a. SEISMIC IMPORTANCE FACTOR	1.0			
b. SEISMIC SITE CLASSIFICATION	D			
c. MAPPED SPECTRAL ACCELERATION				
• SHORT PERIOD, S _s	0.190g			
• 1-SECOND PERIOD, S ₁	0.052g			
d. DESIGN SPECTRAL ACCELERATION				
• SHORT PERIOD, S _{0s}	0.203g			
• 1-SECOND PERIOD, S ₀₁	0.083g			
e. SEISMIC DESIGN CATEGORY	B			
f. SEISMIC FORCE-RESISTING SYSTEM	ORDINARY REINFORCED CONCRETE SHEAR WALLS			
g. RESPONSE MODIFICATION COEF, R	4			
h. SYSTEM OVERSTRENGTH COEF, Ω ₀	2.5			
i. DEFLECTION AMPLIFICATION COEF, C _d	4			
j. ANALYSIS PROCEDURE	EQUIVALENT LATERAL FORCE			
k. SEISMIC RESPONSE COEF, C _s	0.051			
l. SEISMIC WEIGHT, W	161 KIPS			
m. DESIGN BASE SHEAR	8.2 KIPS			
8. FOUNDATIONS				
a. MINIMUM SOIL BEARING CAPACITY	4,000 PSF			
b. FROST DEPTH	38 IN			

FIGURE 1 - DESIGN ROOF SNOW LOAD W/ DRIFT






TABLE 1 - COMPONENTS & CLADDING WIND PRESSURE (PSF)

ZONE		EFFECTIVE WIND AREA (SF)					
		≤10	20	50	100	200	≥500
ROOF	1	-57 / +16	-53 / +16	-48 / +16	-45 / +16	-41 / +16	-36 / +16
	2	-75 / +16	-70 / +16	-64 / +16	-59 / +16	-54 / +16	-48 / +16
	3	-102 / +16	-93 / +16	-80 / +16	-70 / +16	-61 / +16	-48 / +16
WALLS	4w	-36 / +33	-34 / +31	-32 / +30	-31 / +28	-29 / +27	-28 / +25
	5w	-44 / +33	-41 / +31	-37 / +30	-34 / +28	-31 / +27	-28 / +25
PARAPET	4p	-75 / +33	-70 / +31	-64 / +30	-59 / +28	-54 / +27	-48 / +25
	5p	-102 / +33	-93 / +31	-80 / +30	-70 / +28	-61 / +27	-48 / +25

1. FOR MEMBERS, THE EFFECTIVE WIND AREA IS THE SPAN LENGTH MULTIPLIED BY THE WIDTH, WHERE THE WIDTH EQUALS THE GREATER OF THE WIDTH TRIBUTARY TO THE MEMBER OR 1/3 THE SPAN LENGTH.
2. FOR FASTENERS, THE EFFECTIVE WIND AREA MUST NOT BE TAKEN GREATER THAN THE AREA THAT IS TRIBUTARY TO AN INDIVIDUAL FASTENER.
3. PRESSURES INDICATED ARE THE TOTAL APPLIED WIND PRESSURE AND INCLUDE BOTH THE INTERNAL AND EXTERNAL PRESSURES.
4. WIND PRESSURES ARE FACTORED LOADS.
5. POSITIVE VALUES INDICATE PRESSURE ACTING TOWARDS THE SURFACE AND NEGATIVE VALUES INDICATE PRESSURE ACTING AWAY FROM THE SURFACE.



SYN DESCRIPTION DATE APPR



Jacobs

1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED

AE INFO

FOR COMMANDER NAVFAC

ACTIVITY APPROVED BY LCDR ELIZABETH OLOKO
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES	JH	DRW	JT	CHK	LP
-----	----	-----	----	-----	----

BRANCH MANAGER SMS/CWJ

CHIEF ENGINEER NEK

PRE PROTECTION JMJ

HPN

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
DESIGN CRITERIA & LOADS

SCALE: AS NOTED

EPROJECT NO.: 1667770

CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894092

SHEET 4 OF 65

S-002



C1 ROOF
1/4" = 1'-0"



A1 FOUR
1/4" = 1'-0"

- A. TOP OF FIRST FLOOR SLAB, REFERENCE DATUM, IS ELEVATION 0' - 0". REFER TO CIVIL FOR THE ACTUAL FLOOR ELEVATION.
- B. T/FTG EL = [-2'-4"] UON.
- C. TOP OF STRUCTURAL STEEL IS 5-INCHES BELOW THE TOP OF THE CONCRETE ELEVATION INDICATED ON THE PLAN, UON.
- D. REFER TO S-000 SERIES DRAWINGS FOR GENERAL NOTES, DESIGN LOADS AND ABBREVIATIONS.
- E. REFER TO S-500 SERIES DRAWINGS FOR TYPICAL DETAILS.
- F. "Wfx" CONTINUOUS TYPE WALL FOUNDATIONS. REFER TO S-601 GEOMETRY AND REINFORCEMENT INFORMATION. CENTER WALL FOUNDATIONS ON WALL UNLESS NOTED OTHERWISE.

- 1 6" THICK SLAB-ON-GROUND W/ #4 @ 10" EW OVER VAPOR RETARDER OVER 6" POROUS FILL
- 2 SLAB-ON-GROUND CONTRACTION JOINT
- 3 3 1/2" NLWT CONCRETE W/ 6X6 - W2.1XW2.1 WWR ON 1 1/2", 20 GAUGE (0.0358"), COMPOSITE METAL DECK (5" TOTAL THICKNESS)
- 4 8" CAST-IN-PLACE CONCRETE WALL W/ #5@10" EACH WAY CENTERED IN WALL
- 5 5 1/2" CAST-IN-PLACE CONCRETE STEM WALL AT PERIMETER OF STRUCTURE, RE: C1/S-501
- 6 12"x12" CONCRETE PILASTER REINFORCED WITH 4-#7 (2 EF) W/ #3 TIES TOP 2 TIES SPACED @ 1 1/2", REMAINING SPACED @ 9", RE: C2/S-510

C

	AE INFO
APPROVED	

NAVFAC DRAWING NO.


12894094

SHEET 6 OF 65

0 101

S-101

6/20/2025 8:54:55 AM S-201
\\ac119301\l\enr\FDZ\EL628\STRUB\LDG-1667770-S-BIM_V21_SENTRY.rvt




NOTES:

1. C.J. INDICATES CONTROL JOINT LOCATIONS. AT CONTRACTOR'S OPTION, CONSTRUCTION JOINT MAY BE USED IN LIEU OF CONTROL JOINT AT INDICATED LOCATIONS. REFER TO S-503 FOR CONTROL JOINT INFORMATION.
2. ALL REINFORCEMENT SHOWN IN ELEVATION IS SUPPLEMENTAL TO SCHEDULED REINFORCEMENT. REFER TO S-101 FOR TYPICAL WALL REINFORCEMENT REQUIREMENTS.

C1 SOUTH ELEVATION

1/4" = 1'-0"




NOTES:

1. C.J. INDICATES CONTROL JOINT LOCATIONS. AT CONTRACTOR'S OPTION, CONSTRUCTION JOINT MAY BE USED IN LIEU OF CONTROL JOINT AT INDICATED LOCATIONS. REFER TO S-503 FOR CONTROL JOINT INFORMATION.
2. ALL REINFORCEMENT SHOWN IN ELEVATION IS SUPPLEMENTAL TO SCHEDULED REINFORCEMENT. REFER TO S-101 FOR TYPICAL WALL REINFORCEMENT REQUIREMENTS.

A1 NORTH ELEVATION

1/4" = 1'-0"




NOTES:

1. C.J. INDICATES CONTROL JOINT LOCATIONS. AT CONTRACTOR'S OPTION, CONSTRUCTION JOINT MAY BE USED IN LIEU OF CONTROL JOINT AT INDICATED LOCATIONS. REFER TO S-503 FOR CONTROL JOINT INFORMATION.
2. ALL REINFORCEMENT SHOWN IN ELEVATION IS SUPPLEMENTAL TO SCHEDULED REINFORCEMENT. REFER TO S-101 FOR TYPICAL WALL REINFORCEMENT REQUIREMENTS.

C3 WEST ELEVATION

1/4" = 1'-0"



NOTES:

1. C.J. INDICATES CONTROL JOINT LOCATIONS. AT CONTRACTOR'S OPTION, CONSTRUCTION JOINT MAY BE USED IN LIEU OF CONTROL JOINT AT INDICATED LOCATIONS. REFER TO S-503 FOR CONTROL JOINT INFORMATION.
2. ALL REINFORCEMENT SHOWN IN ELEVATION IS SUPPLEMENTAL TO SCHEDULED REINFORCEMENT. REFER TO S-101 FOR TYPICAL WALL REINFORCEMENT REQUIREMENTS.

A3 EAST ELEVATION

1/4" = 1'-0"

GENERAL SHEET NOTES

- A. TOP OF FIRST FLOOR SLAB, REFERENCE DATUM, IS ELEVATION 0' - 0". REFER TO CIVIL FOR THE ACTUAL FLOOR ELEVATION.
- B. REFER TO S-000 SERIES DRAWINGS FOR GENERAL NOTES, DESIGN LOADS AND ABBREVIATIONS.
- C. REFER TO S-500 SERIES DRAWINGS FOR TYPICAL DETAILS.

SHEET KEYNOTES

1. REFER TO B3/S-503 FOR ADDITIONAL REINF AT WALL PENETRATIONS
2. DOOR OPENING, COORDINATE ROUGH OPENING REQUIREMENTS WITH ARCHITECTURAL DRAWINGS
3. OPENING FOR ELECTRICAL DUCT BANK. COORDINATE SIZE AND LOCATION WITH ELECTRICAL. REFER TO B3/S-503 FOR ADDITIONAL REINF AT WALL PENETRATIONS
4. EMBEDDED C8x13.75 WITH A706 #5x2'-0" LONG ANCHOR CENTERED ON CHANNEL @ 10", RE:C3/S-510



SYN	DESCRIPTION	DATE	APPR



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY

APPROVED BY LCDR ELIZABETH

CLOKODE NAVFAC NLON FEAD

DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES JH DRW JT CHK LP

PMOM SMS/CWJ

BRANCH MANAGER NEK

CHIEF ENGINEER JMJ

FIRE PROTECTION HPN

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC

NAVAL STATION - NORFOLK, VA

MID-ATLANTIC

NAVAL SUBMARINE BASE NEW LONDON

GROTON, CONNECTICUT

P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

SENTRY

BUILDING ELEVATIONS

SCALE: AS NOTED

PROJECT NO.: 1667770

CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894095

SHEET 7 OF 65

S-201



B1 STEPPED WALL FOOTING



B2 PIPE BENEATH WALL FOOTING
NTS



S-501		FIRE PROTECTION	
		NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL STATION - NORFOLK, VA	
		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL SUBMARINE BASE NEW LONDON P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY SENTRY TYPICAL FOUNDATION & CONCRETE DETAILS	
		NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL STATION - NORFOLK, VA	
		NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL STATION - NORFOLK, VA	
SCALE: AS NOTED		FIRE PROTECTION	
EPROJECT NO. 1667770		FIRE PROTECTION	
CONSTR. CONTR. NO.		FIRE PROTECTION	
NAVFAC DRAWING NO. 12894096		FIRE PROTECTION	
SHEET 8 OF 65		FIRE PROTECTION	



SCALE: AS NOTED		
EPROJECT NO.:		1667770
CONSTR. CONTR. NO.		
NAVFAC DRAWING NO.		
		12894097
SHEET	9	OF 65
S-502		

6/20/2025 8:55:05 AM S-601
\\bcl1v901\dwg\p\FDZ\1628\STRUBLDG-166770-S-BIM_V21_SENTRY.rvt

D

C

B

A

1

2

3

4

5

1

2

3

4

5

CONCRETE WALL FOOTING SCHEDULE							
MARK	SIZE (UON)		BOTTOM REINFORCEMENT		TOP REINFORCEMENT		REMARKS
	WIDTH	THICKNESS	LONG BARS	SHORT BARS	LONG BARS	SHORT BARS	
WF-1	3' - 0"	1' - 4"	5 - #4	#5@6"	5 - #4	#5@6"	TERMINATE SHORT REINFORCEMENT USING STANDARD HOOK, LAP CORNER BARS USING L-BAR WITH TENSION LAP SPLICE AT EACH END OF BAR



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1600
FAX: 571.218.1600

APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE		05/27/2025			
DES	JH	DRW	JT	CHK	LP
PMIDM			SMS/CWJ		
BRANCH MANAGER			NEK		
CHIEF ENGINEER			JWJ		
FIRE PROTECTION			HPN		

DEPARTMENT OF THE NAVY	NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC	NAVAL STATION - NORFOLK, VA
MID-ATLANTIC	GROTON, CONNECTICUT
NAVAL SUBMARINE BASE NEW LONDON	NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY	SENTRY
SCHEDULES	

SCALE: AS NOTED	
EPROJECT NO.:	1667770
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	
12894101	
SHEET	13 OF 65


S-601

D

C


B

A



C3 SOUTHWEST ISOMETRIC

1		2		3		4		5	
ARCHITECTURAL SYMBOLS				MATERIALS LEGEND				GENERAL SHEET NOTES	
D	DETAIL NUMBER 1 A-501 SHEET WHERE DRAWN DETAIL TAG	ROOM NAME ROOM 101 ROOM NUMBER ROOM TAG	PHOTOGRAPH NUMBER A1 A-901 SHEET WHERE SHOWN PHOTOGRAPH TAG	SECTION WOOD - ROUGH WOOD BLOCKING PLYWOOD CONCRETE MASONRY UNIT BRICK CAST-IN-PLACE CONCRETE STEEL ARCHITECTURAL MASONRY UNIT GYPSUM BOARD BATT/LOOSE FILL INSULATION RIGID INSULATION SAND / MORTAR / PLASTER EARTH / COMPACT FILL POROUS FILL / GRAVEL ACOUSTICAL TILE CEILING CERAMIC TILE FINISHED WOOD PROTECTION BOARD ELEVATION EIFS - PAINTED ARCHITECTURAL MASONRY CMU - PAINTED GLAZED BLOCK GLAZING SPANDREL GLAZING / STEEL PANEL CONCRETE FOUNDATION		1 MATERIALS MUST BE NEW AND PROVIDED BY THE CONTRACTOR UNLESS SPECIFICALLY NOTED AS EXISTING OR AS PROVIDED BY THE GOVERNMENT. 2 WOOD BLOCKING AND MISCELLANEOUS STEEL SHOWN IN DETAILS AND SECTIONS MUST BE CONTINUOUS UNLESS SPECIFICALLY NOTED OTHERWISE. 3 VERIFY FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH THE WORK. DIMENSIONS FOR EXISTING WORK ARE INDICATED AS "±". ALL DISCREPANCIES MUST BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTING OFFICER IN WRITING. 4 STUDY AND COMPARE THE CONTRACT DOCUMENTS WITH EACH OTHER, AND AT ONCE, REPORT TO THE COR ANY ERRORS AND INCONSISTENCIES OR OMISSIONS DISCOVERED. ANY CONSTRUCTION ACTIVITY PERFORMED KNOWING IT INVOLVES A RECOGNIZED ERROR, INCONSISTENCY OR OMISSION IN THE CONTRACT DOCUMENTS WITHOUT SUCH NOTICE TO THE COR, THE CONTRACTOR WILL ASSUME RESPONSIBILITY FOR SUCH PERFORMANCE AND WILL BEAR THE AMOUNT OF THE COST OF THE CONSTRUCTION.			
	SECTION NUMBER A1 A-301 SHEET WHERE DRAWN WALL / PARTIAL BUILDING SECTION TAG	SECTION NUMBER A1 A-301 SHEET WHERE DRAWN BUILDING SECTION TAG	INTERIOR ELEVATION NUMBER A1 A-401 SHEET WHERE DRAWN INTERIOR ELEVATION TAG						
	SECTION NUMBER A1 A-301 SHEET WHERE DRAWN WALL / PARTIAL BUILDING SECTION TAG	KEYNOTE NUMBER 1 NEW WORK KEYNOTE TAG	SPECIALITY ITEM NUMBER 234 SPECIALITY ITEM TAG						
C	DIRECTION OF VIEW ELEVATION NUMBER A1 A-301 SHEET WHERE DRAWN EXTERIOR ELEVATION TAG	KEYNOTE NUMBER 1 DEMO KEYNOTE TAG	PARTITION IN PLAN PARTITION TYPE DESIGNATION (REFER TO PARTITION SCHEDULE) 33 PARTITION TYPE TAG						
	DOOR NUMBER (REFER TO DOOR SCHEDULE) 101 DOOR TAG	WINDOW TYPE LETTER B WINDOW TYPE TAG							
ARCHITECTURAL ABBREVIATIONS									
B	AB ANCHOR BOLT	CORR CORRIDOR	FTG FOOTING	OA OUTSIDE AIR	SH SHINGLES / SINGLE HUNG				
	ACS PNL ACCESS PANEL	CPT CARPET / COMMON PATH OF TRAVEL	GA GAUGE	OC ON CENTER	SIM SIMILAR				
	ADJ ADJUST	CT CERAMIC TILE	GALV GALVANIZED	OD OUTSIDE DIAMETER / DIMENSION	SPC SUSPENDED PLASTER CEILING				
	ALT ALTERNATE, ALTITUDE	CTR CENTER	GFCI GOVERNMENT FURNISHED CONTRACTOR INSTALLED	OPH OPPOSITE HAND	SPEC SPECIFICATION				
A	ALUM ALUMINUM	D DEPTH / DEEP	GL GLASS / GROUND LEVEL	OPNG OPENING	SQ SQUARE				
	ANOD ANODIZED	DEG DEGREE	GR GROSS	OPP OPPOSITE	STD STANDARD				
	APPROX APPROXIMATE	DEMO DEMOLITION	GSU GLAZED STRUCTURAL UNIT	OPT OPTIONAL	STOR STORAGE				
	ARCH ARCHITECT	DET DETAIL	GYP GYPSUM	PCT PERCENT	STR STRAIGHT STRIKE / STRINGERS				
	ASPH ASPHALT	DIA DIAMETER	H HIGH	PEJ PREMOLDED EXPANSION JOINT	SUSP SUSPENDED				
	ATC ACOUSTICAL TILE CEILING	DIM DIMENSION	HB HOSE BIB	PL PROPERTY LINE	T&B TOP AND BOTTOM				
	BD BOARD	DR DRAIN	HDW HARDWARE	PLAS PLASTER / PLASTIC	TEL TELEPHONE				
	BLDG BUILDING	DS DOWNSPOUT	HM HOLLOW METAL	PLYWD PLYWOOD	THRES THRESHOLD				
	BLW BELOW	DW DISHWASHER	HORIZ HORIZONTAL	PNL PANEL	THRU THROUGH				
	BM BEAM	DWG DRAWING	HT HEIGHT	PRELIM PRELIMINARY	TOS TOP OF SLAB / STEEL				
	BOS BOTTOM OF SLAB / STEEL	E EAST	HVY HEAVY	PSF POUNDS PER SQUARE FOOT	TYP TYPICAL				
	BOT BOTTOM	EA EACH	ID INSIDE DIAMETER	PSI POUNDS PER SQUARE INCH	UON UNLESS OTHERWISE NOTED				
	BRG BEARING	EIFS EXTERIOR INSULATION & FINISH SYSTEM	INSUL INSULATION / INSULATED	PT PAINT	V VOLT				
	BSMT BASEMENT	EJ EXPANSION JOINT	INT INTERIOR	QT QUARRY TILE	VAR VARIATION				
	BTWN BETWEEN	EL ELEVATION	J-BOX JUNCTION BOX	R RADUIS / RISER	VB VINYL BASE				
	C TO C CENTER TO CENTER	ELEC ELECTRIC / ELECTRICAL	JAN JANITOR CLOSET	RA RETURN AIR	VCT VINYL COMPOSITION TILE				
	CAB CABINET	EPDM ETHLENE PROPYLENE DIEN MONOMER	LAV LAVATORY	RAD RETURN AIR DUCT	VENT VENTILATION / VENTILATOR				
	CEM CEMENT	EQ EQUAL	LB POUND	RB RESILIENT BASE	VERT VERTICAL				
	CER CERAMIC	EQUIP EQUIPMENT	LT LIGHT	RD ROOF DRAIN / ROAD	VEST VESTIBULE				
	CI CAST IRON	EW EACH WAY	MACH MACHINE	REFL REFLECT	VS VENT STACK				
	CIP CAST IRON PIPE	EWC ELECTRIC WATER COOLER	MATL MATERIAL	REFR REFRIGERATION	VTR VENT THROUGH ROOF				
	CJ CONTROL / CONSTRUCTION JOINT	EXH EXHAUST	MAX MAXIMUM	REINF REINFORCE	VWC VINYL WALL COVERING				
	CLG CEILING	EXIST EXISTING	MECH MECHANICAL	REQD REQUIRED	W WASTE / WATT / WEST / WIDE				
	CLG REG CEILING REGISTER	EXP EXPANSION / EXPOSED / EXPAND	MFG MANUFACTURING	REV REVISION	W/ WITH				
	CLR CLEAR	EXT EXTERIOR	MIN MINIMUM / MINUTE	RF RESILIENT FLOORING	W/O WITHOUT				
	CMU CONCRETE MASONRY UNIT	FD FLOOR DRAIN	MISC MISCELLANEOUS	RL ROOF LEADER	WC WATER CLOSET / WALL COVERING				
	CND CONDUIT	FDTN FOUNDATION	ML MATCH LINE	RM ROOM	WD WOOD				
	CNDS CONDENSATE	FF FINISH FACE	MO MASONRY OPENING / MOTOR OPERATED	RND ROUND	WH WATER HEATER				
	CNSTR CONSTRUCTION	FG FIGURE	MTD MOUNTED	RO ROUGH OPENING	WP WATERPROOFING / WEATHERPROOF / WORKING POINT				
	CNTR CNTR	FHC FIRE HOUSE CABINET	MTG MOUNTING / MEETING	RS ROUGH SAWN	WSCT WAINSCOT				
	CO CLEANOUT	FIN FLR FINISHED FLOOR	MTL METAL	RT RIGHT	WT WEIGHT				
	COL COLUMN	FOF FACE OF FINISH	MWP MEMBRANE WATERPROOFING	S SOUTH	WWF WELDED WIRE FABRIC				
	CONC CONCRETE	FOM FACE OF MASONRY	N NORTH	SAPC SUSPENDED ACOUSTICAL PANEL CEILING	XRMR TRANSFORMER				
	CONN CONNECT	FOS FACE OF STUB / FACE OF SLAB	NIC NOT IN CONTRACT	SCHED SCHEDULE					
	CONT CONTINUE / CONTINUOUS	FR FRAME / FIRE RATING / FIRE RESISTANT	NO NUMBER	SECT SECTION					
	COR CONTRACTING OFFICER REPRESENTATIVE	FT FOOT, FEET	NOM NOMINAL	SF SQUARE FOOT					
1		2		3		4		5	



APPROVED

FOR COMMANDER NAVFAC
ACTIVITY APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON READ DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025




DES PS DRW PS CHK WS
BRANCH MANAGER SMS/CWJ
CHIEF ENGINEER JWC
FIRE PROTECTION HPN

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
ARCHITECTURAL NOTES AND SYMBOLS




SCALE: AS NOTED
EPROJECT NO.: 1667770
CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894103
SHEET 15 OF 65


A-001



C1 ACCESSIBLE DOOR CLEARANCES











C3 AMBULATORY ACCESSIBLE TOILET STALL
1/2" = 1'-0"




ABAAS CH.604

NOTE: WHERE A LAV INCLUDED WITHIN A TOILET STALL, THE REQUIREMENTS FOR AN ACCESSIBLE TOILET ROOM AND CH.603 APPLY



A1 ACCESSIBLE MOUNTING HEIGHTS

[illegible]


Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY					
APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE				05/27/2025	
DES	PS	DRW	PS	CHK	WS
PMDDM				SMS/CWJ	
BRANCH MANAGER				DJD	
CHIEF ENGIAR				JWJ	
FIRE PROTECTION				HPN	


DEPARTMENT OF THE NAVY	NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC	NAVAL STATION - NORFOLK, VA
MID-ATLANTIC	
NAVAL SUBMARINE BASE NEW LONDON	GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY	
SENTRY	
ARCHITECTURAL ACCESSIBILITY STANDARDS & MOUNTING HEIGHTS	

SCALE: AS NOTED		
EPROJECT NO.: 1667770		
CONSTR. CONTR. NO.		
NAVFAC DRAWING NO.		
12894104		
SHEET	16	OF 65
A-002		


6/19/2025 4:44:27 PM A-101
\\ac119501\\img\\pfd\\21628\\AFCH\\BLDG-166770-A-BLM_SENTRY.rvt



C1 ROOF PLAN
1/4" = 1'-0"



A1 FLOOR PLAN
1/4" = 1'-0"



A3 REFLECTED CEILING PLAN
1/4" = 1'-0"

TOILET ACCESSORIES (TBA) SCHEDULE			
ITEM #	DESCRIPTION	FINISH	REMARKS
TBA-01	GRAB BAR	STAINLESS STEEL	18" VERTICAL, 36", 42"
TBA-02	SURFACE MOUNTED SOAP DISPENSER	STAINLESS STEEL	
TBA-03	HOOK	STAINLESS STEEL	
TBA-04	RECESSED PAPER TOWEL DISPENSER AND WASTE RECEPTACLE	STAINLESS STEEL	
TBA-05	RECESSED SEAT COVER DISPENSER	STAINLESS STEEL	
TBA-06	SURFACE MOUNTED MULTI-ROLL TOILET TISSUE DISPENSER	STAINLESS STEEL	
TBA-07	MIRROR		24" W x 36" H

GENERAL SHEET NOTES

- LOCATE EDGE OF DOOR JAMBS 6" OFF THE FINISHED FACE OF ADJACENT GYPSUM BOARD PARTITION UNLESS OTHERWISE NOTED.
- EXTERIOR DIMENSIONS ARE FROM CONCRETE AND ROUGH OPENINGS. DIMENSION STRINGS ON ENDS OF BUILDING ARE TO OUTSIDE FINISH MATERIAL.
- INTERIOR DIMENSIONS ARE FROM METAL STUD TO METAL STUD, OR CONCRETE UNLESS NOTED OTHERWISE.
- DIFFERENT FLOOR FINISH MATERIALS MUST MEET UNDER THE CENTERLINES OF DOORS UNLESS OTHERWISE NOTED.
- PARTITION / WALL MOUNTED EQUIPMENT NOT INDICATED ON THE DRAWINGS MUST BE COORDINATED WITH THE COR PRIOR TO INSTALLATION.
- REFER TO PLUMBING, MECHANICAL, ELECTRICAL, FIRE SUPPRESSION, FIRE ALARM AND TELECOMMUNICATION DRAWINGS FOR VENTS, SPRINKLER HEADS, GRILLES, REGISTERS, DIFFUSERS, DUCTS, LIGHTS, DETECTORS, ETC AND COORDINATE BETWEEN DISCIPLINES.
- CEILING HEIGHTS TO BE 10'-0" AFF. UON.
- CENTER CEILING MOUNTED FIXTURES (SPRINKLER HEADS, SMOKE AND HEAT DETECTORS, OCCUPANCY SENSORS, ETC.) UON.
- ROOF TO BE A FULLY ADHERED TPO ROOFING SYSTEM.
- ROOF SYSTEMS MUST BE FURNISHED AND INSTALLED PER ROOF MANUFACTURER'S INSTRUCTIONS AND STANDARDS.
- STAGGER ROOF INSULATION JOINTS. INSULATION JOINTS GREATER THAN 1/4" MUST BE FILLED WITH INSULATION STRIPS.
- ROOF MUST HAVE A CONTINUOUS MINIMUM VALUE OF R-35 INSULATION.
- CRICKET SLOPE MUST BE 1" PER 1'-0".
- REFER TO A-002 FOR TYPICAL TOILET ACCESSORY/ FIXTURE MOUNTING HEIGHTS.
- PROVIDE BLOCKING FOR INSTALLATION OF EQUIPMENT.

SHEET KEYNOTES

- BLAST RESISTANT STOREFRONT SYSTEM
- THROUGH WALL SCUPPER W/ CONDUCTOR HEAD, TYP
- PREFINISHED SLOPED METAL COPING (MTL-1)
- ROOF CRICKET, TYP
- LIGHTNING PROTECTION, TYP. REFER TO ELECTRICAL
- COUNTERTOP, REFER TO INTERIORS
- DOWNSPOUT (MTL-3) W/ CONCRETE SPLASHBLOCK, TYP

REFLECTED CEILING PLAN LEGEND

SYMBOL	DESCRIPTION
	AREA NOT IN CONTRACT
	NO CEILING - EXPOSED TO ROOF DECK ABOVE
	2' - 0" X 2' - 0" ACOUSTICAL CEILING TILE
	GYPSUM BOARD CEILING.
(X'-X")	FINISHED CEILING HEIGHT ABOVE FINISHED FLOOR
	LIGHT FIXTURE - REFER TO ELECTRICAL DRAWINGS
	EMERGENCY LIGHT FIXTURE - REFER TO ELECTRICAL DRAWINGS
	EXIT SIGN - REFER TO ELECTRICAL DRAWINGS
	OCCUPANCY/ VACANCY SENSOR. REFER TO ELECTRICAL DRAWINGS.
	CEILING SUPPLY DIFFUSER. REFER TO MECHANICAL DRAWINGS.
	CEILING RETURN OR EXHAUST. REFER TO MECHANICAL DRAWINGS.

0 2' 4' 8' 12'
1/4" = 1'-0"



APPR	DATE	SYN	DESCRIPTION
Jacobs 1100 NORTH GLEBE ROAD SUITE 500 ARLINGTON, VIRGINIA 22201 571.218.1000 FAX: 571.218.1600			
APPROVED			
FOR COMMANDER NAVFAC			
ACTIVITY: APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON HEAD DIRECTOR NEW LONDON, GROTON, CT			
SATISFACTORY TO DATE: 05/27/2025			
DES	PS	DRW	PS
PS	PS	PS	PS
BRANCH MANAGER: DJD			
CHIEF ENGINEER: JMJ			
PRE-PROTECTION: HPN			
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL STATION - NORFOLK, VA			
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC NAVAL SUBMARINE BASE NEW LONDON P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY SENTRY			
ARCHITECTURAL FLOOR PLANS			
SCALE: AS NOTED			
EPROJECT NO.: 1667770			
CONSTR. CONTR. NO.			
NAVFAC DRAWING NO.: 12894105			
SHEET 17 OF 65			
A-101			


6/30/2025 4:44:52 PM A-201
\\06119501\\0609\\FDZELG2BAPCHBLDG-1667770-A-BIM_SENTRY.rvt

D


C

B


A




C1 NORTH ELEVATION
1/4" = 1'-0"



C3 EAST ELEVATION
1/4" = 1'-0"



A1 SOUTH ELEVATION
1/4" = 1'-0"




A3 WEST ELEVATION
1/4" = 1'-0"

GENERAL SHEET NOTES

- A. DOWNSPOUT DISCHARGE TO BE DETERMINED FOR NEXT SUBMISSION
B. REFER TO SHEET A-603 FOR EXTERIOR FINISHES AND ARCHITECTURAL CMU PATTERN, FINISH, AND COLOR

SHEET KEYNOTES

- 1 PREFINISHED SLOPED METAL COPING (MTL-1)
2 ARCHITECTURAL CMU
3 BLAST RESISTANT STOREFRONT SYSTEM
4 EXTERIOR LIGHTING, TYP
5 CONDUCTOR HEAD, TYP
6 LIGHTNING PROTECTION, TYP. REFER TO ELECTRICAL
7 OVERFLOW SCUPPER. LOCATE 2" ABOVE ROOF SURFACE, TYP
8 DOWNSPOUT (MTL-3) W/ CONCRETE SPLASHBLOCK, TYP
9 GALVANIZED STEEL COVER AROUND REFRIGERANT PIPING, TYP. REFER TO MECHANICAL. FINISH TO MATCH METAL COPING
10 EXTERIOR BUILDING SIGNAGE



Jacobs

1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1600
FAX: 571.218.1600

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY APPROVED BY LCDR ELIZABETH
CLOKODE NAVFAC NLON FEAD
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES PS DRW PS CHK WS

PMOM SMS/CWJ

BRANCH MANAGER DJD

CHIEF ENGINEER JWJ

FIRE PROTECTION HPN

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC

NAVAL STATION - NORFOLK, VA

NAVAL SUBMARINE BASE NEW LONDON

GROTON, CONNECTICUT

P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

SENTRY

ARCHITECTURAL EXTERIOR ELEVATIONS

SCALE: AS NOTED

PROJECT NO.: 1667770

CONSTR. CONTR. NO.

NAVFAC DRAWING NO. 12894106

SHEET 18 OF 65

A-201

1

2

3

4

5

SHEET KEYNOTES

- 1 CONCRETE SLAB, REFER STRUCTURAL
- 2 CONCRETE FOOTING, REFER TO STRUCTURAL
- 3 GRAVEL
- 4 STRUCTURAL STEEL FRAMING, REFER TO STRUCTURAL
- 5 SCHEDULED CEILING
- 6 PREFINISHED SLOPED METAL COPING (MTL-1) (BEYOND)
- 7 CASEWORK (BEYOND), REFER TO INTERIORS
- 8 COUNTERTOP, REFER TO INTERIORS
- 9 LIGHTNING PROTECTION, TYP. REFER TO ELECTRICAL

#	SYN	DESCRIPTION	DATE	APPR



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600


APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY					
APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE				05/27/2025	
DES	PS	DRW	PS	CHK	WS
PM/DM				SMS/CWJ	
BRANCH MANAGER				DJD	
CHIEF ENGINEER				JWJ	
FIRE PROTECTION				HPN	

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
GROTON, CONNECTICUT
SENTRY
ARCHITECTURAL BUILDING SECTIONS

SCALE: AS NOTED
PROJECT NO.: 1667770
CONSTR. CONTR. NO.
NAVFAC DRAWING NO. 12894107
SHEET 19 OF 65
A-301

D


C



C1 BUILDING SECTION
1/4" = 1'-0"

B

A



A1 BUILDING SECTION
1/4" = 1'-0"



1

2



3

4


5

A. REFER TO STRUCTURAL FOR ADDITIONAL INFORMATION.


- 1 AIRSPACE
- 2 AIR BARRIER/ VAPOR RETARDER
- 3 SCHEDULED PARTITION
- 4 SCHEDULED CEILING
- 5 2-1/2" CAST-IN-PLACE CONCRETE SLAB OVER METAL DECKING
- 6 CONCRETE SLAB, REFER STRUCTURAL
- 7 CONCRETE FOOTING, REFER TO STRUCTURAL
- 8 ARCHITECTURAL CMU
- 9 EXTERIOR LIGHTING, TYP
- 10 CONCRETE SIDEWALK (SLOPE AWAY FROM BUILDING), REFER TO CIVIL
- 11 DAMPPROOFING
- 12 BLAST RESISTANT STOREFRONT SYSTEM
- 13 SCHEDULED PARTITION (BEYOND)
- 14 PREFINISHED SLOPED METAL COPING (MTL-1)
- 15 5/8" COVER BOARD
- 16 FULLY ADHERED TPO MEMBRANE
- 17 R-35 CONT RIGID INSULATION
- 18 CAST-IN-PLACE CONCRETE, REFER TO STRUCTURAL
- 19 THERMALLY BROKEN VENEER ANCHOR, TYP
- 20 TPO MEMBRANE ADHERED TO WALL. EXTEND UP AND OVER COPING
BLOCKING AND TERMINATE ON FACE OF COPING BLOCKING
- 21 WEEP VENT INSERTS AT 24" OC
- 22 R-13.3 FOIL-FACED CONT RIGID INSULATION



6/19/2025 4:44:50 PM A-503
\\bcl1p501\lhp\pfd\21628AFACH\BLOG-167770-A-BM_SENTRY.rvt



SYN	DESCRIPTION	DATE	APPR



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600


APPROVED
AE INFO

FOR COMMANDER NAVFAC					
ACTIVITY: APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON HEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE	05/27/2025	DES	PS	DRW	PS
PM/DM	SMS/CWJ	CHK	WS		
BRANCH MANAGER	DJD				
CHIEF ENGINEER	JWJ				
FIRE PROTECTION	HPN				


DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
GROTON, CONNECTICUT
SENTRY
OPENING DETAILS

SCALE: AS NOTED	
EPROJECT NO.:	1667770
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	12894111
SHEET	23 OF 65
A-503	


DOOR SCHEDULE														
DOOR NO.	DOOR						FRAME					FIRE RATING	HARDWARE SET NO.	REMARKS
	TYPE	SIZE			MATERIAL	GLAZING	TYPE	MATERIAL	DETAILS					
		WIDTH	HEIGHT	THICKNESS					HEAD	JAMB	SILL			
FIRST FLOOR														
001A	B	3'-0"	7'-0"	1 3/4"	AL	ATFP	F1	AL	C2/A-503	B2/A-503	A2/A-503	NR	1	STOREFRONT
001B	B	3'-6"	7'-0"	1 3/4"	AL	ATFP	F1	AL	C2/A-503	B2/A-503	A2/A-503	NR	1	STOREFRONT
002	A	3'-0"	7'-0"	1 3/4"	HM	-	F1	HM	C5/A-503	C5/A-503	-	NR	17	
003	A	3'-6"	7'-0"	1 3/4"	HM	-	F1	HM	C5/A-503	C5/A-503	-	NR	8	
004	A	3'-0"	7'-0"	1 3/4"	HM	-	F2	HM	C1/A-503	B1/A-503	A2/A-503 SIM	NR	7	
LOUVER SCHEDULE														
TYPE	SIZE		LOUVER DETAILS			REMARKS								
	WIDTH	HEIGHT	HEAD	JAMB	SILL									
L1	1'-0"	1'-0"	C3/A-503	B3/A-503	A3/A-503	WIND DRIVEN RAIN LOUVER WITH BIRD SCREEN, COORDINATE LOUVER LOCATION WITH MECHANICAL, BOTTOM OF LOUVER MUST BE 10'-0" ABOVE GRADE, MIN.								



C3 STOREFRONT ELEVATION - EAST
1/4" = 1'-0" (A-201)



A3 BUILDING SIGNAGE
1 1/2" = 1'-0"



GENERAL SHEET NOTES

A. REFER TO 08 71 00 FOR DOOR HARDWARE SETS.

#	PATTERN
AB-1	
AB-2	
AB-3	
AB-4	
AB-5	
AB-6	

LEGEND



Jacobs

1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED

FOR COMMANDER NAVFA.

APPROVED BY LCDR ELIZABETH
OLOKODE NAVFAC NLON FEAD
DIRECTOR NEW LONDON, GROTON.

DES	PS	DRW	PS	CHK	W
-----	----	-----	----	-----	---

PM/DN	3M3J
BRANCH MANAGER	

CHIEF ENG/ARCH

D	A	T	
---	---	---	--

IC	DLK,	FIG	ITY
----	------	-----	-----

AN
ORI
NE
CI

STE
ATI
DN -
CO
SF

	NO	NO
MID		
STAT		
IG S		

DEER	D -	VAL	RO	AT
------	-----	-----	----	----

MAINTENANCE

FO	
MC	

ACI	NC	FD
SO		

WAL
TEN
INC
Y
CORP

OF
ENT
DAN

NG	ON	8	'	OT
----	----	---	---	----

10

AIN	W L	GA	AF
-----	-----	----	----

EN	EN	M
----	----	---

BA:	ON
-----	----

HEI
CIL
RINEE
AP

OF	FA	MA	WI
----	----	----	----

MEI	SL
VAN	102
ANT	

NPAT
D-AT
AV
P-

SCALE: AS NOTED

PROJECT NO.: 1667770

12804112

SHEET 24 OF 65

A-601

CODE	COUNT	DESCRIPTION	PROVIDED/INSTALLED	COMMENTS
FURNITURE FIXTURES & EQUIPMENT (FF&E) & COLLATERAL EQUIPMENT (CEQ) PACKAGE				
AC01	1	WALL CLOCK	FF&E CEQ PACKAGE	
AC03	1	WASTE & RECYCLING STATION	FF&E CEQ PACKAGE	
AC06	1	MARKERBOARD, 72"W X 48"H	FF&E CEQ PACKAGE	
C01	1	TASK CHAIR	FF&E CEQ PACKAGE	
EQ02	2	FLOOR MAT	FF&E CEQ PACKAGE	

PLAN
NORTH

SCALE: AS NOTED		
EPROJECT NO.:		1667770
CONSTR. CONTR. NO.		
NAVFAC DRAWING NO.		
		12894114
SHEET	26	OF 65
I-101		

6/30/2025 4:42:27 PM
\\06119501\\0609\\FD2E162BAFACHBLOG-166770-A-BM_SENTRY.rvt

I-102

A


B

C

D

ROOM FINISH SCHEDULE						
ROOM		FLOOR FINISH	BASE FINISH	WALL FINISH	CEILING FINISH	NOTES
NO.	NAME					
001	GATE / SENTRY HOUSE	RF-1	RB-1	PT-4	ACP-1	SS-1 AT COUNTERTOP, PL-1 AT MILLWORK
002	TOILET	PFT-1	MCB-1	PWT-1, PWT-2	ACP-3	
003	ELECTRICAL	SC-1	N/A	EXP	EXP	
004	PLUMBING	SC-1	N/A	EXP	EXP	

B1 FINISH PLAN
1/4" = 1'-0" (A-201)



FINISH GENERAL NOTES

- A. REFER TO SHEET I-601 OF THE OPERATIONS BUILDING DRAWINGS FOR INTERIOR MATERIALS FINISH SCHEDULE.
- B. REFER TO ARCHITECTURE DRAWINGS FOR REFLECTED CEILING PLANS AND DETAILS.
- C. FIELD VERIFY DIMENSIONS PRIOR TO ORDERING MATERIALS AND FINISHES.
- D. TRANSITIONS OCCUR AT THE CENTERLINE OF THE DOOR, DOORWAY OR CEILING LINE, UNLESS OTHERWISE NOTED.

SHEET KEYNOTES

- 1 PROVIDE WINDOW BLINDS WB-1 AT WINDOW EXTENTS.


FINISH LEGEND

- PFT-1
RF-1
SC-1

FINISH ABBREVIATIONS

- CEILING FINISHES**
ACP ACOUSTICAL CEILING PANEL
EXP EXPOSED TO STRUCTURE
- WALL FINISHES**
PT PAINT
PWT PORCELAIN WALL TILE
- BASE FINISHES**
MCB METAL COVE BASE
RB RESILIENT BASE
- FLOOR FINISHES**
PFT PORCELAIN FLOOR TILE
RF RESILIENT FLOORING
SC SEALED CONCRETE

0 2' 4' 8' 12'
1/4" = 1'-0"



SYM	DESCRIPTION	DATE	APPR




Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED					
FOR COMMANDER NAVFAC					
ACTIVITY APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT					
SATISFACTORY TO DATE 05/27/2025					
DES	NM	DRW	AW	CHK	AB
PWDM SMS/CWJ				DJD	
BRANCH MANAGER				JWJ	
CHIEF ENGINEER				HPN	
FIRE PROTECTION					

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
INTERIOR FINISH PLAN & ROOM FINISH SCHEDULE

SCALE: AS NOTED	
EPROJECT NO.:	1667770
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	12894115
SHEET 27 OF 65	


I-102



NOTES:


1. MOUNTING OPTIONS VARY PER SIGN TYPE.
2. WHERE THERE IS LESS THAN 18" CLEAR SPACE ON THE LATCH SIDE OF A SINGLE DOOR, OR ON THE RIGHT SIDE OF DOUBLE DOORS, SIGNS ARE LOCATED TO THE NEAREST ADJACENT WALL.
3. WHERE THERE IS A SIDE LIGHT WINDOW LOCATED ADJACENT TO THE DOOR, MOUNT THE SIGN TO THE GLASS AND PROVIDE A BACKER PLATE OF THE SAME SHAPE AND BACKGROUND COLORS AS THE SIGN ON THE GLASS TO CONCEAL MOUNTING DEVICE.
4. ATTACH SIGNAGE WITH REMOVABLE DOUBLE SIDED TAPE PRIOR TO PERMANENT INSTALLATION. COR TO REVIEW AND PROVIDE APPROVAL PRIOR TO PERMANENT INSTALLATION.

C1 TYPICAL SIGN MOUNTING

$$1/2'' = 1'-0''$$


S1 UTILITY SIGN


S2 EXTERIOR PERMANENT
ROOM SIGN



S5U UNISEX RESTROOM SIGN


S9 REGULATORY SIGN

R1 SIGN TYPE DETAILS


$$3'' = 1'-0''$$


① MILLWORK SECTION AT BOX/FLIE/FILE

1 1/2" = 1'-0"



42 MILLWORK SECTION AT DESK

$$1\frac{1}{2}'' = 1'-0''$$
[illegible]

Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED

AF INFO

FOR COMMANDER NAVFAC

ACTIVITY
APPROVED BY LCDR ELIZABETH
OLOKODE NAVFAC NLON FEAD
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES	NM	DRW	AW	CHK	AB
-----	----	-----	----	-----	----

PM/DM	SMS/CW
-------	--------

BRANCH MANAGER	D1
----------------	----

CHIEF ENG/ARCH	14
----------------	----

CHIEF ENGINEER	JW
FIRE PROTECTION	HD

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
GROTON, CONNECTICUT
ORDNANCE OPERATIONS FACILITY
CENTRY
FOR DETAILS

SCALE: AS NOTED


















PROJECT NO :	1667770
--------------	---------

CONSTR. CONTR. NO.

NAVEAC DRAWING NO.

SHEET 30 OF 65

I-501



PLUMBING LEGEND			
	2-WAY VALVE		DCW DOMESTIC COLD WATER PIPING
	3-WAY VALVE		DHW DOMESTIC HOT WATER PIPNG
	AUTOMATIC AIR VENT		DHWL DOMESTIC HOT WATER RETURN PIPING
	AUTOMATIC BALANCING VALVE		SS SOIL, WASTE OR SANITARY SEWER PIPING
	BACKFLOW PREVENTER		SD RAIN LEADER - PRIMARY STORM DRAINAGE
	BALL VALVE		OD RAIN LEADER - OVERFLOW STORM DRAINAGE
	BUTTERFLY VALVE		V VENT PIPING
	CHECK VALVE		CA COMPRESSED AIR PIPING
	DOWNWARD SLOPE		
	DRAIN VALVE		THIN LINE WEIGHT INDICATES EXISTING ITEM TO REMAIN
	CONCENTRIC REDUCER		HEAVY LINE WEIGHT INDICATES NEW WORK TO BE PROVIDED
	ECCENTRIC REDUCER		HEAVY DASHED LINE WEIGHT INDICATES EXISTING ITEM TO REMOVE, REFER TO DEMOLITION NOTES
	FLANGE		
	FLOOR CLEAN OUT		
	FLOOR DRAIN		
	GAS OR WATER METER		
	GATE VALVE		
	GLOBE VALVE		
	ISOLATION VALVE		
	MANUAL AIR VENT		
	MANUAL FLOW CONTROL BALANCING VALVE		
	PIPE CAP		
	PIPE DOWN		
	PIPE UP		
	PRESSURE GAUGE WITH SHUTOFF COCK		
	PRESSURE REDUCING VALVE		
	RELIEF VALVE		
	SOLENOID VALVE		
	SQAURE HEAD BALANCING VALVE		
	STRAINER WITH BLOWDOWN VALVE		
	TEMPERATURE PRESSURE RELIEF VALVE		
	UNION		
	WALL CLEAN OUT		
	WATER METER		
	WATER PUMP		
	WYE STRAINER		
	POINT OF DISCONNECTION		
	POINT OF CONNECTION		

NOTE:
NOT ALL ABBREVIATIONS
& SYMBOLS MAY BE USED.

PLUMBING ABBREVIATIONS		
ABA	ARCHITECTURAL BARRIERS ACT	
ADA	AMERICANS WITH DISABILITIES ACT	
AFF	ABOVE FINISHED FLOOR	
AFG	ABOVE FINISHED GRADE	
AMI	ADVANCED METERING INFRASTRUCTURE	
AP	ACCESS PANEL	
BF	BELOW FLOOR	
BFF	BELOW FINISHED FLOOR	
BFP	BACKFLOW PREVENTER	
BG	BELOW GRADE	
BTUH	BRITISH THERMAL UNIT PER HOUR	
CLG	CEILING	
CO	CLEANOUT	
COR	CONTRACTING OFFICER'S REPRESENTATIVE	
DCW	DOMESTIC COLD WATER	
DFU	DRAINAGE FIXTURE UNITS	
DHW	DOMESTIC HOT WATER	
DHWH	DOMESTIC HOT WATER HEATER	
DWV	DRAIN, WASTE, VENT	
EA	EACH	
EFF	EFFICIENCY	
ELEV	ELEVATION	
EQUIP	EQUIPMENT	
ET	EXPANSION TANK	
EWC	ELECTRIC WATER COOLER	
F	FAHRENHEIT	
FCO	FLOOR CLEANOUT	
FD	FLOOR DRAIN	
FLA	FULL LOAD AMPS	
FT	FEET	
GAL	GALLON	
GFCI	GOVERNMENT FURNISHED, CONTRACTOR INSTALLED	
GPH	GALLONS PER HOUR	
GPM	GALLONS PER MINUTE	
H x W	HEIGHT AND WIDTH	
HB	HOSE BIB	
HP	HORSEPOWER	
I.E.	INVERT ELEVATION	
IN.	INCHES	
KS	KITCHEN SINK	
KW	KILOWATTS	
LAV OR L	LAVATORY	
MAX	MAXIMUM	
MIN	MINIMUM	
MS	MOP SINK	
N.C.	NORMALLY CLOSED	
N.O.	NORMALLY OPEN	
NFHB	NON-FREEZE HOSE BIBB	
OD	OVERFLOW DRAIN	
PH	PHASE	
PSI	POUNDS PER SQUARE INCH	
RD	ROOF DRAIN	
REF	REFRIGERATOR	
RL	ROOF LEADER	
RPM	REVOLUTIONS PER MINUTE	
RPZ	REDUCED PRESSURE ZONE BACKFLOW PREVENTER	
SAN OR SS	SANITARY	
SF	SQUARE FEET	
SH	SHOWER	
SIM	SIMILAR	
SOV	LINE SIZE, FULL OPEN PORT SHUT OFF VALVE	
SS	SERVICE SINK	
TAB	TESTING, ADJUSTING, BALANCING	
TMV	THERMOSTATIC MIXING VALVE	
TP	TRAP PRIMER	
TYP	TYPICAL	
U	URINAL	
U.O.N.	UNLESS OTHERWISE NOTED	
V	VENT	
VTR	VENT THROUGH ROOF	
W	WASTE	
WI	WITH	
WC	WATER CLOSET	
WCO	WALL CLEANOUT	
WHA	WATER HAMMER ARRESTOR	
WM	WATER METER	
WSFU	WATER SUPPLY FIXTURE UNITS	
°C	DEGREES CELSIUS	
°F	DEGREES FARHENHEIT	
Ø	DIAMETER	

GENERAL PLUMBING NOTES	
1.	THE INTENT OF THESE DRAWINGS IS TO PROVIDE COMPLETE AND PROPERLY FUNCTIONING PLUMBING SYSTEMS. LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO COMPLETE THIS WORK MUST BE PROVIDED.
2.	PLUMBING DRAWINGS ARE IN PART DIAGRAMMATIC AND INTENDED TO SHOW THE SCOPE AND GENERAL ARRANGEMENT OF THE WORK UNDER THIS CONTRACT. FOLLOW THESE DRAWINGS FOR SIZES OF THE EQUIPMENT, PIPING AND GENERAL PIPE ROUTING. DRAWINGS ARE NOT INTENDED TO BE SCALED FOR ROUGH-IN MEASUREMENTS NOR TO SERVE AS SHOP DRAWINGS. WHERE JOB CONDITIONS REQUIRE CHANGES OR ADJUSTMENTS IN THE INDICATED LOCATIONS OR ARRANGEMENT OF THE WORK, SUCH CHANGES MUST BE MADE WITHOUT CHANGE IN THE CONTRACT AMOUNT.
3.	PLUMBING WORK ON THIS PROJECT MUST BE PROVIDED IN ACCORDANCE WITH THE 2021 INTERNATIONAL PLUMBING CODES AND APPLICABLE LOCAL CODES.
4.	COORDINATE PLUMBING WORK WITH SITE CONDITIONS AND THE WORK OF OTHER TRADES.
5.	VERIFY SLOPES AND INVERT ELEVATIONS PRIOR TO COMMENCEMENT OF WORK.
6.	THE WORK REQUIRED MUST INCLUDE PROVIDING MATERIALS, CUTTING, PATCHING, ADAPTING AND OTHER INCIDENTAL WORK, TOGETHER WITH SUCH TEMPORARY CONNECTIONS AS MAY BE REQUIRED.
7.	HORIZONTAL VENT PIPING MUST RUN ABOVE CEILING AND HORIZONTAL SANITARY PIPING MUST RUN BELOW SLAB UNLESS OTHERWISE NOTED.
8.	SLOPE ALL HORIZONTAL SANITARY WASTE PIPING 2" AND SMALLER AT 1/4" PER FOOT AND SLOPE ALL HORIZONTAL SANITARY WASTE PIPING 3" AND LARGER AT 1/8" PER FOOT UNLESS OTHERWISE SPECIFIED ON PLANS.
9.	PROVIDE FIRE-STOPPING AT PENETRATIONS THROUGH RATED PARTITIONS. THIS INCLUDE PENETRATIONS THROUGH RATED WALLS, BARRIERS, CEILINGS, ROOFS, AND FLOORS. PROVIDE MANUFACTURER'S STANDARD FIRE-STOPPING SEALANT, WITH ACCESSORY MATERIALS, HAVING A MINIMUM FIRE RESISTANCE RATING EQUAL TO THE FIRE-RATED BARRIER THAT IS PENETRATED. FIRE-STOPPING SYSTEMS MUST BE UL 1479 LISTED AND TESTED IN ACCORDANCE WITH ASTM E814.
10.	PROVIDE ACCESS PANELS FOR VALVES, TRAP PRIMERS AND OTHER PLUMBING SPECIALTIES LOCATED INSIDE CHASES, BEHIND WALLS OR ABOVE INACCESSIBLE CEILINGS.
11.	SHUT OFF VALVES MUST BE PROVIDED AT THE BEGINNING OF BRANCH LINES AND AT EACH INDIVIDUAL WATER LINE SERVING WALL HYDRANTS OR HOSE BIBBS. INDIVIDUAL SHUT OFF VALVES (ANGLE STOP VALVES) MUST BE PROVIDED AT WATER SUPPLY LINES SERVING THE PLUMBING FIXTURES. REFER TO RISER DIAGRAMS FOR LOCATIONS OF SHUT OFF VALVES.
12.	PAINT VENT THROUGH ROOF (VTR) TO MATCH THE ADJACENT ROOF.
13.	SANITARY AND STORM PIPE INVERTS EXITING THE BUILDING MUST BE COORDINATED WITH BUILDING FOOTERS.
14.	FLOOR DRAINS AND FLOOR CLEANOUTS MUST HAVE SQUARE STRAINERS/TOPS IN AREAS WITH TILE FLOOR AND ROUND STRAINERS/TOPS IN OTHER FLOOR TYPES.

DEPARTMENT OF THE NAVY		NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND		NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC		NAVAL STATION - NORFOLK, VA		NAVAL SUBMARINE BASE NEW LONDON		GROTON, CONNECTICUT		P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY		SENTRY		PLUMBING LEGEND AND GENERAL NOTES	
SCALE: AS NOTED		EPROJECT NO.: 1667770		CONSTR. CONTR. NO.		NAVFAC DRAWING NO. 12894119		SHEET 31		OF 65		P-001					



AE INFO

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES CWH DRW BPT CHK MJL

PMOM SMS/CWJ

BRANCH MANAGER ALG

CHIEF ENGINEER JWJ

FIRE PROTECTION HPN

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
PLUMBING LEGEND AND GENERAL NOTES

SCALE: AS NOTED


EPROJECT NO.: 1667770

CONSTR. CONTR. NO.


NAVFAC DRAWING NO. 12894119

SHEET 31 OF 65


P-001



C5 ELECTRIC WATER HEATER
BELOW SINK DETAIL



A3 WATER SERVICE ENTRANCE DETAIL
N.T.S.

[illegible]

Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED			AVE INFO	
FOR COMMANDER NAVFAC				
ACTIVITY				
APPROVED BY LCDR ELIZABETH				
OLOKODE NAVFAC NLON FEAD				
DIRECTOR NEW LONDON, GROTON, CT				
SATISFACTORY TO DATE			05/27/2025	
DES	CWH	DRW	BPT	CHK MJL
PM/DM			SMS/CW	
BRANCH MANAGER			AL	
CHIEF ENG/ARCH			JW	
FIRE PROTECTION			HP	

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC MID-ATLANTIC NAVAL SUBMARINE BASE NEW LONDON P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY SENTRY	NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND NAVAL STATION - NORFOLK, VA GROTON, CONNECTICUT
PLUMBING DETAILS	


SCALE: AS NOTED	
EPROJECT NO.:	1667770
CONSTR. CONTR. NO.	
NAVFAC DRAWING NO.	
12894121	
SHEET 33	OF 65
P-501	

NOTES:

1. PROVIDE PISTON OPERATED, COPPER BODY, LEAD FREE WATER HAMMER ARRESTOR.
2. WATER HAMMER ARRESTOR SIZING MUST BE BASED ON SPECIFIC MANUFACTURER'S FIXTURE UNIT CAPACITY TABLE.
3. WATER HAMMER ARRESTORS MUST BE CERTIFIED BY THE PLUMBING AND DRAINAGE INSTITUTE.

SCALE: AS NOTED			
EPROJECT NO.:		1667770	
CONSTR. CONTR. NO.			
NAVFAC DRAWING NO.			
		12894122	
SHEET	34	OF	65
P-601			

6/30/2025 5:28:58 PM M-101
\\ac11950\\l\\eng\\P\\D\\21628\\MECH\\BLOG-166770-M-BM_SENTRY_v21.rvt




GENERAL SHEET NOTES

- DUCTWORK AND EQUIPMENT SHOWN ON THIS DRAWING IS DIAGRAMMATIC. LOCATE ALL DUCTWORK AND EQUIPMENT SO AS TO CLEAR ALL OBSTACLES.
- WORK TO BE PERFORMED IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, AND LOCAL CODES.
- COORDINATE HVAC INSTALLATIONS WITH EACH APPLICABLE TRADE.
- VERIFY DIMENSIONS AND CONDITIONS PRIOR TO THE START OF INSTALLATION OF MECHANICAL AND PLUMBING EQUIPMENT. CONSTRUCTION DISCREPANCIES TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTING OFFICER FOR A RESOLUTION.

SHEET KEYNOTES

- PROVIDE WALL MOUNTED DUCTLESS AIR CONDITIONING UNIT.
- PROVIDE ENERGY RECOVERY VENTILATOR UNIT ABOVE CEILING WITH WALL SWITCH.
- PROVIDE CONDENSING UNITS. PROVIDE CONCRETE PAD 6-INCHES ABOVE GRADE.
- PROVIDE WALL MOUNTED ELECTRIC UNIT HEATER.
- PROVIDE LOUVER MINIMUM 10'-0" ABOVE GRADE. SEE ARCHITECTURE FOR DETAILS.
- PROVIDE OPERATOR WORKSTATION.
- PROVIDE LOW LEAKAGE MOTORIZED OUTDOOR AIR AND EXHAUST AIR DAMPERS.
- THERMOSTAT PROVIDED BY SPLIT AC UNIT MANUFACTURER.
- SWITCH PROVIDED BY ENERGY RECOVERY VENTILATOR MANUFACTURER.



Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1600
FAX: 571.218.1600

APPROVED

FOR COMMANDER NAVFAC

ACTIVITY APPROVED BY LCDR ELIZABETH
CLOKODE NAVFAC NLON FEAD
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE 05/27/2025

DES CWH DRW CWH CHK MJL

PMOM SMS/CWJ

BRANCH MANAGER ALG

CHIEF ENGINEER JWJ

FIRE PROTECTION HPN

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
MECHANICAL FLOOR PLAN - DUCTWORK

SCALE: AS NOTED

EPROJECT NO.: 1667770

CONSTR. CONTR. NO.


NAVFAC DRAWING NO.

12894125

SHEET 37 OF 65

M-101

6/30/2025 5:28:49 PM MP101
\\ac119301\\img\\FDZEL628MECH\\BLOG-166770-4-BIM_SENTRY_v21.rvt




GENERAL SHEET NOTES

- DUCTWORK AND EQUIPMENT SHOWN ON THIS DRAWING IS DIAGRAMMATIC. LOCATE ALL DUCTWORK AND EQUIPMENT SO AS TO CLEAR ALL OBSTACLES.
- WORK TO BE PERFORMED IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, AND LOCAL CODES.
- COORDINATE HVAC INSTALLATIONS WITH EACH APPLICABLE TRADE.
- VERIFY DIMENSIONS AND CONDITIONS PRIOR TO THE START OF INSTALLATION OF MECHANICAL AND PLUMBING EQUIPMENT. CONSTRUCTION DISCREPANCIES TO BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTING OFFICER FOR A RESOLUTION.

SHEET KEYNOTES

- ROUTE 1" CD DOWN TO FLOOR DRAIN.

SYN	DESCRIPTION	DATE	APPR





Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED	AE INFO
FOR COMMANDER NAVFAC	
ACTIVITY	APPROVED BY LCDR ELIZABETH CLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT
SATISFACTORY TO DATE	05/27/2025
DES	CWH
DRW	CWH
CHK	MJL
PMIDM	SMS/CWJ
BRANCH MANAGER	ALG
CHIEF ENGINEER	JWJ
FIRE PROTECTION	HPN


DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC
NAVAL STATION - NORFOLK, VA
NAVAL SUBMARINE BASE NEW LONDON
GROTON, CONNECTICUT
P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY
SENTRY
MECHANICAL FLOOR PLAN - PIPING

SCALE: AS NOTED
EPROJECT NO.: 1667770
CONSTR. CONTR. NO.
NAVFAC DRAWING NO. 12894126
SHEET 38 OF 65
MP101







C1 MINISPLIT CONDENSING UNIT DETAIL - ON GRADE




C3 WALL-MOUNTED DUCTLESS SPLIT SYSTEM UNIT DETAIL



A1 REFRIGERANT PIPE WALL PENETRATION



A3 ERV SUPPORT DETAIL

[illegible]

Jacobs
1100 NORTH GLEBE ROAD
SUITE 500
ARLINGTON, VIRGINIA 22201
571.218.1000
FAX: 571.218.1600

APPROVED				
FOR COMMANDER NAVFAC				
ACTIVITY				
APPROVED BY LCDR ELIZABETH OLOKODE NAVFAC NLON FEAD DIRECTOR NEW LONDON, GROTON, CT				
SATISFACTORY TO DATE			05/27/2025	
DES	CWH	DRW	CWH	MJL
PM/DM			SMS/CWJ	
BRANCH MANAGER				ALG
CHIEF ENGINEER				JWJ
CDE PROTECTION				MDM

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC MID-ATLANTIC NAVAL SUBMARINE BASE NEW LONDON GROTON, CONNECTICUT P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY SENTRY MECHANICAL DETAILS	PHOTOLOGICAL UNIT
---	-------------------

SCALE: AS NOTED		
EPROJECT NO.: 1667770		
CONSTR. CONTR. NO.		
NAVFAC DRAWING NO. 12894127		
SHEET	39	OF 65

ENERGY RECOVERY VENTILATOR UNIT SCHEDULE

EQUIPMENT TAG	LOCATION	UNIT AIRFLOWS			ENERGY RECOVERY						FAN DATA			ELECTRICAL DATA						FILTER TYPE	WEIGHT (LBS)	NOTES
		SUPPLY AIR (CFM)	OUTSIDE AIR (CFM)	EXHAUST AIR (CFM)	SUMMER			WINTER			QUANTITY	HP (EA)	ESP (IN WG)	V	PH	HZ	FLA	MCA	MOP			
					OA EAT (F DB/F WB)	EA EAT (F DB/F WB)	SA LAT (F DB/F WB)	OA EAT (F DB/F WB)	EA EAT (F DB/F WB)	SA LAT (F DB/F WB)												
ERV-1	GUARD ROOM	50	50	50	82.0 / 72.0	78.0 / 65.1	78.6 / 67.6	14.0 / 12.0	68.0 / 56.8	60.2 / 50.9	2	0.03	0.5	120	1	60	0.35	10	15	MERV13	40	1.2

NOTES:

1. PROVIDE LOW VOLTAGE WALL SWITCH.
2. PROVIDE PLUG-IN TYPE CONNECTION.

SPLIT SYSTEM AIR CONDITIONING SCHEDULE

EQUIPMENT TAG	LOCATION	SUPPLY AIR (CFM)	OUTDOOR AIR (CFM)	ESP (IN WG)	REFRIGERANT TYPE	ELECTRICAL DATA	DX COIL DATA						OPERATING WEIGHT (LBS)	FILTER TYPE	NOTES	
							COOLING			HEATING AT 47°F		HEATING AT 17°F				
							TOTAL CAPACITY (MBH)	EAT DB/WB (°F)	LAT DB/WB (°F)	TOTAL CAPACITY (MBH)	RATED CAPACITY (MBH)	TOTAL CAPACITY (MBH)				RATED CAPACITY (MBH)
AC-1	ELEC ROOM	635	-	-	410A	POWER FROM CU	24	85.0 / 70.8	55.1 / 56.0	28	26	18.3	15.7	46	MERV8	1 THRU 6
AC-2	GUARD ROOM	255	-	-	410A	POWER FROM CU	12	78.0 / 65.0	51.8 / 52.0	18	14	10.5	10.5	28	MERV8	1 THRU 6

NOTES:

1. PROVIDE SPLIT SYSTEM VARIABLE CAPACITY AIR CONDITIONING UNIT, DX COOLING CONTROL.
2. PROVIDE FACTORY MOUNTED, WIRED, AND CONFIGURED WATER LEVEL SENSOR/SWITCH IN THE CONDENSATE DRAIN PAN INTERLOCKED TO STOP UNIT OPERATION AT DRAIN PAN HIGH LEVEL.
3. WHERE CONDENSATE CANNOT BE GRAVITY DRAINED, PROVIDE MANUFACTURER'S INTEGRAL, FACTORY MOUNTED, WIRED, AND CONFIGURED CONDENSATE PUMP.
4. PROVIDE MANUFACTURER'S DISPOSABLE FILTER MEDIA AT INDOOR UNIT, MINIMUM MERV 8.
5. COORDINATE INTERFACE BETWEEN INDOOR AND OUTDOOR UNITS.
6. WALL MOUNTED DUCTLESS UNIT. PROVIDE MANUFACTURER'S FACTORY MOUNTING BRACKETS AND HARDWARE.
7. PROVIDE MANUFACTURER'S WALL MOUNTED THERMOSTAT.

CONDENSING UNIT SCHEDULE

EQUIPMENT TAG	ASSOCIATED INDOOR UNIT	OUTDOOR DESIGN TEMPERATURE		ELECTRICAL DATA					WEIGHT (LBS)	NOTES
		SUMMER DB/WB (F)	WINTER DB (F)	V	PH	HZ	MCA	MOCp		
CU-1	AC-1	86.2 / 75.8	14.3	208	1	60	19.0	26	153	1 THRU 6
CU-2	AC-2	86.2 / 75.8	14.3	208	1	60	11.0	28	93	1 THRU 6

NOTES:

1. PROVIDE SPLIT SYSTEM VARIABLE CAPACITY CONDENSING UNIT, WITH VARIABLE COMPRESSOR.
2. PROVIDE MANUFACTURER'S FACTORY APPLIED COATING SUITABLE FOR A CORROSIVE SALT SPRAY ENVIRONMENT ON CASING AND COILS.
3. PROVIDE SINGLE POINT POWER CONNECTION WITH FACTORY MOUNTED AND WIRED FUSED DISCONNECT SWITCH, NEMA 4X OUTDOOR USE RATED.
4. OUTDOOR CONDENSER UNIT MUST POWER INDOOR EVAPORATOR UNIT.
5. PROVIDE MANUFACTURER'S FACTORY LOW AMBIENT KIT AND WIND BAFFLE.
6. COORDINATE INTERFACE BETWEEN INDOOR AND OUTDOOR UNITS.

ELECTRIC UNIT HEATER SCHEDULE

EQUIPMENT TAG	AREA SERVED	TYPE	CAPACITY (KW)	V	PH	HZ	FLA	NOTES
UH-1	TOILET ROOM	WALL MOUNTED	1.5	208	1	60	7.3	1,2,3
UH-2	PLUMBING ROOM	WALL MOUNTED	1.5	208	1	60	7.3	1,2,3

NOTES:

1. PROVIDE WITH MANUFACTURER'S INTEGRAL UNIT MOUNTED NON-FUSED DISCONNECT SWITCH.
2. PROVIDE WITH MANUFACTURER'S MOUNTING BRACKETS AND HARDWARE.
3. PROVIDE WITH MANUFACTURER'S UNIT MOUNTED THERMOSTAT.

AIR TERMINAL SCHEDULE

TAG	TYPE	CFM RANGE	NECK SIZE (IN)	NOTES
EG-1	EXHAUST GRILLE	0-149	6"X6"	1 THRU 5
SD-1	SUPPLY DIFFUSER	0-199	6"	1,2,6,7

NOTES:

1. COORDINATE AIR TERMINAL DEVICE FRAME WITH CEILING TYPE.
2. PROVIDE ALUMINUM GRILLES AND DIFFUSERS.
3. FLEX DUCT MUST NOT BE USED ABOVE INACCESSIBLE CEILINGS.
4. PROVIDE 1/2" SPACED SINGLE DEFLECTION, INDIVIDUALLY ADJUSTABLE, LONG DIMENSION BLADES IN FRONT.
5. PROVIDE OPPOSED BLADE DAMPERS FOR GRILLES.
6. MAXIMUM FLEX DUCT LENGTH MUST BE 5 FT.
7. PROVIDE PLAQUE TYPE DIFFUSER WITH 4-WAY THROW PATTERN.

OUTDOOR AIR SCHEDULE

ROOM	OCCUPANCY COUNT	OA CFM
GUARD ROOM	1	50

NOTES:

1. THE NUMBER OF OCCUPANTS LISTED IS FOR INFORMATION PURPOSES ONLY.

DESIGN CONDITIONS

14th WEATHER SQUADRON STATION ID	ICAO_KGON
LOCATION	GROTON NEW LONDON, CT
ELEVATION	9 FEET
CLIMATE ZONE	5A
OUTDOOR DESIGN CONDITIONS - COMFORT COOLING	
SUMMER	82°F DB / 72°F WB (1% DATA)
SUMMER DEHUMIDIFICATION	121 GR/LB (75°F WB) / 80°F MCDB (1% DATA)
CONDENSING UNITS	87°F DB (5°F ADDED TO SUMMER DESIGN)
WINTER	14°F DB / 12°F WB (99% DATA)
INDOOR DESIGN SET POINTS - GENERAL OCCUPIED AREAS	
COOLING	78°F
HEATING	68°F
DEHUMIDIFICATION	50% RH / 57.9°F DEWPOINT
INDOOR DESIGN SET POINTS - ELECTRICAL ROOMS	
COOLING	75°F
HEATING	68°F

DAMPER SCHEDULE

DAMPER TAG	SYSTEM EQUIPMENT	DESCRIPTION	DESIGN DUCT SIZE	BLADE ACTION	FAIL POSITION	CONTROL ACTUATOR			NOTES
			DIAMETER (INCHES)			CONTROL SIGNAL	CONTROL VOLTAGE	POSITION FEEDBACK	
OAD	ERV-1	OUTSIDE AIR	6	PARALLEL	CLOSE	TWO POSITION	24 VAC	YES	
EAD	ERV-1	EXHAUST AIR	6	PARALLEL	CLOSE	TWO POSITION	24 VAC	YES	



DUCTWORK CONSTRUCTION AND LEAKAGE TESTING SCHEDULE

SYSTEM	DUCT PRESSURE CLASS				DUCTWORK				DUCT TEST PRESSURE: INCHES OF WATER...	NOTES
	INCHES OF WATER COLUMN				ROUND / OVAL		RECTANGULAR			
	SUPPLY DUCT	RETURN DUCT	EXHAUST DUCT	OUTSIDE AIR DUCT	DUCT SEAL CLASS	DUCT LEAKAGE CLASS	DUCT SEAL CLASS	DUCT LEAKAGE CLASS		
ERV-1	0.5	0.5	0.5	0.5	A	4	A	8	1.0	1,2,3

NOTES:

1. BALANCER MUST NOT SUM THE AIRFLOWS AT EACH AIR TERMINAL DEVICE WITHOUT ACCURATELY MEASURING THE TOTAL FLOW RATE AT THE FAN FOR COMPARISON AND DETERMINATION OF APPROXIMATE LEAKING RATES.
2. TEST IN ACCORDANCE WITH UFGS 23 05 93, TESTING, ADJUSTING AND BALANCING FOR HVAC AND THE PROCEDURES IN SMACNA'S HVAC AIR DUCT LEAKAGE TEST MANUAL.
3. STEEL SHEET AND STRIP USED FOR DUCTWORK AND CONNECTORS MUST BE G-90 COATED GALVANIZED STEEL OF LOCKFORMING GRADE CONFORMING TO ASTM A653 AND A924 STANDARDS. MINIMUM YIELD STRENGTH FOR SHEET STEEL AND REINFORCEMENTS MUST BE 30,000 PSI.

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



APPROVED

FOR COMMANDER NAVFAC

ACTIVITY : APPROVED BY LCDR ELIZABETH
CLOKODE NAVFAC NLON READ
DIRECTOR NEW LONDON, GROTON, CT

SATISFACTORY TO DATE : 05/27/2025

DES : CWH DRW : CWH CHK : DRE

PMOM : SMS/CWJ

BRANCH MANAGER : ALG

CHIEF ENGINEER : JWJ

FIRE PROTECTION : HPN

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND - MID-ATLANTIC

NAVAL STATION - NORFOLK, VA

GROTON, CONNECTICUT

NAVAL SUBMARINE BASE NEW LONDON

P-1102 WEAPONS MAGAZINE & ORDNANCE OPERATIONS FACILITY

SENTRY

CONTROL'S LEGEND

SCALE : AS NOTED

EPROJECT NO. : 1667770

CONSTR. CONTR. NO.

NAVFAC DRAWING NO.

12894129

SHEET 41 OF 65

M-800

