

Statement of Work

Super Orlof Intaglio Press Wiper Tank(s) Replacement

1. SECTION I: Background

The objective of this project is to enhance the existing Wiper Tank(s) by retrofitting to the Super Orlof Intaglio (SOI) press. This upgrade is intended to meet operational, safety, and quality standards, as well as currency production requirements. The focus will be on retrofitting the current SOI 1 Press with the aim of reducing downtime on the press, decreasing parts and chemical consumption, and extending the lifetime of the wiper rollers.

Initially, the upgrade will be applied to SOI 1 located at Washington DC facility (DCF). If successful after initial use period, there will be an option to retrofit the remaining three (3) presses. One (1) system is located at DCF and two (2) systems at WCF. The upgrade will help ensure and sustain quality performance and operations at the Bureau of Engraving and Printing (BEP).

2. SECTION II: Purpose

2.1. Product, Service or Outcome Needed: The BEP requires replacements for the existing SOI 1 wiper tank(s) and the option for three additional tanks. The contractor shall provide new wiper tank(s) systems, ensure delivery and proper installation of the systems, conduct commissioning for Bureau Accepting Test (BAT), supply any necessary spare parts required, offer training to the BEP staff on operation and maintenance of the new systems, provide comprehensive documentation related to the systems, integrate the new systems into the existing workflow without requiring approval from the Change Control Board (CCB), and furnish a warranty to assure reliability and support.

2.1.1. The upgrade will be applied to a single Super Orlof Intaglio Press

Outcome Needed:

A - Successful Retrofit: implementation of the new fleece-type wiping system and the existing tank ensuring functional capability

B - Design Enhancement: incorporation of tensioned stainless steel plates improving system efficiency and reliability

C - Reversibility: ability to reverse the upgrade if major issues occur provided flexibility and reducing risk

- D** - Updated Documentation: comprehensive updates including schematics manuals and data sheets for maintenance and operation
- E** - Operational Readiness: availability of consumable and spare parts to ensure uninterrupted passage
- F** - Sustained support: a warranty of at least one year post acceptance to cover any different issues arising from the retrofit
- G** - Skilled operation: training provided to ensure personnel can effectively operate and maintain the upgraded system
- H** - Documentation and training shall be provided in English for BEP personnel.

3. SECTION III: Technical Requirements/Tasks/Outcomes

3.1 Super Orlof Intaglio (SOI) Presses Wiper Tank Replacement Specifications

- A** - Vendor shall retrofit new fleece-type (Scotch Brite fleece) wiping system in existing Presses (SOI) 1 wiping tank including all parts and labor.
- B** - New tank design shall incorporate tensioned stainless-steel plates with use of scotch Brite in lieu of current brush/blade system.
- C** - Option to reverse initial upgrade back shall be possible if major issues occur and the BEP does not want to proceed with upgrade on other presses.
- D** - A documentation update to the press shall be provided including electrical/mechanical schematics, manuals, and datasheets.
- E** - Vendor shall supply enough consumable spare parts for initial running of the press.
- F** - Warranty shall include materials and labor for the repair or replacement of defective parts and service at the installation site for a period of at least one year (12 calendar months) after the BEP's final acceptance of the equipment.

Vendor shall provide any initial training needed to operate and maintain upgrade.

3.2 Design Review Task:

As part of the development of the system, the Contractor shall schedule and conduct at least one (1) Design Review with the BEP to discuss the specifics of the design and development activities planned for the SOI 1 Press Wiper Tank. Test criteria/plans will also be developed during the design review process.

3.3 Security Requirements (*Mandatory Minimum Element*)

Non-Disclosure Agreement. The Contractor shall complete the Non-Disclosure Agreement (NDA) prior to the Government's release of proprietary and/or sensitive information. The NDA will cover all work to be performed under this contract and shall apply to all contractor personnel as well as any subcontractors.

Safeguarding Government Furnished Materials. Under the performance of this contract, the BEP shall provide Government Furnished Materials that are considered items of security. The Contractor shall abide by all requirements and instructions of the BEP's Office of Security during the performance of this contract.

3.4 On-site Services Requirements (*Mandatory Minimum Element*)

All Contractors must comply with the requirements and procedures established through the BEP Environmental, Health, and Safety (EHS) document(s):

75D-07.0-04 EHS Contractor Requirements (*Attachment 0001*)

75W-08.0-02 EHS Contractor Requirements at the WCF (*Attachment 0002*)

The applicable contents of the document(s) must be adhered to. The BEP shall furnish the document(s) as part of the contract.

3.5 Safety Requirements (*Mandatory Minimum Element*)

The following safety requirements shall be met:

- a. Noise Level: The noise produced by the operation of the press within specified speed range shall not exceed 85 Decibels A-weighted Sound Level (dBA) when measured at 914 mm (3 feet) distance along the plan view of the press from the press and at an elevation of 1,524 mm (5 feet) including the wiper and inking areas of the press.
- b. General Safety: The press shall be designed to always prevent injury to operation and maintenance personnel. The press shall be equipped with service access equipment, such as catwalks, access platforms, access ladders, lifts, and other equipment for operation and maintenance. Fixed stairs shall be provided in compliance with Occupational Safety and Health Administration (OSHA) 29 Code of Federal Regulations (CFR) 1910.24, Fixed Industrial Stairs. All catwalks, access platforms, access ladders, lifts, hoists, and any other equipment that are furnished, shall be built, and tested to comply with American National Standards Institute (ANSI) and OSHA standards. Special attention shall be given to providing proper 'angle of steps as indicated in paragraph (e) of the referenced standard. All press and service access equipment shall be guarded as required by applicable portions of OSHA Regulations.
- c. The presses shall comply with ANSI Standard B65.1, Safety Standard-Printing Presses.

- d. Sharp Edges: All sharp edges and corners, which present personnel hazards, shall be guarded or padded. All covers and safety guards shall be interlocked with press control to prevent its normal operation while any cover or guard is open or absent. Only local jogging control at a reduced speed is allowable provided no other covers are opened or removed. The location of opened switches shall be displayed on the Master Control Station. Covers and guards shall be manufactured for easy removal by Bureau personnel with tools to facilitate removing mechanical and electrical parts for repair. All rotating and reciprocating parts shall be guarded as specified by OSHA regulation 29 CFR 1910.212.
- e. Heated Surfaces: Prevent heated surfaces from causing burns to personnel during operation.
- f. Asbestos: Materials containing asbestos shall not be used.
- g. Airborne Contaminants Employee Exposure: Operation of the SOI Wiper Tank(s) shall not result in worker exposure to airborne contaminants exceeding the current permissible exposure limits (PELs) established by the Occupational Safety and Health Administration (OSHA) (29 CFR 1910.1000) or American Conference of Governmental Industrial Hygienists (ACGIH) Threshold Limit Values (TLVs). Airborne contaminants of concern include, but are not limited to, volatile organic compounds (VOCs) present in inks and sodium hydroxide mist generated from the BEP wiping solution. The system design shall incorporate effective local exhaust ventilation (LEV), specifically positioned at the wiper tank area, to capture and control these emissions at their source. Any redesign or modification of the wiper tank shall include evaluation and implementation of appropriate LEV and other engineering controls necessary to minimize worker exposure to all identified airborne hazards.
- h. Safety Data Sheets: Safety Data Sheets (SDS) for all contractor supplied and specified chemicals that are part of the process shall be supplied by the contractor and must be approved by WCF EHS Branch and/or DCF OEHS prior to bringing onto the respective site. The SDS shall comply with the OSHA, as listed in standard 29 CFR 1910.1200, with particular emphasis on paragraphs (g) and (i).
- i. Overload Protection: SOI Wiper Tank(s) shall be equipped with overload protection and power factor correction devices to prevent damage to its components and operating personnel.
- j. Safe-Ready: All control stations shall include a "safe-ready" collar or equivalent. Upon turning the collar into a safe position, it shall be impossible to start the SOI Wiper Tank(s) from any other station. Console shall indicate that the interlock, including emergency stop buttons, causes the SOI Wiper Tank(s) to start or not.

- k. Emergency Stop: Whenever an Emergency Stop is activated, the machine shall stop within one (1) second to reduce damage to the machinery and injury to personnel. An Emergency Stop may be initiated due to the machine's internal control logic detecting an emergency situation, activation of personnel safety devices (i.e., safety curtains, cover interlocks or other devices designed to protect personnel), or by personnel manually activating an Emergency Stop Button.

3.6 Environmental Protection Requirements (***Mandatory Minimum Element***)

All equipment installed at the Bureau shall meet all local, state, and federal environmental regulations, including but not limited to air quality, industrial solid waste, hazardous waste, and wastewater. The equipment installed at the Bureau shall comply with the following regulations:

Reference

- Federal Regulation: Environmental Protection Agency, EPA Clean Air Act Amendments of 1990, Section 112-Air Toxics (http://www.epa.gov/air/oaq_caa.html).
- 30 TAC – Chapter 335 for Industrial Solid Waste and Municipal Hazardous Waste
- 40 CFR 403 - General Pretreatment Regulations for Existing and New Sources of Pollution
- 40 CFR 433 – Metal Finishing Point Source Category
- 40 CFR 261 – Identification and Listing of Hazardous Waste
- District of Columbia Municipal Regulations (DCMR), Title 20, Subtitle A, Air Quality Regulations
- District of Columbia Municipal Regulations (DCMR), Title 20, Subtitle E, Hazardous Waste Regulations
- District of Columbia Municipal Regulations (DCMR), Title 21, Water and Sanitation, Chapter 15, Discharges to Wastewater System Regulations
- P.L. 102-486, Energy Policy Act of 1992, October 24, 1992
- 40 CFR Part 247, Comprehensive Guideline for Procurement of Products Containing Recovered Materials, May 1, 1996

Maryland Department of the Environment (MDE) regulations in Code of Maryland Regulations (COMAR) Title 26 Subtitles 01 through 27 as applicable

3.7 Air Pollution Control

The DCF is in a non-attainment area for Volatile Organic Compounds (VOCs) and 2.5 Particulate Matter (PM 2.5). Any equipment installed in either the DCF or the WCF must meet Lowest Achievable Emissions Rate (LAER) standards in accordance with EPA, TCEQ, and District of Columbia regulations. Maximum Achievable Control Technology (MACT) standards may also be applicable to control the emissions of any Hazardous Air Pollutants that result due to the installation of new equipment or change in the method of operations of existing equipment.

The Contractor shall identify potential source locations of air pollutant emissions from the equipment. Equipment must be designed so that pollutants can be captured and ventilated to air pollution control devices. If emission capture and control are required, the Contractor may be required to propose and provide a design and equipment for capture and control of the pollutant in question.

a. Third Party Performance Test

Third Party Performance Test— A compliance test which demonstrates that the equipment and/or air pollution control device (APCD) meets the applicable EPA or DC performance requirements, may be required. If required, the compliance test must be performed according to a test plan that uses approved EPA methods and be submitted to the Office of Environment, Health and Safety (OEHS) or WCF Environmental Health and Safety for approval prior to the test.

b. Construction Permits

The BEP is required to submit and receive approval from regional environmental regulatory agencies prior to beginning construction to support the installation of equipment that is expected to emit pollutants. The contractor shall provide sufficient information to the BEP to facilitate the preparation of the air permitting applications for the equipment and control devices so that the permit is in place prior to construction. The air permitting process may take from 6 to 18 months to complete. The contractor shall furnish drawings of all equipment to be delivered to the BEP identifying pollutant emitting locations and furnish information on the types and quantities of pollutants from the operation and cleaning of the equipment. Contractor shall furnish the information to the BEP during the first design review meeting or within 30 days after contract award if no design review is to occur.

Interlocks and Standby Mode—All APCDs shall be interlocked with the equipment to prevent operation without emission capture. The Contractor is responsible for coordinating with Bureau representatives, including OEHS or WCF EHS, to establish the parameters that warrant a shutdown of equipment. Standby Modes shall be established for periods when equipment is not operating. The Contractor shall document

the parameters established and include this information in the operation and maintenance manuals.

3.8 Wastewater

Information shall be provided to the OEHS or WCF EHS through the Contracting Officer Representative on the characteristics of all effluents (liquids which can be pumped or gravity flow liquids) that will come from the equipment, either regularly or intermittently, including routine or scheduled maintenance work. This information will be used to determine the feasibility and method of treating the effluents either in the Wastewater Pre-Treatment Plant or requiring that the materials be handled through the Solid/Hazardous Waste Program.

3.9 Energy, water, and materials usage programs

The Contractor shall make every effort to provide the most energy and water efficient equipment to the Bureau. The contractor shall furnish all information to document the energy and water usages for the system, including all calculations. The Contractor shall comply with:

- a. P.L. 102-486, Energy Policy Act of 1992, October 24, 1992
- b. 40 CFR Part 247, Comprehensive Guideline for Procurement of Products Containing Recovered Materials, May 1, 1996

3.10 Fluorescent Bulbs

All lamping shall be Light Emitting Diode (LED).

3.11 Solid Hazardous Waste

Equipment that generates non-liquid wastes (wastes which cannot be pumped, or which do not flow by gravity), either continuously or intermittently, scheduled or routine maintenance work, and normal operation, must be designed to allow for removal of the waste in an ergonomic manner to allow the operator to transfer the waste into a fifty-five (55) gallon drum (1A1, 1A2, or other appropriate container) as needed. Information shall be provided as to the specific quantity, nature and characteristics of the non-liquid waste generated so that a waste determination may be performed by OEHS in accordance with 40 CFR 261 – Identification and Listing of Hazardous Waste.

4. SECTION IV: Testing

The Contractor shall perform a Bureau Acceptance Test (BAT) on each BEP system updated. Test criteria/plans will be developed during the design review process. The test plans shall be submitted for the design review meeting. The Contractor is responsible for scheduling the system

testing, as well as any retesting required. System validation is required internally after the BAT is accepted.

The FIT (Factory Integration Test) is expected to be five (5) working days for each SOI Presses Wiper Tank, of which four (4) days will require production. Since BEP items of reproduction (i.e. seals or test seals) may be present for the performance of the FIT, the contractor shall submit in conjunction with their detailed Test Plan, a Security Plan, how they will address the Security and Accountability requirements of Section H of resultant contract to safeguard BEP items during the preparation and performance of the FIT six (6) weeks before FIT has begun.

The contractor shall perform in the presence of BEP personnel a BAT. Additional testing or demonstrations may be required to demonstrate the system, or subsystems, capabilities, and compliance with the requirements.

The duration of BAT is expected to be two (2) working days for each SOI wiper tank, of which four (2) days will require production.

All control system programs, wiring diagrams, and bill of materials showing the equipment used at the FIT shall be provided to BEP for review at each FIT.

4.1 Outcome Required for FIT and BAT Acceptance:

Contractors must provide User Operations Manuals, Technical Service Manuals, and spare parts support.

Contractor must provide in the English language, Operation Training, Technical Training

To the greatest extent possible, components and configuration will first be developed, tested, and demonstrated to the BEP at the contractor's site. A detailed list of contractor site specific components and configurations will be mutually agreed upon by the contractor and BEP at Design Review 1.

The systems component and configuration list will be tested by BEP via Factory Inspection Test (FIT) prior to shipping. After BEP acceptance, the systems components will be delivered to the BEP DCF / WCF location.

The contractor shall perform all required testing on the machine at BEP DCF / WCF facility. After the wiper tank has passed the Bureau Acceptance Testing (BAT), the contractor shall provide on-site operator and technical training required for full production.

5. SECTION V: Training

5.1 Training:

Training shall be based upon the information included in the equipment's operation and maintenance manuals, any other supplemental devices, and information the Contractor and BEP jointly deem necessary for satisfactory training.

5.2 Training Plan

The contractor shall submit for approval a training plan to the BEP.

Two (2) months prior to the start of the training, the contractor shall prepare and deliver to the Contracting Officer Representative (COR), a detailed training plan and schedule. The training plan shall include an hourly breakdown of the subject matter to be covered during each training session. One week prior to conducting a class, the contractor will be informed as to the hours that the training sessions will take place.

5.3 Operator Training

The Contractor shall conduct training classes for the operators of the SOI Presses Wiper Tank, including any subsystems and supporting equipment.

Training shall be sufficient to adequately prepare the operators to safely run the SOI Presses Wiper Tank independently while meeting the production requirements.

Operator training shall include related safety, health, and environmental topics such as those outlined in Section 3.5 – 3.11. One (1) operator class shall be provided, lasting five (5) days for up to six (6) BEP Subject Matter Experts (SME) and up to three (3) additional BEP specialists may attend as observers.

Contractors shall provide an approximate need of projected downtime of machine in order to complete maintenance and training as to allow for BEP adjustments to meet production needs.

Contractor shall inform the BEP COR thirty (30) days prior to maintenance to coordinate and schedule maintenance and training. The contractor shall provide all training materials to the COR prior to maintenance for review and approval by the BEP. The training shall be in person. All printed training aids shall be provided for the course, be in English language, and become the property of the Government.

Training personnel shall be qualified representative(s) and be proficient in the English language. Contractor shall provide specialized training to familiarize BEP personnel on the operation of the system, parts, and to help ensure reliable performance and maximum service life, during normal usage.

5.4 Instructor Qualifications

Instructors shall create a positive learning environment to facilitate the intellectual development of students. Instructors shall have the following qualifications:

Capable of developing, managing, and delivering training using classroom and hands-on instruction to attain learning objectives in relation to BEP organizational needs.

Reviewing training materials considering the students' backgrounds and course objectives to ensure consistency of quality and accuracy of content.

Ensure a variety of learning styles can be met by selecting appropriate methods and media for instructional delivery.

Monitoring participant progress and instructional program effectiveness; establishing and maintaining a learning environment to promote student engagement and participation actively and freely.

Fluent in English and all training materials shall be presented in English.

Must have successfully completed training in the craft, of which training will be provided, to a level sufficient to be classified at least at the Journeyman level, Master level preferred.

Possesses full and detailed knowledge, experience, skills, and proficiency with the subject equipment; capability to configure, set up, trouble-shoot, and make adjustments, or adjust settings, etc.

Shall be considered a SME in the area being covered by the training. Continually updating technical knowledge of equipment and techniques within the subject area.

Training requirements and trainee prerequisites will be defined in detail during the SOI Presses Wiper Tank design reviews and will include the following criteria in section 5.5.

5.5 Maintenance Training

The Contractor shall conduct training classes for all maintenance personnel on the SOI Presses Wiper Tank, including subsystems and supporting equipment. BEP Electro-Machinists are cross-trained Electricians-Machinists and shall be trained in both the electrical and mechanical maintenance of the SOI Presses Wiper Tank.

Training shall be sufficient to adequately prepare maintenance personnel to support the SOI Presses Wiper Tank, including debugging problems or incidents, independently to meet the unscheduled corrective maintenance and preventative maintenance requirements.

Maintenance training shall include related safety, health, and environmental topics such as those outlined in Section 3.5 – 3.11. One (1) maintenance class shall be provided, lasting five (5) days for up to six (6) BEP SMEs and up to three (3) additional BEP specialists may attend as observers.

5.5.1 Included Documentation and Training:

User manual + maintenance documents - English

Hardcopy + softcopy - English

Updated Spare part catalogue - English

Five (5) days operator training per installation - English

Five (5) days maintenance training per installation – English

6. SECTION VI: Technical Documentation

The contractor shall provide the BEP with accurate, complete, and current technical documentation of the SOI Presses Wiper Tank, including all supporting equipment. The documentation shall include engineering drawings, bill of materials, operation and maintenance manuals, and purchase component information.

One (1) complete set of documentation shall be provided in electronic format upon delivery of the first system to BEP. The set shall be provided on Compact Disk – Read Only Memory (CD-ROM) or Flash Drive. The files shall enable the BEP to copy the data onto servers for access not only on the machinery but also for engineering, maintenance, and operations personnel via the BEP's intranet.

The Contractor shall also be responsible for providing updates to the technical documentation, whenever changes or modifications occur during the term of this contract. These updates should reflect the latest functionality and maintenance of the system. The Contractor shall supply technical data covering the Super Orlof Intaglio (SOI) Presses Wiper Tank.

The Technical Documentation shall provide means to export data/information into Micro-Soft (MS)-Excel or other programs.

In the event the equipment is to be furnished by firms whose standard technical documentation does not use the English language or engineering terminology commonly used in the U.S., the technical documentation shall be modified as follows:

All documentation shall be provided in the English language, including drawing titles, part names, material specifications, manufacturing processes, heat treatments, finishes, or any other notations necessary for manufacturing the part. It will not be necessary to translate metric (SI) measurements into inch or foot measurements.

Any international standards (ISO and DIN) referenced shall be provided translated into the English language.

6.1 Engineering Drawings

Drawings covering the SOI Presses Wiper Tank shall be provided to the COR; mechanical and electrical; and shall include individual parts, subassemblies, and assemblies. Drawings for all individual parts, detail drawings, shall show the form, fit and function of the part, materials utilized, and any manufacturing process information required for the BEP to reproduce the part in an emergency. Detail drawings shall reference their respective subassemblies and assembly drawings.

Drawings shall be provided as raster images in Tagged Image File Format (TIFF) (.tif) electronic format. If generated via a Computer Aided Drafting (CAD) system, the drawings shall also be provided as vector images in AutoCAD (.dwg) electronic format.

Each drawing shall be a separate independent file. Drawings that consist of multiple pages shall be supplied as a single file. Drawings shall be scanned at an industry standard resolution not finer than 200 x 200 dpi. Consultative Committee for International Telegraphy and Telephony (CCITT) Group 4 (2d) Fax standard for compression shall be used. All drawing images shall be supplied free of scanning or conversion defects. Images shall be cropped to the border of the drawing with no outside white remaining. Images shall be straightened and oriented so that the title block is located on the lower right corner. The technical rights the BEP obtains under this contract to the drawings shall be annotated on the images.

The BEP utilizes the properties tab fields for the purposes of sorting and incorporating inventory information with part drawings. All TIFF(.tif) image files provided shall include the following fields within the properties summary tab available for utilization by the BEP: Author, Keyword, Comments, Title and Subject.

Files shall be identified using the drawing number as the title. A separate folder shall be provided for each logical group of assemblies.

6.2 Documentation Requirement

Operation and maintenance manuals shall be provided for the SOW wiper tank. Manuals via text and graphical illustrations, shall address all the requirements necessary for operation and maintenance personnel to operate and maintain the equipment without prior training and be in the English language. A list of trouble-shooting procedures should be available for quick reference to identify malfunctions. One (1) electronic copy in Adobe Intelligent PDF format or MS-Word shall be provided. This copy shall have links added from the table of contents, list of figures and an index, if available, to the referenced pages. Any internal table of contents or references to figures shall be linked to the referenced page or figure. In addition, the Contractor shall add bookmarks to the PDF files for all major headings. The manuals shall include a listing of all codes/programs used in the equipment and include a section devoted to safety, health, and environmental topics. The manuals shall detail all safety functions and locations.

6.3 Electronic Database Documentation

A complete detailed design document for the Data Collection System (DCS) shall be provided to the COR prior to the commencement of the FIT. The documentation shall include a complete listing of all database tables, all calculation items, interface points, DCS functions and processes, hardware and software configurations, and a glossary of all terms and entries.

7. SECTION VII: Warranty

The Contractor shall provide the following warranties.

7.1 Equipment Warranty

The contractor shall warrant all equipment, materials and workmanship delivered to be free from defects, damage, or failure for a period of one (1) year (12 calendar months) after BEP's final acceptance of the equipment. Warranty shall include materials and labor for the repair or replacement of defective parts and service at the installation site. This warranty will be at no additional cost to the government.

During the warranty period, the contractor personnel shall respond to a service call within seventy-two (72) hours or less, and have spare parts, if required, for the service call. The contractor shall provide all necessary information for the COR to make service contacts, i.e., names, addresses and telephone numbers. Upon completion of a service call, the contractor shall furnish a report, in English, documenting the work performed and any recommendations, including preventative maintenance, to lessen the potential of a future occurrence.

7.2 Parts Warranty

A one (1) year warranty shall be included on all parts from the time the parts are removed from BEP stock to be used on the SOI Presses Wiper Tank. The total amount of time from when the part is received from the manufacturer into stock shall not exceed twenty-four (24) months.

7.3 Spare Parts

The BEP intends to purchase spare parts for the SOI Presses Wiper Tank by ordering from the Spare Parts Listing supplied by the Contractor.

Each individual spare part ordered and delivered shall bear a tag with the manufacturer's part number and the BEP's stock number that will be on the BEP purchase order. Any parts not identified properly will be returned to the Contractor for correction at the Contractor's expense.

8. SECTION VIII: Deliverables

SOW Paragraph #	Deliverable	Due Date	Deliverable Recipient	Deliverable Format
----------------------------	--------------------	-----------------	----------------------------------	-------------------------------

3.2	Design Review Meeting	2 weeks after contract award	COR	Requirements
3.7(a)	Third Party Performance Test	<i>If required</i> , prior to the test	COR	OEHS Determined Not Requirements
3.7(b)	Construction Permits	<i>If required</i> , during the first design review meeting	COR	OEHS Determined Not Requirements
4.1	A detailed list of contractor site specific components and configurations	At design review 1	COR/VENDOR	PDF
5.2	Training Plan	Two months prior to start of training	COR	PDF
6.0	Technical Documentation	Two months prior to start of training	COR	PDF or Word
6.3	Data Collection System (DCS)	Prior to FIT	COR	PDF or Word

8.1 Special Delivery Instructions.

Performance/ Delivery Period. Contractor shall deliver and install the wiper tank(s) to BEP within 12 months of contract award. The period of performance for this contract includes a one (1) 12-month base period and three (3) options. The anticipated period of performance is 30 August 2026 to 29 August 2028.

8.2 Place/ Location of Performance/ Delivery.

The wiper tank(s) shall be delivered and installed freight on board destination to the following location(s):

DCF: Bureau of Engraving and Printing District of Columbia Facility
14th and C Streets, S.W.
Washington, DC 20228

WCF: Bureau of Engraving and Printing Western Currency Facility
9000 Blue Mound Rd.

Fort Worth, TX 76131

8.3 Federal Holidays and Year-End Shutdown

The BEP observes all Federal Holidays outlined by the Office of Personnel Management.

BEP observes the federal holidays that are listed on the Office of Personnel website at: <https://www.opm.gov/policy-data-oversight/pay-leave/federal-holidays/>. The Presidential Inauguration Day is applicable only to the Washington, DC Currency Facility.

BEP's Year End Shutdown Period typically occurs *December 25th through January 1st* of each calendar year.

Government Holidays:

New Year's Day	January 1st
Martin Luther King's Birthday	Third Monday in January
Washington's Birthday	Third Monday in February
Memorial Day	Last Monday in May
Juneteenth	June 19th
Independence Day	July 4th
Labor Day	First Monday in September
Columbus Day	Second Monday in October
Veterans Day	November 11th
Thanksgiving Day	Fourth Thursday in November
Christmas Day	December 25 th

Deliveries are not accepted on Federal Holidays unless there are extenuating circumstances and arrangements have been made in advance with appropriate BEP personnel.

END OF SECTION