




(1

1. COORDINATE WITH MECHANICAL DRAWING (M-101) FOR CONCRETE PAD LOCATION.
2. TOP OF CONCRETE PAD ELEVATION TO BE DETERMINED ON SITE.
3. MINIMUM OF CONCRETE STRENGTH 4000 PSI NORMAL WEIGHT CONCRETE WITH 6% AIR ENTRAINMENT FOR EXTERIOR CONCRETE.
4. STEEL WELDED WIRE FABRIC MESH SHALL CONFORM ASTM A185.



①

1

C

INFO

FOR COMMANDER NAVFAC		
ACTIVITY		
NRL CODE 3531		
SATISFACTORY TO DATE March 7, 2025		
DES: WX	DRW: WX	CHK: WX
PROJECT TEAM LEAD - Daniel Ebert		
CODE 3531 ENGINEERING - XXX		

NAVAL RESEARCH LABORATORY DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND WASHINGTON, DC	DISTRICT OF COLUMBIA CHILLER PAD OUTSIDE A69 PW 6860 BUILDING A69 CHILLER PAD
---	---

SCALE:	
SHOP NO.	
NRL PW NO.	PW 6860
SHEET	1 OF 1