



SSBN 737 [REDACTED] #1 and #2
500KW SSMG Sets In-Place
Reconditioning and Maintenance

Date: 27 FEB 2026

STATEMENT OF WORK (SOW)

1. GENERAL INFORMATION:

- 1.1. GENERAL: This is a non-personnel services contract to provide onboard technical overhaul/ refurbishment (in-place reconditioning) and maintenance/repair services of 500KW Ships Service Motor Generator (SSMG) Sets upon approved CFR. The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.
- 1.2. DESCRIPTION OF SERVICES/INTRODUCTION: The contractor shall provide all personnel, equipment, supplies, transportation, tools, materials, supervision, other items and non-personal services necessary to perform in-place reconditioning and maintenance/repair services of 500KW SSMG Sets as defined in this Statement of Work (SOW), except for those items specified as government furnished material, property and services. The contractor shall perform to the standards in this contract.
- 1.3. BACKGROUND: Trident Refit Facility, Bangor, WA (TRFB) in support of SSBN 737 [REDACTED] Extended Refit Period (ERP) requires in-place reconditioning and maintenance/repair services of the No. 1 and No. 2 500KW SSMG Sets. In-place reconditioning of [REDACTED] "Classic Design" 500KW Ships Service Motor Generator (SSMG) by USN maintenance activities is governed by the requirements Set forth in SUBMEPP Maintenance Standard 3140-081-039, Ref. 2.1, which mandates NAVSEA approval of activities performance thereof. TRFB does not possess this capability, thus TRFB requires a contractor with documented NAVSEA approval to conduct in-place reconditioning of Ship Service Motor Generators. Documented proof of the contractor's NAVSEA approval shall be provided at solicitation with the proposal for technical review and consideration. NAVSEA Letter 4710 SER 04X/320 dtd 04 OCT 2011, Ref. 2.2, provides NAVSEA approval of one known commercial entity.
- 1.4. SCOPE: Current baseline conditions: SSBN 737 [REDACTED] No. 1 & No. 2 500KW SSMG are in an operational status during a dry-docking availability. Performance of 500KW SSMG Set in-place reconditioning and maintenance under this contract is required by class maintenance plan and not to correct address specific equipment or operating deficiencies or material discrepancies.
- 1.5. PERIOD OF PERFORMANCE: [REDACTED]
 - 1.5.1. Contractor work to perform in-place reconditioning and maintenance services of the first of two 500KW SSMG Sets shall start and conclude within the first of two three-week periods. Upon conclusion of in-place contractor work on the first of two 500KW SSMG Sets, the work shall then pause for approximately one week to enable sufficient time to permit Ship's Forces (SF) scheduled maintenance and retest actions to restore the first of two 500KW SSMG Sets to operation. Upon operational

restoration of the first of two 500KW SSMG Sets, the in-place contractor work to perform in-place reconditioning and maintenance services of the second of two 500KW SSMG Sets shall start and conclude within the second of two three-week periods.

1.6. LOCATION OF WORK: [REDACTED]

1.7. TYPE OF CONTRACT: Government will award a Firm-Fixed Price Contract.

1.8. TECHNICAL CLARIFICATION: All technical clarifications will be coordinated through the Contracting Officer's Representative (COR).

1.9. GOVERNMENT POINT OF CONTACT: Contracting Officer's Representative (COR) Identified in contract.

1.9.1. Coordinate delivery and shipment of Contractor equipment and supplies with the COR:

1.9.2. Government Delivery and Shipping Address:

[REDACTED]

2. REFERENCES:

2.1. SUBMEPP Maintenance Standard 3140-081-039 Rev-C Chg-10, 500KW SSMG Set "Classic" In-Place Clean, Inspect and Re-Condition [NOFORN]

2.2. NAVSEA Letter [REDACTED]; Authorization to Utilize [REDACTED] for Work Onboard Nuclear Powered Ships.

2.3. NAVSEA S0400-AD-URM-010/TUM Rev-08 – Tag-out User's Manual

2.4. COMUSFLTFORCOMINST 4790.3 Rev-D Chg-4 Joint Fleet Maintenance Manual [NOFORN]

2.5. Northwest Regional Maintenance Center (NWRMC) Local Standard Items 099-12NW

2.6. NAVSEA S6269-A1-MMM-010 Rev-09, MG Set & Assoc. Controls [NOFORN]

3. REQUIREMENTS:

- 3.1. Provide all tools, parts, test equipment, consumables, including hazardous materials, personnel, labor, technical expertise, and Personnel Protection Equipment (PPE) to accomplish requirements.
- 3.2. Prohibit accomplishment of work requiring personnel monitoring of radiation, i.e. wearing a Thermoluminescent Dosimeter (TLD) by contractor employees.
- 3.3. Planning, supervising, or performing nuclear work is not authorized without the express approval of Puget Sound Naval Shipyard (PSNSY) Nuclear Regional Maintenance Division (NRMD) [REDACTED].
- 3.4. Attend an arrival and safety brief with [REDACTED] 737ERP Project Team, Work Integration Manager (WIM), Ship's Forces (SF), and Contracting Officer's Representative (COR), for all contractor and subcontractor employees, upon arrival.

3.5. WORK CONTROLS:

- 3.5.1. Comply with the work authorization IAW COMUSFLTFORCOMINST 4790.3 Vol. IV Chapter 10, Ref. 2.3, and tag-out requirements of NAVSEA S0400-AD-URM-010/TUM, Ref. 2.4, to ensure all work is authorized and controlled by the government. Ship's Forces (SF) acting as the designated Repair Activity Representative (RAR) as detailed:

- 3.5.1.1. Coordinate with the SF to verify boundaries and ensure entire site is isolated and ready for work.

- 3.5.1.2. Ensure all work on ship's systems and components properly authorized and controlled to ensure personnel and ship safety standards are met. SF will complete the tag out, Work Authorization Form(s) (WAF) and testing of the system.

- 3.5.1.3. Review WAF with SF to ensure understanding authorized work areas prior to starting work and maintain a copy of the WAF onsite during production work.

- 3.5.1.4. Make request at least three days prior to needing changes to isolation or work boundary to SF.

- 3.5.1.5. Ensure the isolation, de-energizing, drainage of the components are isolated and depressurization of mechanical, electrical, electronics and pressure system is accomplished.

- 3.5.1.6. Submit changes to isolation or work boundaries to SF, upon completion of production work, sign Block 16 of WAF.

3.6. SECURITY REQUIREMENTS:

- 3.6.1. Level of Facility Security Clearance (FCL) Required: Confidential.

- 3.6.2. Level of Safeguarding for Classified Information/Material Required at Contractor Facility: Confidential.

- 3.6.3. Consider this project, and all materials including records, files, documents, and work papers provided to the contractor by the Government and all test results, conclusions and recommendations obtained thereof as Government property.
- 3.6.4. The information shall not be disclosed, copied, modified, used (except in the completion of this contract) or otherwise disseminated to any other person or entity at any time to include, but not limited to, inclusion in any database external to the Government without the Government's expressed written consent.
- 3.6.5. Restricted Data: Contractor employees require access to and control of RESTRICTED DATA (RD), regarding Naval Nuclear Propulsion Information (NNPI and U-NNPI), to accomplish the requirements of this contract. Safeguarding of NNPI and U-NNPI shall be per the requirements of OPNAVINST N9210.3. Contractor employees will require access to Engine Room, Middle and Lower Levels, in the vicinity of No. 1 and No. 2 500KW SSMG Sets.

3.7. SAFETY:

- 3.7.1. Safety-Mishap Notification and Investigation: Notify (via telephone) the cognizant Contracting Officer's Representative (COR) and project within four hours of all contractor mishaps or incidents. If requested by the cognizant COR and/or Project, the contractor shall immediately secure the mishap scene/damaged property and impound pertinent maintenance and training records until released by the investigating safety office. Cooperate if the Government investigates the mishap and assist the Government personnel until the investigation is completed.
- 3.7.2. Ensure employees understand fire safety requirements and actions taken when a fire or emergency occurs during work onboard the ship.
- 3.7.3. Ensure that personnel mark their areas shipboard for hazards created, using the local Hazardous Area/Personal Protective Equipment (PPE) required signs. Signs are to be placed at all entrances to the industrial work areas. Typical hazards are overhead work, rigging lifts, grinding, and welding, banding and electrical hazards.

3.8. TECHNICAL WORK REQUIREMENTS:

- 3.8.1. Comply with the Northwest Regional Maintenance Center (NWRMC) Local Standard Items 099-12NW, Ref. 2.5.
- 3.8.2. Re-condition No. 1 and No. 2 500KW SSMG Sets in-place per vendor generated NAVSEA approved "Classic Design" 500KW SSMG in-place reconditioning procedure(s) meeting the requirements of Ref. 2.1. Ensure the following requirements are fulfilled:
 - 3.8.2.1. Document the 500KW SSMG Set's initial operating condition and Measure and record insulation resistance values of the 500KW SSMG Sets. Report the operating condition and all electrical and mechanical measurements/readings

in each 500KW SSMG Set's Work Completion Report (CDRL A002, DI-MGMT-82061).

- 3.8.2.2. Submit one Legible copy, in approved transferrable media, a condition found report (CFR) of the inspection results, including any missing or damaged parts, to the Contracting Officer's Representative (COR) for each piece of equipment inspected within 24 hours of completing the inspection. COR will forward to requirement generator. (CDRL A001, DI-MGMT-81648).
- 3.8.2.3. Request delivery of "mandatory" Government Furnished Materials (GFM) via TRFB [REDACTED] Supervisor, a minimum of 24 hours prior to required use; see SOW paragraph 4.6.
 - 3.8.2.3.1. GFM not planned for replacement may be necessary to be provided to resolve unsatisfactory material condition(s) identified by contractor inspections performed. This "contingent" GFM shall be identified to the COR and TRFB [REDACTED] Supervisor within twenty-four hours of the identified "contingent need". "Contingent" GFM not locally on hand/in shop, will be procured and expedited to the greatest extent possible for delivery. TRFB [REDACTED] Supervisor will ensure "contingent" GFM is provided to the contractor within 24 hours of its receipt from off station.
- 3.8.2.4. Upon arrival/start of work, the contractor shall inform the COR of any additional interference items that require removal to support 500KW SSMG Sets' in-place work.
- 3.8.3. Disassemble, clean, and inspect the 500KW SSMG Sets, including onboard rigging of 500KW SSMG Set components during the in-place reconditioning process. Document each 500KW SSMG Sets' inspection deficiencies as findings in the CFR.
 - 3.8.3.1. This includes detergent and water cleaning of the SSMG Set frame internal surfaces, air coolers, static exciter, rotor, fans, AC stator, DC commutating poles, AC brush rigging, and DC brush rigging and support yoke.
 - 3.8.3.2. Inspect gaskets of the 500KW SSMG Sets' covers that are routinely removed for maintenance and replace any damaged gaskets. Replacement gasket material is "contingent" GFM; see SOW paragraph 3.8.2.3.1 regarding obtaining "contingent" GFM.
 - 3.8.3.3. Recondition in-place the 500KW SSMG Sets' AC stators, DC commutating field poles, static exciters, AC brush riggings, DC brush riggings and yokes.
 - 3.8.3.4. Replace 500KW SSMG Sets' DC main field poles meeting the requirements of NAVSEA S6269-A1-MMM-010, Ref. 2.6. Replacement DC main field poles are new/refurbished Depot Level Repairable (DLR) GFM. The removed DC main field poles are DLR GFM and shall be provided to TRFB [REDACTED] for turn-in to the Navy Supply system; ensure the TRFB [REDACTED] Supervisor is informed on the return of the DLR GFM.

- 3.8.3.5. Recondition 500KW SSMG Sets' rotors in-place including the following:
- 3.8.3.5.1. Resurfacing, undercutting, and beveling of the DC commutators
 - 3.8.3.5.2. Resurfacing of the AC slip/collector ring assemblies
 - 3.8.3.5.3. AC field lead replacement, which is contingent on existing leads having unsatisfactory material conditions. Replacement field lead material is "contingent" GFM; see SOW paragraph 3.8.2.3.1 regarding obtaining "contingent" GFM.
 - 3.8.3.5.4. Commutator seal band (Resi-Glass or Teflon) replacement, which is contingent on existing commutating seal having unsatisfactory material conditions. Replacement commutator seal material is "contingent" GFM; see SOW paragraph 3.8.2.3.1 regarding obtaining "contingent" GFM.
 - 3.8.3.5.5. Clean, inspect, and measure rotor shaft AC and DC end bearing seats.
- 3.8.3.6. Clean, inspect, and measure 500KW SSMG Sets' AC and DC end bearing support bracket assemblies, i.e., AC and DC end brackets, AC and DC bearing inner caps, DC bearing outer cap, AC spring pack, AC and DC bearing cartridges.
- 3.8.3.6.1. Replace existing 500KW SSMG Sets' AC bearing, AC bearing cartridge, DC bearing, and DC bearing cartridge with GFM.
- 3.8.3.7. Replace existing 500KW SSMG Sets' AC, DC, and over-speed electrical brushes with GFM.
- 3.8.3.8. Replace 500KW SSMG Sets' existing DC air filters with GFM.
- 3.8.3.9. Repair or replace stripped fasteners and/or repair threaded bolt holes of 500KW SSMG sets discovered during work. Replacement fasteners are "contingent" GFM, see SOW paragraph 3.8.2.3.1 regarding obtaining "contingent" GFM.
- 3.8.3.10. Perform torque checks of 500KW SSMG Sets bolted electrical connections.
- 3.8.3.10.1. Replace 500KW SSMG Sets' disturbed DC electrical connections existing Belleville Washers with GFM.
- 3.8.3.11. Reassemble 500KW SSMG sets, seat electrical brushes, and set the DC electrical neutral plane.

(V) (G) "CLOSE OUT INSPECTION"

- 3.8.4. Upon completion of work, schedule with the COR and Ship's Forces (SF) a joint close out inspection of each 500KW SSMG Set.

(V) (G) “CHECK POINT; OPERATIONAL TEST”

3.8.5. Following completion of joint close out inspection of each 500KW SSMG Set, with the COR in attendance, observe SF conduct of the 500KW SSMG Set’s operational retest.

3.8.6. Within five days following completion of the initial operational test of each 500KW SSMG Set, submit one legible copy, in approved transferable media, of a Work Completion Report of each affected 500KW SSMG Set that shall contain the following data, at a minimum: (CDRL A002, DI-MGMT-82061):

3.8.6.1. Electrical and mechanical measurements/readings taken during performance of work on the affected 500KW SSMG Set.

3.8.6.2. Results of initial operational testing following performance of work on the affected 500KW SSMG Set.

4. GOVERNMENT WILL SUPPLY:

4.1. Provide disposal of HAZWASTE.

4.2. Provide crane and rigging services of contractor tooling/equipment from/to a dry dock adjacent laydown area to/from middle level engine room onboard ship.

4.3. Provide the following temporary services, as required: 120VAC/60HZ (20 Ampere) tooling electrical power, 450VAC/60HZ (30 or 60 Ampere) 3-phase industrial electrical power, industrial (non-potable) water via 1-inch or 3/4-inch industrial hose connection, an industrial “tooling” air manifold ($\approx$ 100 PSI) to within 25-feet of work site, and 3-inch/8-inch ventilation duct.

4.3.1. If the contractor requires potable water shipboard, Ship’s Forces (SF) may provide a potable water source. Alternatively, the contractor may contact the Government to arrange specific TRFB services for potable water via TRFB [REDACTED] Supervisor.

4.4. Provide a temporary lay-down area ($\approx$ 20-feet x 20-feet) adjacent to the Delta Pier dry-dock to support the loading/off-loading of contractor equipment/tooling to/from the SSBN 737 engine room middle level work site.

4.5. Provide interference removal in the vicinity of No. 1 and No. 2 500KW SSMG Sets ahead of contractor’s arrival.

4.5.1. The Government will engage TRFB [REDACTED] Supervisor for assistance to remove any additional interference for removal or coordinate its removal by SF or other TRFB work center(s) when beyond TRFB [REDACTED] area of responsibility.

4.6. Provide the “mandatory” GFM listed in SOW paragraphs 4.6.1 and 4.6.2 when requested by the contractor, not to exceed twenty-four hours from the time of the request to TRFB

GFM.

4.6.1. The following “mandatory” GFM is provided to the contractor for performance of work on the No. 1 500KW SSMG Set:

4.6.2. The following “mandatory” GFM is provided to the contractor for performance of work on the No. 2 500KW SSMG Set:

[REDACTED]

[REDACTED] [REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

4.7. Government affected equipment description:

4.7.1. Equipment manufacturer data:

General Electric Company
Drives Motor and Generator Department
3001 East Lake Road, Erie, PA 16531

4.7.2. Equipment nomenclature, make, model part number and allowance parts list (APL):

Nomenclature: 500kW DC/AC or AC/DC Ship's Service Motor Generator Set
Make: General Electric Company

[REDACTED]

5. CONTRACTOR FURNISHED MATERIALS:

5.1. Submit one legible copy, in approved transferable media, a Contractor Furnished Material Report (CFM) of the complete accounting of Contractor's Furnished/Consumable Materials used in the reconditioning and reassembly of the 500KW SSMG Sets, to the Contracting Officer's Representative (COR) for each 500KW SSMG Set within three days of work completion (CDRL A003, DI-MGMT-82049).

5.1.1.1. The CFM shall include the following: cleaning products, lubricants, sealants, insulating tapes/compounds/epoxies/coatings, and hardware not otherwise provided as "contingent" GFM. The contractor may opt to exclude the "mandatory" GFM items listed in SOW paragraphs 4.6.1 and 4.6.2 from the CFM.

- 6. QUALITY:** The Quality Assurance Surveillance Plan (QASP) will be used as a tool to verify the contractor is performing all services and delivery/installation of replacement parts required by the above requirements in a timely, accurate and complete fashion.

7. DELIVERABLE ITEMS:

- 7.1. Provide deliverables as described in this SOW and as outlined for format and delivery schedule in Contract Data Requirements Lists (CDRLs).

Number	Name	Frequency	Quantity
A001	Conditions Found Report	On Time	As Req.
A002	Work Completion Report	On Time	One Each
A003	Contractor Furnished Material Report	On Time	As Req.