

3. PRE-PROPOSAL INQUIRY RESPONSES:

Question #	Reference			Question	Government Response
	Page	Section	Paragraph		
1	12	00 21 00		As we prepare our proposal, we are experiencing a challenge related to the timing of subcontractor and vendor quotations. Many subcontractors and vendors do not release final pricing until one to two hours before our proposal is due. This significantly affects our ability to finalize our price volume, as we cannot determine which subcontractors or vendors will ultimately be included in our final pricing until just before submission. Because the RFP requires the Small Business Subcontracting Plan (SBSP) to be submitted with the Price Proposal volume, contractors must either (1) base the SBSP on preliminary assumptions made several hours in advance of submission, or (2) submit the SBSP at a later time on bid day, once subcontractor and vendor selections are confirmed. To ensure full compliance, while providing the most accurate information possible, we respectfully request your guidance and preference: Submit our SBSP based on assumptions made prior to receiving final subcontractor and vendor pricing OR submit an accurate SBSP by 5:00p EDT on bid day, once all pricing and selections are finalized.	Propose per RFP
2		SF1442		PPIs are currently due on 7 April (within 14 calendar days prior to the solicitation closing date). Allowing for one week for NAVFAC to provide PPI responses, and one week for contractors to incorporate any changes with subcontractors, we request a one-week extension of the proposal due date from 21 April 2026 to 28 April 2026 at 2:00p EDT.	Proposal due date extended to 28 April 2026 via Amendment 0002.
3	5-10 of 60	00 10 00 and Attachment F		Pages 5-10 of Section 00 10 00 of the solicitation provide the Contract Line-Item Number (CLIM) Schedule with Additional Information/Notes. Also included as part of the solicitation is the separate Attachment F Price Proposal Form, which differs from the one provided in Section 00 10 00. Please confirm which of these two	Submit (revised) Attachment F Price Proposal Form provided with Amendment 0002 in accordance with the RFP.

				documents contractors are to submit with our Price Proposal volume.	
4	BID SHEET	CLINS 07 & 014		CLIN's 0007 and 0014 are to provide Electronic Security System (ESS) for both P-993 and P-995. Please confirm if the Fire alarm system will be considered as ESS. Or is the intent to cover all work as shown on the TY (Security) drawing set?	ESS will not be included in the Plans and Specifications, but the infrastructure (conduit and boxes) is included in the Base Bid of the contract. Specification Section 28 08 10 Electronic Security System Acceptance Testing and 28 10 05 Electronic Security Systems (ESS) will be removed from P993. Further Specifications changes will be included in an upcoming amendment. CLIN(s) 0007 and 0014 have been REMOVED from the Price Proposal Form. See Amendment 0002 revised Price Proposal Form.
5	P-993	Sheet S-540		The CLT roof to steel connection uses a CLT "nailer" per (sheet S-540). Can a glulam nailer be provided in lieu of the 12" wide CLT nailer? A glulam nailer is much easier to fabricate - and has less exposed wood end grain. The glulam nailer would be a 3.5"x12" glulam laid flat.	This can be considered during the CA phase and will require additional time to investigate the impact. Prior to further investigation, please confirm that a 3.5" glulam will be adequate to accommodate roof slope, please see Note 2 in each of the associated details on S-540.
6	P-995	41 22 13.15	1.3.1.1 1.3.1.3	Section 1.3.1.1 identifies the crane system as an under running crane, while Section 1.3.1.3 classifies the system as a top running crane. These crane types have fundamentally different structural support requirements, runway beam configurations, and cost implications. Please clarify which crane type is required for this project: Under Running (Underhung) Bridge Crane, or Top Running Bridge Crane Additionally, confirm whether the supporting structure (runway beams, columns, and building framing) has been designed to accommodate the intended crane type.	PENDING RESPONSE
7	P995, 2	45 52 00	1.3.1	The specification references NAVSEA Manual S0420-AA-RAD-010; however, this document has not been provided within the solicitation package and is not readily accessible	The document is not available for public release. The Government will release the appropriate sections once the vendor for the X-ray

				through standard public sources. Please provide a copy of NAVSEA Manual S0420-AA-RAD-010 or identify an official source/location where the document can be obtained.	equipment has been selected. Additional criteria will be added by amendment.
8	P995, 2	45 52 00	1.3.1	The specification states that “Acceptance testing is calibrated to Fleet Readiness Center East (FRCE) quality standards.” However, no criteria, procedures, tolerances, or reference documents defining these standards have been provided. Please provide detailed requirements for the referenced FRCE quality standards, including: -Applicable testing procedures and protocols -Acceptance criteria and tolerances -Calibration requirements -Any governing documents or standards to be followed	Testing procedures, acceptance criteria and tolerances added by amendment. Calibration requirements and governing documents will be added to the specification by amendment.
9	P995, 4	45 52 00	3.4, Item 9	Paragraph 3.4 specifies the use of a “1515DX detector.” It is unclear whether this represents a strict basis-of-design requirement or a performance benchmark. Please clarify whether: -The specified 1515DX detector is mandatory, or -Equivalent or superior detectors meeting or exceeding the required performance criteria are acceptable Additionally, if alternatives are acceptable, confirm whether: -They may be proposed as equals within the base bid, or -They must be submitted as a separate line-item option / alternate	It is intended that the detector cited is a basis of design only. Other manufacturers’ products will be accepted provided they meet the performance requirements of the basis of design.
10	P995, 2	45 52 00	1.4	Paragraph 1.4 requires a 5-year warranty for the system. However, certain critical components—specifically the x-ray source and detector—typically do not carry a 5-year manufacturer warranty under standard industry practice. Please clarify whether: -The 5-year warranty requirement applies to all system components without exception, or -Exceptions are permitted for components with standard	PENDING RESPONSE

				manufacturer warranty limitations Additionally, if full compliance is not feasible, confirm whether the Contractor may: -Propose standard manufacturer warranties for these components, and/or -Provide recommended spare parts (e.g., x-ray source, detector) as an optional line item to support long-term operability in lieu of extended warranty coverage Basis of Concern / Impact: The specified 5-year warranty exceeds typical industry standards for key system components and may: -Limit availability of compliant equipment vendors -Introduce sole-source or non-competitive procurement conditions -Result in significant cost premiums or infeasible requirements	
11	P995, 2	45 52 20	1.3.1.1	Reference: “Vault and Manipulator Equipment: 480 Volt, 3 Phase, 60 Hertz, 50 Amp” Question: Is the use of a step-down transformer (480V to 240V) acceptable to meet the power requirements for the Vault Manipulator Equipment, or should the building electrical service be adjusted to accommodate the actual equipment power requirements? Basis of Concern / Impact: Clarification is required to confirm compatibility with available facility power and to support accurate electrical design and pricing.	Use of step-down transformer is intended and is acceptable.
12	P995, 3	45 52 00	2.2	Reference: “X-ray vaults are constructed of shielded modular panels.” Question: The specification indicates shielded modular panel construction for the x-ray vault. Please confirm whether: -Self-shielded modular vault systems are acceptable, and -Cast-in-place (concrete-shielded) vault construction may be provided as an equivalent alternative, provided shielding and performance	Propose per plans and specifications.

				requirements are met Basis of Concern / Impact: Multiple industry-standard approaches exist for x-ray vault construction. Clarification is required to: -Confirm allowable system types -Maintain competitive vendor participation -Optimize cost, constructability, and schedule	
13	P995, 3	45 52 00	2.2	Section 45 52 20 ¶2.2: Section 2.2 cites compliance with 21 CFR 1020.4; however, this reference appears incorrect. It is understood that the applicable regulation for cabinet x-ray systems is 21 CFR § 1020.40. Please confirm whether the intended requirement is 21 CFR § 1020.40 and revise the specification accordingly. Clarification is required to ensure proper regulatory compliance, equipment selection, and accurate pricing.	PENDING RESPONSE
14	P995, 4	45 52 00	3.2.1	Section 45 52 20 ¶3.2.1: The specification states, "Provide two hours of onsite training." Please confirm whether this represents the full training requirement, or if separate operator training and maintenance training sessions are required as part of commissioning and turnover. Clarification is required to ensure proper scope definition, coordination with end users, and accurate pricing.	PENDING RESPONSE
15	P995, 4	45 52 00	3.4 XTE-1 Item 3	Section 45 52 20 ¶3.4, Item 3: The schedule indicates a "6'-0" high by 8'-0" wide biparting motorized slider," which appears restrictive for loading a 33.7-foot blade with associated handling fixtures or carts. Please confirm: (a) the required clear opening height and width for blade loading, and (b) whether the stated door dimensions are a strict requirement or may be adjusted as part of the delegated design. Clarification is required to ensure constructability, equipment compatibility, and accurate pricing.	PENDING RESPONSE

16	P995, 4	45 52 00	3.4 XTE-1 Item 7	Section 45 52 20 ¶3.4, Item 7: "Internal bridge crane: 2 tons, for loading blades from transport cart to blade manipulator" Please confirm: a) Will the transport cart be positioned inside the X-ray vault for loading via the internal bridge crane, or is blade transfer expected to occur outside the vault? b) Please confirm whether the transport cart and lifting fixtures are Owner-furnished or included within the Aerospace X-ray Testing Equipment scope.	The transport cart is going to be positioned inside the vault for loading and unloading the blades to the fixture. The carts are owner furnished.
17	P995, 4	45 52 00	3.4 XTE-1 Item 8	Section 45 52 20 ¶3.4, Item 8: "X-ray characteristics: Mark X system with MXR 160-HP11 having 0.4 to 1.0 focal spots at 800 to 1,800W, 160 kV source, cooler and controller" Please confirm: A Mark X system is referenced. Does this refer to a device that physically places a fiduciary mark on the blade so that it is easy to identify the place on the blade which must be reworked or repaired?	Yes, the Mark X system is a feature that allows the system to mark the blade where the damage is and later the operator can go and examine the blade further.
18	P995, 4	45 52 00	3.4 XTE-1 Item 8-10	From an X-ray imaging standpoint, the specifications are prescriptive and design-based rather than performance-based. Please define the required inspection performance criteria for acceptance, including target defect types (e.g., water intrusion, crushed core, debonds, foreign object inclusion), minimum defect size / sensitivity, and any required IQI or image quality standard.	PENDING RESPONSE
19	P995, 4	45 52 00	3.4 XTE-1 Item 4,9,10	Please provide the required inspection throughput / cycle time per blade.	PENDING RESPONSE
20	P995, 4	45 52 00	3.4 XTE-1 Item 4-5	Please clarify the required degrees of freedom for the blade manipulator and scan system. As it currently reads, this specification could be satisfied with a total of three axes. Specifically, one axis to: 1) Move the source and detector along the length of the blade 2) Move the source and detector along the height of the blade 3) Rotate the blade	PENDING RESPONSE

				In practice, many more axes are typically provided to achieve the intended inspection coverage. Also, is there a preference or requirement to have the gantry mounted source and detector manipulator mounted to the floor or ceiling? We interpret this as floor-mounted because it would interfere with the 2-ton internal bridge crane	
21	P995, 4	45 52 00	3.4 CH-1 Items 1,7,10	Please confirm the intended computer hardware requirement. CH-1 identifies a Dell Mobile Precision 7865 tower workstation, but also calls for wireless capability and provision of a MAC address for a laptop 60 days prior to delivery. a.) Please clarify whether the basis of design is a tower workstation, a laptop, or either. Additionally, the way the computer is specified (e.g., Threadripper PRO, RTX 5000 Ada.), it seems intended for CT reconstruction, AI / automatic defect recognition software, or very heavy image stitching / batch processing. b.) Is this a strict owner requirement or IT / cybersecurity standard? Or for anticipated future use such as advanced imaged processing?	4 tower workstation is intended. 3.4, CH-1 has been amended to delete requirements 7 and 10.
22	P995, 3	41 34 23	1.3	Specification Section 41 34 23, Paragraph 1.3 requires the Paint Booth Contractor (PBC) to perform a Hazard Evaluation and Analysis in accordance with ANSI Z9.7, 29 CFR 1910.107, and NFPA 33, as well as a Dust Hazard Analysis (DHA) in accordance with NFPA 652, Chapter 7. However, the specification does not appear to provide sufficient Basis of Design information necessary to perform these analyses. Specifically, the following information is not defined: -Identification of processes that generate airborne particulates (e.g., sanding, grinding, composite repair, etc.) -Characterization of particulate matter (metallic, composite, organic, etc.) -Material properties required for DHA, including but not limited to Kst, Pmax, MEC, particle size distribution,	1 - Answered by Government in Specification. The specification explicitly defines "Sanding Mode," "Spray Mode," and "Brush/Roll Painting Mode" as required operational modes (Section 1.7.3). These are the core processes the system must be designed to handle. 2 - Responsibility of the Contractor. The specification provides a detailed list of all metals, composites, coatings, and adhesives to be used (Section 1.3). It is standard practice for the expert contractor to be responsible for obtaining the Safety Data Sheets (SDS) for these specified materials to conduct their analysis. 3 - Responsibility of the Contractor. The Government

				and combustibility classification -Safety Data Sheets (SDS) or emission data for coatings, adhesives, and associated materials listed in Paragraph 1.3 -Expected concentrations, generation rates, or operational scenarios for both particulates and vapors -Confirmation whether combustible dust conditions are anticipated within the paint booth As these inputs are required to determine compliance with NFPA 652, NFPA 33, and ANSI Z9.7—including evaluation of recirculation permissibility, explosion protection requirements, and ventilation system design—the Contractor is unable to fully develop the required analyses or accurately size and price the system. <u>Request:</u> Please provide clarification and/or supplemental information regarding the Basis of Design for the required Hazard Evaluation and Dust Hazard Analysis, including: 1. Identification of all dust- and vapor-generating processes to be performed within the booth 2. SDS documentation for all coatings, solvents, adhesives, and materials listed in the specification 3. Characterization of expected particulate types and whether combustible dust is anticipated 4. Any available existing Hazard Evaluations, Dust Hazard Analyses, or environmental/air permitting studies 5. Confirmation whether exhaust air recirculation is intended to be permitted as part of the design Alternatively, confirm that the Contractor may base the Hazard Evaluation and Dust Hazard Analysis on reasonable industry-standard assumptions, and that any impacts resulting from actual material properties or regulatory requirements will be addressed as a contract modification.	has characterized the particulate types by listing the materials (e.g., Nickel, Titanium, Carbon Fiber) in Section 1.3. The core task of the DHA, which the contractor must perform per NFPA 652, is to analyze these materials to determine if they are combustible and what their properties are. The Government does not need to pre-determine this; they are paying the expert contractor to make that determination. 4 - Answered by Government in Specification. The specification does not reference any existing studies. Instead, it explicitly requires the PBC to "perform a Hazard Evaluation and Analysis" and submit a report for approval *before* developing their design (Section 1.3 & 1.8.b). This makes it clear that a new analysis is a required deliverable of the contract. 5 - Answered by Government in Specification. The specification confirms that recirculation is a key design requirement. It specifies "80% Recirculation" for both Spray and Brush/Roll modes (Section 1.7.3) and outlines the NFPA 33 requirements that must be met for this to be permissible (Section 1.7.4.d).
23	P-993 Drawings	FA140		The Fire Alarm devices in the paint booth areas are all Explosive Proof. The Fire alarm Devices in the locker rooms are listed as weatherproof only.	Fire alarm devices in the locker rooms do not need to be explosive proof type.

				Please confirm the Fire Alarm devices in the locker rooms in the paint booth areas are not required to be explosive proof?	
24	P-993 Drawings	S-510		Are the Pile caps included in CLIN 0001D Building Piles or CLIN 0001A?	Piles caps to be included in CLIN0001A
25	P-993 Drawings	EP618-621, 624-629, 633, 635-636		On the EP panel schedules (EP618-621, 624-629, 633, 635-636) they show breakers for “Mech Ctrl Pnl”. On the EP floorplan layouts they show “Mechanical Control Panel” but they do not indicate what piece of equipment the panel is associated with. It does look like the panel locations align on the 1st floor plan below the associated equipment above on the roof. There is no marking on the “Roof Power Plan” for “Mechanical control panel” which makes me think they intend to be inside. Are the panels required to be installed adjacent to the roof top equipment or installed inside the buildings directly beneath the equipment?	Electrical drawings are for circuiting only. See mechanical and controls MIXXX sheets for information on location and connections.
26	P-993 Drawings	MI801-M805		Please confirm the network architecture shown on MI801-805 is a general depiction to show intended equipment connections only. The current MI801-MI805 drawings are not aligned with the JCI Metasys Design guidelines. Please confirm that contractors will be required to work with the Governments DOR during DDC submittal process to align final DDC network design with JCI Metasys product design guidelines?	Network architecture shown is for general intent. Controls contractor (JCI) must create final DDC network architecture according to current design guidelines and standards and with Government approvals.
27	P995, 3	42 15 00	1.4.1	1.4.1 specification indicates that the airflow pattern within the autoclave will be solely underneath the autoclave floor. Typical autoclave airflow specifications are four 300 ft./m minimum. The existing autoclaves at Cherry point and at North Island utilize full annular airflow configurations. The cross-sectional area of the airflow under the floor only does not allow achieving 300 ft./m in workspace across operating pressures. The requirement also specifies maximize heat transfer capacity, which would be a different style of autoclave (not air under the floor only). Is design to meet the	Design intent is to maintain temperature uniformity regardless of air flow distribution configuration.

				maximize heat transfer requirement the priority?	
28	P995, 6	42 15 00	3.8	Please confirm 150 psi 450 F maximum operating pressures and temperatures (per 3.8)	Confirmed that maximum operating pressure is 150 psi and maximum operating temperature is 450 degrees F. These are minimum requirements and higher capabilities are acceptable.
29	P995, 6	42 15 00	3.8	Per requirement 2.1.1, part thermocouples would be 20 and part vacuum sources would be 20. Per requirement 3.8 AC-2 item 22, 24-part thermocouples and 12-part vacuum sources. What is the requirement?	Requirement is as scheduled. Paragraphs 2.1.1 and 2.1.2 will be modified to eliminate conflict.
30	P995, 6	42 15 00	3.8	Per req 2.1.1, it says 1 vacuum line per ft of workspace, which would be 5. Per req 3.8, item 22 says 3 vacuum source lines. What is the requirement?	See response to PPI #29
31	P995, 6	42 15 00	3.8	Per req 2.1.1, it says 3-part thermocouples per ft of workspace, which would be 15-part thermocouples. Per req 3.8 item 22, it says 6-part thermocouples. What is the requirement?	See response to PPI #29
32	P995, 6	42 15 00	3.8	Section 42 15 00 ¶3.8, Item 23: The specification references a specific manufacturer's brand name software, "CPC 2024 level 1 & 2 software". Please clarify whether this is intended as a sole-source requirement or as a basis-of-design. If not sole-source, confirm that equivalent software solutions meeting the project's functional and technical requirements are acceptable. Clarification is requested to ensure competitive bidding and proper coordination with qualified vendors.	It is intended as a basis of design only. Other software will be accepted that meet the performance characteristics of the basis of design.
33	P995, 6	42 15 00	3.8	8 ft autoclave (AC-2) specifies a vent silencer. The 3 ft autoclave does not specify a vent silencer. Please advise vent silencer requirement to align with OSHA noise requirements.	Refer to paragraph 3.8, AC-1 Small Composite Curing Autoclave item 10 for schedule.
34	P995, 6	42 15 00	3.8	8 ft autoclave (AC-2) specifies computer controlled vacuum source lines, and it is not specified computer controlled source lines in the 3ft autoclave list. Are computer controlled vacuum source lines required for 3ft autoclave?	The intent is that vacuum source lines are computer controlled.
35	P995, 3	42 15 00	1.4.2	1.4.2 does the government assume responsibility for the performance of the oven with the blowers and heaters	Prioritize uniformity and heating rate requirements and size accordingly.

				specified? Or is the uniformity and heating rate requirements priority and to be sized accordingly?	
36	P995, 3	42 15 00	1.4.2	Does the government require control system capabilities as specified in 1.4.1?	Yes.
37	P995, 3	42 15 00	1.4.2	Per req 1.4.2, the door shall be vertical lift via pneumatic cylinder and req 2.1.2 it says swing doors with view ports. Which is the preferred door type?	Vertical lift doors intended para 2.1.2 modified to eliminate the conflict
38	P995, 6	42 15 00	3.8	Per requirement 3.8 CO-1, it specifies a make up air blower. In requirement 1.4.2 is specifies the CFM of the blowers and does not specify that of the make up air blower. Is it required?	100% make up air is required.
39	P995	42 15 00		PPI – Price Proposal Form (CLIN 022, Option 20 – Composite Oven Complete): Based on review of the drawings, the following composite ovens are identified: Rm 131 (x6 – 2 EA, 6'x6'), Rm 131 (x7 – 2 EA, 10'x10'), Rm 136 (x20 – 2 EA, 12'x20'), and Rm 130 (CO-1 – 1 EA). Please clarify which of these units are included in CLIN 022. It is currently assumed that x6, x7, and x20 are included within CLIN 022 and that these items are carried in the Government estimate, with the Contractor only required to apply the HAR percentage. Additionally, please confirm that CO-1 is to be included under CLIN 0002A. Clarification is required to ensure alignment with the Price Proposal Form and accurate pricing.	On the new Price Proposal Form from Amendment 0001, CLIN 0023 is the large Composite Oven to be installed by the Contractor, and CLIN 0024 includes the six smaller composite ovens that only require the HAR cost to be added to the government estimated cost.
40				Please provide a copy of the most current Construction Security Plan.	The CSP has been provided to the Two General Contractors proposing on the projects previously.
41				Please provide a copy of the latest 3D Model files	3D files will be released to the successful offeror.
42	CU800			Keynote 1 on Sheet CU800 calls out the elevated storage tank. Please provide foundation information to support the elevated storage tank.	Due to tank manufacturer design differences, foundation design to be included be the delegated design professional.
43	C-002			General Note 8 on C-002 says, "UPON REQUEST, ELECTRONIC DRAWING FILES CAN BE PROVIDED TO AID WITH CONSTRUCTION STAKING AND	AutoCAD files will be released to the successful offeror.

				LAYOUT. THE FILES PROVIDED WILL BE IN AUTOCAD CIVIL 3D 2018 FORMAT. COORDINATE AND VERIFY ACCURACY IN THE FIELD." Please provide the AutoCAD Civil drawing files.	
44	M-608			M-608 Notes unit mounted thermostat for the Electric Unit Heaters. MI861, detail B3, shows DDC Controls. Please confirm what is desired.	MI861/B3 does not show/request DDC controls. It shows the electric heater with a electric line thermostat. Per Keynote 2, it states that BCS Contractor will mount and wire the "hardwired thermostat" provided as part of the electric unit heater.
45		09 97 13.27	2.2	UFGS 09 97 13.27 dated (), states "Use the second bracketed paragraph option for applied coatings systems applied entirely in the shop, where required such as, but not limited to, exterior and interior ferrous metal components identified in UFC 4-211-01 Aircraft Maintenance Hangars". Followed by "Prepare surface and apply the complete coating system in the shop. Follow all temperature, humidity, and testing requirements listed herein". Please remove first paragraph in 2.2 and allow all applied coatings systems entirely in the shop and touch-up to be performed in the field as referenced per UFGS for hangar structural steel.	Concur. Delete paragraph 2.2 "Apply the entire coating system in the field.....preparation requirements". Shop applied coatings with field touch up is acceptable.
46		09 97 13.27		09 97 13.27 calls for contractors and subcontractors applying industrial coatings identified in the Project Program to be SSPC QP 1 and QS 1 certified. These certifications pertain to contractors specializing in complex industrial structures such as bridges, chemical plants, storage tanks, etc. Please consider removing this certification requirement for coatings required for hangar structural steel.	Concur. Delete 099713.27 paragraph 1.4.6.5
47		13 49 20.00 10	2.3	The General Contractor and the Shielding Specialist Subcontractor are comfortable to test the shielded space per IEEE 299 standards, however, there is no performance guarantee that can be provided for a field-built facility. The shielding effectiveness test results will be provided in a confidential manner but may show small local failure points in the shielding. Any potential failure points, in the confidential report, will	Comply with the plans and specifications. The Contractor is responsible for providing a facility that meets the plans and specifications. If the spaces do not meet the independent third party testing, it will be investigated to determine why it does not conform to the required results and the Contractor will be required to repair areas that do

				be provided for information only. As discussed in IEEE 299, the testing standard is built around six-sided, continuously welded steel enclosures, bolted together panel enclosures, etc. When trying to use metal sheets with aluminum foil taping, cut and applied on a construction site, around obstacles, openings, etc., it doesn't yield the same level of shielding results as a prefabricated, continuously welded, six-sided box. With that being said, you will not be able to guarantee the specified performance (Shielding Effectiveness, 35 decibel(s) (dB) from 9 kilohertz (KHz) to 16 KHz and 80 dB from 16 KHz to 18 (GHz)). Please confirm the contractor is not responsible for RF enclosure guarantee, rework or repairs for any failures points that would occur since we are bidding the project as designed.	not conform due to workmanship. The design has been reviewed by the Site Security Manager and is in general conformance with the requirements. The Contractor is responsible for implementation of the design.
48				Multiple architectural drawing sheet General Sheet Notes say to see A-531 for partition schedule and details. Drawing A-531 is the INTERIOR DETAILS drawings. Please update general sheet notes and confirm the only partition schedule and details drawing is on A-519.	Confirmed. Partition schedule is on A-519.
49		13 49 20.00 10	3.9.1.2	Performance Test Plan states "Also include specific test dates and durations during the overall construction period so that the Contracting Officer and Accrediting Authority may be scheduled to observe the testing and so that repairs may be made to the shield and retests conducted". Due to the current design the shielded enclosure will fail in a field installed application when tested to IEE-29. Please confirm the contractor will not be held accountable for system failures due to design limitations itself.	Comply with the plans and specifications. The Contractor is responsible for providing a facility that meets the plans and specifications. If the spaces do not meet the independent third party testing, it will be investigated to determine why it does not conform to the required results and the Contractor will be required to repair areas that do not conform due to workmanship. The design has been reviewed by the Site Security Manager and is in general conformance with the requirements. The Contractor is responsible for implementation of the design.
50		13 49 20.00 10	1.6.3	Paragraph 1.6.3 only applies to HEMP shielded enclosures. Please remove this section from the specifications as this does not apply to this project.	Section 1.6.3 to remain. Delete all reference to "EM" shielding. Contractor required to provide operating and maintenance manuals for the

					shielded enclosure and penetrations.
51	TT602			Please confirm that Keynote 6 on TT602 is to provide an EMI filter for CAT5/6 Ethernet. Confirm if "EMI Filter" is for a CAT5/6 Ethernet, one EMI filter can support up to one (1) CAT5/6 Ethernet cable. Please confirm the quantity of Cables that applies to each note.	Response is to confirm that TT602 is a grounding diagram only. Keynote 6 and 2 provide one EMI filter to one AWG #1.0 ground cable routed into the secure space. No CAT-5/6 run outside the secure space shown on this diagram, the cables in that space are also provided to be provided by the NIWC team.
52	A-604	13 49 20.00 10	2.5.1	There are no commercially available RF Shielded / STC-50 or greater door assemblies that provide 10db greater than the performance requirements specified in paragraph 2.3. Please confirm note from paragraph 2.5.1, a does not apply or provide manufacture that provides the specified requirements for RF doors listed.	PENDING RESPONSE
53	S-504			The CLT roof to steel connection uses a CLT "nailer". Can a glulam nailer be provided in lieu of the 12" wide CLT nailer? A glulam nailer is much easier to fabricate - and has less exposed wood end grain. The glulam nailer would be a 3.5"x12" glulam laid flat.	See response to PPI #5.
54	MH134 & MH135			See MH135 (Keynote 2 for DOAS-07) and MH131 (Keynote 2 for AHU-03) for instance. The Building Control System (BCS) Panel is shown mounted to the DOAS or AHU unit on the roof. Please verify this is what is desired. Or, should the plans be amended to mount panel on a wall in the interior of the building on 1st floor and run conduit/wire up to the units instead?	The intent is to have the BCS for all units on the roof be mounted on the wall on the 1st floor.
55	MI823			MI823: Is the Paint Booth Toxicity Hazard Monitoring panel to be explosion proof?	No. For the Paint Booth Toxicity panel, please provide an "Intrinsically Safe" panel, not an "explosion proof" panel.
56	PL111			PL111: There is a dashed line shown crossing through Elect room 127 from LO Shop Room 151 ESEW-01. Is this a vent pipe?	This is a graphics issue. The dashed line is a buried sanitary line, refer to PF111.
57	P-504			B3/P-504 shows a natural gas meter w/ AMI capability that is added in addition to the utility company gas meter. Could this additional gas meter be a small pulse type meter in lieu of unit shown?	Pulse meter is acceptable. Gas sub-meter must have AMI capability.

58	MH141			MH141: Should there be a Keynote 4? The number is shown, but no note is given.	This is a graphics issue. Keynote 4 is not applicable.
59	MH142			MH142: section A4 /M-302 is given, but that detail seems like it's in the wrong location. Please revise.	Section is intended for below roof ductwork. Because section crop is set above roof level, section tag appears on MH142.
60	MP125			MP125: It appears 2 heat pump units are added at Secure 208, please label.	Tag is missing from MP125. Refer to MH125 for labels and M-609 for schedules.
61	MP129			MP129: 4 pipe are shown south of DOAS-01, should this pipe be removed? This pipe is drawn between CL VV and WW, from CL 9 to about 15.5.	No, these pipes penetrate the roof and serve DOAS-06. Refer to MP130.
62	MP131			MP131: HRS units are missing labeling and RS/RL lines need to be moved and drawn at new units. Please revise this plan.	HRS-126-01 and HRS-126-02 require refrigerant lines routed to associated indoor CRAC units. Piping will be revised in forthcoming amendment.
63	MP131			MP131: There are 6 HP units that show the RS/RL pipe coming from the unit, should be pipe turn down to below roof where it is shown ending South of CL X?	Refrigerant piping for heat pumps serving the secure area (HP-208-## and HP-213-##) enter the building and turn up. Heat pumps serving the first floor (HP-127-##) turn down and enter the building through the roof without penetrating the secure boundary.
64	MI871, MI872			Detail C1 on MI871 notes "24VAC By Div 25". This should be "by div 23 09 00 BAS Contractor". There are also a few other details on this sheet w/ same language. See also MI872 Please revise.	Agreed. The intent is to have the Controls Contractor (part of Div 23 scope) provide 24Vac power distribution to terminal units as required. Note that the reference to Div 25 is a typo.
65	11 11 11			The Fume Exhaust Extraction Systems per 11 11 11 do not appear on the mechanical plans. This is in regard to CEQ-11 Open-Face Paint Booth w/ Integral Worktable and CF/CI-09 Downdraft table. Will anything be required for mechanical besides 18" dia duct going down to booth shown on MH121. Could you please provide a section detail to show how this ties into the booth? Will Controls/BAS integration be required?	The downdraft booth is provided as CFCI equipment and requires an 18" exhaust duct connection. Coordinate duct connection with downdraft booth. Controls integration is required so that CAVR-P014 provides make-up air during downdraft operation.
66	11 61 43			Decontamination Showers (Air Showers) are not shown on Mechanical plans. Should these be shown for coordination? are these located in blowdown areas in Area A,	The decontamination showers are self-contained and only require power. These do not need to be shown on the mechanical plans and do not

				Paint Booth? Will controls/BAS integration be required?	require integration with the building control system.
67		41 34 23		There is a sources sought on Sam.gov for the P-993 and P-995 Paint Booths (N4008526R0002). It is requesting qualifications of potential suppliers who believe they meet the requirements for this project. The notification lists Global Finishing Systems as the Basis of Design. Will the Gov't please confirm if any other suppliers were found acceptable/having met the requirements of the inquiry? If the results can not be provided, should the P993 bidders assume the only acceptable manufacturer for 41 34 23 is the basis of design, Global Finishing Systems?	Other manufacturers that meet requirements will be accepted. Disregard Sources Sought.
68	I-606			Please confirm CLIN 16 includes all the collateral equipment shown on the CEQ (COLLATERAL EQUIPMENT) - BID OPTION - PAINT BOOTH 3 & 4 including the paint booths, pneumatic paint shaker and open-faced paint booth with integral worktable.	CLIN 0016 includes equipment. See CLIN 0005E for Paint Booth
69	I-606			Please confirm if the aircraft work stands, labeled as collateral equipment on I-606, are included as part of CLIN 15.	Confirmed CLIN 0015 should read "Collateral Equipment (Sheet I-606 for aircraft work stands"
70	I-606			Optional paint booths 3 and 4 are listed on the bid form in CLIN 5E or CLIN 16. Please confirm CLIN 5E should be deleted, and Paint Booths 3 and 4 should only be priced in CLIN 16.	No, Paint booths are to be included in CLIN 0005E. CLIN 16 is for other collateral equipment inside the booths only. The Government Estimated cost is incorrect and should be \$26,770.00.
71	I-606			Paint booths 1 and 2 are considered collateral equipment on I-606 and have a different funding source than base bid construction work. As such, please confirm if CLIN 1F should be modified to a Gov't Estimate with a Contractor HAR, identical to CLIN 0015.	No. Paint Spray Booths are industrial equipment, and require coordination with other trades during construction, and therefore require more Contractor coordination than typical collateral equipment.
72		01 57 19.01 20	1.1.1.1.4	Spec 01 57 19.01 20 - 1.1.1.1.4 Contaminated Soils says, "All excavated soil may be re-utilized as backfill at the same location from which it was removed unless petroleum contamination is discovered. If petroleum contamination is discovered, the soil shall be segregated by PID (>= 10 ppm or exhibits staining), properly	Confirmed

				stockpiled, tested, and disposed. If soil is stockpiled, it shall be stockpiled on plastic, bermed, and covered in accordance with NC DENR Groundwater Section Guidelines for the Investigation and Remediation of Soil and Groundwater, Vol. 1 dated July 2000 (Guidelines), or placed in a rolloff container and covered with plastic. Any excess soil that cannot be re-utilized as backfill at the same location from which it was removed shall be disposed at a Subtitle D landfill (e.g.; Tuscarora) as a minimum with the understanding that the analytical testing results shall determine the final disposal facility. Contactor shall provide supporting laboratory analysis to the EAD for review. The EAD shall review and sign the waste manifests/bill of lading for the soil disposal prior to any of this soil leaving the Air Station. The manifest shall also contain the amount of soil (weight) and supporting laboratory results for EAD to review. One composite sample shall be taken and analyzed for each 200 cubic yards of the stockpile per DENR Guidelines in order to determine the proper method for disposal." Please confirm that the unit price CLIN 0003, OPTION 1 is for any excess soil that cannot be re-utilized as backfill at the same location from which it was removed shall be disposed at a Subtitle D landfill. Any material that tests higher and is considered hazardous would then need to go to a Subtitle C landfill and would be a change in conditions.	
73		12 00 01.00 20	1.3	12 00 01.00 20 - 1.3 notes that the FF&E package may also include the Specialty CEQ Package. 3.1.1 requires the contactor to hire an Interior Design and Equipment Specialist to validate the Concept (Schematic) Package requirements of the FF&E. This would include developing the Final FF&E and potential Specialty CEQ Package required for the project, validation, and BVD for selection of vendors. The Price Proposal has several FF&E and Collateral Equipment option CLINs, may of	Interior Designer / Equipment designer is not required for 0017 Stacker Storage Units and 0018 Sun Shelters,

				which are already designed and don't appear to need a Interior Designer or Equipment Specialist to valid only may need a BVD for the selection of the vendor, such as the Paint Booths, Sun Shelters, and Vertical Stakers to name a few. Please confirm which CLIN's for FF&E and Collateral Equipment are required to follow the full specification of 12 00 01.00 20	
74		01 45 00	1.6.5	01 45 00-1.6.5 identifies that all QC Specialists must have no duties other than their assigned QC duties, these individuals or specialized technical companies must be directly employed by the prime contractor and cannot be employed by a supplier or subcontractor. Please confirm these must be employees of the Prime except for the such as TAB, Roofing Manufacturer, Fire Protection QC, and Building Envelope as these would be specialized technical companies that are subcontractors to the prime contractor.	Confirmed. Specialists noted can be employed by specialized technical companies.
75		04 45 00	1.6.5	01 45 00-1.65 identifies the QC Specialist in the Experience Matrix, however the 2-1 Qualification and 2-2 Experience requirements are a little confusing. For instance, for Civil it notes: 2-1 Graduate Civil Engineer or Construction Manager with a Professional Engineer Registration and 2-1 2 years' experience in the type of work being performed on this project OR technician with 5 years related experience. Please confirm this means the Civil must have a graduate civil engineer or construction manager with a professional engineer registration and 2 years' experience OR Technician (no graduate degrees or professional engineer requirement) and 5 years experience. This is applicable to the other QC Specialists listed in the matrix.	Confirmed.
76	P-112			P-112, Plan Note 6 says "provide 1/2" DCW & 1/2" DHW ball valves for connection to eyewash in paint booth by others". It is noted in 1.4.p of 41 34 23 to provide "emergency showers and eyewash stations as code required, min two (2)". Please show this on the P-112 since this will be the	The booth manufacturer will provide the eyewashes inside the booth. The plumbing contractor is only responsible for providing the DCW & DHW to the booth.

				responsibility of the plumbing contractor.	
77	P-107			P-107 appears to show a Contaminated Waste Pit where moveable totes are stored that collect CW from the Duplex Sump Pump System. No detail is referenced for this tote pit, and no details are provided in plumbing and civil utility plans. Is this pit to be fiberglass similar to sump pump basin? Please provide details.	This information is shown on Detail A4 on sheet P-503.
78	M-315			Reference drawing M-315 and Price Schedule. Please verify that all ductwork shown on mechanical plans dedicated for the Paint booth and (2) Sanding Booths is to be a part of CLIN011 Option 09 booth equipment pricing. Please note that specification 41 34 23-2.6 states the ductwork shall be designed and furnished by the Paint Booth Contractor and installed by the division 23 mechanical contractor.	Ductwork size and routing shown on plans associated with delegated design equipment is for coordination purposes only. DOR confirms it is to be part of booth equipment pricing.
79	P-118			P-118: Plan note 6 shows a Nitrogen Tank located outside by Nitrogen Supplier that is not sized, nor detail is given. Please verify this tank is GFGI.	The nitrogen tank size is listed in the Basis of Design as a suggestion based on assumed amount of use and preferred fill times. The tank is GFGI and will be supplied by a local gas supplier.
80	P-119			P-119: there is a "Paint & Sand Booth Notes" section giving noting Booth Manufacturer responsibilities. It notes "Vacuum Systems" are to be included, but the only piping system that is shown running to the unit is the CA and BA. Please verify Vacuum systems are not required in booths.	Vacuum piping will be required in the booths, but they will be provided by the booth manufacturer. The vacuum system will sit on top of the paint booth and be separate from the building vacuum systems.
81	41 34 23	1.4.p		Please verify two (2) combo emergency shower/eye wash stations are to be provided per booth for a total of 6. See 41 34 23-1.4.p and P-502.	Confirmed, provide as code required, w/ minimum (2) combination eyewash/emergency shower units per booth.
82				Please provide a copy of the appropriate Division 1 specifications for P995.	Division 1 Specifications for P993 and P995 are combined in the P993 Specification.
83				Please provide a copy of the latest 3D Model files	3D Model files will be provided to the successful Proposers after award.
84	P-601,P-404, EP105			P-601 and P-404 note the faucets, and flush valves are hardwired and require transformers. EP105 doesn't reflect hardwired toilet, urinals and lavs. Are we to assume low voltage wiring is to be provided for these fixtures from the	EP105 has a note that confirms the use of hardwired fixtures. Low voltage wiring shall be provided from the fixture to the junction box as listed in the note.

				nearest j-boxes provided or should additional j-boxes be required?	
85	M-001			M-001 notes all exposed ductwork must be insulated with Rigid Duct Board. M-502 notes all exposed flat oval/spiral duct must be double wall insulated. Please verify this is what is desired.	Provide double wall insulated for all exposed ductwork.
86	MH102			MH102: Note 7 is provided for the sand booth and notes "Provide Equipment and all associated accessories, ductwork, controls as part of a delegated design. See specialty equipment sheets for more information. Ensure Installation is coordinated with all other equipment and systems in adjacent areas". Can you please add note that this delegated design is per Paint Booth Contractor per 41 34 23. It also needs to clarify what CLIN/Option this scope is applied to.	Propose per plans and specs.
87	MH104			Plan Note 7 on MH104 states "see specialty equipment sheets". Please provide these "specialty equipment sheets" referenced.	Note is intended to reference sheets MH110-MH111.
88	MH401			MH401: Plan Note 3 notes to provide ductwork for air compressor instake to exterior wall louver, louver to match size of duct plenum. This ductwork to a louver does not appear to be drawn tying into louver. The only ductwork shown tied to louver (L-1) is OA duct from DOAS-1 in that area. Please provide ductwork layout and louver noted.	AC unit exhaust is tied to L-6 & L-7. Refer to sheet M-907 and M-601. [CCE]
89	MP105, MP102, MP107			Gas pipe is shown running to sand booth MAU shown on MP107. This MAU (BMAU-3) is on the roof. Gas pipe is not shown running to Paint/Spray booth MAU's on MP105 and MP102. There is a gas riser showing pipe to the other PBC MAU's shown on M-910. Please revise floor plan drawings to show gas running to the gas fired MAU's BMAU-1&2.	Final gas routing/sizing is dependent on requirements of delegated design. Use M-910 for bidding purposes.
90	MP105			Please show gas piping on MP105. MP401 shows the gas pipe in the mechanical room the route for the other gas line in the remainder of the building is not shown.	Final gas routing/sizing is dependent on requirements of delegated design. Use M-910 for bidding purposes.
91	25 05 11.02 20			25 05 11.02 20 Risk Management Framework for HVAC/DDC Facility-Related Control System was removed for P993, but this spec is listed for	Concur with removing this RMF specification which is actually 25 08 11.02 20

				P995. Please remove RMF 25 05 11.02 20.	
92	33 40 00	2.3.5		33 40 00 - 2.3.5 says Provide flexible, watertight connectors conforming to ASTM C923/C923M for connecting pipe to manholes and inlets. Suppliers cannot manufacture precast boxes that require a booted connection. Please remove this resilient connector requirement.	There are products available which will meet the criteria set forth in the specification. The flexible, watertight connector conforming to ASTM C923 requirement remains in the specification. Bid as specified.
93	33 40 00	2.4.1		33 40 00 - 2.4.1 says Perform a hydrostatic test on the watertight joint types. RCP suppliers cannot test concrete pipe by hydrostatic testing. Please remove this testing requirement.	The specified test is performed at the plant or independent laboratory. Suppliers of the watertight connectors should be able to supply KTRs with results of their tests which conform to ASTM standards for watertight joints. The requirement remains in the specification. Bid as specified.
94	M-314			EA and RA ductwork is sized for the dust collector, exhaust fan and MAU, see M-313, M-314, & M-315. Please verify this ductwork is oval/spiral and to be double wall insulated.	Ductwork size and routing shown on plans is for coordination purposes only. Exact duct requirements such as size, construction and routing must be coordinated with equipment manufacturer selected and final equipment selections.
95	M-711			M-711 notes a new gas meter to be located in mechanical room. There is the utility company gas meter (NIC) that is provided outside the mechanical room, is this gas meter described on M-711 to be a pulse meter provided by the BAS Contractor?	Correct, additional gas meter is to be provided to ensure communication/monitoring is available through the BAS.
96	M-601			M-601: Duct-Mounted Motorized Dampers MD-8&9. Please indicate where these Motorized Dampers are located.	Propose per plans and specs.
97	26 29 23	1.8.1		26 29 23-1.8.1 Spare Parts noted to provide one spare ASD of each model provided for HVAC equipment. This is not typical to provide a spare ASD/VFD. Please verify spares are required.	Delete paragraph 1.8.1 in Section 26 29 23.
98	01 45 00			Please provide Schedule of Fire Protection System Inspections per 01 45 00.	Provided in Specification section 01 45 00 of the Spec for P-993, which is for both P-993 and P-995 projects.
99	25 05 11			Three (3) Div 25 Cybersecurity specifications are given for FA/MNS, HVAC/DDC and Lighting Controls. If cybersecurity is required for Div 41 &	Confirmed- no cybersecurity specifications associated with Division 41 and 42 items.

				42 equipment, please provide Division 25 specifications for those systems.	
100	22 00 00			Can you please provide Nitrogen Pipe requirements in division 22 00 00 specifications?	Nitrogen piping material is listed on the Detail B1 on Sheet P-505.
101	A-111			Drawing A-111 RCP calls out note #2 for all rooms. There is only note #1 "open to structure above". Please confirm the #2 tag for all rooms should be #1 "open to structure above". Also, please confirm all of these ceilings are to be painted.	Correct: #2 tags ON SHEET A-111 are intended to be #1 "OPEN TO STRUCTURE ABOVE". Confirmed, all elements of exposed overhead structure are to be painted in accordance with 09 90 00 PAINTS AND COATINGS, paragraph 3.13.2.3 B. Interior overhead steel structural members and galvanized metal decking coatings are modified alkyd paint with 36% to 49% solids by volume, 3.30 to 3.34 pounds VOC per gallon and flat finish. Coatings settle as a dry powder in approximately ten feet depending on temperature, humidity and air movement. Do not thin. Clean with xylene. Furnish compatible primers.
102	A-112			Drawing A-111 RCP calls out note #2 at COMM 144. However, the hatching appears to be calling for gypsum ceilings. Please confirm whether COMM 144 is to receive gyp ceilings or OTS painted ceilings.	Patterning indicating gypsum board ceilings is in error-confirmed the intention is as indicated per keyed note #2, OPEN TO STRUCTURE ABOVE.
103	A-116			Please confirm if the underside of the (2) canopies and associated structural steel components are to be painted in the field per 09 90 00.	Confirmed. Bid per specification paint tables in 09 90 00.
104	Price Schedule and M-701			CLIN0022 Option 20 for P995 is for the Composite Oven Complete per Gov't Estimated Price of \$1,034,463. This is for the composite ovens and autoclaves. It is noted on M-701, that the Controls Contractor must coordinate with Owner and Specialty Equipment Manufacturer to provide Controller Building Integration where applicable for these units. Can you please provide the manufacturers BAS requirements so the Controls Contractor can include proper integration?	This is dependent on the equipment manufacturer and available control options. The awarded contractor must coordinate with the manufacturer and the Government to verify that available control options meet the desired control requirements.
105	MH110			Will the Composite Oven and Autoclave manufacturer provide and install the piping systems needed between Cooling Towers, Cooling	Awarded contractor must be responsible for coordinating exact responsibilities and scope demarcations between

				System Pumps and ovens shown on MH110? How about Controls/BAS work required?	various subcontractors, equipment suppliers and delegate designs. This will be very specific to the <u>manufacturers selected</u> .
106	10 51 00			Can Columbia Lockers be listed as an approved option in the Solid Plastic Locker Specs?	Government specifications are performance based and may not include specific manufacturers and/or models of specified items. Bid as specified.
107	C1/A-505			Roof edge detail for lower curved roof says to to see structural drawings for sizes and detailing. This does not appear to be included in the structural plans other than note saying "radiused light gage stud framing at soffit". Please provide sizes of CFMF members required. Please confirm gypsum sheathing and insulation are not required at these soffit locations.	(KDE P995) Cold formed metal framing is a delegated design per the Deferred Submittal list on Sheet S-002. Framing to match architectural drawings but the gage to be designed by the CFMF engineer.
108	S-202 and S-504			Drawing S-202 calls for "CB12" at column line 6. However, CB12 is not included within the Concrete Beam Schedule on Drawing S-504. Please provide clarification in regard to the design intent for the concrete beam shown at column line 6 on Drawing S-202.	There is a typo on Drawing S-202. Please replace "CB12" with "CB2" on column line 6 on Drawing S-202.
109	C3/A-505			Roof edge detail for upper curved roof says to to see structural drawings for sizes and detailing. This does not appear to be included in the structural plans other than note saying "radiused light gage stud framing at soffit". Please provide sizes of CFMF members required. Please confirm gypsum sheathing and insulation are not required at these soffit locations.	Cold formed metal framing is a delegated design per the Deferred Submittal list on Sheet S-002. Framing to match architectural drawings but the gage to be designed by the CFMF engineer.
110	D4/C-501			Key Note 4 on CS101 calls out Heavy Duty Concrete Pavement, D4/C-501. That detail D4/C-501 shows Full Depth Heavy Asphalt Pavement. Please confirm that Key Note 4 should reference detail D1/C-501.	Confirmed; Revise keynote #4 on drawing sheet C-501 to reference detail D1/C-501.
111	CG102			Sheet CG102 – Spot elevations on the sidewalk running parallel to the parking lot has an elevation 25.51' and 25.52 feet sandwiched between 27.61' and 27.12'. It appears that the 25' elevations are incorrect. Please confirm.	Confirmed; on drawing sheet CG102, disregard spot elevations 27.61' and 27.12'.
112	CG102			Sheet CG102 – Spot elevation on MH-07 is 20.20' and the rim elevation	On drawing sheet CG102, disregard spot elevation 20.20' referencing MH-07; the

				shown on Sheet CG-100 is 28.30'. Please confirm which is correct.	correct rim elevation is 28.30' as indicated on drawing sheet CG100.
113	06 61 16 & 22 00 00			Spec 22 00 00 Plumbing spec notes precast terrazzo shower floors under 2.4.10. Spec 06 61 16-2.3.6 seems to know solid surface pans to match enclosures. See also Detail A5 on A-404 which shows a solid surface shower pan. Please verify the shower pans will be solid surface.	Confirmed, shower pans are solid surface as detailed A5/A-404. Spec 22 00 00 revised
114	I-606			P-995 has CLIN's 22 and 23 for the Composite Oven's and Collateral Equipment. The drawings clarify the Large Autoclave is Not in Contract (by others). However, the drawings still have many other equipment items, such as: Paint, Sanding, and Blast Booths, Medium & Small Autoclaves, X-Ray Equipment, etc. Please clarify if additional CLIN's will be added for each of these major pieces of equipment being funded outside base bid construction work (i.e. a Gov't Allowance with a Contractor HAR for the autoclaves, x-ray, etc.).	For clarification, Collateral Equipment for P995 is listed on sheet I-603. Please see CLIN 0011 Option 9 for Paint Spray Booth and Sanding Booth, CLIN 0012 Option 10 for Med/Small Autoclaves and CLIN 0013 Option 11 for the X-Ray Booth.
115	B-201			B-201 shows the Settlement Monitoring plan with plate locations and proposed contours. Note 4 calls for a waiting period of 90 days after the completion of fill placement. Is the intent to place the fill to the building FFE of 29.75' and monitor it for settlement for 90 days? Please confirm that there is no additional surcharge required.	PENDING RESPONSE
116	CU101			Sheet CU101 – Key Notes 2 (Connect to P-993 Water Stub with 6" DIP and a 6" to 4" DIP Reducer), if you then follow the unlabeled line towards the building it shows Key Notes 15, (6" to 2.5" Reducer). With the two conflicting reducers the water line diameter is not actually labeled on this sheet. On the profile sheet CU202 the waterline is shown as a 2.5" Waterline the full length with no reducers. Please advise.	On drawing sheet CU101, revise Keynote #2 to read "Remove existing 2" blowoff, 2" gate valve, and MJ plug and connect to P-993 water stub with 6" x 2 1/2" MJ reducer." Disregard keynote 15.
117	CU101			Sheet CU101 – Key Note 6 calls out an FDC, C1/C-511. Please indicate the size and material type the fire line is coming from the building to the FDC. The detail C1/C-511 shows a 6" galvanized steel stand pipe and a wafer check valve w/ ball drip inside of a precast concrete vault w/ cast iron	On drawing sheet CU101, revise Keynote #6 to read "6" DIP to remote FDC, C1/C-511". Regarding detail C1/C-511, the check valve and vault shown may be removed as we

				frame & cover. The check valve vault is not shown on the plan view (CU101). However, key note 6 on CU102 calls for a water meter and backflow preventer assembly (inside mechanical room) See plumbing drawings. Please confirm that the check valve is required on the fire department connection line, if so indicate where it is to be located on the plans.	have confirmed with Fire Protection that a check valve is located inside the building on the remote FDC line. Revise location of remote FDC to be directly across the driveway to match Fire Protection Drawings.
118	A-307			Knockout Wall Notes says "AT A MINIMUM FOR BIDDING PURPOSES, MINIMUM 8" COLD FORMED STUD FRAMING DESIGNED TO WITHSTAND WIND LOADING, 1/2" EXTERIOR GYPSUM BOARD SHEATHING". However, A5/A-307 calls for 6" cold-formed studs. Please confirm what is required.	Confirmed provide 8" studs as indicated in note #3 of KNOCKOUT WALL NOTES sheet A-307. References to 6" stud walls in detail A5/A-307 are incorrect.
119	C1/A-307			Please provide design clarity for the knockout panel in wall for Autoclave Delivery	PPI question is unclear. Clarified with PPI #118 response above, bid as shown and described.
120	A-601			Drawing A-601 detail A1 shows an elevation for a Type G door. This door type is not found in the door schedule. Please confirm that the type G door is not required for any door opening.	Confirmed.
121	A3/A-304			A3/A-304 calls for furring wall type K but wall details on A-503 wall type K does not call for furring. Please confirm that for the gypsum furring wall that we should reference wall type L for wall section A3/A-304.	Type K is incorrect, however for this location the correct furring wall type is Type H.
122	A-407			The Walk in Cooler on A-407 currently shows no waterproofing at the depressed freezer slab. Please confirm that no waterproofing is required at the walk-in cooler.	Membrane waterproofing is required at the walk-in freezer. See revised detailing on sheet A-407.
123	A-116			Keyed construction note 5 on A-116 is not found on the roof plan. Please call out all locations where note 5 is applicable.	Keyed Construction Note #5 is intended to apply to a single downspout located at the NW corner of the curved upper roof above the administrative area, which leads from that gutter to the lower membrane roof area below. DS is depicted in section A3/A-303 also. See revised sheet A-116 for keynote added to plan.
124	A-116			The roof plan on A-116 does not show any walk pads on the membrane roof	See revised roof plan sheet A-116 for walk pads added to

				in between the roof top equipment. Please clarify if walk pads will be required and quantify their location and quantity.	plan and added description in keynote #6.
125	45 52 00			Please confirm if a physics design report has been completed for this project, if so, please provide a copy of the report.	No physics design report has been completed.
126	45 52 00	3.4	Item 3	Please confirm that the vault door opening is to be 6' in height.	Door size has been amended. See amendment language.
127	45 52 00			Please confirm how all penetrations will enter the vault (foundation, walls, or ceiling), including any customer required locations & sizes.	Wall penetrations through the vault can be through the wall or ceiling at the supplier's discretion in the least visible location while not impeding egress.
128	45 52 00			Please confirm if there are any special voltage or amperage requirements for equipment other than the KV machine & crane inside the vault or operator room.	No special electrical requirements for other equipment.
129	45 52 00			Please confirm the total degree of rotation required for the KV tube.	The kv tube does not rotate, nor does the detector. They are mounted to a gantry system. The specification will be revised to add additional data.
130	45 52 00			Please provide the complete required specifications for the modular components of the vault.	Specs cover the requirements for the modular component of the vault CR1020.40 and NAVSEA SO420-AA-RAD-010
131	A3/A-301			Please confirm if typical note "3-5/8" STEEL STUDS @16" O.C. W/ 1/2" GYPSUM SHEATHING BOARD AT EXTERIOR SIDE FROM TOP OF CMU WALL TO TOP OF BEAM: SEAL W/ SPRAY FOAM INSULATION AT JUNCTURE TO DECK". Please confirm that this is required at A3/A-301 above CMU wall.	Confirmed. Upper wall condition in section A3/A-301 is the same as depicted in enlarged detail section C3/A-302.
132	A3/A-302			A3/A-302 appears to be missing typical note "3-5/8" STEEL STUDS @16" O.C. W/ 1/2" GYPSUM SHEATHING BOARD AT EXTERIOR SIDE FROM TOP OF CMU WALL TO TOP OF BEAM: SEAL W/ SPRAY FOAM INSULATION AT JUNCTURE TO DECK". Please confirm that this is required at A3/A-302 above CMU wall.	Confirmed; note applies to same area.
133	P-993	CT126	2	sheet keynote 2. on CT126 states to, "Provide and install 70' x 70' aircraft	Confirmed. The sunshades to be included in CLIN 0018.

				sunshade...", please confirm the sunshades are an option, and pricing for the work is included in "CLIN 0018 Option 16 for P993: subtotal for Sun Shelters Complete....".	
134	P-993	ES503		will the electrical rough-ins and equipment be required for the F-36 sunshade canopies in the base bid? or is the electrical work as shown on drawing ES503 to be included in CLIN 0018 OPTION 16 for P993 subtotal for sun shelters...	See ES405. Base bid to include power for everything in cells 1 through 7, 13 and 14. Rough in only in base bid for cells 8 thru 12. Rough in work for base bid includes installation of all conduits with pull strings in and under concrete.
135	P-993	CS117		Drawing CS-117 shows a potential laydown site on the future P-1055 Building site. when does the Government anticipating awarding a contract for P-1055 and construction starting? similarly, when does the Government anticipate awarding and exucting the building work for the skuff and refresh building. This is to help identify and plan for laydown areas and material staging and storage.	Construction dates for P-1055 have not been determined. Scuff and Refresh contract has been awarded and construction is underway.
136	P-995	T-001		see ERCES (BDA) NOTE. The note states that contractors are to provide a sperate line item in our bid for the complete installation and testing of an ERCES (BDA) system. The provided bid sheet does not include a sperate line-item for this scope. Please provide a separate line-item for pricing or confirm this work is not required.	Disregard ERCES (BDA) NOTE. ERCES system is NOT IN CONTRACT.
137	P-995	T-114		Please confirm that contractors are not required to furnish and install devices for the digital tracking system and that this is a GFGI item. Contractors are only required to furnish and install conduit, cables, junction boxes and other raceway items required for others to install the devices.	Confirmed.
138	P-993			Due to the footprint of the project, can the contractors laydown and/or trailer site be located outside of the limits of disturbance? Any disturbed area will be returned to existing condition after demobilization.	Yes, contractor laydown area can be outside of the area of disturbance as approved by the Contracting Officer in consultation with Facilities Asset Management Department and FEAD Cherry Point. As mentioned, any disturbed areas will be returned to existing conditions after demobilization.
139	P-993	Bridge		According to the bridge plans the pile lengths are anticipated to be between	PENDING RESPONSE

				70 and 85 in VLF. Which would generate a tip elevation of between -50 and -65 feet. The specifications note a minimum tip elevation of -2 for EB 1; -18 for BT2/3; and -9 for EB 4. Installing piles to the minimum tip elevation would be approximately 2,000 VLF less than using 70–85-foot piles. Please confirm if bidders should assume meeting the minimum tip elevation or to anticipate using the longer piles as shown in the drawings. We believe a quick resolution would be to provide the anticipated tip elevations based on the design loading on the bridge drawings.	
140	P-993	Bridge		Per the pile specifications 31 62 13.20 paragraph 3.2.7 splicing of the piles will not be permitted. The project is requesting the installation of 70-85 VLF piles, with test piles being an additional 10 feet. Pile Manufacturers are indicating that maximum pile length is 55 VLF. Please review specifications to allow for splicing.	Revise 31 62 13.20 3.2.7 to the following: "Splicing of piles is only permitted for pile lengths over 55 feet. Splices must be capable of developing the full strength of the member in compression, tension, shear, and bending. Submit detail drawings of splices and design calculations demonstrating the strength of the splice for approval. Submit information for shop and field pile splices prior to fabrication."
141	Bid Sheet			CLIN0001G and CLIN0002D are both to remove buried concrete debris. CLIN0001G is using Tons as the unit and CLIN0002D is using C.Y. Please revise CLIN0002D to tons to match CLIN 0001G.	Updated. See revised Price Proposal F provided with Amendment 0002.
142	Specification	01 58 00	1.4	Is a project Identification job board required for both P-993 and P-995 job site or is only one sign board required for the Task Order?	Provide one sign for each project, hence two signs.
143	P995	45 52 00	-	Section 45 52 00 requires delegated design of the aerospace X-ray testing equipment, including compliance with NAVSEA S0420-AA-RAD-010 and incorporation of shielding, safety interlocks, and associated radiological controls. Please confirm whether a project-specific radiation shielding analysis / physics design report has been completed by the Government or Owner to establish design criteria (e.g., shielding requirements, dose limits, controlled area boundaries, occupancy classifications, etc.).	The document is not available for public release. The Government will release the appropriate sections once the vendor for the X-ray equipment has been selected. Additional criteria will be added by amendment.

				If such documentation exists, please provide it for use in delegated design and pricing. If not, please confirm that development of the radiation shielding analysis and associated design criteria is to be included as part of the Contractor's delegated design scope.	
144	P995, 4	45 52 00	3.4 XTE-1 Item 3	Section 45 52 20 ¶3.4, Item 3: The schedule indicates a "6'-0" high by 8'-0" wide biparting motorized slider". Please confirm: (a) Please confirm that the 6'-0" height is correct. Clarification is required to ensure constructability, equipment compatibility, and accurate pricing.	See response to PPI #15.
145	P995	45 52 00	-	Section 45 52 00 requires a shielded modular X-ray vault; however, the documents do not clearly define requirements for penetrations into the enclosure. Please confirm how all required penetrations are to be routed into the vault (e.g., through foundation, walls, or ceiling), including any Owner-directed locations, sizes, and quantities for electrical, mechanical, controls, and other utilities. If specific penetration requirements or constraints exist, please provide them for coordination with the delegated design.	Penetration into the enclosure shall be manufacturer's standard through the walls or ceiling in an inconspicuous location so as to not impede egress and to be in as least visible location as possible.
146	P995	45 52 00	-	Section 45 52 00 identifies primary power requirements for the vault and X-ray equipment; however, it is unclear if additional systems require supplemental power beyond those noted. Please confirm whether any additional equipment, systems, or accessories (within the vault or control room) have specific voltage, phase, or amperage requirements not currently identified in the contract documents. If so, please provide the required electrical characteristics for	No additional equipment systems or accessories have any additional power requirements within the vault or control room. If the system requires a transformer, it shall be provided.

				incorporation into the delegated design and pricing.	
147	P995	45 52 00	-	The Aerospace X-Ray Testing Equipment Schedule identifies a gantry-mounted X-ray source and detector manipulator; however, the required range of motion is not defined. Please confirm the required total degree of rotation and motion parameters for the X-ray tube and associated manipulator (e.g., rotational limits, axes of movement, and positioning requirements). This information is required to properly define system configuration and delegated design.	PENDING RESPONSE
148	P995	45 52 00	-	Section 45 52 00 indicates that the X-ray vault is constructed of shielded modular panels; however, detailed performance and construction requirements are not fully defined. Please provide complete specifications for the modular vault system, including but not limited to: Required shielding performance criteria (e.g., lead equivalency or dose limits) -Panel construction and materials -Structural requirements and support conditions -Jointing and sealing requirements -Radiation compliance criteria and applicable standards If these requirements are to be determined by the Contractor as part of delegated design, please confirm.	PENDING RESPONSE
149	P995	41 34 23	-	Specification Section 41 34 23 requires that: -All components within the paint booth be rated for Class I, Division 1, and -All components within three (3) feet outside the paint booth be rated for Class I, Division 2 Additionally, Paragraph 1.5 requires the system to be designed and installed in accordance with NFPA 33, NFPA 91, and applicable OSHA and ANSI standards.	The specification will be revised regarding onsite training by amendment.

				Based on review of the drawings, the currently indicated blowoff chamber locations appear to fall within or adjacent to these classified hazardous areas. Blowoff chamber operations (compressed air cleaning, particulate removal) may: -Introduce or disperse flammable vapors and/or combustible particulates -Require compliance with hazardous location equipment classifications -Impact the extent of classified areas beyond the defined 3-foot boundary -Require dedicated ventilation, separation, and fire protection per NFPA requirements As currently depicted, it is unclear how the blowoff chamber configuration achieves compliance with the specified hazardous area classifications and applicable NFPA standards. Please clarify the following: 1. Confirm the intended hazardous area classification for the blowoff chambers and associated equipment 2. Clarify whether the blowoff chambers are intended to be: a. Part of the spray area, or b. A separate operation with independent ventilation and separation 3. Provide the basis of design demonstrating compliance with: a. NFPA 33 b. NFPA 91 c. NFPA 652 (if applicable) 4. Confirm whether the indicated layout is intended to remain as shown or will be revised to meet hazardous area and NFPA compliance requirements	
150	P995, 8	41 34 23	1.7.3 g. & h.	Specification Section 41 34 23 indicates that during Sanding Mode and Wash Mode: -All fans and make-up air units shall not operate (0 FPM airflow) -Protective curtains shall cover all filter sections Sanding and washdown operations inherently generate airborne	The specification will be revised regarding onsite training by amendment.

				particulates, aerosols, and/or contaminants. As currently specified, these modes would result in no active ventilation or filtration during contaminant-generating activities. Additionally, covering all filter sections appears to eliminate the primary airflow and contaminant capture pathway within the booth. These requirements appear to be in potential conflict with ventilation and safety provisions of: -NFPA 33 -NFPA 91 -Applicable OSHA and industrial hygiene practices Please clarify the following: 1. Confirm whether Sanding Mode and Wash Mode are intended to operate without ventilation (0 FPM) 2. Clarify the intended method of contaminant control during these modes 3. Confirm whether protective curtains are intended to: a. Fully isolate filters, or b. Be used in conjunction with an alternate airflow path 4. Provide the basis of design demonstrating compliance with applicable NFPA and OSHA ventilation requirements for these operating modes 5. Confirm whether localized exhaust, temporary ventilation, or alternate systems are required during sanding and wash operations 6. If strict compliance with the specified operating modes (0 FPM with filters fully isolated) does not meet applicable NFPA, OSHA, or industry ventilation requirements, please confirm whether: a. The design is to be revised to achieve compliance, or b. The Contractor is to proceed as specified, with the understanding that any resulting deviations from governing codes, standards, or best practices are the responsibility of the Government/End User	
--	--	--	--	---	--

151	Solicitation Page 13 of 50			The RFP for the P-993 F-35 Sustainment Center requires all contractors performing work on the project to hold CMMC Level 2 (Self). Currently, the vast majority of local and regional subcontractors, equipment suppliers, vendors and service providers – particularly those that qualify as SB - do not possess this certification, and estimates indicate it will take most companies 6–18 months to obtain it, with costs ranging from tens of thousands to hundreds of thousands of dollars per vendor. This requirement is especially burdensome on the local small-business community, many of whom do not have the resources necessary to pursue certification. As a result, the mandate is severely hindering the project's ability to meet the Government's 40% small-business participation target. Can the Government reduce the small-business participation target for this Opportunity from 40% to 20%?	PENDING RESPONSE
-----	----------------------------------	--	--	---	-------------------------

(End Summary of Changes)