

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J	PAGE 1 OF 3 PAGES
2. AMENDMENT/MODIFICATION NUMBER 0001	3. EFFECTIVE DATE 18 MAR 2026	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER (If applicable) PAN 026130		
6. ISSUED BY W07V ENDIST VICKSBURG KO CONTRACTING DIVISION, 4155 CLAY STREET VICKSBURG, MS 39183-3435 UNITED STATES AMY STARKS, EMAIL: AMY.L.STARKS@USACE.ARMY.MIL TELEPHONE: 601-631-5693	CODE W912EE	7. ADMINISTERED BY (If other than Item 6) SCD: PAS:			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)		(X)	9A. AMENDMENT OF SOLICITATION NUMBER W912EE26RA009		
		☒	9B. DATED (SEE ITEM 11) 19 FEB 2026		
		☐	10A. MODIFICATION OF CONTRACT/ORDER NUMBER		
			10B. DATED (SEE ITEM 13)		
CODE	FACILITY CODE				

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

SEE SECTION G - CONTRACT ADMINISTRATION DATA

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

See Schedule

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)	16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) ROBERT E. SCREWS		
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		 (Signature of Contracting Officer)	18 MAR 2026

Previous edition unusable

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Block 14 (Description of Amendment/Modification): Reference Solicitation No. W912EE26RA009, for MR&T, East Bank Mississippi River Levees, Magna Vista-Brunswick, Mississippi Levee Enlargement and Berms MRL ITEM 465-L Slide Repair.

THE PURPOSE OF THIS ADMENDMENT IS AS FOLLOWS:

SPECIFICATIONS: Section 01 00 00.00 09 and Section 31 11 00.00 09 are revised.

Specifications revised by this amendment have the notation "Revised by Amendment 0001" at the bottom of the page. Text added by this amendment is shown as underlined. Text deleted by this amendment is shown as overstruck.

PROPOSAL DUE DATE REMAINS UNCHANGED FRIDAY, 20 MARCH 2026 AT 1400 CST.

Section 00 01 15 - List of Drawing Sheets

The attachments table has changed from:

Identifi er	Document Name	Document Description	Reference Identifier	Date	Line Item	Page N umbers	Docum ent Type	Provid ed Under Separa te Cover
0001	Statement of Work (SOW) final	Statement of Work		17 Feb 2026			Attach ment	No
0002	MRL Item 465- L Drawings	Drawings		17 Feb 2026			Attach ment	No
0003	Wage Determination MS20260002	Wage Determination		05 Feb 2026			Attach ment	No

To:

Identifi er	Document Name	Document Description	Reference Identifier	Date	Line Item	Page N umbers	Docum ent Type	Provid ed Under Separa te Cover
0001	Statement of Work (SOW)	Statement of Work		17 Feb 2026		203	Attach ment	No

	final							
0002	MRL Item 465-L Drawings	Drawings		17 Feb 2026		37	Attachment	No
0003	Wage Determination MS20260002	Wage Determination		05 Feb 2026		5	Attachment	No
0004	Amendment W 912EE26RA009-0001_Specs	Specification		18 Mar 2026		28	Attachment	No

The following contract documents were added:

Amendment W912EE26RA009-0001_Specs

The following contract documents Page Counts were changed:

DOCUMENT PAGE COUNTS		
DOCUMENT NAME	FROM	TO
Amendment W912EE26RA009-0001_Specs	none	28

PROJECT TABLE OF CONTENTS**DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS**

00 80 00.00 09 SPECIAL CONTRACT REQUIREMENTS

DIVISION 01 - GENERAL REQUIREMENTS

01 00 00.00 09 GENERAL CONTRACT REQUIREMENTS
 01 22 00.00 09 MEASUREMENT AND PAYMENT
 01 32 01.00 09 PROJECT SCHEDULE
 01 33 00 SUBMITTAL PROCEDURES
 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS
 01 42 00 SOURCES FOR REFERENCE PUBLICATIONS
 01 45 00.00 09 QUALITY CONTROL
 01 45 00.15 09 RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE (RMS CM)
 01 57 20.00 09 ENVIRONMENTAL PROTECTION
 01 57 23.00 09 STORM WATER POLLUTION PREVENTION PLAN

DIVISION 02 - EXISTING CONDITIONS

02 50 00.00 09 REMOVAL OF EXISTING PAVEMENT

DIVISION 31 - EARTHWORK

31 11 00.00 09 CLEARING AND GRUBBING
 31 23 00.00 09 EXCAVATION
 31 24 00.00 09 EMBANKMENT
 31 25 00.00 09 TEMPORARY EROSION CONTROL

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 15 00.00 09 LEVEE SURFACING
 32 92 00.00 09 EXISTING TURF MAINTENANCE AND NEW TURF ESTABLISHMENT
 32 92 04.00 09 EROSION CONTROL MATTING

DIVISION 33 - UTILITIES

33 42 29.01 09 CULVERTS

DIVISION 35 - WATERWAY AND MARINE CONSTRUCTION

35 41 20.00 09 EMERGENCY LEVEE CLOSURE

-- End of Project Table of Contents --

SECTION TABLE OF CONTENTS
DIVISION 01 - GENERAL REQUIREMENTS
SECTION 01 00 00.00 09
GENERAL CONTRACT REQUIREMENTS

PART 1 GENERAL

- 1.1 REFERENCES
- 1.2 SUBMITTALS
- 1.3 PARTNERING
- 1.4 RIGHTS-OF-WAY
- 1.5 SURVEY LAYOUT AND MARKING FOR RIGHTS-OF-WAY AND CONSTRUCTION
- 1.6 PRECONSTRUCTION CONFERENCE
- 1.7 SUBMITTAL OF SUBCONTRACTING PLAN
- 1.8 NOTIFICATION OF AREA ENGINEER BEFORE BEGINNING WORK
- 1.9 PROHIBITED WORK DURING FLOOD STAGES
- 1.10 ORDER OF WORK
- 1.11 DESIGNATED BILLING OFFICE
- 1.12 PAYMENT INVOICES
- 1.13 TEMPORARY PROJECT FENCING
- 1.14 AS-BUILT DRAWINGS
- 1.15 PROJECT SIGN
- 1.16 MINIMUM REQUIRED INSURANCE
- 1.17 WORK IN QUARANTINED AREA
- 1.18 CERTIFICATES OF COMPLIANCE
- 1.19 PROCESS FOR OBTAINING CURRENT REQUIREMENTS OF THE U.S. ARMY CORPS
OF ENGINEERS SAFETY AND HEALTH REQUIREMENTS MANUAL (EM 385-1-1)
- 1.20 SAFETY SIGN
- 1.21 ACCIDENT PREVENTION PLAN
- 1.22 DAILY INSPECTIONS
- 1.23 ACCIDENT INVESTIGATIONS AND REPORTING
- 1.24 ACCOMMODATIONS FOR GOVERNMENT REPRESENTATIVES
- 1.25 MACHINERY AND MECHANIZED EQUIPMENT
- 1.26 VEHICLE WEIGHT LIMITATIONS
- 1.27 PUBLIC AND PRIVATE UTILITIES
- 1.28 DAMAGE TO WORK
- 1.29 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER
- 1.30 EXCLUSION OF PERIODS IN COMPUTING COMPLETION SCHEDULES
- 1.31 CONTROL OF ACCESS TO CONSTRUCTION AREAS
- 1.32 MAINTENANCE OF TRAFFIC
- 1.33 HARBOR MAINTENANCE FEE
- 1.34 ACCEPTANCE OF COMPLETED WORK

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section Table of Contents --

SECTION 01 00 00.00 09

GENERAL CONTRACT REQUIREMENTS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1 (2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

19 CFR 24.24 Harbor Maintenance Fee

33 CFR 156 Oil and Hazardous Material Transfer Operations

1.2 SUBMITTALS

Government approval is required for all submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan; G, GA

1.3 PARTNERING

The Government encourages formation of informal project partnerships on all projects. A project partnership strives to utilize a cooperative working relationship to jointly establish and effectively reach mutual project execution goals. The partnering process will in no way relax or stiffen the requirements of the contract, but will enhance the likelihood of success through improved working relationships and joint risk management. The possibility of an informal partnership may be discussed at the Pre-construction Conference for this project.

1.4 RIGHTS-OF-WAY

a. The rights-of-way for Contractor performance under this contract, within the limits indicated on the drawings, will be provided by the Government without cost to the Contractor. It is the Contractor's responsibility to carefully review and determine the scope of the rights-of-way. Any questions should be clarified with the Government prior to use. If these rights-of-way are used by the Contractor, he shall, at his own expense, do all work necessary to make such

rights-of-way suitable for safe travel to and from the worksite. Upon completion of the Contractor's work, any such rights-of-way furnished by the Government shall be left in a condition satisfactory to the Contracting Officer.

b. When so directed by the Contracting Officer, the Contractor shall, without expense to the Government, promptly vacate and clean up any part of the Government grounds or rights-of-way that have been allotted to or have been in use by the Contractor.

c. The Contractor shall not obstruct any existing roads or any other means of existing ingress or egress on lands controlled by the United States except with written permission of the Contracting Officer and shall maintain such roads and other means of ingress or egress in as good condition as exists at the time of commencement of work performance under this contract.

d. Notwithstanding any language or drawings to the contrary in this contract, the United States will not provide access or rights-of-way over any public lands and will not be responsible for acquiring such.

e. The Contractor shall repair at no expense to the Government, any and all damage to any existing roads or other means of existing ingress or egress when such damage is a result of his operations under this contract.

1.5 SURVEY LAYOUT AND MARKING FOR RIGHTS-OF-WAY AND CONSTRUCTION

The contractor shall be required to obtain the services of a licensed professional surveyor that is licensed in the state of contract performance to perform the following:

a. Field verify all control before start of construction activities. The contractor's surveyor shall be required to document any discrepancies discovered and any additional control that is required to facilitate construction activities. This information shall be submitted in writing to the Contracting Officer prior to initiating construction activities.

b. The Contractor shall layout and mark the rights-of-way limits as indicated on the drawings prior to beginning any other work, unless otherwise approved. The marking shall be placed at intervals approved by the Contracting Officer. The rights-of-way limits shall be marked by stakes, flagging or other approved means. The marking shall be highly visible from a distance of at least 100 feet, and shall be maintained for the duration of the contract. If the rights-of-way marking should fade significantly in color, become damaged or lost as a result of the Contractor's operation or as a result of vandalism, or in any other way cease to function as a highly visible marker of the rights-of-way limits, the Contractor shall layout and restore the marking to the original condition. After all work is complete and upon approval of the Contracting Officer, the Contractor shall remove all marking. No separate payment will be made for layout, marking and maintaining the rights-of-way limits or for removing the marking.

c. Crown stakes referenced to the project centerline shall be placed

at 100 foot intervals and at event points along the centerline alignment of the project. These stakes shall be labeled with the station number and proposed fill elevation. The stakes shall be maintained at a minimum on a monthly basis for all reaches under construction.

d. Cut and fill stakes shall be placed on all toe of slopes at 200 foot intervals at both the toe of berms and the toe of levee. The stakes shall be labeled with the proposed slope, indicate the direction of slope, and the horizontal distance from centerline. The stakes shall be maintained at a minimum on a monthly basis for all reaches under construction.

e. Stakes shall be placed at the midpoint or breakpoint of the slopes at 200 foot intervals. The midpoint stakes or breakpoint shall be labeled with the proposed grade elevation at the midpoint and the horizontal distance from the centerline levee enlargement. The stakes shall be maintained at a minimum on a monthly basis for all reaches under construction.

f. No separate payment will be made for layout, marking and maintaining the rights-of-way limits or for removing the marking.

1.6 PRECONSTRUCTION CONFERENCE

a. A preconstruction conference will be arranged by the Area Engineer as soon after contract award as possible, and the conference will be conducted before work is allowed to commence. The Area Engineer will notify the Contractor of the time, date, and location for the meeting. At this conference, the Contractor will be oriented with respect to contract administration procedures, lines of authority, opportunity for formation of project partnerships including joint risk management, and construction matters. All known subcontractors performing at least 20 percent of the contract are required to attend this conference. Additional conferences may be established by the Area Engineer for any major subcontractors unknown at the time of the initial conference.

b. Submission by the Contractor of the items listed below will determine the date of the conference. The following items shall be submitted to the Area Engineer in hard copy and electronic (pdf) format for review at least seven (7) calendar days prior to the preconstruction conference:

- (1) Accident Prevention Plan
- (2) Quality Control Plan
- (3) Environmental Protection Plan
- (4) One copy of the certified Large Construction Notice of Intent (LCNOI) for each site
- (5) Submittal register
- (6) Project Schedule in accordance with Section 01 32 01.00 09
PROJECT SCHEDULE

c. The Contractor shall bring to this conference, in completed form,

the following:

- (1) Letter of superintendent appointment and authority
- (2) List of subcontractors

d. Minutes of this conference will be taken and prepared by the Area Engineer and sent to the Contractor for his concurrence and signature.

1.7 SUBMITTAL OF SUBCONTRACTING PLAN

- a. This paragraph does not apply to small business concerns.
- b. After bid opening, and within 7 days, the apparent low bidder, upon telephone notification by the Small and Disadvantaged Business Utilization Specialist, shall submit a Small and Disadvantaged Business Subcontracting Plan. The plan shall be submitted in accordance with the Contract Clauses SMALL BUSINESS SUBCONTRACTING PLAN - ALTERNATE I. The person responsible for administering the plan shall be named in paragraph AGENT FOR SUBMITTING SMALL BUSINESS SUBCONTRACTING PLAN of the Representations and Certifications.

1.8 NOTIFICATION OF AREA ENGINEER BEFORE BEGINNING WORK

At least 7 days before beginning work, and at least one day before resuming work after a period of 7 days or more when no work has been performed, the Contractor shall notify U.S. Army Corps of Engineers, Mr. Jason Overstreet, Area Engineer, Greenwood Area Office, 100 Moore Street, Greenwood, Mississippi 38930-4512, telephone (662) 453-5531.

1.9 PROHIBITED WORK DURING FLOOD STAGES

Any work performed during flood stages is prohibited unless approved by the Contracting Officer. Any work with the potential to threaten the integrity of the levee will not be allowed. Working in areas of heavy seepage or operations causing pumping of the material on or near the levee are some examples of activities that would be prohibited. Upon notice of forecasted flood stages, Contractor shall take actions to ensure their ongoing work does not impact the levee system. Delays due to flood stages will be considered excusable delays and granted time extensions as provided for under the DEFAULTS clause. No additional compensation will be provided for flood stage delays or impacts except as provided for under DAMAGES to work clause.

1.10 ORDER OF WORK

The work shall be carried on in accordance with the Project Schedule required by Section 01 32 01.00 09. In preparing the Project Schedule, the Contractor shall adhere to the following order of work:

- a. All required BMP's shall be implemented as prescribed by the Storm Water Pollution Prevention Plan prior to any land disturbing activities.
- b. Construction borrow area shall be excavated beginning at Sta. 8207+00 and continuing West and downstream to the permissible depths and to the full riverside limits shown on the drawings.
- c. Ramp shall be constructed prior to beginning any levee and berm embankment or excavation to be used as a detour around the project

site. The levee crown and/or the landside berm may be used as a haul route between Sta. 8215+00 and Sta. 8255+00 for construction of proposed ramp only.

d. Prior to any levee or berm embankment excavation, borrow material specified for use in the Embankment must be stockpiled to a height not-to-exceed 8 FT, sloped to drain, and processed on the landside seepage berm in the location shown on the drawings, with the volume of stockpiled material equal-to or greater-than the volume of material required to construct the levee and berm embankment to existing Levee elevation (123.0 FT NAVD) within the excavated reach.

e. Levee excavation shall not begin until the Mississippi River is forecasted to be at 28.0 feet at the Vicksburg gage and falling. No excavation will be allowed during the exclusion period. Before demobilizing for extended periods the levee line of protection must be restored to 123' minimum.

f. During the excavation and placement of the embankment from Sta. 8183+00 to 8194+65, the Contractor may be directed by the Contracting Officer or his authorized representative to implement the Emergency Levee Closure Plan as described in SECTION 35 41 20.00 09 EMERGENCY LEVEE CLOSURE.

g. Levee excavation reach lengths shall not exceed 600 feet measured along the bottom of the fully excavated section. This limitation will result in a minimum of two excavation reaches during construction. Excavation of the second reach will not be allowed until embankment placement in the first reach has been completed to an elevation of ~~115.0~~123.0 ft.

h. New stability berm from Sta. 8173+00 to 8183+00 shall be completed prior to any levee embankment placement on that reach.

i. Berm construction from Sta. 8183+00 to 8194+65 shall be completed concurrently with adjacent levee embankment.

j. Levee embankment placement from Sta. 8173+00 to 8183+00 can be performed concurrently with levee embankment placement from Sta. 8183+00 to 8194+65.

k. New surfacing material shall be placed on completed embankment construction in one continuous reach.

l. The existing levee crown shall not be used as a haul road for normal levee and berm construction project. Completed levee embankment (with or without surfacing material) shall not be used as a haul road.

m. Temporary or permanent seeding of the completed levee and berm embankments will be required within 14 days of beginning work on a new reach of embankment as required by the Stormwater Permit or work must cease until the seeding is accomplished.

1.11 DESIGNATED BILLING OFFICE

The designated billing office for this contract shall be U.S. Army Corps of Engineers, Greenwood Area Office, 100 Moore Street, Greenwood, Mississippi 38930-4512.

1.12 PAYMENT INVOICES

a. The Federal Acquisition Regulation requires that the "REMIT TO" address on the invoice match the "REMIT TO" address on the contract or a proper notice of assignment. The Payment Office will verify a match of the "REMIT TO" address in the contract and Contractor's invoice prior to payment. If the addresses do not match, the invoice will be determined improper and returned to the Contractor for correction and resubmission. If an invoice is improperly returned, the original invoice receipt date shall be used as the basis for determining interest to be paid in accordance with the PROMPT PAYMENT ACT.

b. Among other things, the Contract Clause PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS requires that a proper invoice for payment include substantiation of the amounts requested. As required in Office of Management and Budget, 5 CFR Part 1315, September 29, 1999, PROMPT PAYMENT, substantiation of the amount requested for progress payments under construction contracts includes the following:

- (1) An itemization of the amounts requested related to the various elements of work required by the contract covered by the payment request;
- (2) A listing of the amount included for work performed by each subcontractor under the contract;
- (3) A listing of the total amount of each subcontract under the contract;
- (4) A listing of the amounts previously paid to each such subcontractor under the contract; and,
- (5) Additional supporting data in a form and detail required by the Contracting Officer.

c. Failure to include the above information in a Contractor's invoice will result in the invoice being considered defective under the provisions of the PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS clause of the contract, and it will be returned to the Contractor for correction and resubmission.

1.13 TEMPORARY PROJECT FENCING

Temporary project fencing as required by Section 4, "Temporary Facilities", paragraph 04.A.04 of EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements Manual, is not required on this project.

1.14 AS-BUILT DRAWINGS

This paragraph supplements the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION.

a. As-Built Contract Drawings. The Contractor shall maintain two (2) full-size sets of blueline prints of the contract drawings depicting in red a record of as-built conditions. These drawings shall be maintained in current condition at all times during the entire contract period. The blueline drawings shall be updated daily by the Contractor showing all changes from the contract plans which are made

in the work, additional information which might be uncovered in the course of construction, and information for future construction reference (such as debris disposed by burying). For levee and berm construction, the riverside toe of completed levee and berm sections shall be plotted on profiles of construction drawings. Levee and berm toe profiles shall depict elevations of newly constructed slope intersection with natural ground and depressions which extend the toe line between routine section surveys. This information shall be recorded on the blue-line prints accurately and neatly by means of details and notes. Each month, prior to submitting a request for progress payment, the Contractor shall review the blue-line as-built drawings with the Contracting Officer, and the Contractor shall certify that the as-built drawings are accurate and up-to-date before progress payment is made. The Contractor shall deliver to the Contracting Officer the two (2) original full-size completed sets of as-built marked blue-line prints at the time of the final inspection of the project. In addition, the Contractor shall provide two CD-ROM's, each containing a full-size, 400 dpi PDF (portable document format) set of as-built drawings, to the Contracting Officer at the time of final inspection. The as-built drawings shall be identified by entering the words "AS-BUILT DRAWINGS" in letters at least 3/16-inch high, placed in the lower right corner of each drawing.

b. No separate measurement or payment will be made for providing as-built drawings, electronic drawings and plates, or for any of the work required by this clause, and all costs therefor shall be included in the applicable contract prices contained in the Bidding Schedule.

1.15 PROJECT SIGN

The Contractor shall fabricate, erect and maintain one sign for project identification. The sign shall be displayed and positioned for reading by passing viewers. The exact location is subject to Contracting Officer's approval. Information for the right side of the project sign shall be as follows:

Project Title: MR&T, EAST BANK MISSISSIPPI RIVER LEVEES
MAGNA VISTA - BRUNSWICK, MISSISSIPPI
LEVEE ENLARGEMENT AND BERMS
MRL ITEM 465-L SLIDE REPAIR

Contract No: W912EE-265-B-0XXX

Contractor: (Contractor's name and city)

The project identification sign shall meet the requirements specified in the U.S. Army Corps of Engineers Sign (USACES) Standards Manual, EP 310-1-6a and EP 310-1-6b. A copy of the sign standards manual is available for review at the office of the Vicksburg District Sign Program Manager and questions concerning manufacture and installation of the project identification sign may be addressed to:

Vicksburg District Sign Program Manager (Aaron Posner)
ATTN: CEMVK-OD-MN
4155 Clay Street
Vicksburg, MS 39183-3435
Telephone: (601) 631-5287

1.16 MINIMUM REQUIRED INSURANCE

The following paragraph is applicable if the services involved are performed on a Government Installation. Government Installation is defined as property where the Government holds by fee simple title, by construction rights-of-way, or perpetual easement, etc., an interest in real property. See the Contract Clause INSURANCE-WORK ON A GOVERNMENT INSTALLATION.

- a. Workmen's Compensation and Employer's Liability Insurance. The Contractor shall comply with all applicable workmen's compensation Statutes of the State of Mississippi and shall furnish evidence of Employer's Liability Insurance in an amount of not less than \$100,000.
- b. General Liability Insurance. Bodily injury liability insurance in the minimum limits of \$500,000 per occurrence on the comprehensive form of policy.
- c. Automobile Liability Insurance. Minimum limits of \$200,000 per person and \$500,000 per occurrence for bodily injury and \$20,000 per occurrence for property damage. This insurance shall be on the comprehensive form of policy and shall cover the operation of all automobiles used in performance of the contract.

1.17 WORK IN QUARANTINED AREA

The work called for by this contract involves activities in counties quarantined by the Department of Agriculture to prevent the spread of certain plant pests which may be present in the soil. The Contractor agrees that all construction equipment and tools to be moved from such counties shall be thoroughly cleaned of all soil residues at the construction site with water under pressure and that hand tools shall be thoroughly cleaned by brushing or other means to remove all soil. In addition, if this contract involves the identification, shipping, storage, testing, or disposal of soils from such quarantined area, the Contractor agrees to comply with the provisions of ER 1110-1-5, "Plant Pest Quarantined Areas and Foreign Soil Samples" attachments, a copy of which will be made available by the Contracting Officer upon request. The Contractor agrees to assure compliance with this obligation by all subcontractors.

1.18 CERTIFICATES OF COMPLIANCE

Any certificates required for demonstrating proof of compliance of material with specification requirements shall be executed in accordance with Section 01 33 00 SUBMITTAL PROCEDURES. Each certificate shall be signed by an official authorized to certify on behalf of the manufacturing company and shall contain the name and address of the Contractor, the project name and location, and the quantity and date or dates of shipment or delivery to which the certificates apply. Copies of laboratory test reports submitted with certificates shall contain the name and address of the testing laboratory and the date or dates of the tests to which the report applies. Certification shall not be construed as relieving the Contractor from furnishing satisfactory material, if, after tests are performed on selected samples, the material is found not to meet the specific requirements.

1.19 PROCESS FOR OBTAINING CURRENT REQUIREMENTS OF THE U.S. ARMY CORPS OF ENGINEERS SAFETY AND HEALTH REQUIREMENTS MANUAL (EM 385-1-1)

Contractors are required to comply with the latest version, and all posted changes, of the U.S. Army Corps of Engineers Safety and Health Requirements Manual in effect on the issue date of this solicitation. EM 385-1-1 version 2014 and changes are available on the Internet at <http://www.publications.usace.army.mil/USACEPublications/EngineerManuals.aspx>, Search for EM_385-1-1, then click on EM_385-1-1 2014 english version. Prior to making an offer, offerors should check the referenced website for the latest changes. No separate payment will be made for compliance with the requirements of this paragraph, or for compliance with other safety requirements of the contract.

1.20 SAFETY SIGN

The Contractor shall fabricate, erect and maintain a safety sign at the site, as located by the Contracting Officer. The sign shall be erected as soon as practicable, but not later than 15 calendar days after the date established for commencement of work. The data required shall be current. The safety sign shall meet the requirements specified in the U.S. Army Corps of Engineers Sign (USACES) Standards Manual, EP 310-1-6a and EP 310-1-6b. A copy of the sign standards manual is available for review at the office of the Vicksburg District Sign Program Manager and questions concerning manufacture and installation of the safety sign may be addressed to:

Vicksburg District Sign Program Manager (Aaron Posner)
ATTN: CEMVK-OD-MN
4155 Clay Street
Vicksburg, MS 39183-3435
Telephone: (601) 631-5287

1.21 ACCIDENT PREVENTION PLAN

Refer to the Contract Clause ACCIDENT PREVENTION (Alternate I). Within 15 days after receipt of award of the contract, an Accident Prevention Plan shall be submitted to the Contracting Officer for review and acceptance. The plan shall be prepared as specified in Appendix A, "Minimum Basic Outline for Accident Prevention Plans" of EM 385-1-1. In addition to the requirements listed, the Contractor shall also submit the required information on the forms outlined below, which can be found on the Vicksburg District Construction Division home page, <http://www.mvk.usace.army.mil/Missions/EngineeringandConstructionDivision.aspx>, click on Construction Services Branch, then click on Forms.

- a. An executed LMV Form 358-R, "Administrative Plan".
- b. An executed MVK Form 385-359-R, "Hazard Analysis" for each definable feature of work.
- c. When marine plant and equipment are in use under a contract, the method of fuel oil transfer shall be submitted on LMV Form 414R, "Fuel Oil Transfer-Floating Plant". (Refer to 33 CFR 156.)
- d. The Contractor shall not commence physical work at the site until the plan has been accepted by the Contracting Officer, or his authorized representative. At the Contracting Officer's discretion, the Contractor may submit his Hazard Analysis only for the first phase

of construction provided that it is accompanied by an outline of the remaining phases of construction. All remaining phases shall be submitted and accepted prior to the beginning of work in each phase. Also, refer to Section 1, "Program Management", paragraph 01.B, "Indoctrination and Training" of EM 385-1-1.

1.22 DAILY INSPECTIONS

Refer to Section 01 45 00.00 09 CONTRACTOR QUALITY CONTROL and the Contract Clause INSPECTION OF CONSTRUCTION. The Contractor shall perform daily safety inspections and record them on the forms approved by the Contracting Officer. Reports of daily inspections shall be maintained at the job site. The reports shall be records of the daily inspections and resulting actions. As a minimum each report shall include the following:

- a. Phase(s) of construction underway during the inspection.
- b. Locations or areas inspections were made.
- c. Results of inspection, including nature of deficiencies observed and corrective actions taken, or to be taken, date, and signature of the person responsible for its contents.

1.23 ACCIDENT INVESTIGATIONS AND REPORTING

Refer to EM 385-1-1, Section 1, "Program Management", paragraph 01.D, "Accident Reporting and Recordkeeping". Accidents shall be investigated and reports completed by the immediate supervisor of the employee(s) involved and reported in writing to the Contracting Officer or his representative within one working day after the accident occurs.

1.24 ACCOMMODATIONS FOR GOVERNMENT REPRESENTATIVES

- a. Accommodations. The Contractor shall furnish and maintain a temporary building for the exclusive use of the Government Representatives at an approved location. The building shall be of light, but weatherproof construction, approximately 240 square feet in size with not less than 7 feet of headroom. The building shall either be divided into two separate rooms or have a lockable storage closet on the opposite end from the workbench. It shall have a substantial workbench along one side and sufficient number of windows to admit ample working light. Windows shall be arranged to open and to be securely fastened from the inside. The door shall be of wood panel or solid core construction and be equipped with a padlock and heavy duty hasp bolted to the door. Insect screens shall be provided for windows. Glass panels in windows shall be equipped with bars or heavy mesh screens which will prevent easy access to the building through these panels. The Contractor shall heat the building by means of heaters and shall cool the building by means of an air conditioning unit. Electric current shall also be provided for operation of lights, appliances, computers, and electric calculators at 115 volts AC. Electric current may be provided by use of a portable generator. A minimum of four wall outlets and two ceiling drops shall be provided in the building. Electrical surge protection is required at all wall outlets. One office desk and a minimum of two chairs shall be provided in the building. Internet service shall be provided capable of a minimum transfer data rate of 10 Mbps for downloading and 2 Mbps for Uploading. When available, a data line shall be provided to the facility, capable of providing the required service above. When there

is an unavailability of a hard data line, a wireless service shall be provided to the Government capable of providing the data transfer indicated above. Permanent toilet facilities shall be provided within the building. The building shall remain the property of the Contractor and upon completion of all work under the contract shall be removed as provided in the Contract Clause OPERATIONS AND STORAGE AREAS. An office trailer meeting the above requirements will be acceptable.

b. Janitor Services. The Contractor shall furnish daily janitorial services for the above office and perform any required maintenance of subject facility and adjacent grounds during the entire life of the contract. Toilet facilities shall be clean and sanitary at all times. Services shall be performed at such a time and in such a manner to least interfere with the operations but will be accomplished only when the office is in daily use. The Contractor shall also provide daily trash collection and cleanup of the building and adjacent outside areas, and shall dispose of all discarded debris in a manner approved.

c. No separate measurement or payment will be made for providing and maintaining the prescribed building, accommodations, utilities and janitor services, and all costs associated therewith shall be distributed throughout the existing bid items. Should the Contractor refuse, neglect, or delay compliance with the above requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and the cost thereof will be deducted from any amount due or to become due the Contractor.

1.25 MACHINERY AND MECHANIZED EQUIPMENT

Machinery and mechanized equipment used under this contract shall comply with the following:

a. When mechanized equipment is operated on floating plant, the Contractor shall provide positive and acceptable means of preventing this equipment from moving or falling into the water. The type of equipment addressed by this clause includes front-end loaders, bulldozers, trucks (both on- and off-road), backhoes, hydraulic excavators (track hoes), and similar equipment. If the Contractor plans to use such equipment on floating plant, an activity hazard analysis must be developed for this feature of work. The plan must include a detailed explanation of the type or types of physical barriers, curbs, structures, etc., which will be incorporated to protect the operator and prevent the equipment from entering the water. Nonstructural warning devices may be considered for situations where the use of structural barriers is determined to be impracticable. The activity hazard analysis must thoroughly address the procedure and be submitted to the Corps for review and acceptance prior to start of this feature of work.

b. The stability of crawler, truck, and wheel-mounted cranes shall be assured.

(1) The manufacturer's load-rating chart may be used to determine the maximum allowable working load for each particular crane's boom angle provided a test load, with a boom angle of 20 degrees, confirms the manufacturer's load-rating table.

(2) Stability tests are required if:

- (i) there is no manufacturer's load-rating chart securely fixed to the operator's cab;
- (ii) there has been a change in boom or other structural member;
or
- (iii) there has been a change in the counterweight.

The test shall consist of lifting a load with the boom in the least stable undercarriage position and at an angle of 20 degrees above the horizontal. The test shall be conducted under close supervision on a firm, level surface. The load that tilts the machine shall be identified as the test load. The test load moment (in ft-lbs) shall then be calculated by multiplying the horizontal distance (in feet) from the center of rotation of the machine to the test load, times the test load (in lbs). Three-fourths of this test-load moment shall then be used to compute the maximum allowable operating loads for the boom at 20, 40, 60, and 80 degrees above horizontal. From these maximum allowable operating loads, curve shall be plotted and posted in the cab of the machine in sight of the operator. These values shall not be exceeded except in the performance test described below. The test load shall never exceed 100 percent of the manufacturer's maximum rated capacity.

- (3) In lieu of the test and computations above, the crane may be load tested for stability at each of the four boom positions listed above.

c. Performance tests shall be performed in accordance with Section 18.G, "Machinery and Mechanized Equipment" of EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Requirements Manual, except as specified below. Performance tests shall be conducted after each stability test, when the crane is placed in service on a project, and at least every 12 months.

- (1) When conducting a performance load test which is required of a new crane or a crane in which load sustaining parts have been altered, replaced, or repaired (excluding replacement of the rope), the test load shall be as specified in ASME/ANSI B30 Series. That is, for overhead, gantry, portal, pillar, tower, monorail, and underhung cranes, the test load shall not exceed 125 percent of the manufacturer's load rating capacity chart at the configuration of the test; and for hammerhead tower, mobile, and floating cranes and boom trucks, the test load shall not exceed 110 percent of the manufacturer's load rating capacity chart at the configuration of the test.

- (2) When conducting a performance load test which is required because a crane is reconfigured, or reassembled after disassembly, or because the crane requires an annual load test, the test loads shall not exceed 100 percent of the manufacturer's load rating capacity chart at the configuration of the test.

- (3) All load tests are required to be conducted in accordance with the manufacturer's recommendations.

d. Inspections shall be made which will ensure a safe and economical

operation of both cranes and draglines with inspection documented. Copies of the inspections and tests shall be available at the job site for review. All stability and performance tests on cranes and all complete dragline inspections shall be witnessed by the Contracting Officer or his authorized representative.

e. A complete dragline inspection shall be made:

- (1) at least annually;
- (2) prior to the dragline being placed in operation; and
- (3) after the dragline has been out of service for more than 6 months.

f. All heavy equipment moved onto the worksite shall be inspected for compliance with this contract. The CEMVK-SO Inspection forms attached at the end of this section shall be completed by the Contractor. All completed forms, including abatement schedule of any violations, shall be maintained at the job site for continued review and update as needed.

1.26 VEHICLE WEIGHT LIMITATIONS

Vehicle weight limitations for operation on rural roads and bridges may affect the prosecution of work in this contract. The Contractor will be responsible for obtaining all necessary licenses and permits in accordance with the Contract Clause PERMITS AND RESPONSIBILITIES. Current information regarding road and bridge weight limits may be obtained by contacting the Mississippi Department of Transportation and the president of the county Board of Supervisors for the counties through which equipment and materials will be transported as a result of this contract.

1.27 PUBLIC AND PRIVATE UTILITIES

a. Unless otherwise specified, shown on the drawings, or stated in writing by the Contracting Officer, the Contractor shall not remove or disturb any public or private utilities. Such removals, alterations, and relocations, where necessary, will be made by others. The locations, if any, shown on the drawings for underground utilities are approximate only. The exact locations of such utilities shall be determined by the Contractor in the field prior to commencing construction operations in their vicinity.

b. The attention of the Contractor is directed to the possibility that he may encounter, within the right-of-way limits, utilities, some of which may be buried, and the existence of which is presently not known. Should any such utilities be encountered, the Contractor shall immediately notify the Contracting Officer so that he may determine whether they shall be removed, relocated, or altered. After such determination is made, the Contractor shall, if so directed by the Contracting Officer, remove, relocate, or alter them as required, and an equitable adjustment will be made in accordance with the Contract Clause CHANGES. In event the Contracting Officer arranges for such removals, alterations, or relocations to be performed by others, the Contractor shall cooperate with such others during the latter's removal, alteration, or relocation operations in accordance with the Contract Clause OTHER CONTRACTS.

1.28 DAMAGE TO WORK

a. The responsibility for damage to any part of the permanent work shall be as set forth in the Contract Clause PERMITS AND RESPONSIBILITIES. However, if, in the judgment of the Contracting Officer, any part of the permanent work performed by the Contractor is damaged by flood (see Section 00 80 00.00 09 SPECIAL CONTRACT REQUIREMENTS, paragraph PHYSICAL DATA, subparagraph FLOODS) or earthquake, which damage is not due to the failure of the Contractor to take reasonable precautions or to exercise sound engineering and construction practices in the conduct of the work, the Contractor shall make repairs as ordered by the Contracting Officer and full compensation for such repairs to permanent work will be made at the applicable contract unit or job prices as fixed and established in the contract. If, in the opinion of the Contracting Officer, for any part of such damaged permanent work, there is no applicable contract unit or job price, then an equitable adjustment pursuant to the Contract Clause CHANGES will be made as full compensation for the repairs for that part of the permanent work for which there is no applicable contract unit or job price.

b. Except as herein provided, damage to all work (including temporary construction), utilities, materials, equipment, and plant shall be repaired to the satisfaction of the Contracting Officer, at the Contractor's expense, regardless of the cause of such damage.

1.29 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER

a. This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance with the Contract Clause DEFAULT (FIXED PRICE CONSTRUCTION). In order for the Contracting Officer to award a time extension under this paragraph, the following conditions must be satisfied:

(1) The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.

(2) The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the Contractor.

b. The following schedule of monthly anticipated adverse weather delays is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the project location and will constitute the base line for monthly weather time evaluations. The Contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent activities.

MONTHLY ANTICIPATED ADVERSE WEATHER DELAY
WORK DAYS BASED ON FIVE (5) DAY WORK WEEK

JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC

(NA) (NA) (NA) (NA) (NA) (10) (7) (7) (2) (3) (7) (7)

c. Upon acknowledgement of the Notice to Proceed (NTP) and continuing throughout the contract, the Contractor shall record on the daily CQC

report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the Contractor's scheduled work day. The number of actual adverse weather days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph b, above, the Contracting Officer will convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the Contract Clause DEFAULT (FIXED PRICE CONSTRUCTION).

1.30 EXCLUSION OF PERIODS IN COMPUTING COMPLETION SCHEDULES

Except for the work required in Section 01 57 20.00 09 ENVIRONMENTAL PROTECTION, Section 01 57 23.00 09 STORM WATER POLLUTION PREVENTION PLAN, and Section 32 92 00.00 09 EXISTING TURF MAINTENANCE AND NEW TURF ESTABLISHMENT, no work will be required during the period between 1 January and 31 May inclusive, and such period has not been considered in computing the time allowed for completion. The Contractor may, however, perform work during all or any part of this period upon giving prior written notice to the Contracting Officer. Impacts occurring during the Exclusion Period will not be considered for time extensions.

1.31 CONTROL OF ACCESS TO CONSTRUCTION AREAS

- a. This paragraph supplements the Contract Clauses PERMITS AND RESPONSIBILITIES and OPERATIONS AND STORAGE AREAS.
- b. It shall be the responsibility of the Contractor to prevent possible injury to visitors to the project site. Only personnel engaged in contract work and others authorized by the Contracting Officer shall be permitted to enter into the construction areas. Suitable barriers, warning signs and directives shall be placed by the Contractor to direct persons not engaged in the work away from the areas of danger. The Contractor shall be responsible for effective enforcement of this paragraph during the period of this contract.

1.32 MAINTENANCE OF TRAFFIC

- a. The Contractor shall conduct his operations in such manner as to offer the least possible obstruction to the safe and satisfactory movement of traffic over the existing roads and detour road during the life of the contract.
- b. The Contractor shall be responsible for providing, erecting/installing, maintaining monthly, and removal of all traffic signs, barricades, and other traffic control devices necessary for maintenance of traffic. See also paragraph ACCIDENT PREVENTION PLAN of these specifications and the Contract Clause ACCIDENT PREVENTION.
- c. All barricades, warning signs, lights, temporary signals, other devices, flagmen, and signaling devices shall meet or exceed the minimum requirements of Mississippi DOT, Standard Specifications for Road and Bridge Construction. See EM 385-1-1, U.S. Army Corps of Engineers Safety and Health Manual, Section 8, paragraph 08.C, "Traffic Control". The Contractor is responsible for the protection,

monthly maintenance, and replacement of all existing signs, route markers, traffic control signals, and other traffic control features during the life of this contract.

d. Prior to the commencement of construction operations the Contractor shall submit for the acceptance of the Contracting Officer, complete details of his proposed plans for the maintenance of traffic and access through the construction area.

e. The requirements of this paragraph shall be met by the Contractor at no additional expense to the Government.

1.33 HARBOR MAINTENANCE FEE

a. Offerors or bidders contemplating use of U.S. ports in the performance of contract are subject to paying a harbor maintenance fee on cargo. Federal law establishes an ad valorem port use fee on commercial cargo imported into or exported from various U.S. ports. The fee is 0.125 percent (0.00125). Cargo to be used in performing work under contracts with the U.S. Government is not exempt from the fee, although certain exemptions do exist. Offerors are responsible for ensuring that the applicable fee and associated costs are taken into consideration in the preparation of their offers. Failure to pay the harbor maintenance fee may result in assessment of penalties by the Customs Service.

b. The statute is at Title 26 U.S. Code section 4461 and 4462. Department of Treasury Customs Service regulations implementing the statute, including a list of ports subject to the fee, are found at 19 CFR 24.24, Harbor Maintenance Fee. Additional information may be obtained from local U.S. Customs Service Offices or by writing to the Director, Budget Division, Office of Finance, Room 6328, U.S. Customs Service, 1301 Constitution Avenue, N.W., Washington, D.C. 20229.

1.34 ACCEPTANCE OF COMPLETED WORK

For the purpose of acceptance, the work to be done is divided into sections as follows:

a. Levee slide repair section from approximate Station 8194+65 to Station 8183+00.

b. Enlargement and berm from approximate Station 8183+00 Station 8173+00.

c. Ramp at Station 8242+85.

d. All remaining work.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

SAFETY INSPECTION FOR CONSTRUCTION ACTIVITY U.S. Army Engineer District, Vicksburg		Date of Inspection:		
Contractor or Unit		Contract No. or Activity		
Inspected by (Signature)		Witness (Signature)		
NIGHT OPERATIONS NOTE: Safety and Health Requirements Manual (EM385-1-1) references in parentheses.		Yes	No	N/A
1	General			
a	On construction contracts, is there a designated Contractor's representative on duty during night operations? FAR Clause			
b	Are weekly safety meetings being held for night-shift employees, by field supervisors or foremen? (01.B.05)(A)(B)			
c	Are regularly scheduled safety meetings being held (at least once a month) for night supervisors? (01.B.05 (a)			
d	Are there adequate communications and/or transportation available in the event of serious injury to personnel? (03.A.01)			
e	Is there two qualified first-aid and CPR attendant per shift on duty? (03.A.02)(a)			
f	Are fire, man-overboard & abandon-ship drills (as applicable) conducted at least monthly? (19.A.04 (e)) NOTE: The first set of drills shall be conducted within 24 hours of the vessel's occupancy or commencement of work. (19.A..04(e) (1) Night drills shall be conducted within the first two weeks of vessel's occupancy. (19.A.04 (e) (2)).			
2	Lighting - Section 7 at Table 7-1			
a	Are haul roads properly marked for night work? (Section 7, Table 7-1)			
b	Is there adequate lighting in work areas, On decks and walkways? (07.A)			
c	Is there adequate lighting at crew boat loading area on floating plant? (07.A)			
d	Are all vehicles, construction equipment properly lighted? (16.A.11) (16.A.07)(b)			
3	Transportation to and from float plant			
a	Is boat equipped with sufficient number of life preservers? (05.H.01)(a ,b ,c ,d ,e)			
b	Are all vehicles and construction equipment properly lighted for night work? (18.A.02)			
c	If boat is less than 26 feet in length, has it been tested for flotation and stability, or does it carry BIA certification? (19.A.01)			
d	If more than 6 passengers are carried, or boat is greater than 26 feet in length, is vessel Coast Guard certified and operator licensed? (19.A.02)			
e	For boats of less than 26 feet in length, is operator licensed, and certified ? (19.A.02(b , c))			
f	Is weather deck of boat coated with non-skid material? (19.B.01)(b)			
g	Is there safe, easy access from boat to landing? (19.B.02)			
h	Do guard rails meet requirements of EM 385-1-1? (19.B.02)(c)			
i	Is the capacity of boat posted in accordance with EM 385-1-1? (19.C.02)(a)			

May 04

Proponent CEMVK-SO

SAFETY INSPECTION FOR MISCELLANEOUS EQUIPMENT U.S. Army Engineer District, Vicksburg		Date of Inspection:		
Contractor or Unit		Contract No. or Activity		
Inspected by (Signature)		Witness (Signature)		
CRANE/DERRICK INSPECTION CHECKLIST NOTE: Safety and Health Requirements Manual (EM385-1-1) references in parentheses.		Yes	No	N/A
1	Are the following documents with the crane at all times? (16.C.02)			
1a	Is the Operating manual available from the manufacturer for the specific crane being inspected?			
	(1) Any operator aids for which the crane is equipped?			
1b	Does the load rating chart for the crane include?			
	(1) The crane make and model, serial number, and year of manufacturer?			
	(2) Load ratings for all crane operating configurations: including optional equipment?			
	(3) Recommended reeving for the hoist line?			
	(4) Operating limits in windy or cold conditions?			
1c	Does crane log book show operating hours, inspections, tests, maintenance & repair? Note: Has log been updated daily when crane is used, and is signed by operator & supervisor? Note: Mechanics shall sign after conducting maintenance or repairs. (16.C.02(d))			
2	Does operator have certification that he meets operator qualification and training as stated in 16.C.04 and Appendix G?			
3	Has a hazard analysis been conducted for set-up and set-down procedures (mobilization, assembly, dismantling, etc.)? (16.C.08)			
4	Are adequate clearances provided from electrical sources, fixed objects, and swing radius? (16.C.09)			
5	Is communications provided as required? (16.C.11)			
6	Has inspection been performed in accordance with 16.C.12 and Appendix H?			
7	Have performance load tests been in accordance with 16.C.13 and Appendix I?			
8	Are tag lines used to control loads? (16.C.16)			
9	Is critical lift plan required? (16.C.18)			
10	Are all environmental considerations of 16.C.19 being met?			
11	Is crane equipped with boom angle indicator, load indicating device, means to visually determine levelness, and anti-two block devices? (16.D.01 & 02 & 05)			
12	Are cable supported booms equipped with boom stops? (16.D.06)			
13	Are booms lowered to ground or secured when not in use? (16.D.11)			
14	Do all floating cranes and derricks meet the requirements of 16.F?			
15	Are all moving parts (gears, drums, shafts, belts, etc.) and all hot surfaces (exhaust lines, pipes, etc.) guarded? (16.B.03)			

16 Does the unit have a suitable fire extinguisher? (16.A.34) NOTE: Minimum 5 BC			
REMARKS:			

SAFETY INSPECTION FOR MISCELLANEOUS EQUIPMENT U.S. Army Engineer District, Vicksburg		Date of Inspection:		
Contractor or Unit		Contract No. or Activity		
Inspected by (Signature)		Witness (Signature)		
CRAWLER TRACTORS-DOZERS NOTE: Safety and Health Requirements Manual (EM385-1-1) references in parentheses.		Yes	No	N/A
1	Are inspection records kept available as part of the project files? (16.A.01 (a))			
2	Has equipment been inspected and tested by a competent person and certified to be safe? (16.A.02 (a) (b))			
3	Are only designated qualified operators assigned to operate mechanized equipment? (16.A.04)			
4	Are sufficient lights provided for night operations? (16.A.11)			
5	Is the unit shut down before refueling? (16.A.15)			
6	Does the unit have a suitable fire extinguisher - 5 BC min.? (16.A.34)			
7	Is there an effective, working, reverse alarm? (16.B.01)			
8	Are moving parts, shafts, sprockets, belts, etc., guarded? (16.B.03 (a) and 16.B.07 and 16.B.13)			
9	Is protection against contact with hot surfaces, exhaust, etc., provided? (16.B.03 (b))			
10	Are all fuel tanks located in a manner to prevent spills or overflows from running onto engine exhaust or electrical equipment? (16.B.04)			
11	Are exhaust discharges from equipment so directed that they do not endanger persons or obstruct the view of the operator? (16.B.05)			
12	Are seat belts provided? (16.B.08)			
13	Is protection (grills, canopies, screens) provided to shield operator from falling or flying objects? (16.B.10 and 16.B.11)			
14	Is adequate roll over protection provided? (16.B.12)			
REMARKS:				

SAFETY INSPECTION FOR MISCELLANEOUS EQUIPMENT U.S. Army Engineer District, Vicksburg		Date of Inspection:		
Contractor or Unit		Contract No. or Activity		
Inspected by (Signature)		Witness (Signature)		
DRAGLINE INSPECTION CHECKLIST NOTE: Safety and Health Requirements Manual (EM385-1-1) references in parentheses.		Yes	No	N/A
1	Are the following documents with the crane at all times? (16.C.02)			
1a	Operating manual from the manufacturer for the specific crane being inspected.			
	(1) Any operator aids for which the crane is equipped?			
1b	Load rating chart for the crane which shall include:			
	(1) the crane make and model, serial number, and year of manufacturer			
	(2) load ratings for all crane operating configurations: including optional equipment			
	(3) wire rope type, size, and reeving; line pull, line speed and drum capacity			
	(4) operating limits in windy or cold conditions			
1c	Crane log book that shows operating hours, inspections, tests, maintenance & repair. Note: Has log been updated daily when crane is used, and is signed by operator & supervisor? Note: Mechanics shall sign after conducting maintenance or repairs.			
2	Does operator have certification that he meets operator qualification and training as stated in 16.C.04 and Appendix G?			
3	Has a hazard analysis for set-up and set-down procedures (mobilization, assembly, dismantling, etc.). (16.C.08)			
4	Are adequate clearances provided from electrical sources, fixed objects, and swing radius. (16.C.09)			
5	Has inspection been performed in accordance with 16.C.12 and Appendix H?			
6	Are cable supported booms equipped with boom stops? (16.D.06)			
7	Is boom lowered to ground or secured when not in use? (16.D.11)			
8	Are all moving parts (gears, drums, shafts, belts, etc.) and all hot surfaces (exhaust lines, pipes, etc.) guarded? (16.B.03)			
9	Does the unit have a suitable fire extinguisher? (16.A.34) NOTE: Minimum 5 BC			
REMARKS:				

SECTION TABLE OF CONTENTS

DIVISION 31 - EARTHWORK

SECTION 31 11 00.00 09

CLEARING AND GRUBBING

PART 1 GENERAL (Not Applicable)

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

3.2 CLEARING

3.2.1 General

3.2.2 Trees

3.2.3 Vegetation Removal

3.2.4 Areas to be Cleared

3.2.4.1 General

3.2.4.2 Borrow Areas

3.2.4.3 Other Areas

3.3 GRUBBING

3.3.1 General

3.3.2 Areas to be Grubbed

3.3.2.1 General

3.3.2.2 Ditches

3.3.2.3 Berms

3.3.3 Borrow Areas

3.3.4 Pipes and Drains

3.3.5 Filling of Holes

3.4 DISPOSAL OF DEBRIS

3.4.1 General

3.4.2 Burning

3.4.3 Burying

3.4.4 Removal from Site of Work

-- End of Section Table of Contents --

SECTION 31 11 00.00 09

CLEARING AND GRUBBING

PART 1 GENERAL (Not Applicable)

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

All clearing and grubbing work, including vegetation removal, for all required excavations and embankment construction shall be completed at least 500 feet in advance of the required work. If regrowth of vegetation or trees occurs after clearing and grubbing and before beginning excavation or placement of fill, the Contractor will be required to clear and grub the area again prior to beginning the work, and no payment will be made for this additional clearing and grubbing.

3.2 CLEARING

3.2.1 General

Clearing shall be limited to those areas within the rights-of-way as specified herein. Existing trees and vegetation not required to be cleared shall be preserved to the maximum extent practicable and shall not be damaged. Clearing, unless otherwise specified, shall consist of the complete removal above the ground surface of all trees, saplings, stumps, down timber, snags, brush, vegetation, old piling, loose stone, abandoned structures, abandoned fencing, fencing, drift, trash, and similar debris.

3.2.2 Trees

Trees shall be felled in such a manner so as to avoid damage to trees to be left standing, to existing structures and installations, and to those under construction, and with due regard for the safety of employees and others.

3.2.3 Vegetation Removal

Vegetation to be removed shall consist of crops, grass, bushes and weeds. Close-growing grass and other vegetation shall be removed from levees to be degraded and from areas to receive semicompacted and compacted fill to provide a completely bare earth surface immediately prior to beginning excavation and foundation preparation. Removal of vegetation from the side of the existing levees shall be limited to 1,000 feet in advance of embankment placement. Acceptance of the vegetation removal operation shall precede the initiation of foundation preparation in the area from which vegetation has been removed. If the required 15 wide strips contiguous to new and existing levee and berm toes are covered by grass, vegetation removal as defined herein is not required. It is intended that the grass on these strips shall be preserved to the extent practicable, except as necessary for required clearing and grubbing of trees, saplings, stumps, etc.

3.2.4 Areas to be Cleared

3.2.4.1 General

The entire area to be occupied by the required levee embankment, berm embankment, and ramps, together with strips 5 feet wide contiguous to each of these areas, shall be cleared. An additional 10 feet wide strip adjacent to and beyond the 5 feet wide strips contiguous to the new levee embankment, berm embankment and ramps shall also be cleared, except that grass shall not be removed from this 10 feet wide strip to the extent practicable. ~~Clearing shall also be performed within strips 15 feet wide contiguous to the all existing riverside and landside levee and berm toes where no new embankment is required, except that grass shall not be removed from this 15 feet wide strip to the extent practicable.~~

3.2.4.2 Borrow Areas

Only those portions of borrow areas from which borrow material will actually be obtained under this contract shall be cleared, and this clearing shall be to the extent necessary to provide materials free from unsuitable matter as described in Section 31 24 00.00 09 EMBANKMENT, paragraph UNSUITABLE MATERIALS. Certain stumps and areas containing masses of organic matter or other unsuitable material may be left in place upon approval of the Contracting Officer.

3.2.4.3 Other Areas

Clearing of the area between the 15 feet strip contiguous to the levee embankment and berm embankment and the borrow area, and traverses left between borrow areas, shall be limited to the minimum required for construction operations.

3.3 GRUBBING

3.3.1 General

Grubbing shall consist of the removal of all stumps, roots, buried logs, old paving, old foundations, pipes, drains, and other unsuitable matter as described in Section 31 24 00.00 09 EMBANKMENT, paragraph UNSUITABLE MATERIALS.

3.3.2 Areas to be Grubbed

3.3.2.1 General

Grubbing shall be performed within the limits of the required levee embankment, berms, and ramps, together with strips 15 feet wide contiguous to each of these areas. ~~Grubbing shall also be performed within strips 15 feet wide contiguous to the all existing riverside and landside levee and berm toes where no new embankment is required.~~ All roots and other projections over 1-1/2 inches in diameter shall be removed to a depth of 3 feet below the natural surface of the ground or surface of existing embankments. The areas to be grubbed are those specific areas, within the limits specified herein, from which trees, stumps, down timber, snags, and other projections have been removed.

3.3.2.2 Ditches

All stumps and exposed roots and other obstructions shall be removed from

within the limits of all ditches to be constructed.

3.3.2.3 Berms

Areas which are to be occupied by berms shall shall be grubbed in accordance with paragraph AREAS TO BE GRUBBED, subparagraph GENERAL.

3.3.3 Borrow Areas

Only those portions of borrow areas from which borrow material will actually be obtained under this contract shall be grubbed, and this grubbing shall be to the extent necessary to provide materials free from unsuitable matter as described in Section 31 24 00.00 09 EMBANKMENT, paragraph UNSUITABLE MATERIALS.

3.3.4 Pipes and Drains

The Contractor shall inform the Contracting Officer of all pipes and drains not shown on the drawings which are encountered during grubbing. Such pipe and drains shall not be removed or disturbed until so directed by the Contracting Officer. Material excavated in the process of removing pipes and drains shall be disposed of as specified in Section 31 23 00.00 09 EXCAVATION, paragraph DISPOSITION OF MATERIALS.

3.3.5 Filling of Holes

All holes caused by clearing and grubbing operations and removal of pipes and drains, excluding holes in borrow areas, shall be backfilled with suitable material in 12 inch layers to the elevation of the adjacent ground surface, and each layer shall be compacted to a density at least equal to that of the adjoining undisturbed material.

3.4 DISPOSAL OF DEBRIS

3.4.1 General

The primary method of disposing of all debris resulting from clearing and grubbing operations shall be burning as specified in paragraph BURNING. The following additional methods will also be permitted: burying in the borrow area in accordance with paragraph BURYING, or removal from the site in accordance with paragraph REMOVAL FROM SITE OF WORK.

3.4.2 Burning

In accordance with the Contract Clause PERMITS AND RESPONSIBILITIES, the Contractor shall obtain any permit which may be required for burning. Subject to applicable Federal, State and local laws and burning restrictions, the Contractor may burn material within the contract area at any time within the contract period. The Contractor shall thoroughly burn clearing and grubbing debris and continue burning until as much debris as practicable is completely reduced to ashes. Burning operations shall be conducted so as to prevent damage to standing timber or other flammable growth. The Contractor shall be responsible for any damage to life and property resulting from fires that are started by his employees or as a result of his operations. The Contractor shall furnish adequate fire fighting equipment at the site of burning operations to properly equip his personnel for fighting fires. Fires shall be guarded at all times and

shall be under constant surveillance until they have been extinguished.

3.4.3 Burying

Upon approval, the Contractor will be allowed to bury debris that is unburnable and debris that has been thoroughly burned but cannot be further reduced to ashes. The Contracting Officer will determine which debris is unburnable and which debris cannot be further reduced to ashes. The area available for burial will be adjacent to the riverside limit of excavation within the riverside borrow areas. All material disposed of by burying shall be covered with a minimum of 24 inches of earth. No material shall be buried within 20 feet of any standing timber.

3.4.4 Removal from Site of Work

The Contractor may elect to remove all or part of the debris from the site of the work. Such disposal shall comply with all applicable Federal, State and local laws. The Contractor is precluded from retaining for his own use or disposal by sale or otherwise, any such materials of value. If debris from clearing operations is placed on adjacent property, the Contractor shall obtain, without cost to the Government, additional rights-of-way for such purposes in accordance with Section 01 00 00.00 09 GENERAL CONTRACT REQUIREMENTS, paragraph RIGHTS-OF-WAY. Such material shall be so placed as not to interfere with roads, drainage or other improvements and in such a manner as to eliminate the possibility of its entering into channels, ditches, or streams. The Contracting Officer reserves the right to approve or disapprove the use of Contractor-furnished disposal areas based on the location of the areas and a determination of the overall impact the proposed disposal areas will have on the environment or the integrity of the levee. Contractor-furnished disposal areas shall not be located in woodlands or wetlands. Disapproval by the Contracting Officer of Contractor-furnished disposal areas shall not form the basis of a claim against the Government.

-- End of Section --