

Continuation Sheet – Amendment “0005”

eProjects Work Order Number: 1737012
Construction Contract Number: N4008525R2639
Building: Buildings LP48 and LP48A
Project Title: **DESIGN-BID-BUILD P-222: MQ-25 AIRCRAFT
LAYDOWN FACILITIES, NAVAL STATION NORFOLK,
NORFOLK, VA**
Date: **19 March 2026**

DRAWINGS:

REVISE the following sections:

Replace the following Civil Drawing Sheets: (Vol 1) C-001, CS101, CG201, CU101, CU201; and (Vol 2) C-001

Replace the following Structural Drawing Sheets: (Vol 2) SF521, SF802, SF803, SF804, SF805, SF831, SF833, SF834, SF835, SF852.

Replace following Architectural Drawing Sheets: AE101A, AE101B, AE102A, AE102B, AE112B, and AE505

Replace the following Interior Drawing Sheets: (Vol 2) IN602

Replace the following Fire Protection Drawings Sheets: (Vol 1) FA001, FX002 and (Vol 2) FA001

Replace the following Mechanical Drawing Sheets: (Vol 2) M-601, M-602, M-802, M-806.

Replace the following Electrical Drawing Sheets: (Vol 2) EP131, EP601, EP606.

SPECIFICATIONS:

Revise the following sections:

Section 01 33 00 SUBMITTAL PROCEDURES

Replaced section attachment **SUBMITTAL REGISTER** in its entirety.

Section 01 91 00.15 BUILDING COMMISSIONING

REPLACED in its entirety with Section **01 91 00.15 22 TOTAL BUILDING COMMISSIONING**

Section 03 42 13.00 10 PLANT-PRECAST CONCRETE PRODUCTS FOR BELOW GRADE CONSTRUCTION

DELETED from project.

Section 04 20 00

Paragraph 3.3.5 deleted last sentence – “Dampproof cavity face of interior wythe in accordance with Section 07 11 13 BITUMINOUS DAMPPROOFING.”

Section 07 11 13 BITUMINOUS DAMPPROOFING

DELETED from project.

Section 07 21 13 BOARD AND BLOCK INSULATION

ADDED Concrete Faced Insulated Perimeter Wall Panels to paragraph 1.2 SUBMITTALS in SD-03

ADDED new paragraph 2.6 CONCRETE FACED INSULATED PERIMETER WALL PANELS and sub-paragraph 2.6.1 Extruded Polystyrene Board.

Section 07 60 00 FLASHING AND SHEET METAL

ADDED Bellow Type Building Expansion Joint Cover to paragraph 1.3 SUBMITTALS in SD-02 and SD-03

ADDED new paragraph 2.4 BELLOW TYPE BUILDING EXPANSION JOINT COVER.

Section 09 62 38 STATIC-CONTROL FLOORING

DELETED from project.

Section 09 29 00 GYPSUM BOARD

EDITED paragraph 3.4 FINISHING OF GYPSUM BOARD – deleted 6th sentence “Unless otherwise specified, finish all gypsum board walls, partitions and ceilings to Level 5 in accordance with GA 214.”

DELETED sub-paragraph 3.4.1 Uniform Surface in its entirety.

EDITED first sentence in paragraph 3.10 SOUND RATED ASSEMBLY FIELD TESTING to be: “Provide third party testing of sound rated assemblies of 50 and above tested in accordance with ASTM E336.”

Section 12 22 00 CURTAINS AND DRAPES

DELETED from project.

Section 13 34 20 PREFABRICATED STEEL BUILDINGS

REPLACED in its entirety.

Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE

REPLACED in its entirety.

Section 32 13 13.06 PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES

ADDED new paragraph 2.3.4.3 Other Types of Finishing Equipment. Making original 2.3.4.3 now 2.3.4.4 Work Bridge

REPORTS:

ADD the following report to accompany this Amendment.

Report of Subsurface Exploration and Geotechnical Engineering Services

REVISE the following reports:

HAZMAT Report: Delete reference to Table 1A-ACM Estimated Quantities.

ATTACHMENTS:

Attachment H, Price Schedule:

ADD the following Price Schedule to accompany this Amendment. Replace the previous Price Schedule in its entirety.

P222 – Crane Data Sheets added.

--End of Amendment--