

**PERFORMANCE WORK STATEMENT (PWS)**  
**Full Preventive Maintenance of Fire Alarm, Evacuation, Sprinkler, and**  
**Fire Suppression Systems within USAG Wiesbaden**  
*02/06/2026*

**Part 1**  
**General Information**

**1. General:** This is a non-personal service(s) contract under which the personnel rendering the service(s) are not subject, either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees.

**1.1 Description of Services/Introduction:** This is a non-personal service(s) PWS to provide maintenance, inspection, programming and repair of the fire alarm systems (including the Fire Alarm Dispatch Center and Fire Department full operating and integrated systems), evacuation systems, sprinklers, and fire suppression systems within United States Army Garrison (USAG) Wiesbaden. The contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform maintenance, programming, inspections, and repair of fire alarm systems, evacuation systems, sprinklers, and fire suppression systems within USAG Wiesbaden as defined in this PWS. The contractor shall perform to the minimum standards set forth in the PWS and contract.

**1.2 Background:** USAG Wiesbaden must ensure that all installed fire alarm (including the Fire Dispatch Center and Fire Department full operating and integrated systems), evacuation, sprinkler, and fire suppression systems listed in the attached inventory (Attachment 1-3, Inventory Price book), are maintained, programmed and repaired in accordance with (IAW) established life safety standards as specified herein.

**1.3 Scope:** The contractor shall provide maintenance, programming, inspections, and repair of the fire alarm, evacuation, sprinkler, and fire suppression systems listed on the attached inventory (Attachment 1-3, Inventory Price book). The Government shall not exercise any supervision or control over the contract service providers performing the services herein. Such contract service providers shall be accountable solely to the Contractor who, in turn, is responsible to the Government.

**1.4 Objectives:** The Contractor shall perform all related administrative actions required to provide services including material requisitioning, quality control (QC), attend meetings, and prepare correspondence. The Contractor shall maintain accurate and complete records, files, and have access to libraries of documents to include all U.S., German, and local regulations, standards, provisions, codes, laws, technical manuals, and manufacturers' instructions and recommendations that are necessary and related to the functions being performed. The

Contractor shall compile historical data and prepare required reports. The required services include the performance of programming, repairs, replacements and maintenance on building fire alarm and evacuation systems, sprinkler systems, fire suppression systems and the complete integrated fire station main dispatch and connected subsystems. On-call repairs are required, as needed, for the equipment listed in Attachments 1-3.

## **1.5 General Information:**

**1.5.1 Quality Control Plan (QCP):** The Contractor shall develop and maintain a QCP to ensure services are performed in accordance with this PWS. The Contractor shall develop and implement procedures to identify, prevent, and ensure non-recurrence of defective services. The Contractor's QCP is the means by which it assures that the work provided complies with the requirements of the contract. The Contractor's proposed QCP shall be submitted to the Contracting Officer's Representative (COR) for review within 10 work days after date of contract award (Deliverable #A.001). The COR will review and notify the Contractor in writing of acceptance of the plan or return their comments to the Contractor within 10 days. If the Government has provided comments, the Contractor shall address all comments and submit a final QCP within three (3) days. After receipt of the final QCP, the Contractor may receive the COR's acceptance in writing. Any proposed changes to the accepted QCP shall be resubmitted for acceptance by the COR no later than 30 days prior to the anticipated change and before implementation by the Contractor. The timeline noted above will apply for review and acceptance for proposed changes. At a minimum, the QCP must include the following to be acceptable:

(a) A chart showing the organizational structure and lines of authority, the names, qualifications, duties, responsibilities, and classification of each member of the Contractor's Quality Control Team;

(b) How the Contractor will monitor work to ensure performance complies with all deliverables (etc. timelines, deadlines, and goals);

(c) How the Contractor will monitor work to ensure performance complies with all specifications and requirements of the contract, including the contract's clauses;

(d) How the Contractor will monitor and ensure staff qualifications remain current and valid including Department of Defense (DoD) Contractor Personnel Office (DOCPER) processes/approvals throughout contract performance; **N/A**

(e) How the Contractor will ensure all keys issued will remain controlled items (Paragraph 1.7 Key Control);

(f) How the Contractor will inventory and track maintenance of any Government Provided Equipment / Materials;

(g) How the Contractor will identify, investigate, and correct any non-conforming performance and prevent similar deficiencies in the future; and

(h) How the Contractor will file and save all Quality Control related documents for the life of the contract plus 5 years.

**1.5.1** The Contractor shall inform the COR of issues or potential issues that might affect the performance within 24 clock hours of identifying those issues. Verbal reports shall be followed up by written reports within 5 workdays (Deliverable #A.001).

**1.5.2 Quality Assurance:** The Government will evaluate the Contractor's performance under this contract in accordance with the Quality Assurance Surveillance Plan (QASP). This plan is primarily focused on what the Government must do to ensure that the Contractor has performed in accordance with the performance standards. It defines how the performance standards will be applied, the frequency of surveillance, and the acceptable quality levels (performance thresholds).

**1.5.3 Recognized Holidays:** The following provides information on recognized holidays for the purpose of the PWS. If submittal of any documentation (e.g. deliverables, submittals, etc.) deadlines fall on a holiday, the closest work day prior to the holiday will apply as the deadline for submittal.

**1.5.3.1 U.S. Holidays:** Work shall not be performed on U.S. federally recognized holidays occurring during the normal workweek unless otherwise directed by the Contracting Officer. When a U.S. holiday occurs on a Saturday or a Sunday, the holiday is observed on the preceding Friday or following Monday, respectively.

New Year's Day January 1<sup>st</sup>  
Presidents Day 3<sup>rd</sup> Monday in February  
Juneteenth June 19<sup>th</sup>  
Labor Day 1<sup>st</sup> Monday in September  
Veteran's Day November 11<sup>th</sup>  
Christmas Day December 25<sup>th</sup>

M. L. King Memorial Day 3<sup>rd</sup> Monday in Jan  
Memorial Day last Monday in May  
Independence Day July 4<sup>th</sup>  
Columbus Day 2<sup>nd</sup> Monday in October  
Thanksgiving Day 4<sup>th</sup> Thursday in November

**1.5.3.2 Host Nation Holidays:** Routine work shall not be performed on local Host Nation holidays occurring during the normal workweek unless otherwise directed by the Contracting Officer.

**The German national and local holidays are:**

New Year's Day  
Good Friday  
Easter Monday  
Labor Day  
Ascension Day  
Whit Monday

01 January  
varies yearly  
varies yearly  
01 May  
varies yearly  
varies yearly

|                     |               |
|---------------------|---------------|
| Corpus Christi      | varies yearly |
| Day of German Unity | 03 October    |
| 1st Christmas Day   | 25 December   |
| 2nd Christmas Day   | 26 December   |

**1.5.4 Operating Hours:** The Government facility office hours, facility operating hours, and the Contractor support hour requirements are 0715 to 1600, Monday through Friday except on U.S. or German holidays specified above or when the Government facility is closed due to local or national emergencies, administrative closings, or similar Government directed facility closings. The Contractor will not be reimbursed when the Government facility is closed for the above reasons. The Contractor shall not normally provide services on U.S. or German holidays. However, the Contractor may be required to provide On- Demand services on holidays, as coordinated with the COR.

**1.5.4.1 Government Facility Office Hours** The Government facility office hours specified in 1.5.4 above..

**1.5.4.2 Government Facility Operating Hours:** The Contractor shall conduct business during the hours specified in 1.5.4 above.

**1.5.4.3 Contractor Support Hours:** The Contractor shall provide regular support during the hours specified in 1.5.4 above and 24/7 response for on-demand services. The Contractor shall at all times maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when the Government facility is not closed for the above reasons. When hiring personnel, the Contractor shall keep in mind that the stability and continuity of the workforce are essential.

**1.5.4.3.1 Contractor Work Plan:** RESERVED

**1.5.5 Training Holidays:** USAREUR has historically granted military personnel training holidays as compensation for time that they spent in field training. These are typically combined with regular holiday leave schedules (for example, Christmas half days or day on day off schedules). Training holidays may affect access to military operated facilities. If scheduled work or access to facilities is required, coordination with occupants will be necessary or the work in affected facilities shall be rescheduled after the training holiday. However, announced training holidays or exodus of military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas. The Contractor shall take full advantage of such opportunities by planning maintenance or actions that are better accomplished when such areas are vacant.

**1.5.6 Place of Performance:** The services under the contract shall be performed at various locations and buildings within USAG Wiesbaden.

**1.6 Security Requirements:** The following information is provided on security related matters.

**1.6.1 Security Program:** RESERVED

**1.6.2 Personnel Security Clearance Requirements:** RESERVED

**1.6.3 Installation Access:** Access to U.S. installations and controlled areas is limited to personnel who meet security criteria and are authorized by Host Nation law to work in that country. Failure to submit required information/data and obtain required documentation or clearances in accordance with Army in Europe (AE) Regulation 190-16 (AE Reg 190-16) Installation Access Control or (AE) Regulation 604-1 for Germany specific contracts, will be grounds for denying access to U.S. installations and controlled areas. The Contractor shall ensure that any subcontractors used in performance of the contract complies with these requirements and that all employees, of both the Contractor and any subcontractor utilized by the Contractor, are made aware of and comply with these requirements. Should anything in this paragraph conflict with AE Reg 190-16 or (AE) Regulation 604-1, the regulation takes precedent.

The Contractor shall be aware of and comply with the requirements associated with Installation Access Control. The Government is not liable for any costs associated with performance delays due solely to a firm's failure to comply with Installation Access Control System (IACS) processing requirements.

The Contractor shall return installation passes to the issuing IACS office when the contract is completed or when a Contractor employee no longer requires access.

AE Reg 190-16 (and AE 190-16-G German translation) can be found on the following website:  
<https://www.aepubs.eur.army.mil/AE-Regulations/>

Below is the responsible Organizational Sponsor & Installation Access Control Office for the contract:

Organizational Sponsor: USAG Wiesbaden, Clay Kaserne  
Location: Clay Kaserne Building No: 1557  
DSN Phone No: 548-4081 Commercial Phone No: 0611-143 548 4081

Installation Access Control Office:  
Location: Clay Kaserne Building No: 1004  
DSN Phone No: 548-47080/1/2/3 Commercial Phone No: 0611-143 548 7080/1/2/3

**1.6.3.1 Installation Pass Log:** In addition, the Contractor shall provide the Contracting Officer, via the COR, an Initial Installation Pass Log within five (5) calendar days after contract award (Deliverable #A.002). The log shall at a minimum contain the following information Last name, First name, nationality, date of birth, ID card number (Personalausweisnummer), Vehicle type and plate number. The log shall be updated as employees are added or removed. The Updated Installation Pass Log shall be current and available at any time upon request by the Government and submitted to the COR within five (5) days after any changes to the log.

**1.6.3.2 Individual Termination or Expiration of Employment:** The Contractor shall collect the installation access passes the same day employment of an individual has expired or has been terminated and shall return them to the issuing office within five (5) working days. (Deliverable #A.002).

**1.6.3.3 Contract Termination or Cancellation:** Upon termination or cancellation of the contract, the Contractor shall collect all outstanding installation access passes and return them to the issuing office within five (5) working days. (Deliverable #A.002).

**1.6.3.4 Common Access Cards (CAC) and CAC Log:** RESERVED

**1.6.4 Background Checks:** Army in Europe (AE) Regulation 604-1 provides guidance pertaining to background checks for U.S. and Host Nation Contractors. The Contractor shall provide all information required for background checks to meet installation access requirements to be accomplished by the installation Provost Marshal Office, Director of Emergency Services, or Security Office, and residence permits for local national installation passes and access rosters. The Contractor workforce shall comply with all personal identity verification requirements as directed by DoD, HQDA, and local policy. The Contractor may have to complete additional security training to comply with the security standards of the contract. In addition to the changes otherwise authorized by the changes clause of the contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in Contractor security matters or processes.

**1.6.4.1 U.S. Citizen** RESERVED.

**1.6.4.2 Local Nationals and Third Country Nationals:** Local national and third country national Contractors are subject to background checks as determined by the Requiring Activity Manager. Contractors employing local national and third country nationals shall submit to the COR a police good conduct certificate (Polizeiliches Fuehrungszeugnis), issued within the previous four months, no later than five (5) days after contract award (Deliverable #A.003). Forwarding correspondence from the Contractors shall identify the associated contract number. The Requiring Activity Manager will determine the favorability of the police good conduct certificate (Polizeiliches Fuehrungszeugnis) and notify the Contractor. The Contractor shall forward a copy of unfavorable police good conduct certificate (Polizeiliches Fuehrungszeugnis) to the Contracting Officer via the COR and the Requiring Activity Manager within five (5) days of receipt, identifying such with the appropriate contract number. (Deliverable #A.003)

**1.6.5 Physical Security:** The Contractor shall safeguard all Government equipment, information, and property provided for Contractor use. At the close of each work period, Government facilities, equipment, and materials shall be secured IAW the Army Physical Security Program (AR 190-13).

**1.6.6 Operations Security (OPSEC) Requirements:** Contractor personnel shall adhere to facility security policies and restrictions. The Contractor shall immediately report suspicious activities to security personnel.

**1.7 Key Control:** The Contractor shall establish and implement methods of making sure all keys issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards. No keys issued to the Contractor by the Government shall be duplicated. The Contractor shall develop procedures covering key control that shall be included in the Contractor's Security Plan and the Quality Control Plan (Deliverable #A.001). Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas. The Contractor shall immediately report any incidents of lost or duplicate keys to the Contracting Officer. In the event keys, other than master keys, are lost or duplicated, the Contractor shall, upon direction of the Contracting Officer, re-key or replace the affected lock or locks; however, the Government, at its option, may replace the affected lock or locks or perform re-keying. When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from payment due to the Contractor. In the event a master key is lost or duplicated, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the payment due to the Contractor. The Contractor shall prohibit the use of Government issued keys by any persons other than the Contractor's employees. The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of persons other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the Contracting Officer. The Contractor shall establish and implement methods of ensuring that all lock combinations are not revealed to unauthorized persons. The Contractor shall ensure that lock combinations are changed when personnel having access to the combinations no longer have a need to know such combinations. These procedures shall be included in the Quality Control Plan.

**1.8 Post Award Conference/Periodic Progress Meetings:** The Contractor shall attend any post award conference convened by the contracting activity or contract administration office in accordance with FAR Subpart 42.5. The Contracting Officer, COR, and other Government personnel, as appropriate, may meet periodically with the Contractor to review the Contractor's performance. At these meetings the Contracting Officer will apprise the Contractor of how the Government views the Contractor's performance and the Contractor shall apprise the Government of problems, if any, being experienced. Appropriate action shall be taken to resolve outstanding issues. These meetings shall be at no additional cost to the Government.

**1.8.1** The Contractor shall attend, participate in, and furnish input to scheduled and unscheduled meetings, conferences, and briefings that relate to the functions and services herein as required by the Government to provide effective communication and impart necessary information. The Contract Manager or designated representative shall attend meetings as requested by the Government. Meeting attendees shall at times include Contractor managerial, supervisory, and other personnel knowledgeable of the subject matter. Meetings may start or end outside of regular duty hours.

**1.9 Contracting Officer's Representative (COR):** Refer to Part 2 of this PWS for the definition of a COR. As determined by the Contracting Officer, a COR will be appointed and identified by letter of designation, a copy of which will be provided to the Contractor by the Contracting Officer. The designation letter states the responsibilities and limitations of the COR, especially with regard to changes in cost or price, estimates, or changes in delivery dates. The COR is not authorized to change any of the terms and conditions of the resulting order. The COR monitors all technical aspects of the contract and assists in contract administration. The COR is not authorized to obligate the Government. If the work is not written in the contract, the COR is not authorized to request new work. The COR is authorized to perform the following functions: assure that the Contractor performs the technical requirements of the contract, perform inspections necessary in connection with contract performance, maintain written and oral communications with the Contractor concerning technical aspects of the contract, issue written interpretations of technical requirements, including Government drawings, designs, specifications, monitor Contractor's performance and notifies both the Contracting Officer and Contractor of any deficiencies, coordinate availability of Government property, and coordinate site entry of Contractor personnel.

**1.10 Key Personnel:** The following personnel are considered key personnel by the Government:

The Contractor shall provide a Program/Contract Manager who shall be responsible for the performance of the work. The name of this person and an Alternate Program/Contract Manager, who shall act for the Contractor when the Program/Contract Manager is absent, along with a Curriculum Vitae (CV) for each of these individuals, shall be provided in writing to the Contracting Officer no later than during the post-award meeting (Deliverable #A.004). The Contract Manager and Alternate Contract Manager shall have full authority to act for the Contractor on all contract matters relating to daily operation of the contract. The Contract Manager or Alternate Contract Manager shall be available between 0730 - 1600 on working days. The Contractor shall be available 24 hours by phone, Monday thru Sunday, on Federal holidays and local holidays. Qualifications for all key personnel are listed below:

- a. **Special Qualifications:** The Contractor shall be certified in accordance with the Verband der Schadenversicherer (VDS) and shall have a current and valid VDS Certificate in accordance with DIN EN 14675 and related additional certification in accordance with the related regulation for sprinkler, smoke exhaust and fire extinguishing systems (VdS anerkannte Errichterfirmen für Brandmelde-, Sprinkler, Feuerlöschanlagen und Rauch- und Wärmeabzugsanlagen). The Contractor shall be ISO9001 certified and provide a copy of the certification annually (Deliverable #A.005). The Contractor shall ensure that all personnel performing required services are professionally certified as required by regulation.

The Contractor shall provide current training certificates for all technicians ("befähigte Person mit Sachkundnachweis") responsible for maintaining Fire Detection Systems described in the PWS within five (5) calendar days after award (Deliverable #A.006). If any of the technicians change during contract performance, the Contractor shall notify the COR immediately and provide a substitute with the same qualifications within five (5) calendar days of the change. The Contractor shall provide the name, title, training

status and telephone number of the personnel providing services on the contract to the COR within five (5) calendar days after award (Deliverable #A.006). This list shall be updated and submitted to the COR via email within 24 hours of changes that occur throughout the duration of the contract. Work performed by personnel not on this list will not be accepted by the COR and, as such, will not be compensated by the Government. The contractor shall be certified by the Main System builder, distributor or manufacturer, and shall provide VdS Certification for Fire Alarm Systems, in accordance to DIN 14675 and related additional certification in accordance to the regulation for Sprinkler Systems, Evacuation Systems and Suppression Systems (VdS-anerkannter Errichter fuer Brandmeldeanlagen, Sprinkler Anlagen, Rauch und Waermeabzugsanlagen) to the COR five (5) days after award (Deliverable #A.006). The Contractor shall also provide certification from TUEV for specialized speaking alert systems (Fachfirma fuer Sprachalarmanlagen) to the COR within five (5) days after award (Deliverable #A.006). The Contractor shall have a master craftsman (HWK) certificate for the fire alarm, sprinkler extinguishing systems or be registered in the Chamber of Commerce and Industry (IHK) accordingly. The contractor shall provide current DIN 14675 certification for fire alarm systems and related additional certification in accordance with the regulation for sprinkler, smoke exhaust and fire extinguishing systems" (VdS anerkannten Errichterfirmen fuer Brandmelde-, Sprinkler, Feuerlöschanlagen und Rauch -und Waermeabzugsanlagen) five (5) days after contract award to the COR (Deliverable #A.006).

b. Master Electrician:

The Contractor shall provide a certificate for at least one (1) employee qualified as a Master (Meister) in the category of "Master Electrician (Elektrotechniker-Meister)" and a specialized qualification for fire protection systems to the COR five (5) days after contract award (Deliverable #A.007). This person shall be responsible for all electrical work under the contract for the entire performance period IAW the PWS. If the Master Electrician changes during contract performance, the Contractor shall notify the COR immediately and provide a substitute with the same qualifications within two (2) calendar days prior to the change.

c. Technicians:

The Contractor shall provide only qualified personnel ("befaehigte Person mit Sachkundnachweis") for all specialized work required for the equipment listed in the attached inventory list (Attachment 1-3, Inventory Pricebook). At least one (1) employee for each single system shall be qualified for smoke protection doors, fire flaps, fire shutters and kitchen installations (Ansul and Flamefast), and be specialized for speaking alert systems. This person shall be responsible for all specialized work at the single system for the entire performance period IAW the PWS. If the personnel changes during contract performance, the contractor shall notify the COR immediately and provide a substitute with the same qualifications within (2) calendar days prior to the change.

- d. English language: All Contractor personnel performing technical services under the contract shall read, write and speak English to communicate with Government personnel, accurately record data, and perform required work suppliers and as specified in this PWS.

**1.11 Identification of Contractor Employees:** All Contractor personnel attending meetings, answering Government telephones, and working in other situations where their Contractor status is not obvious to third parties must identify themselves, to include proper marking of signature blocks in correspondence, to avoid creating an impression in the minds of members of the public that they are Government officials. The Contractor shall ensure that all documents or reports, produced by Contractors are suitably marked as Contractor products or that Contractor participation is appropriately disclosed.

**1.12.2** Contractor personnel shall be easily identifiable through the display of badges IAW Contractor Identification (AE Reg. 27-715). (For services at Child, Youth, and School Services where children are present, recommend personnel wear identification when children are present.) The Contractor (to include subcontractors) shall provide each of their employees an easily readable identification badge. The badge must include the employee's name, the Contractor's company name, the functional area of assignment, and a recent color photograph of the employee. The Contractor shall collect all ID Badges upon completion of the contract or termination of employee. A listing of issued ID cards shall be furnished to the COR prior to the contract performance date and updated as needed to reflect Contractor personnel changes (Deliverable #A.008).

**1.13 Contractor Travel:** RESERVED

**1.14 Other Direct Costs (ODCs):** RESERVED

**1.15 Data Rights:** The Government has unlimited rights to all documents and materials produced under this contract. All documents and materials, to include the source codes of software, produced under this contract shall be Government owned and are the property of the Government with all rights and privileges of ownership and copyright belonging exclusively to the Government. These documents and materials may not be used or sold by the Contractor without written permission from the Contracting Officer. All materials supplied to the Government shall be the sole property of the Government and may not be used for any other purpose. This right does not abrogate any other Government rights.

**1.16 Non-Disclosure Requirements:** Performance under this contract may require the Contractor to access data and information proprietary to a Government agency, another Government Contractor, or of such nature that its dissemination or use other than as specified in this work statement would be adverse to the interests of the Government or others. The Contractor and Contractor personnel, shall not divulge or release data or information developed, or obtained under performance of this PWS, except to authorized Government personnel or upon written approval of the Contracting Officer. The Contractor shall not use,

disclose, or reproduce proprietary data, which bears a restrictive legend, other than as specified in this PWS. All documentation showing individual names or other personal information shall be controlled and protected under the provisions of the Privacy Act of 1974, Public Law 93-579, 5 United States Code (U.S.C.) Section 552a.

**1.17 Protection of Government and Contract Information:** Per Public Use Notice of Limitations stated by Defense imagery Management operations Center and contained at [www.dimoc.mil/resources/limitations/](http://www.dimoc.mil/resources/limitations/), the Contractor shall not cite any information (e.g., contract information, pictures, locations, etc.) obtained through this contract on any hard copy or digital marketing tools to include its company website.

**1.18 Non-Disclosure Statements:** RESERVED

**1.19 Organizational Conflict of Interest (OCI):** RESERVED

**1.20 Phase In /Phase Out Period:** RESERVED

**1.21 Safety:** The following provides information pertaining to Safety and Accident Prevention:

**1.21.1 Host Nation Safety Laws and Regulations:** The Contractor shall comply with FAR 52.236-13, Accident Prevention (November 1991), the references contained therein (e.g. *U.S. Army Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1)*), and applicable Host Nation Safety Laws and Regulations.

The requirements under FAR 52.236-13 and specifically of the EM 385-1-1 include, but are not limited to the following:

(a) Before initiation of work at the job site, an Accident Prevention Plan, written by the Contractor for the specific work and hazards of the contract and implementing in detail the pertinent requirements of EM 385-1-1; will be reviewed for acceptance by designated Government personnel (Deliverable #A.009). Specific requirements for development of the Accident Prevention Plan are found in 01.A and Appendix A of EM 385-1-1. EM 385-1-1 is available online at [www.usace.army.mil](http://www.usace.army.mil).

(b) Before beginning each activity involving a type of work presenting hazards not experienced in previous project operations or where a new work crew or subcontractor is to perform work, activity hazard analysis (AHA) shall be prepared by the Contractor performing the work activity (See paragraph 01.a.09 of EM 385-1-1);

(c) The Contractor shall require subcontractors to submit their plan of operations showing methods they propose to use in accomplishing major phases of work;

(d) The Contractor shall discuss the plans in conferences convened by the Contracting Officer prior to starting work on each major phase of operation. Plans shall include all pertinent information such as layout of haul roads, access roads, storage areas, electrical distribution

lines, methods of providing minimum exposure to overhead loads, and methods of access to work areas. The plan for accomplishing the initial work phase shall be submitted within fifteen (15) calendar days after award of the contract. Plans for subsequent major phases of work shall be submitted no later than fifteen (15) calendar days prior to initiation of work on each major phase; and

(e) In all areas where construction, demolition, alteration, building, or similar related activities take place, the Contractor shall have the following minimum personal protective clothing and equipment requirements in place for any person working on or visiting the site:

- (i) Short sleeve shirt;
- (ii) Long trousers;
- (iii) Steel-toed safety boots; and
- (iv) Hard hat.

**1.21.1.1** In addition to other requirements for accident prevention specified in the contract, the Contractor shall comply with all Federal and State requirements governing safety and health protection on construction sites and other applicable occupational safety codes. In particular, within the requirements of the German Safety and Health Protection Regulation for Construction Sites, Baustellenverordnung (BaustellV) (current version in effect), the Contractor shall coordinate all work at the site, including development of plans and providing advance notices.

The Contractor shall indicate its plan for compliance considering conditions of the work described by the design, technical proposal, operational activities of the Government or others in the area of the work, identification of the coordinator, and implementation of all other accident prevention provisions of the contract. For the compliance with host nation laws and regulations, the Contractor shall comply with the non-exclusive list of duties described in this paragraph. If the Contractor determines that additional activities are required to fully comply, the Contractor shall ensure that compliance with the laws is complete. The duties include:

(a) Conditions of construction and operational activities to be considered include but are not limited to:

(i) For all construction activities meeting the following criteria: the work is scheduled to last longer than 30 working days and more than 20 workers are occupied simultaneously, or the volume of work is scheduled to exceed 500 person days, or the work presents particular tasks, e.g. excavations deeper than 5 meters, falls from a height of greater than 7 meters, exposures to hazardous chemical or biological substances, work at less than 5 meters from high voltage lines, underground earth works or tunnels, danger of drowning, diving, use of compressed air, work with ionizing radiation, explosives, or work involving assembly or dismantling of heavy prefabricated components (10 tons or greater).

(b) If the Contractor determines that the BaustellV, dated 10 June 1998, applies, the Contractor shall prepare a Safety and Health Protection Plan (SIGE) as required under that regulation. The SIGE shall be submitted two weeks prior to mobilization. In addition, the Contractor shall appoint a qualified Safety Coordinator who will ensure that safety measures are

implemented during construction. The Safety Coordinator must meet minimum training and experience requirements required under Host Nation laws.

(c) The SIGE will be written in a comprehensive form and explained in language the workers understand and shall contain the following minimum information:

(i) Maintenance of tools and equipment.

(ii) Provisions for the storage and disposal of materials and waste, particular hazardous materials and substances.

(iii) Modifying performance periods for such work, taking into consideration the site conditions.

(iv) Organizing cooperation between different employers and Contractors without employees.

(v) Interaction between work at the site and other operational activities in the area, on which or near which the first identified work will be performed, and taking into consideration the instructions and advice of the coordinator as well as safety and health plans.

**1.21.1.2** The Contractor shall complete and provide safety notifications required by host nation authorities and will provide documented proof to the Contracting Officer via the COR, no later than five (5) days (Deliverable #A.010) that such notifications were made.

**1.22 Environmental Compliance:** The following provides information on Environmental Compliance.

**1.22.1 Environmental Compliance Plan and Program:**

The Contractor shall ensure that all of its operations and activities conform to the USAG Wiesbaden's environmental policy requirements. The Contractor shall ensure that all contract personnel have received appropriate levels of training in the handling, use, storage, and disposal of hazardous material. In addition, the Contractor shall ensure that all Contractor controlled activities on USAG Wiesbaden installations are conducted in accordance with the USAG Wiesbaden Spill Prevention and Response Plan, Solid Waste Policy, Final Governing Standards-Germany, and applicable German environmental laws/standards.

The Contractor shall, prior to mobilization, inform the Contracting Officer (KO)/Contracting Officer Representative (COR) of the types and amount of hazardous materials needed to be brought onto the Garrison in order to fulfill their contractual requirements. Contractor shall also provide the Safety Data Sheets, storage requirements and proposed storage locations for the hazardous material. The KO/COR shall provide a copy of this information to the Garrison Fire Department and the Environmental Division.

The Contractor shall remove all hazardous materials and dispose of all hazardous waste (HW) generated in accordance with Final Governing Standards Germany and applicable German environmental laws/standards. A copy of the HW disposal documents must be forwarded to the HW program manager at the Department of Public Works (DPW) Environmental Division.

The Contractor shall clean up at its own expense any contamination, including soil and ground water contamination caused by hazardous materials/substances brought onto the garrison, or

by his activities. The Contractor must immediately report any hazardous substance spills to the Garrison Fire Department at CIV 0611-705-117.

The Contractor shall contact the COR or the USAG Wiesbaden Directorate of Public Works-Environmental Division (DPW-ED), DSN 548-4092, CIV 0611143-548-4092, Bldg. 1059, Clay Kaserne for a copy of the Garrison Environmental Policy, Spill Prevention and Response Red Plan, Garrison Solid Waste Policy and German Final Governing Standards.

Current Environmental Policy (Garrison policy Number 22) will be provided by the COR after award.

Current Prohibited Refuse Disposal Practices Policy (Garrison policy Number 27) will be provided by the COR after award.

**1.23 Required Training:** The following provides information on training requirements.

**1.23.1 Anti-Terrorism (AT) Level I Training:** All Contractor employees, including subcontractor employees, who are employed under the contract, shall complete AT Level I Training within 30 calendar days (Deliverable #A.008) after contract start date or effective date of incorporation of this requirement into the contract, whichever applies, or 30 calendar days after employment of new personnel. Contractor personnel travelling overseas shall complete area of responsibility (AOR) specific AT awareness training for U.S. based Contractor employees and associated subcontractor employees. The Contractor shall submit certificates of completion (Deliverable #A.011) for each affected Contractor employee and subcontractor employee to the COR (or to the Contracting Officer, if a COR is not assigned) within (Deliverable #A.011) after completion of this training by all employees and subcontractor personnel. AT Level I awareness training is available at <https://jkodirect.jten.mil>. Contractor personnel shall complete refresher training (Deliverable #A.011) every twelve (12) months except AOR specific AT Level I training which shall be completed as required by local AT policies

If training cannot be conducted on the website, the Contractor shall coordinate with the COR who will contact the local AT Officer at their assigned location for classroom training. Contractor personnel completing training in the classroom will receive a certificate or the training attendance roster signed by the AT Officer. Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.011).

**1.23.2 OPSEC Training:** All Contractor employees, including subcontractors, shall complete Level I OPSEC training within 30 calendar days of employment under the contract (Deliverable #A.012). Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.012). OPSEC Level I training is available at <http://www.cdse.edu/catalog/elearning/GS130.html>. Contractor personnel must complete refresher training every 12 months (Deliverable #A.012). Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.012).

If training cannot be conducted on the website, the Contractor shall coordinate with the COR, who will contact the local OPSEC Officer at their assigned location for classroom training. Contractor personnel completing training in the classroom will receive a certificate or the training attendance roster signed by the OPSEC Officer. Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.012).

**1.23.3 iWATCH Training:** The Contractor and all associated subcontractors shall brief all employees on the local iWATCH program (training standards provided by the requiring activity ATO). This locally developed training will be used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the COR. This training shall be completed within 30 calendar days after the contract is awarded and within 30 calendar days after new employees commence contract performance, with the results reported to the COR within 30 calendar days after the contract is awarded and within 30 calendar days after new employees commence contract performance (Deliverable #A.013). Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.013). Training slides can be found on the Army OneSource website: <http://www.myarmyonesource.com/familyprogramsandservices/iwatchprogram/default.aspx>.

#### **1.23.4 Information Assurance (IA) Training**

**1.23.4.1** All Contractor employees, including subcontractors, requiring access to Government information systems shall complete the Department of Defense (DoD) IA Cyber Awareness Training within 30 calendar days (Deliverable #A.014) after contract start date or effective date of incorporation of this requirement into the contract, whichever applies, or 30 calendar days after employment of new personnel. Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.014).

**1.23.4.2** All Contractor employees, including subcontractors, working information technology (IT)/IA functions shall comply with DoD and Army training requirements per Information Assurance Training Certification and Workforce Management DoD Directive (DoDD) 8570.01, Information Assurance Workforce Improvement Program DoD 8570.01-M, and Information Assurance AR 25-2 within thirty (30) calendar days of employment. Training is available at <https://ia.signal.army.mil/DoDIAA/default.asp>.

**1.23.4.3** All Contractor employees, including subcontractors, performing services under this contract with access to a Government information system must be registered in the Army Training Certification Tracking System (ATCTS), the web address is [p](#) (requires CAC to access). Verification of registration shall be provided to the COR within 30 calendar days after registration. (Deliverable #A.014). Contractor personnel must complete refresher training every twelve (12) months (Deliverable #A.014). Verification of the training shall be provided to the COR within 30 calendar days after completion of the training (Deliverable #A.014).

#### **1.23.5 Personally Identifiable Information (PII): RESERVED**

## **1.24 Authorization to Perform Services in Germany**

**1.24.1** Contractors performing services in the Federal Republic of Germany (FRG) shall comply with German law. The Contractor shall determine whether performance requires registration with German authorities or authorization to do business in Germany and, if so, shall comply with all requirements. Whether or not registration or authorization to do business is required, the Contractor shall determine what documents or authorization its employees and any subcontractor employees must possess to work in Germany. The Contractor shall ensure affirmatively that its employees and subcontractor employees possess such documents or authorizations.

**1.24.2** Contractor employees who: (a) are not nationals of Germany or other European Union countries; (b) are not members of the force, the civilian component or their dependents; or c) do not have assimilated status under Articles 71, 72, or 73 of the Supplementary Agreement to the North Atlantic Treaty Organisation Status of Forces Agreement shall possess work and residence permits.

**1.24.3** By acceptance of and performance under this contract, the Contractor affirms that it has complied with the requirements above. Compliance with this requirement and German law is a material contract requirement. Noncompliance by the Contractor or subcontractor at any tier shall be grounds for issuing a negative past performance evaluation and terminating this contract for default.

**1.25 Notice to Proceed:** RESERVED

**1.26 Electromagnetic Compatibility Directive:** RESERVED

**1.27 Government Property and Services:** RESERVED

**1.28 Conventional Forces Europe (CFE) Treaty Verification Inspection:** RESERVED

## PART 2 DEFINITIONS & ACRONYMS

### **2. Definitions and Acronyms**

**2.1 Definitions:** Although not inclusive of every term used within this PWS, the following provides a list of definitions used throughout this PWS and commonly used in the acquisition field.

**Contracting Officer** – means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

**Contracting Officer's Representative (COR)** – As defined in DFARS 202.101, means an individual designated and authorized in writing by the Contracting Officer to perform specific technical or administrative functions. DoD Instruction (DoDI) 5000.72, Part II Definitions states the following when defining a COR: “Defined in subpart 202.101 of Reference (f). Any individual delegated responsibilities pursuant to subpart 1.602-2 of Reference (e), regardless of local terminology, must be certified in accordance with this instruction. For example, local terminology can be COR, Contracting Officer’s technical representative, technical point of contact, technical representative, alternate COR, administrative COR, assistant COR, line item manager, task order manager, quality assurance personnel, quality assurance evaluator, or COR management.” In addition, Army Regulation 70-13, Chapter 2, paragraph 2-2g, states, in part, the following when providing other surveillance support personnel to assist the COR when needed, “...These other surveillance support personnel may serve as on-site representatives of the COR in performance of actual contract surveillance if they meet all COR requirements and have been appointed by the Contracting Officer as alternate CORs.”

**Contractor** – means a supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

**Contractor-acquired Property** - means property acquired, fabricated, or otherwise provided by the Contractor for performing a contract and to which the Government has title.

**Day** – means, unless otherwise specified, a calendar day.

**Defective Service** – means a service output that does not meet the standard of performance associated with the Performance Work Statement.

**Deliverable** – means anything that can be physically delivered, but may include non-manufactured things such as meeting minutes or reports.

**Government-furnished Property** – As reflected in FAR 52.245-1, Government-furnished Property “means property in the possession of, or directly acquired by, the Government and subsequently furnished to the Contractor for performance of a contract. Government-furnished

property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification. Government-furnished property also includes contractor-acquired property if the contractor-acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract

**Government Property** - means all property owned or leased by the Government. Government property includes both Government-furnished and Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

**Property Administrator** - means an authorized representative of the Contracting Officer appointed in accordance with agency procedures, responsible for administering the contract requirements and obligations relating to Government property in the possession of a Contractor.

**Physical Security** – means that part of security concerned with physical measures designed to safeguard personnel; to prevent unauthorized access to equipment, installations, material, and documents; and to safeguard against espionage, sabotage, damage, and theft.

**Quality Assurance** – (or Government contract quality assurance) means the various functions, including, inspection, performed by the Government to determine whether a Contractor has fulfilled the contract obligations pertaining to quality and quantity.

**Quality Assurance Surveillance Plan (QASP)** – means the key Government-developed surveillance process document, and is applied to Performance-Based Service Contracting (PBSC). The QASP is used for managing Contractor performance assessment by ensuring that systematic quality assurance methods validate that Contractor quality control efforts are timely, effective, and are delivering the results specified in the contract or task order. The QASP directly corresponds to the performance objectives and standards (i.e., quality, quantity, timeliness) specified in the Performance Work Statement (PWS). It provides specific details on how the Government will survey, observe, test, sample, evaluate, and document Contractor performance results to determine if the Contractor has met the required standards for each objective in the PWS. The QASP, with very few if any exceptions, is an internal to Government document.

**Quality Control** – means all necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

**Statement** – means the specific results-based activities required to satisfy HLOs. A statement contains a result, the context of the statement, and the required action(s). Statements focus on “what” is to be accomplished; however they are not prescriptive in describing “how” the outcome is to be achieved. Each HLO may have several statements to flesh out the areas necessary to meet the objective. Statements are similar to Level 3 in a Work Breakdown Structure.

**Subcontractor** – means one that enters into a contract with a prime Contractor. The Government does not have privity of contract with the subcontractor.

**Work Day** - The number of hours per day the Contractor provides services in accordance with the contract.

**Work Week** - Monday through Friday, unless otherwise specified.

**2.2 Acronyms:** Although not inclusive of every term used within this PWS, or that may be included in an acquisition, the following provides a list of acronyms commonly used in the acquisition field.

|       |                                                             |
|-------|-------------------------------------------------------------|
| ACOR  | Alternate Contracting Officer's Representative              |
| AE    | Army in Europe                                              |
| AFARS | Army Federal Acquisition Regulation Supplement              |
| AHA   | Activity Hazard Analysis                                    |
| AOR   | Area of Responsibility                                      |
| AR    | Army Regulation                                             |
| AT    | Anti-terrorism                                              |
| ATCTS | Army Training Certification Tracking System                 |
| CAC   | Common Access Card                                          |
| CCE   | Contracting Center of Excellence                            |
| CFE   | Conventional Forces Europe                                  |
| CFR   | Code of Federal Regulations                                 |
| CONUS | Continental United States (excludes Alaska and Hawaii)      |
| COR   | Contracting Officer's Representative                        |
| COTS  | Commercial-Off-the-Shelf                                    |
| DA    | Department of the Army                                      |
| DD250 | Department of Defense Form 250 (Receiving Report)           |
| DD254 | Department of Defense Contract Security Requirement List    |
| DFARS | Defense Federal Acquisition Regulation Supplement           |
| DMDC  | Defense Manpower Data Center                                |
| DoD   | Department of Defense                                       |
| FAR   | Federal Acquisition Regulation                              |
| FRG   | Federal Republic of Germany                                 |
| GFP   | Government Furnished Property                               |
| HLO   | High Level Objective                                        |
| HIPAA | Health Insurance Portability and Accountability Act of 1996 |
| IA    | Information Awareness                                       |
| IAC   | Installation Access Control                                 |
| IACO  | Installation Access Control Office                          |
| ID    | Identification                                              |
| IGCE  | Independent Government Cost Estimate                        |
| IT    | Information Technology                                      |
| JTR   | Joint Travel Regulation                                     |
| JPAS  | Joint Personnel Adjudication System                         |

|         |                                                                |
|---------|----------------------------------------------------------------|
| KO      | Contracting Officer                                            |
| OCI     | Organizational Conflict of Interest                            |
| OCONUS  | Outside Continental United States (includes Alaska and Hawaii) |
| ODC     | Other Direct Costs                                             |
| OPSEC   | Operations Security                                            |
| PA      | Property Administrator                                         |
| PII     | Personally Identifiable Information                            |
| PIPO    | Phase In/Phase Out                                             |
| POC     | Point of Contact                                               |
| PRS     | Performance Requirements Summary                               |
| PWS     | Performance Work Statement                                     |
| QA      | Quality Assurance                                              |
| QAP     | Quality Assurance Program                                      |
| QASP    | Quality Assurance Surveillance Plan                            |
| QC      | Quality Control                                                |
| QCP     | Quality Control Program                                        |
| RA      | Requiring Activity                                             |
| RCO     | Regional Contracting Office                                    |
| SIGE    | Safety and Health Protection Plan                              |
| TE      | Technical Exhibit                                              |
| USAG    | United States Army Garrison                                    |
| USAREUR | United States Army Europe                                      |
| UOM     | Unit of Measure                                                |
| DIN     | Deutsches Institut fuer Normung                                |
| VDE     | Verband der Elektrotechnik                                     |
| VdS     | Verband der Sachverstaendiger                                  |
| NFPA    | National Fire Protection Association                           |

**PART 3**  
**GOVERNMENT PROPERTY (GP) AND SERVICES**

**3. Government Property and Services**

**3.1 Services:** RESERVED

**3.2 Facilities:** RESERVED

**3.3 Utilities:** The Government will provide electricity, water for Contractor use in the performance of services. The Contractor shall instruct employees in utilities conservation practices. The Contractor shall operate under conditions that preclude the waste of utilities, which include turning off the water faucets or valves, light switches, etc. after using the required amount to accomplish tasks requiring the use of the utilities.

**3.4 Equipment:** RESERVED

**3.5 Special Tooling and Test Equipment:** RESERVED

**3.6 Materials:** RESERVED

**3.7 Training:** As specified in section 1.23 of this PWS.

**3.8 Common Access Cards (CAC):** RESERVED

## **PART 4**

### **CONTRACTOR FURNISHED ITEMS AND SERVICES**

#### **4. Contractor Furnished Property and Services**

**4.1 General:** The Contractor shall furnish materials required in accordance with pertinent German accident and safety regulations and National Fire Protection Association (NFPA) regulations and those required to meet the requirements under this PWS.

**4.2 Secret Facility Clearance:** RESERVED

**4.3 Materials:** The Contractor shall furnish materials required in accordance with pertinent German accident and safety regulations and NFPA regulations to meet the requirements under this PWS. All parts and materials utilized for the services under the contract shall be factory new. All exchanged parts shall be handed over to the COR or disposed of as directed by the COR. The Contractor shall provide a warranty of at least 12 months after the repair and installation date for all work performed.

**4.4 Vehicles and Equipment:** The Contractor shall furnish all equipment, tools, testing devices, lifting platform and spare parts required in accordance with pertinent German accident and safety regulations. If a lifting platform or scaffold is required, it shall be provided by the Contractor at no additional cost and is part of the maintenance and inspection. Any transportation of equipment is also included hereto.

**4.5 Background Checks):** The Contractor shall provide Background Checks in accordance with this PWS and as determined by the Government.

## PART 5 SPECIFIC TASKS

**5.1 Basic Services:** The Contractor shall provide maintenance, inspection and functionality tests on the evacuation, sprinkler and fire extinguishing systems, programming and repair of the fire alarm systems (including the Fire Alarm Dispatch Center and Fire Department full operating and integrated systems), and fire suppression systems. The contractor shall conduct testing, four (4) times a year to ensure the systems are functional and meet all safety requirements according to the manufacturer's accident and security directions, as well as the applicable European Norms, German DIN/VDE regulations and VdS regulations, specifically EN 54, DIN 14675, DIN 14497, DIN 14489, DIN VDE 0833, VdS 2095, NFPA (National Fire Protection Association) Norm 12a und 12b, 13, 72, 101

**5.2 Tasks:** Regularly-scheduled Inspection, Maintenance, and Functionality Tests shall be completed in accordance with the schedule below.

| SYSTEM                                                          | TEST FREQUENCY                                                                                             |
|-----------------------------------------------------------------|------------------------------------------------------------------------------------------------------------|
| Fire Alarm and Evacuation Systems                               | Four (4) times per year (quarterly)                                                                        |
| Programming and repair of the fire alarm dispatch systems(FADS) | Two (2) times per year (semi-annually)<br>(must be performed in accordance with manufacturer instructions) |
| Sprinkler Systems                                               | Two (2) times per year (semi-annually)                                                                     |
| Suppression Systems                                             | Two (2) times per year (semi-annually)                                                                     |
| Fire protection doors                                           | Two (2) times per year (semi-annually)                                                                     |
| Programming and connection to FADS                              | On-Demand Service. Shall be performed by the system builder.                                               |

The equipment within the OMA and AFH facilities are listed in the following Attachments 1-3-Inventory Price book:

- a. Attachment 1 - Fire Alarm and Evacuation systems
- b. Attachment 2 - Sprinkler systems
- c. Attachment 3 – Suppression systems

**5.2.1 The functionality test of Fire Alarm Systems and Evacuation Systems:** In accordance with Inventory Price book 1, this test shall include the following:

- Announcement to the customer, as necessary, with information about the temporary shutdown of system parts like fire extinguishing systems or control panel for the operations control center.
- Shutdown of external controls i.e. transducer fire alert.
- Announcement of maintenance work at the system to the firefighters or COR.
- Required to inform fire fighters or COR about completion of maintenance work and changed parts or Batteries
- Restart of all system parts that were shut down

- Complete entry into operation book
- Notice of completion to the customer, operator or briefed personnel

#### **5.2.1.1 Inspection and function testing**

##### **a. Power supply** - The Contractor shall:

- . Check function network failure
- . Conduct the strain test of batteries in accordance with manufacturer information.
- . Check battery charging voltage at battery clamps and exchange batteries that fail.
- . Check function battery failure.

##### **b. Alert Counter** - The Contractor shall:

- . Compare alert counter reading with entries in operation log and investigate reason for all false alerts.
- . Examine background memory for deviations or special incidents.

##### **c. Transmission Paths / Detectors:** The Contractor shall:

- . Complete a physical check-up per transmission path (primary line) for at least one detector that can be checked without destroying them. Complete a virtual (computer-based) check-up per transmission path (primary line) quarterly for the transmission paths of those that cannot be checked without destroying them, including:
- . Check transmission paths for proper function.
- . Check all manual fire alerts.
- . Check automatic fire alert.
- . Check speech alert system and speakers.
- . Check call system.
- . Check sprinkler system.

##### **d. Function Check:** The Contractor shall complete a function check on:

- . All detection, optical and acoustic alert devices
- . All additional peripheral devices (i.e. fire-fighter key depot,)
- . Control panels of UE for fire alert
- . Control panels of UE for failure transmission
- . Control panels (i.e. extinguishing system, arrest system)
- . Control panels for evacuation announcement
- . All connected systems like magnetic door clamps, door closing mechanisms, fire flaps, call system, speech alert system and speakers

##### **e. Visual Check/Inspection:** The Contractor shall:

- . Check unobstructed space (0.5 m) around detectors
- . Check all detectors, push buttons, acoustical and optical alarms, speakers, fire flaps and fire doors for proper mounting and mechanical damage

#### **5.2.1.2 Maintenance**

- . Quarterly maintenance shall be performed in accordance with manufacturer regulations and IAW EN 54, DIN VDE 0833 and all applicable VDS regulations, including:
- . Maintenance and cleaning of system parts
- . Replacement of components with limited life span (i.e. fire detectors, accumulators, devices and storage batteries) after expiration of operating life.
- . Calibration, adjusting, matching of construction parts and devices

- . Firefighter key depot: check all functions including removal of object keys
- . Check if firefighter route cards are up-to-date
- . Check all documentation records for completeness and actuality
- . Replacement of missing documents and operating books.

**5.2.2 The functioning Test of Sprinkler Systems during the maintenance:** (IAW Inventory Price book – Attachment 2) shall include the below listed tasks and minimum requirements.

The Contractor shall:

- . Check water level in storage tank, refill storage tank as needed, refresh water as needed
- . Check float, float gauge and filling pump
- . Check all check valves, back draft dampers, valves and sliders
- . Check automatic start-up during pressure drop (all contact makers)
- . Check pressure maintenance pump and pressure switch as well as turn-on- and shut off-point
- . Perform test alert of wet alarm stations
- . Test run (approx. 30 minutes) of sprinkler pumps
- . Check dry alert valves
- . Check alert pressure switch
- . Check flaps and gaskets
- . Empty and clean system, lubricate movable parts and check gaskets
- . Check alarm bells
- . Check flow monitors and delay unit
- . Clean and check back draft dampers and clean system parts as needed, at least once per year
- . Check control cabinets, measuring devices, mains voltage and fuses
- . Check firefighter connections, hose couplings and drainage
- . Drain dry systems, check pipeline system
- . Check oil level and compressor

**5.2.3 The functioning Test of Fire Suppression System during the maintenance:** (IAW Inventory Price book - Attachment 3) shall include the below listed tasks and minimum requirements. The Contractor shall:

- . Remove lid of mechanical release device
- . Install safety strap (release blockage)
- . Unscrew propellant bottle
- . Demounting of extinguishing agent tank and checking of extinguishing agent's fill level (Ansul)
- . Check gaskets and rupture disk at the dip pipe for damages and soiling
- . Checking of pressure hose between pressure reducing valve and dip pipe
- . Check extinguishing agent hose between extinguishing agent bottle and pipe system for damages and tight fit
- . Weigh propellant bottle and check pressure gauge
- . Check all nozzles for soiling and clean as necessary
- . Check distance from nozzles to devices (maximum distance to surface is 127 cm)
- . Check nozzle protection caps and replace when misfit

- . Demount soldered struts, clean and reinstall
- . Check cable pull by using a test link. If activation is delayed, clean deflector rolls and protective tube if applicable, test again with a test link afterwards
- . Check manual activation with a test
- . Check tubing for tight fit
- . Check if bolt lever for the cable pull of the soldered struts and the mechanical release device is tensioned
- . Note in the maintenance report manufacturer data of extinguishing agent and propellant bottles
- . Security check of propellant bottles including valid inspection plate by manufacturer-certified personnel.
- . Replace all soldered struts and nozzle protection caps (rubber)
- . Check soldered strut activation rope for damages, exchange if necessary
- . Check extinguishing agent for further usability (not be milky or flaky)
- . Drain tank for extinguishing agent and thoroughly rinse with water
- . Replace pressure reducing valve, extinguishing agent bottle, and any propellant bottle older than 10 years.
- . Replace filter pads, respective carbon filters, clips and light bulbs for Guardian.

Within five (5) working days after completion of functioning test, Contractor shall submit a PM Work Certificate IAW PWS 5.6 (Deliverable # A.015). Submission of reports and travel for the preventive maintenance shall be included in the firm fixed service price. Minor repairs include labor and parts up to Euro 300.00 to keep systems operational. Defective parts that were detected during the maintenance must be replaced during maintenance.

**5.3 Non-minor Repair during maintenance:** Travel on a round trip basis is included for repair services including minor repairs caused by wear and tear of the system. At the time on-demand services are ordered and prior to the Contractor commencing work, the COR or Fire Department POC will identify what type of on-demand services are required. Should the Contractor determine that more time is required to complete the repair to the extent that services move from one on-demand category to another, the Contractor must notify the COR and obtain approval prior to proceeding with the work. If material for repair exceeds 1,000.00 Euro, the Contractor shall provide the COR with a Cost Estimate with reference to the Repair Call information, within 3 working days of the identification of need for repair.

**5.3.1 Emergency Services:** The Contractor shall provide On-Demand Repairs as notified by the COR or by the Fire Inspector on duty at the Wiesbaden Air Base Fire Department 24 hours per day, seven (7) days per week.

The Contractor shall arrive on site, commence, and complete performance of On-Demand Repairs within eight (8) hours after receipt of notification with all required tools, spare parts and materials in order to repair the damages and restore the system(s) to operational status. If repairs cannot be completed during the initial service call due to unavailability of repair parts, the Contractor shall not invoice for additional costs for the return trip to complete services.

**5.3.2 Routine On-Demand Repair Services:** The Contractor shall provide Routine On-Demand Repairs during Contractor Support Hours. The Contractor shall arrive on site, commence, and complete performance of Routine On-Demand Repairs within twenty-four (24)

hours after receipt of notification with all required tools, spare parts and materials in order to repair the damages and restore the system(s) to operational status. If repairs cannot be completed during the initial service call due to unavailability of repair parts, the Contractor shall not invoice for additional costs for the return trip to complete services.

### **5.3.3 Major On-Demand Repair Services:**

Major On-Demand Repair Services are repairs that exceed 1,000.00 Euro or require more than twenty (20) hours for the Contractor to arrive on site, commence, and complete the repair. The Contractor shall provide a detailed firm-fixed-price quote for the labor, repair, and parts to the COR for approval before proceeding with the repair. If repairs cannot be completed during the initial service call due to unavailability of repair parts, the Contractor is not authorized to charge additional costs for the return trip to complete services.

After completion of the repair work Para.5.3 -5.3.3 the Contractor shall provide an On Demand Service Report IAW PWS 5.7 (Deliverable #A.019) within two (2) days after performance of the repair service.

### **5.4 Fire Alarm Dispatch System (FADS):**

The Contractor shall ensure compatibility when maintaining and programming the FADS due to the number of interfaces as specified in Attachment 1-3 (fire alarm systems, mobile fire department operations center fallback option, installed in mobile container and in a redundant facility, 100% absorption of the fixed monitoring station in case of failure), mass information systems, building control elevator systems, recording equipment, video intercom, door controller, interface for operating the radio, telephony, loudspeaker system Bldg. 1001, Base Operations (red telephone line) and an interface to the Military Police (Help Desk)) as well as the control center technology (management system),. The system is certified IAW DIN EN 50518. All systems shall comply with the Technical Standard for the connection of Fire Alarm Systems in the Area of USAG Wiesbaden and the signal standards of the USAG Wiesbaden to ensure the accreditation is not jeopardized. The maintenance of the FADS shall be conducted twice a year, after completion of the maintenance the Contractor shall submit a PM Work Certificate IAW PWS 5.6 (Deliverable # A.015). New connections to the system will be ordered through Routine On-Demand Repairs or will be conducted through renovation or construction projects outside the scope of the contract.

**5.4.1 Repair Parts:** The Contractor shall furnish all parts and materials required for repair of equipment under the contract and shall complete services during the initial scheduled maintenance or On –Demand Service call. There may be instances where repair services cannot be completed during the initial visit due to unavailable parts or material.

If parts cannot be obtained with five (5) working days, or if there is no assurance that the parts will be available in the specified period of performance, the Contractor shall inform the COR to determine whether the initial repair request shall be maintained or closed, and initiate the acquisition of the repair part. The Contractor shall coordinate with the COR if equipment should be reassembled while awaiting receipt of part(s). The Contractor shall inform the COR when parts have been received so that another repair request can be initiated if needed. If a

new repair request was initiated, a new work certificate shall be issued to document the completion of repair and the original work certificate shall be referenced on this document. The Contractor shall submit a written proposal to the COR to eliminate the deficiencies. The proposal shall itemize all cost elements including the flat rate for travel on a round trip basis.

## **5.5 Required Documents**

**5.5.1 Maintenance Control Book:** The Contractor shall obtain published technical manuals pertinent to the equipment to be maintained and repaired at the Contractor's own expense. For US manufactured equipment, the Contractor shall obtain published technical manuals pertinent to the equipment to be maintained and repaired at the Contractor's own expense. For non-US manufactured equipment, the Contractor shall obtain technical manuals applicable to German manufactured equipment at the Contractor's own expense.

Equipment for which no technical manuals can be obtained shall be maintained and repaired by the Contractor IAW current standard commercial industrial practice. All documents shall be provided in English. Log Books must be kept at the system and shall be maintained during maintenance and repair at all times. All entries shall include written name and signature of the technician, start time, a description of the conducted work, end result, and end time.

The Contractor shall submit an updated electronic log of the Maintenance Control Book no later than the last Friday of each month (Deliverable #A.016).

**5.5.2 Inventory and Density List:** The Contractor shall use the density list to create an inventory list, which shall contain, at a minimum, the information shown in Attachments #1-3. The Contractor shall keep the inventory list up-to-date as changes occur. The most current inventory list shall be submitted to the COR no later than the fifth working day of each month (Deliverable #A.017). All new equipment shall also be documented, labeled and provided to the COR.

**5.6 PM Work Certificate:** After each functional test, the Contractor shall submit a written condition report of each individual system to the COR within five (5) working days. The report shall contain the following information:

1. Printed first and last name of the technician (clearly written)
2. Printed first and last name and signature of the customer
3. Start and end time of the functional test
4. Name of the system and type of connected sub systems
5. Type and amount of tested parts
6. Specifications of defects
7. Results of measurements and checks
8. Assessment of condition and function
9. Safety and efficiency of the operation
10. Detailed scope of work for any required repair
11. Material and spare parts for all required repairs
12. Cost Estimate for any required repair

See samples test reports:

Attachment 5: Sample of test report for Fire Alarm Systems

Attachment 6: Sample of test report for Sprinkler Systems

Attachment 7: Sample of test report for Fire Suppression Systems

The Contractor shall submit electronically a copy of each PM Work Certificate to the COR within five (5) calendar days after the performance of the inspection and maintenance (Deliverable #A.015).

**5.7 On Demand Service Report:** The Contractor shall complete a report for each completed service under the contract. The report shall contain:

1. Contract Number
2. Service No.
3. Type of system and Manufacturer Number
4. Location
5. Date and time when the on-call repair was received.
6. Printed first and last name and title of the person who ordered the services
7. Description of Malfunction
8. Date, start time and completion time of services
9. Printed first and last name(s) of individual(s) performing the services and signature
10. Type and amount of required material and replacement parts
11. Information or recommendations pertaining to the condition or function of the system
12. Amount of labor hours identified by type (Within Contractor Support Hours, Outside Contractor Support Hours)
13. Cost Estimate

Contractor shall submit electronically a copy of each On-Demand Repair Service report to the COR within two (2) days after the performance of the repair service (Deliverable #A.018).

**5.8 Maintenance Inspection Schedule:** Within ten (10) working days after contract start date, the Contractor shall submit a Microsoft Excel spreadsheet electronically with a proposed Preventive Maintenance (PM) schedule for equipment covered under the contract for the entire performance period IAW VDI 2989 (Deliverable #A.019). Within five (5) working days after submission of the proposed schedule, the COR will approve or disapprove the proposed schedule. If disapproved, the Contractor shall submit corrections to the COR within two (2) working days. As PM progresses, the Contractor shall annotate its schedule to reflect additions, deletions and other changes. The Contractor shall not deviate from the approved maintenance schedule without prior approval from the COR. An updated schedule shall be submitted to the COR one month prior to the end of each Task Order, and upon request. The updated schedule will be subject to COR approval in the same manner as the original schedule.

## **5.9 Service Contract Reporting**

**5.9.1 System for Award Management (SAM) Service Contract Report (SCR):** N/A

## PART 6 APPLICABLE PUBLICATIONS

**6. Applicable Publications (Current Editions):** The following publications, manuals, regulations, etc. are mentioned in this PWS and are listed below.

- 6.1.1 Department Of Defense Contract Security Classification Specification (DD Form 254)
- 6.1.2 Department of Defense Security Agreement (DD Form 441)
- 6.1.3 National Industrial Security Program Operating Manual (DoD 5220.22-M)
- 6.1.4 Installation Access Control (AE Reg 190-16)
- 6.1.5 The Army Physical Security Program (AR 190-13)
- 6.1.6 Contractor Identification (AE Reg 27-715)
- 6.1.7 U.S. Army Corps of Engineers Safety and Health Requirements Manual (EM 385-1-1)
- 6.1.8 Information Assurance Workforce Improvement Program (DoD 8570-M)
- 6.1.9 Information Assurance Training Certification and Workforce Management Directive (DoDD 8570.01)
- 6.1.10 Information Assurance (AR 25-2)
- 6.1.11 Electromagnetic Compatibility Directive (2004/108/EC)
- 6.1.12 Policies and Procedures for Property Accountability (AR 735-5)
- 6.1.13 UFC 3-600-01 Unified Facility Criteria - Fire protection engineering for facilities UFC 3-600-02 Unified Facility Criteria – Operation and maintenance: inspection, testing, and maintenance of fire protection systems
- 6.1.14 NFPA 12 A, B
- 6.1.15 NFPA 13 Installation of Sprinkler Systems
- 6.1.16 NFPA 20 Installation of Stationary Pumps
- 6.1.17 NFPA 72 National Fire Alarm and Signaling Code ANSI/NFPA
- 6.1.18 NFPA 75 Fire Protection of Information Technology Equipment
- 6.1.19 NFPA 76 Fire Protection of Telecommunications Facilities
- 6.1.20 NFPA 80 Fire Doors and Other Opening Protectives
- 6.1.21 NFPA 80A Protection of Buildings from Exterior Fire Exposures
- 6.1.22 NFPA 88A Parking Structures
- 6.1.23 NFPA 90A Installation of Air-Conditioning and Ventilating Systems
- 6.1.24 NFPA 90B Installation of Warm Air Heating and Air-Conditioning Systems NFPA 92A Standard for Smoke Control Systems Utilizing Barriers and Pressure Differences
- 6.1.25 NFPA 101 Life Safety Code, NFC
- 6.1.26 DIN 0833 1-4 Gefahrenmeldeanlagen für Brand und Einbruch (Fire and Intrusion Alarm Systems)
- 6.1.27 DIN 14675 Brandmeldeanlagen - Aufbau und Betrieb (Fire Alarm Systems – Design and Operation)
- 6.1.28 DIN EN 54 Brandmeldeanlagen (Fire Alarm Systems)
- 6.1.29 DIN 14661 Feuerwehr-Bedienfeld für Brandmeldeanlagen
- 6.1.30 DIN 14662 Feuerwehr-Anzeigetableau (Anunciator Panel)
- 6.1.31 DIN 14034 Graphische Symbole (Pictographs and Symbols)
- 6.1.32 TAB Technische Anschlussbedingungen Brandmeldeanlagen der USAG Wiesbaden (Technical Connection Standard Fire alarm Systems - USAG Wiesbaden)
- 6.1.33 VDS 2095, 2129, 2132, 2133, 2221, 2222, 2843

DRAFT

**PART 7**  
**ATTACHMENT AND TECHNICAL EXHIBIT LISTING**

**7. Attachment and Technical Exhibit List**

**7.1 Technical Exhibit A** – Performance Requirements Summary

**7.2 Technical Exhibit B** – Deliverables Schedule

**7.3 Attachment 1** - Inventory - List of OMA-AFH Fire Alarm Systems

**7.4 Attachment 2** - Inventory - List of OMA-AFH Fire Sprinkler Systems

**7.5 Attachment 3** - Inventory - List of OMA-AFH Fire Suppression Systems

**7.6 Attachment 4** - Bidders Price Book

**7.7 Attachment 5** - Fire Alarm Systems Test Reports

**7.8 Attachment 6** - Fire Sprinkler Systems Test Reports

**7.9 Attachment 7** - Fire Suppression Systems Test Reports

## TECHNICAL EXHIBIT A

### Performance Requirements Summary (PRS)

The Contractor service requirements are summarized into performance objectives that relate directly to mission essential items. The performance threshold briefly describes the minimum acceptable levels of service required for each requirement. These thresholds are critical to mission success. Any AQL in Paragraph 5 supersede the PRS

| <b>Performance Objective</b><br>(The Service required—usually a shall statement)                                            | <b>Standard</b>                                                                                   | <b>Performance Threshold</b> (This is the maximum error rate. It could possibly be “Zero deviation from standard”) | <b>Method of Surveillance</b>                    |
|-----------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|--------------------------------------------------|
| <b><u>PWS 1.5.1</u></b> <u>Quality Control Plan is developed and maintained</u>                                             | Contractor performs in accordance with established Quality Control Plan                           | No unauthorized deviations                                                                                         | 100% Inspection                                  |
| <b><u>PWS 1.10.2</u></b> <u>The Contractor shall comply with ISO9001 Standards while performing and areas of the PWS</u>    | ISO9001                                                                                           | Zero Deviation from standard                                                                                       | 100% Inspection of Certification                 |
| <b><u>PWS 1.22</u></b> <u>Required Training is completed</u>                                                                | Contractor completes and remains up to date on training                                           | In compliance >95% at all times.                                                                                   | 100% Inspection                                  |
| <b><u>PWS 4.</u></b> The Contractor shall furnish all supplies, equipment, facilities and services required to perform work | Contractor is prepared with supplies, equipment, facilities and services required to perform work | Preparation level does not affect schedule >95% of the time.                                                       | Periodic Inspection                              |
| <b><u>PWS 5.2</u></b> Contractor shall comply with PWS for Inspection and Maintenance                                       | The contractor inspects and maintains in accordance with the manufacturer instructions            | >95 percent with any deviations corrected within 3 working days.                                                   | Random Sampling, 100% Inspection of corrections. |
| <b><u>PWS 5.3, 5.3.2, 5.3.3</u></b> Contractor shall comply with PWS                                                        | Contractor completes on demand repairs                                                            | >95 Percent of the time                                                                                            | 100 % Inspection                                 |

|                                                                                                                       |                                                                                                       |                                                            |                     |
|-----------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|------------------------------------------------------------|---------------------|
| provisions relating to On Demand Repair.                                                                              | within timelines established at identification of the issue.                                          |                                                            |                     |
| <b>PWS 5.3.1</b><br>Contractor shall comply with PWS provisions relating Emergency Repairs                            | Contractor shall complete all repairs within 8 hours of notification.                                 | >95 Percent of the time                                    | 100% Inspection     |
| <b>PWS 5.4</b><br>Contractor shall comply with PWS provisions updating and maintaining FADS                           | The Contractor shall ensure the systems are up-to-date and maintained in accordance with the schedule | >98 percent of the time                                    | Periodic Inspection |
| <b>PWS 5.5</b><br>Contractor shall comply with PWS provisions relating to Maintenance control books and Density lists | Updated in accordance with the PWS.                                                                   | In compliance >95% of the time.                            | Periodic Inspection |
| <b>PWS. 5.6</b><br>Contractor shall comply with PWS provisions relating Completion of work certificates.              | 0 Safety or Environmental Discrepancies < 1 Technical Discrepancies per report                        | >95% of the time                                           | 100% Inspection     |
| <b>PWS 5.7</b><br>Contractor shall comply with PWS provisions relating to repair reports                              | 0 Safety or Environmental Discrepancies < 1 Technical Discrepancies per report                        | >95% of the time                                           | 100% Inspection     |
| <b>PWS 5.8</b><br>Contractor shall comply with PWS provisions relating to maintenance and inspection schedule         | Contractor performs maintenance in accordance with inspection schedule.                               | No deviations from the without prior approval from the COR | 100% Inspection     |

## TECHNICAL EXHIBIT B

## DELIVERABLES SCHEDULE

DRAFT

| <u>Deliverable #</u>                                                                                  | <u>Frequency</u>                                                                                                                                                                                 | <u># of Copies</u> | <u>Medium/Format</u>                                                         | <u>Submit To</u> |
|-------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|------------------------------------------------------------------------------|------------------|
| <u>A.001 Quality Control Plan PWS 1.5.1</u>                                                           | <u>Within 10 calendar days after award of contract.</u><br><br><u>When Changes are required. No later than 30 days prior to anticipated changes and before implementation by the Contractor.</u> | <u>One each</u>    | <u>Electronic delivery via email using Microsoft (MS) Excel or Adobe PDF</u> | <u>COR</u>       |
| <u>A.002 Contractor Personnel List IAW PWS 1.11(b), Initial Installation Pass Log IAW PWS 1.6.3.3</u> | <u>Within five (5) calendar days of contract award.</u><br><u>Within five (5) calendar days after any changes.</u>                                                                               | <u>One each</u>    | <u>MS Excel or Adobe PDF</u>                                                 | <u>COR</u>       |
| <u>A.003 Polizeiliches Fuehrungszeugnis IAW PWS 1.6.4.2</u>                                           | <u>Within five (5) days of contract award.</u>                                                                                                                                                   | <u>One each</u>    | <u>Digital document or hard copy</u>                                         | <u>COR</u>       |
| <u>A.004 Key Personnel IAW PWS 1.10</u>                                                               | <u>At Post Award Meeting.</u>                                                                                                                                                                    | <u>One each</u>    | <u>MS Excel or Adobe PDF</u>                                                 | <u>COR</u>       |
| <u>A.005 Company ISO 9001 Certification IAW PWS 1.10.a</u>                                            | <u>Annually</u>                                                                                                                                                                                  | <u>One each</u>    | <u>Adobe PDF</u>                                                             | <u>COR</u>       |
| <u>A.006 Technicians Special Qualifications IAW PWS 1.10.a</u>                                        | <u>Within five (5) calendar days of contract award.</u>                                                                                                                                          | <u>One each</u>    | <u>MS Excel or Adobe PDF</u>                                                 | <u>COR</u>       |

|                                                                            |                                                                                                           |                 |                              |            |
|----------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|-----------------|------------------------------|------------|
| <u>A.007 Master Electrician Qualifications IAW PWS 1.10.b</u>              | <u>Within five (5) calendar days of contract award. Within two (2) calendar days prior to any change.</u> | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.008 Contractor Identification Badge List IAW PWS 1.12.2</u>           | <u>Prior to contract performance and updated as needed to reflect Contractor personnel changes.</u>       | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.009 Host Accident Prevention Plan IAW PWS 1.21.1.a</u>                | <u>15 calendar days after contract award. Prior to initiation of work on the job site.</u>                | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.010 Host Nation Safety Notifications IAW PWS 1.21.1.2</u>             | <u>No later than five (5) days that such notifications were made.</u>                                     | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.011 Anti-Terrorism (AT) Level I Awareness training IAW PWS 1.23.1</u> | <u>Within 30 calendar days of contract award or employee start. Refresher training annually</u>           | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.012 OPSEC Level I training IAW PWS 1.23.2</u>                         | <u>Within 30 calendar days of contract award or employee start. Refresher training annually</u>           | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |
| <u>A.013 iWATCH/Salute Training IAW PWS 1.23.3</u>                         | <u>Within 30 calendar days of contract award or employee start.</u>                                       | <u>One each</u> | <u>MS Excel or Adobe PDF</u> | <u>COR</u> |

|                                                                 |                                                                                                 |                 |                                                                             |            |
|-----------------------------------------------------------------|-------------------------------------------------------------------------------------------------|-----------------|-----------------------------------------------------------------------------|------------|
| <u>A.014 Information Assurance (IA) Training IAW PWS 1.23.4</u> | <u>Within 30 calendar days of contract award or employee start. Refresher training annually</u> | <u>One each</u> | <u>MS Excel or Adobe PDF</u>                                                | <u>COR</u> |
| <u>A.015 PM Work Certificate IAW PWS 5.6</u>                    | <u>Within five (5) working days after the inspection and maintenance.</u>                       | <u>One each</u> | <u>Signed originals, MS Excel file, and PDF</u>                             | <u>COR</u> |
| <u>A.016 Maintenance Control Book IAW PWS 5.5.1</u>             | <u>No later than the last Friday of each month.</u>                                             | <u>One each</u> | <u>MS Excel or Adobe PDF</u>                                                | <u>COR</u> |
| <u>A.017 Inventory and Density List IAW PWS 5.5.2</u>           | <u>No later than the fifth working day of each month.</u>                                       | <u>One each</u> | <u>PDF</u>                                                                  | <u>COR</u> |
| <u>A.018 On Demand Service Report IAW PWS 5.7</u>               | <u>Within two (2) days after performance of the repair service.</u>                             | <u>One each</u> | <u>Signed originals, MS Excel file, and backup files of existing system</u> | <u>COR</u> |
| <u>A.019 Maintenance Inspection Schedule IAW PWS 5.8</u>        | <u>Within five (5) calendar days after award of contract.</u>                                   | <u>One each</u> | <u>MS Excel or Adobe PDF</u>                                                | <u>COR</u> |