

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE 1 OF 8 PAGES	
2. AMENDMENT/MODIFICATION NUMBER 0005		3. EFFECTIVE DATE 19 Mar 2026		4. REQUISITION/PURCHASE REQUISITION NUMBER See Continuation Sheet		5. PROJECT NUMBER (If applicable) 1737012	
6. ISSUED BY NAVFACSYS COM MID-ATLANTIC 9324 VIRGINIA AVENUE, NORFOLK NORFOLK, VA 23511-0395 UNITED STATES CATHARINE Keeling, Email: catharine.a.keeling.civ@us.navy.mil Telephone: 757-341-0150		CODE N40085		7. ADMINISTERED BY (If other than Item 6) SCD: PAS:		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				☒ (X)		9A. AMENDMENT OF SOLICITATION NUMBER N4008525R2639	
				☒ (X)		9B. DATED (SEE ITEM 11) 26 Jan 2026	
				☐ ()		10A. MODIFICATION OF CONTRACT/ORDER NUMBER	
				☐ ()		10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;
 or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE
 RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If
 by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic
 communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)
 See Section 00 70 00 - Conditions of the Contract

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
 IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**


CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)
 This amendment is issued to incorporate the following:

1. Provide extended proposal due date
2. Provide updated Wage Determination
3. Provide updated/revised attachments
4. Provide Pre-Proposal Inquiries (PPIs)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) CATHARINE A. KEELING	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA 	16C. DATE SIGNED 19 Mar 2026
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Section 00 00 00 - Procurement and Contracting Requirements

The following changes have been made:

INFORMATION	FROM	TO
Response Due Date	24 Mar 2026	31 Mar 2026

Section 00 21 16 - Instructions to Proposers

Miscellaneous text in this section has been added to:

Amendment 0005

This amendment is issued to incorporate the following:

1. Provide extension to proposal due date
2. Provide Updated Wage Determination
3. Provide attachments (attached separately)
4. Provide Pre-Proposal Inquiries

-
1. The proposal due date has been extended from 24 March 2026 to 31 March 2026 at 2pm ET.
-

2. Updated Wage Determination

"General Decision Number: VA20260160 01/30/2026

Superseded General Decision Number: VA20250160

State: Virginia

Construction Type: Building

County: Norfolk* County in Virginia.

* INDEPENDENT CITY OF NORFOLK

BUILDING CONSTRUCTION PROJECTS (does not include single family homes or apartments up to and including 4 stories).

Modification Number Publication Date

0 01/02/2026

1 01/30/2026

ASBE0024-006 10/01/2024

Rates Fringes

ASBESTOS WORKER/HEAT & FROST
INSULATOR - MECHANICAL (Duct,
Pipe & Mechanical System
Insulation).....\$ 40.77 20.17+a

a. PAID HOLIDAYS: New Year's Day, Martin Luther King Day,
Memorial Day, Independence Day, Labor Day, Veterans' Day,
Thanksgiving Day,the day after Thanksgiving and Christmas
Day provided the employee works the regular work day before

and after the paid holiday.

BOIL0045-003 01/01/2025

Rates Fringes

BOILERMAKER.....\$ 38.97 27.39

BRVA0008-001 05/01/2022

Rates Fringes

BRICKLAYER.....\$ 22.44 10.23

ELEC0080-010 06/01/2025

Rates Fringes

ELECTRICIAN (Includes Low
Voltage Wiring and Alarm
Installation).....\$ 36.85 17.18%+7.80+a

a. Workmen shall take off 1 hour with pay, at the discretion
of the employer, on State and National Election days;
Tuesday following the first Monday in November, provided
they are qualified and vote.

ELEV0052-005 01/01/2025

Rates Fringes

ELEVATOR MECHANIC.....\$ 52.06 38.435+a+b

a. PAID HOLIDAYS: New Year's Day, Memorial Day, Independence
Day, Labor Day, Veterans' Day, Thanksgiving Day, the Friday
after Thanksgiving Day and Christmas Day.

b. VACATIONS: 6% men under 5 years based on regular hourly
rate and 8% men over 5 years based on regular hourly rate
for all hours worked.

ENGI0147-019 06/01/2025

Rates Fringes

POWER EQUIPMENT OPERATOR
Cranes 90 tons & over
capacity; Tower & Climbing
Cranes with Controls 100
ft. above ground.....\$ 40.99 18.05
Cranes under 90 tons.....\$ 39.99 18.05

IRON0028-006 05/01/2023

Rates Fringes

IRONWORKER, RIGGER.....\$ 30.22 11%+14.24

IRON0028-007 05/01/2024

Rates Fringes

IRONWORKER, STRUCTURAL AND
ORNAMENTAL.....\$ 31.00 18.28

* PLUM0110-008 11/01/2025

Rates Fringes

PIPEFITTER (Includes HVAC
Pipe, Unit and Temperature
Controls Installations).....\$ 36.92 18.25
PLUMBER.....\$ 36.92 18.25

SUVA2013-043 01/11/2016

Rates Fringes

CARPENTER, Includes
Acoustical Ceiling
Installation, Drywall
Hanging, and Form Work.....\$ 19.80 3.98

CAULKER.....\$ 18.49 1.33

CEMENT MASON/CONCRETE FINISHER...\$ 20.02 2.00

GLAZIER.....\$ 19.36 4.68

IRONWORKER, REINFORCING.....\$ 27.18 4.13

LABORER: Mason Tender - Brick...\$ 14.82 3.34

LABORER: Mason Tender -
Cement/Concrete.....\$ 12.96 3.12

LABORER: Pipelayer.....\$ 12.40 1.86

LABORER: Common or General,
Including Demolition.....\$ 11.28 1.89

OPERATOR:
Backhoe/Excavator/Trackhoe.....\$ 18.57 1.19

OPERATOR: Bobcat/Skid
Steer/Skid Loader.....\$ 18.95 4.03

OPERATOR: Bulldozer.....\$ 18.07 3.50

OPERATOR: Forklift.....\$ 19.40 7.00

OPERATOR: Loader.....\$ 21.28 3.17

OPERATOR: Roller.....\$ 16.25 4.88

PAINTER (Brush and Roller).....\$ 16.92 0.00

PAINTER: Spray.....\$ 18.10 5.43

ROOFER.....\$ 18.40 2.31

SHEET METAL WORKER, Includes
HVAC Duct Installation.....\$ 20.98 2.62

SPRINKLER FITTER (Fire
Sprinklers).....\$ 18.91 4.67

TILE FINISHER.....\$ 23.40 0.00

TILE SETTER.....\$ 27.80 10.25

TRUCK DRIVER: Dump Truck.....\$ 15.50 0.75

WELDERS - Receive rate prescribed for craft performing
operation to which welding is incidental.

=====

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave
for Federal Contractors applies to all contracts subject to the

Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at <https://www.dol.gov/agencies/whd/government-contracts>.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least \$13.30 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2025. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than ""SU"", ""UAVG"", ?SA?, or ?SC? denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The ""SU"" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

?SU? wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The ""SA"" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the ?SA? identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

- a) a survey underlying a wage determination
- b) an existing published wage determination
- c) an initial WHD letter setting forth a position on a wage determination matter
- d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division

U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

=====
END OF GENERAL DECISION"

3. Provide attachments

The following attachments are included in this Amendment 0005 as supporting documents:

- Amendment 0005 Continuation Sheet
- Attachment H - Price Proposal Form_rev1
- Crane - LP48 #1-DATA SHEET
- Crane - LP48 #2-DATA SHEET
- FY26 Naval Station Norfolk Utility Costs
- P222_1737012_01 91 00.15 22
- P222_1737012_04 20 00
- P222_1737012_07 21 13
- P222_1737012_07 60 00
- P222_1737012_09 29 00
- P222_1737012_13 34 20
- P222_1737012_28 31 76
- P222_1737012_32 13 13.06
- P222_1737012_Drawings_volume I_Rev 001_SIGNED
- P222_1737012_Drawings_volume II_Rev 001_SIGNED
- P222_1737012_Geotech Report
- P222_1737012_REGISTER

4. Pre- proposal Inquiry Responses

PPI #	Page	Section	Paragraph	Question	Response
5				Will FF&E and AV be included in a separate solicitation? If so, when can we expect the solicitation to be published?	FF&E, specification 12 00 01.00 20 details requirements. Design (Technology Refresh) of the FF&E and AV is included in Base Bid (FF&E) and CLIN 0003 (AV). Scope of work for these items are detailed in Spec Section 12 00 01.00 20 (FF&E) and 01 30 02.00 22 (AV). Procurement of the FF&E and AV equipment requires Best Value Source Selection (BVD), of which the GC and their subs, are not eligible to bid on but the GC is entitled to 5% HAR for the respective CLINs
6		01 91 00.15	1.2 & 1.12 and 1.3 & 1.11	In Section 01 91 00.15, paragraphs 1.2 and 1.12 indicate that the Commissioning Provider (CxC) is employed by the Government. Paragraph 1.3 states that the Government has no direct contract authority with the Lead Commissioning Specialist and paragraph 1.11 states that the Commissioning Firm (including the CxC) must be a first-tier subcontractor. Please confirm that the Commission Firm, including the Lead Commissioning Specialist and the Commissioning Specialists for each discipline are employed by the Government.	01 91 00.15 22, Total Building Commissioning specification is to replace the current 01 91 00.15 Building Commissioning in its entirety via this Amendment. Please See Amendment 0005 Continuation Sheet and attachment "P222_1737012_01 91 00.15 22".

7		01 30 02.00 22	1.3.1	Section 01 30 02.00 22 paragraph 1.3.1 states that the Government AV budget on the Bid Schedule/ Price Proposal Form for the AV Mod is \$2,019,600. The Total of A/V CLINs 0004 and 0005 in Attachment H - Price Proposal Form is \$139,850. Please confirm that Attachment H values are correct.	A revised Bid Schedule/ Price Proposal is provided via Amendment. Please see Attachment H - Price Proposal Form_rev1
8		13 50 00	1.2	Section 13 50 00 Ignitable Liquid Drainage Floor Assembly (ILDFA) states in paragraph 1.2 that the Basis of Design manufacturer of the ILDFA is Safespill. To our knowledge, Safespill is the only manufacturer of this product and on other NAVFAC projects, the government has provided a Justification and Approval (J&A) authorizing and approving the use of Safespill as the sole source for the ILDFA. We request that NAVFAC provide a J&A for Safespill on this project as required by the FAR (Subpart 6.3) when only one responsible source will satisfy NAVFAC requirements.	J&A pending and scheduled to be in place prior to the award of this project
9	Page 4	33 83 02		On Page 4 of Section 33 83 02 Steel Antenna Tower, a paragraph has been inserted after 3.1.k. discussing Foundation Requirements. This paragraph states that a Geotechnical Investigation has been performed for this site and has been provided to the contractor for use and design of the foundation. Please provide this Geotechnical Investigation.	The Geotechnical Report provided via this Amendment. Please see attachment "P222_1737012_Geotech Report"

10	Page 18	01 57 19	1.5.1.1.5.3	Please confirm that the cost of establishing the water treatment system as described in Spec Section 01 57 19 paragraph 1.5.1.1.5.3 is to be included in CLIN 0001A and not in CLIN 0001E which describes a Unit Price for treatment of contaminated water.	Confirmed. Permitting, design, and establishment of the water treatment system as described in Spec Section 01 57 19 paragraph 1.5.1.1.5.3 is to be included in CLIN 0001A. It is the responsibility of the contractor to utilize means and methods that minimize the volume of dewatering needed to complete construction of this project.
12		VOL 2 AE411	Dtl: A3	Please provide a specification for the 3-Tiered, wall mounted, adjustable, open grated steel storager shelving indicated by Keynote 13 on Sheet AE411	Bid per construction documents.
13		28 31 76	1.6.1	Drawing FA-001 calls for Fire Alarm Circuits to be Class B, Spec 28 31 76 _ 1.6.1 indicates Class A. Please confirm if Fire Alarm circuits can be Class B.	Please see revision in Amendment 0005 Continuation Sheet and attachment "P222_1737012_28 31 76"
14		28 31 76	2.19	Paragraph 2.19 in Specification Section 28 31 76 indiactes that the mass notification transeiver must meet all the requirements of paragraph, RADIO TRANSMITTER AND INTERFACE PANELS. Please provide this paragraph as we are unable to locate it in the Bid Documents.	Please see revision in Amendment 0005 Continuation Sheet and attachment "P222_1737012_28 31 76"
15	page 10 of 65	Solicitat ion	Basis for Award Factor 1	The size and complexity requirements of the project may prevent adequate competition for this contract. To allow the evaluation of more recent experience and promote more competition we request the Government allow construction projects that are 75% complete, with interim	Bid per construction documents.

				CPARS, to fulfill the corporate experience requirement.	
16	page 13	01 32 17 00.20	1.10.1.10.1-d	Cost Loaded Network Analysis Schedule, specification 01 32 17.00 20 - 1.10.1.10.1-d states that the cost loaded schedule for commissioning, testing, and closeout WBS sections may not be less than 10 percent of the total costs for procurement and construction activities. Please confirm this is not less than 10% of the costs of the equipment to be commissioned and not the entire contract value.	The specification reads “The value of commissioning, testing, and closeout WBS section may not be less than 10 percent of the total costs for procurement and construction activities.”, reads as plural “activities.” and does not say equipment. The intent is for the FOW for the mechanical system commissioning as a whole WBS section, and not just the specific equipment.
18		Sheet IN602 Finish Legend		The Finish Legend indicates that AF2 Access Floor is based on "Tate DirectPERF 32%" Airflow Panels. While these panels may be used in the heavy duty CCN3000, heavy equipment cannot be rolled over these airflow panels. Per the manufacturer, the only airflow panel that will match the load performance of a CCN3000 panel is the HD GrateAire. Please confirm that the design intent is for the airflow panel to match the load performance of the solid access panels and that HD GrateAire panels should be the BoD for the AF2 Access Floor.	Confirming, yes, perforated panels are not recommended to be rolled over. Many facilities will still install them and restrict all equipment moves to the hot aisle where the solid panels are.
19		07 11 13		Advise damproofing is not applicable on this project; if it is applicable to the project, advise specific product / assembly and location where this is required.	Delete Specification 07 11 13. Please see Amendment 0005 Continuation Sheet.

20		07 21 13		Clarify with specific basis of design product / assembly what insulation is required on LP48 and LP48A foundation walls as there are contradictions between the bid documents: A1 & A3 / AE505 (LP48A) calls for XPS, B1 / AE511 (LP48) calls for concrete faced insulation panel, and Specification 07 21 13 - 2.1 calls for poly-iso.	Concrete face insulation panel is added to 07 21 13 and references to XPS are removed from the drawings. Please see Amendment 0005 Continuation Sheet and attachment "P222_1737012_07 21 13".
21		07 92 00		Clarify with specific basis of design product / assembly what Building Expansion Joint (BES) is required for large joints between the existing and new structure on LP-48 and provide revised details to reflect the requirement as specification section for expansion joint do not exist, specification section 07 92 00 Joint Sealants do not have a performance specification for expansion joints, details C1/AE513, A1/AE514, C4/AE514, A2/AE517, A3/AE518, A3/AE519, A1, A3, A4/AE520 depict air barrier membranes / sheets freely draping without direct adherence to solid substrate, which does not appear to be an appropriate application / method, call for Bellow Type, which appears to be an applicable term for expansion fittings for pipings and not building expansion joint, and call out / imply that the covers for the expansion joints are air barrier product, which does not appear to be correct designation.	Specification for bellows expansion joint cover system are added to section 07 60 00 in this Amendment (attachment "P222_1737012_07 60 00"). Application shown is within industry standards. Coordinate with product manufacturer / installer and air barrier consultant as required. The "air barrier" annotation is applicable to the bellow type building expansion joint cover because of the locations where metal flanges occur in the wall assembly. The flanges are sandwiched between the insulated metal panels, sealant, and air barrier materials, making them a component of the air barrier system at those locations.
22	Attachment H			CLIN 0010 Option 9 includes removal and disposal of buried below grade asbestos containing	Removal of the buried steam line is included in the base bid; see Civil demolition

				pipe insulation (insulation on pipe up to 24 inches in diameter). Clarify if pipe must be removed as part of this unit rate, or just the insulation on the pipe - general bid notes item k does not specify.	drawings. CLIN only applies if asbestos containing pipe insulation is identified when the steam line is uncovered. Means and methods are up to the contractor.
23	Attachment H			Clarify if CLIN 0010 Option 9 includes all excavation and backfill related to the asbestos containing pipe insulation removal. If required, please clarify depth of pipe. General bid notes item k does not specify.	Removal of the buried steam line is included in the base bid; see Civil demolition drawings. CLIN only applies if asbestos containing pipe insulation is identified when the steam line is uncovered. Means and methods are up to the contractor.
24	Attachment H			Clarify if FF&E design shall be included as a cost within the bid, or if this cost is not required and by others. If required to be by Contractor, please clarify which CLIN the design shall be included. CLIN 0003 identifies an AV design services cost. No FF&E design services cost CLIN is identified. Design is not identified as part of the scope of the Government Estimated Price in CLIN 0006 or CLIN 0007. Bid notes for ESS, FF&E and A/V (LINE ITEMS 0002 - 0007) item B is unclear if the design is by the Contractor.	The design/BVD of the FF&E is part of the construction contract. It is detailed in specification section 12 00 01.00 20.
25		09 96 00		Note O on IN602 states that various parts of the catwalk are to be coated in HPC2, but the structural drawings state that the external catwalk / antennae platform located above the hangar roof are to be coated in hot-dipped galvanized coating. Please confirm that the catwalk / antenna platform is to be hot-dipped galvanized coating and the extent of	Extents of HPC2 as indicated on IN602 is in reference to the Hangar itself.

				HPC2 is located within the hangar itself.	
26		IN101C (Drawing set 2/2)		Per keynote 36 & the legend, white HPC1 forms a ring around the hangar, and this is located on top of the ILDFA flooring. Please confirm that the HPC1 in this area is to be painted on top of the ILDFA.	Confirming, HPC1, FS1, and FS2 are applied on top of ILDFA (aluminum substrate).
27		IN601 (Drawing set 2/2)		Please confirm that within the hangar, the ring of flooring outside of the ILDFA, is to be RF3, and that the resinous flooring does not go under the ILDFA.	Correct. RF3 applies to floor area outside of ILDFA.
28		misc.		Due to there being 2 drawing sets, please confirm how we should delineate between the first set and the second set when we are asking PPIs. For example, A-001 shows up in volume 1 & volume 2 and is not designated between the two sets.	The 2 drawing sets are to be delineated by building (vol 1 is building LP-48A and vol 2 is LP-48 as depicted in the drawing title blocks).
29		Due Date		Please provide a 3 week bid extension to allow for PPI response integration and subcontractor pricing efforts.	Please see Amendment 0005; the proposal due date has been extended to 31 March 2026 at 2pm ET.
30		Factor 1		For project relevancy, Scope and Complexity is defined as; New construction of a multi-story steel framed building with concrete masonry walls. Question - Will projects that are steel framed without masonry walls be considered? Or do all 5 submitted projects have to have both steel frame and masonry walls?	Bid per factor 1 criteria.
31		41 22 13.15	1.3.1.2	The bridge crane specification describes two different types of classified area, a "general purpose hazardous area"	Class I, Division 2, Group C/D hazardous area for the entire ARS Work Center

				and a “Class I, Division 2, Group C/D hazardous area”. Which one applies to this project?	including Crane. See Volume 1, EH101.
32		10 51 13 Lockers	Part 2 Products	The Finish Legend on Sheet IN502 indicates the Scranton, Duralife Two Tier Z-Locker as the Basis of Design. The Scranton Duralife locker only comes in standard double tier design and is not available in a Z-Locker configuration. The Scranton Tufftec locker does come in a Z-Tier, however it is not Fire Rated as required by NFPA 286 in Section 10 51 13 paragraph 2.2.1. Please clarify the type and configuration of the lockers required.	Z-Tier will be adjusted to 2-high stacked design to maintain NFPA 286 performance. Please see sheet IN602 in revised drawings attachment "P222_1737012_Drawings_volume II_Rev 001_SIGNED".
33		08 34 73	3.3	The specification for the Sound Control Door Assemblies requires third party testing in accordance with ASTM E336. Please confirm that this testing is only required for the STC 50 rated doors and that it is not required at STC 30 or STC 45 door assemblies	Bid per construction documents.
34		09 29 00	3.1	The specification for the Gypsum Board requires third party testing of sound rated assemblies in accordance with ASTM E336. Please confirm the extent of the STC rated partitions to be tested as virtually every drywall partition has an STC rating which varies between 45 and 60.	This has been revised via this Amendment; please see Amendment 0005 Continuation sheet and attachment "P222_1737012_09 29 00".
35		Attach ment H	CLIN 0001C	Please confirm that the Unit Price per VLF associated with Foundation Piling in CLIN 0001C is only applicable to the Precast Concrete Piles. If a Unit Price for Concrete Filled Steel Piles (Micropiles) is	A revised Bid Schedule/ Price Proposal is provided via Amendment. Please see Attachment H - Price Proposal Form_rev1

				required, please provide an additional CLIN.	
36		AE602 & AE603		The Annex Building Door Frame Details J3 & H3 and J7 & H7 indicate "Perimeter Kerf w/Seal where indicated". Please confirm that Kerf is only required when the associated Hardware Set includes a Gasket Seal.	Confirmed.
37		SF521		Sheet SF571 describes modifications to the two (2) existing bridge cranes in the Hangar. In order to price this work, bidders require the Hoist manufacturer, model and serial number for each hoist.. Note 8 on Sheet SF521 refers to Specification 41 22 13.55. Please provide this Specification.	Revise SF521 Note 8 to refer to Specification 41 22 13.15. Hoist manufacturer and serial numbers not available. Please see revised drawings via this Amendment "P222_1737012_Drawings_volume II_Rev 001_SIGNED"
38		32 13 13.06	2.3.4	The Concrete Pavement specification indicates the use of a paver-finisher machine. To increase subcontractor participation in pricing concrete pavement work and logistical limitations of the work areas, please confirm that alternate placement methods (eg. truss screed placement) are acceptable in lieu of a paver-finisher, provided that alternate methods produce a comparable outcome."	Please see revision in Amendment 0005 Continuation Sheet and attachment "P222_1737012_32 13 13.06"
39	62 of 1234	013217.00 20	1.9.2	Confirm the project scheduler needs to be on site full time and they are not allowed to have any other responsibilities.	Confirmed, bid as shown.
40	289 of 1234	13526	1.7	Clarify if the project SSHO is allowed to have additional responsibilities - Section 01 45 00 1.6.1.1 references that the QC manager is to serve as the Level two site safety and health officer (SSHO) but	Confirmed - Dedicated SSHO, QCM and Superintendent. Neither of them can serve as one of the others.

				further states the only duties and responsibilities of the QC manager are to manage and implement the QC program on this Contract. With the complexity of this project please confirm a dedicated SSHO and a dedicated QC manager are required full time onsite.	
41	403 of 1234	15000	3.2.2.b	Provide the utility service rates that will be charged.	Please see attachment "FY26 Naval Station Norfolk Utility Costs" in this Amendment.
42	1195 of 1234	19100.15	1.11	Confirm the Commissioning firm is by the Owner - Section 1.11 states to employ the services of a commissioning firm and all commissioning specialists required to perform work for the project and section 1.2 and 1.12 states the Commissioning Provider (CxC) is an entity hired by the Government.	Yes, that is correct the CxA responsibilities are outlined in 01 91 00.15 22, Total Building Commissioning issued via this Amendment.
43	General	RFP		After attending the site visit and due to the phasing and complexity of the project - we respectfully request an extension of 3 weeks to adequately price the project.	Please see Amendment 0005; the proposal due date has been extended to 31 March 2026 at 2pm ET.
44	General	RFP		Will another site visit for subcontractors be allowed	No, bid per construction documents.
45	6	96723.16	1.3.5.5	Please consider removing both SSPC QP8 and SSPC SQ1 certification requirements for the fuel resistive resinous flooring 5 coat system installers. This certification is outdated and the BOD does not require the certification for their product. Will a portfolio of qualified projects and references from manufacturers suffice for qualifications, product	Bid per construction documents.

				manufacturers do not require the SSPC QP8 or SSPC QS1 certification.	
46	11	99000	1.6.3	Please consider removing the SSPC QP1 Certification requirements for subs performing surface prep and coating application under Specification 099000. Will a portfolio of qualified projects and references from manufacturers suffice for qualifications?	Bid per construction documents.
47	11	99000	1.6.3	If the specified SSPC QP1 Certified painters are not available, will equivalent industry certifications be accepted?	No, bid per construction documents.
48	IN602 Vol 2			Confirm all HPC coatings and subcontractor requirements (HPC1-3) fall under Specification 099600 and not 099000 Paints and Coatings.	Specification 09 96 00 covers HPC coatings and epoxy resin floor striping. Floor striping for ILDFA sounds in specification 13. 50 00, Section 2.12.
49	IN601 Vol 1, IN602, Vol 2	99000	1.6.3	Please clarify which painted metal surfaces fall under Specification 099000, specifically Paragraph 1.6.3, which requires the contractor to be SSPC QP1 certified. Our interpretation is that this requirement applies to finishes PT6 and PT7 when applied to metal, but confirmation is requested. This appears to be a very limited scope for an SSPC QP1 certification requirement.	Painted steel surfaces include: Doors and frames, metal stringers and handrails, exposed ceilings, exposed columns (except those with HPC coatings), bid per construction documents.
50	IN602 Vol 2			For new steel to receive HPC coatings, are they to be field applied or shop applied?	Field-applied, bid per construction documents.
51		11100	1.2	The contract specifications indicate that the building(s) will be occupied during performance of the work. However, the civil drawings identify construction phasing as	This has been revised via this Amendment; please see Amendment 0005 Continuation sheet and attachments "P222_1737012_Drawings_volume I_Rev 001 SIGNED" and

				Phase 1 (all work shown in Volume 1) and Phase 2 (all work shown in Volume 2), with no indication of occupied versus unoccupied areas within either phase. 1. Please confirm LP48 and LP48A will not be occupied during construction and this specification reference is intended for neighboring buildings. If either of them are to be occupied, clarify when and provide a scope / extent of areas that will be made available to the Contractor (by floor / admin vs hanger / percent of hanger etc.) and any operational constraints that must be maintained during construction.	"P222_1737012_Drawings_volume II_Rev 001_SIGNED".
52	IN602 Vol 2			Painted exposed steel structures (HPC3) is this refereeing to primary steel only or are we to paint primary and secondary steel HPC3?	Finish applies to both primary and secondary steel that are not specified to be shop-coated.
53	IN602 & IN601, Vol 2			Please clarify which rooms are to receive finishes HPC1 and HPC3. These finishes are not identified on finish schedule IN601. Many rooms with exposed metals are instead shown to receive PT6 and PT7 (epoxy coating). Since these finishes originate from two separate specifications with differing requirements, please confirm the correct finish designation for each applicable room.	Hangar H001 - reference Vol. II sheets IN101C, IN101D and general notes on IN602 for applications. HPC and FS finishes are captured in specification 09 96 00.
54	CU101 Vol 1 and 2			Confirm the Contractor is not responsible for any site utility charges/installation fees from the gas company. See Note 1 on CU101	Non concur, the contractor is responsible for all utility charges/installation fees from gas company. See attachment "FY26

					Naval Station Norfolk Utility Costs" in this Amendment.
55	IN601, Vol 2			In the Finish Remarks, #2, it reads "Provide (SSM2) Solid Surface Counters With Integral Sinks And A (PL2) Angled Apron." Please confirm the integral sink is required, and not a clipped in porcelain sink, which is typical.	Military projects prefer solid surface integral sinks in restrooms. This applies to both LP48 and LP48A. Provide integral solid surface sinks where noted in drawings.
56		Security Plans Vol 1 and 2		For the CAGs - are these to be provided by the Contractor and if so, how many will be required.	CAGs will be provided by the Government
58	Vol 2	122413		Please provide the locations of the RWS1 Roller Window Shades.	All windows in second floor offices and conference rooms at the building perimeter.
59	C-001	Vol 1 and 2		Construction Phasing - This section talks to Phase 1 (vol 1) having two site phases. Confirm the Tower Site and Power check pad pavement can be concurrent with the construction of LP-48A.	The GBSAA Tower and Power Check Pad scopes are concurrent with the construction of LP-48A.
60	C-003	Security Plan vol 1 and 2		Confirm there is only one Secure laydown area and one ACP -- each security plan references it. Will either need to be relocated / moved between phases? Provide location of the ACP as it is not indicated on the plans.	There is only one Secure Laydown Area, shown on C-003. It will not be relocated/moved between phases. The laydown area is accessed via the two entrances indicated on C-003. The LP-48A and LP-48 sites behind the flightline fence may be accessed via existing gate directly west of the LP-48A site (shown at the westmost keynote 16, Vol 1, CD101) and the existing gate directly north of the under-construction P-1027 hangar. Bid as shown, base access, laydown requirements and additional base access gates will be discussed

					at Preconstruction Kick-Off meeting with the award-winning contractor.
61	General	General		Confirm the P48A, Tower and airfield repairs are considered one project site and do not require additional safety / QC / Superintendent.	Confirmed. Bid per construction documents.
62	M-801, Vol 1	DDC System		Per note #1 within the Backflow Preventor Heated Enclosure Monitoring Schedule, can you please provide where this heated enclosure is located on drawing CP102? Also, please provide and show how the enclosure is being heated? And does this heat source need to be tied into the base wide BAS/DDC system?	Please see Vol 1: CS101 - keynote 17, CU101 - keynote 5, ES401 - keynote 11, and spec section 33 11 00 para 2.1.4., M-801 BACKFLOW PREVENTER HEATED ENCLOSURE MONITORING SCHEDULE
63	FX002 + P-501, Vol 1	Plumbing & Fire Protection		Per drawing P-501, detail C1, shows a 8" combination domestic water and fire protection service. Drawing FX002, detail shows a separate 6" fire protection service. Please confirm what is correct scope of work for both of these systems?	Water service to LP48A is supplied by a single 8" water line. The water service splits inside the building to domestic water and sprinkler. See Civil sheet CU101. See attachment "P222_1737012_Drawings_volume I_Rev 001_SIGNED" and "P222_1737012_Drawings_volume II_Rev 001_SIGNED"
64	SF521 Vol 2			Please provide the manufacturer and model of the existing overhead bridge cranes that are being modified.	See attachments "Crane - LP48 #1-DATA SHEET" and "Crane - LP48 #2-DATA SHEET"
65	SF521 Vol 2			Please provide the manufacturer and model of the existing vertical lift fabric door that is being modified.	Bid per construction documents; also, please see J&A for VLFD that was provided in Amendment 0003.
66	CS101 Vol 1	133420 Prefabricated Steel		Section 133420 calls for a 6'-0" x 7'-0" floor plan and looks to be a guard booth with Cashier Window. We could not find a	The prefabricated steel building is located at the GBDAA tower site. See Amendment 0005 Continuation

		Buildin g		contractor provided guard booth on drawings, only, the (2) guard shacks to be provided by government and installed by contractor shown at keynote 1 on CS101 Vol 1. Please confirm if these guard shacks are as specified in Section 133420 Prefabricated Steel Building?	Sheet and attachment "P222_1737012_13 34 20"
67	B3/ES402, Vol 1	133420 Prefabri cated Steel Buildin g		Please confirm whether the prefab building located at the GBDAA Tower found in Sheet B3/ES402, Vol 1 is that as specified in Section 133420 Prefabricated Steel Building? Section 133420 calls for a 6'-0" x 7'-0" and the prefab building located at the GBDAA Tower is 10' x 15'. To properly price, please provide elevations and section cuts for this prefab structure.	The prefabricated steel building is located at the GBDAA tower site. See Amendment 0005 Continuation Sheet and attachment "P222_1737012_13 34 20"
68	AE401 V1, AE401 V2	102813		Please provide the specifications for the following specialty items: Paper Towel Dispenser (B1), Semi-Recessed Trash Receptacle (B2), Soap Dispenser (C1), and Toilet Paper Holder (G1).	Bid per Construction Documents
69		122200 and 102123.16		Please confirm if Specification 102123.16 Cubicle Track and Hardware and Specification 122200 Curtains and Draperies are referring to the same items.	The correct specification for these items is 10 21 23.16. Spec section 12 22 00 is removed - See Amendment 0005 Continuation Sheet.
70	Vol 1	CU101 / PF101B		CU101 - note 1 calls for 2.5" gas line - PF101B calls for a 2" Natural Gas line - please clarify and update documents	Please see attachment "P222_1737012_Drawings_volume I_Rev 001_SIGNED"
71	Vol 1 and 2	TA001		Please clarify who is responsible for the TV Mounts for the AV system. (Contractor or TBD AV Contractor)	The Best Value Vendor AV contractor is responsible for the TV mounts.

72	Vol 1 and 2	TA101 A /101B		Who is responsible for the IP Video encoder and decoder and the IP Switch located within the telecom rack with fiber link -- is this by the (Contractor or TBD AV Contractor)	AV electronics, to include the AV encoders, decoders and IP switch are provided by the TBD AV contractor. Connectivity between these devices will utilize horizontal cabling on each floor under the Contractor's base telecom scope. The telecom drawings account for this cabling. The TA700 series drawings utilize dashed signal lines and keynotes to indicate which connections utilize the telecom cabling vs. dedicated AV cabling (solid lines). The fiber link between AV IP switches is base telecom scope.
73	Vol 1 and 2	TA001		Please clarify who is responsible for the Rack Cabinets and components for the AV system. (Contractor or TBD AV Contractor)	When referred to as "telecom rack" in the TA drawings, this indicates the rack is to be provided under the Contractors base telecom scope. The AV system is to occupy a small portion of the rack space; see telecom drawings for elevation/details. The AV credenza rack in Conf Rm 218 is a dedicated AV rack and to be provided by the TBD AV contractor.
74	Vol 1 and 2	TA001		Please clarify who is responsible for the cable for the AV system (Contractor or TBD AV Contractor)	The TBD AV contractor is responsible for all "solid line" cables/connections shown in the TA700 series diagrams. In instances where base telecom cabling is used for connectivity between AV devices, these signal lines appear as dashed and

					there is a keynote indicating such. Note, the telecom cable counts shown in the telecom drawings already account for these cables to be used for AV. What is shown in the TA700 series sheets is not in addition, but rather to shown the utilization of these cables where applicable to understand AV connectivity and signal flow.
75	RFP / Bid Form			Option on bid form are valid for 360 after award- RFP states 364 CD - please clarify	The RFP states "365". Please see attached revised bid schedule (Attachment H - Price Proposal Form rev1)
76	Bid Form			Confirm the Contractor is not responsible for the Design of the ESS system -- only the HAR under CLIN 2 - Confirm CLIN 2 is for P222 complete (includes both LP48A and LP48)	Correct - Contractor is only responsible for the infrastructure
77	Vol 1	AE112 B		Note 25 and 26 call that Privacy Curtain is FF & E. Confirm this is the scope of work included in specification section 102123.16	Privacy curtains tagged with Keynote 25 and 26 on Vol. I AE112B are not FFE. They are finish C2 and are part of the contractors scope as per IN102B, in addition to the associated track and hardware. You are correct, the specification for this item is 10 21 23.16. Spec section 12 22 00 to be removed - See Amendment 0005 Continuation Sheet.
78	Vol 1 and 2	IF101A thru IF102B		These sheets call out Lockers (Keynote1) Fire Extinguishers (General note B), VDU1 / VDU3 (General Note F) as FF and E --Please confirm these are to be included in the FF & E Package (not	These items are to be included in this bid - CFCI Keynote 1 on both Vol 1 and Vol II sheet IF101A notes Lockers indicated as CFCI (Contractor

				in base contract) or to be included in the bid.	Furnished/Installed) - these are not called out as FFE. Lockers noted with CFCI are part of the contractors base scope. Other storage lockers (such as S18 noted on Vol I sheet IF102B), which are items not bolted to the structure, are noted on the Furniture Schedule IF-001 and are FF&E since not affixed to the building. There is a third type of "locker" indicated with a GF-tag. These "lockers" are GFGI (Government furnished) and are not part of the Contractors scope. Fire extinguishers (not cabinets or brackets - extinguishers only) are part of FF&E. General Contractor is to provide the cabinets and brackets for each type indicated. VDU1 / VDU3 (General Note F - both Volumes) notes these items are part of Construction and are therefore part of the Contractors scope. Provide as part of base contract.
79	Vol 1 and 2	IF101A thru IF102B		Advise if the Fire Extinguisher cabinets (General Note B) are to be included in the FF & E package (not in the base contract) or to be included in the bid.	These items are to be included in this bid - CFCI Fire extinguisher cabinets and brackets are included in the base contract and provided by the General Contractor.
80	Vol 2	ED111 C		Note 5 calls for hanger door equipment to be replaced - or refurbished by hanger door manufacture - clarify	Refer to Vol 2, SF521 for scope of work requirements

				scope - what is the existing manufacture - is it just the motors to be replaced or additional items. Provide a specification	
81		120001.00 20 Furniture Fixtures and Equipment (FF&E) Package	1.3	Section 120001.00 20 (1.3) defines what is considered FF&E. Please confirm Is signage is to be included in the FF&E interior Design effort scope.	Signage is part of the base contract, not FF&E as it is adhered to the building.
83	Vol 1: AE512, AE513, AE514 and Vol 2: AE506, AE507 and AE508	134920.00 10 RFI Shielding		The RF Shielding Detail Drawings Vol 1: AE512, AE513, AE514 and Vol 2: AE506, AE507 and AE508 refer to a shielded panel system. Is the intent to use modular RF shielding, as opposed to a wall finish such as foil?	Bid per construction documents. The RF shielding is under a J&A for SRG Shielding Resources Group that was in Amendment 0003.
84		134920.00 10 RFI Shielding		Specification 134920.00 10 refers to SELDS testing throughout, which only applies to welded shielding. Is any portion of the RF shielding to be welded?	Bid per construction documents. The RF shielding is under a J&A for SRG Shielding Resources Group that was in Amendment 0003.
85		134920.00 10 RFI Shielding		How will the RF performance be verified? Is the shielding contractor to test the RF shielding per IEEE299 and at what frequency(ies)?	Bid per construction documents. The RF shielding is under a J&A for SRG Shielding Resources Group that was in Amendment 0003.
86	Vol 2	EP131		Confirm the CDL Platform is GFGI and the Contractor only owns the CDL Power Terminal Box and conduits / power switch / CDL Fiber patch panel.	The CDL Platform is GFCL. The structural framing of Platform to catwalk is CFCL. See amendment.
87	Vol 2	CD101		General Note 3 states 12" thick layer of cement treated aggregate is existing under existing pavement surfaces -- Geotech references 18" What should be assumed. Additionally, is this condition located under LP-48.	Bid per CTA is 12" thick.

88	Vol 2	PD100 B		Per drawing PD100B, please confirm there will be no plumbing work required within this drawing.	No plumbing work required on PD100B
89	Vol 2	P-501		Per detail A4, Gas Fired Water Heater -DWH-1, please indicate where the venting associated with the water heater is shown on the Mechanical Drawings.	The intent is to replace the existing domestic water heater in the same location and use the existing water heater flue vent
90	Vol 2	P-001		Per drawing P-001, General Note #40, since this scope of work is not shown on the drawings, please provide quantities for each item, so we can provide accurate pricing or provide a bid form allowance for this scope of work	For bidding, include patching 200 linear feet of existing pipe insulation and repair/replace 20 existing pipe supports.
91	Vol 2	230130.41		Regarding specification 230130.41 (HVAC System Cleaning), please provide quantities of existing equipment, ductwork and piping that will require cleaning or provide drawings, showing all HVAC system cleaning scope of work.	All Equipment, ductwork, louvers, screens, etc that are existing to remain. Refer to MD101C, MD101D, MD101A (Plan North of Column line A), MD102(North of Column line A & South of Column line C), and MD401. Items include but are not limited to Fans, ductwork, unit heaters, ductwork, louvers, ventilation hoods, screens.
92	A2/AE513 Vol 1			Will the RAF required a sealed concrete floor at the slab?	The slab below the static dissipative ESD raised access floor system does not require an additional sealed concrete floor finish.
93	Vol 2	335210		Regarding the Fuel System Piping specification, where is this scope shown on the drawings? What is this piping system associated with?	The fuel piping system associated with this specification begins at the point where the ILDFA Effluent Pipe exits LP-48 (see PL101A). All above grade piping related to the ILDFA Effluent

					Containment Tank and ILDFA Effluent Pipe outside of the building must adhere to 33 52 10 unless recommended otherwise by the tank manufacturer.
94	Vol 2	SB503 & SB504		Please confirm that new slab on grade concrete and slab on grade infills require gas barrier system per specification 072623.1922.	Bid per construction documents. Provide gas barrier system where indicated.
95	General			Due to the reach and the adjacent building locations, please confirm that we are permitted to have a crane on the Air Side of the LP48 Hangar to install the trusses and towers. The crane will be layed down at the end of each shift.	To be coordinated with NAVFAC construction team post contract award. Bid per construction documents.
96	SECTION 01 91 00.15 Page 7	01 91 00.15	1.12 GOVERNMENT HIRED COMMISSIONING PROVIDER	Section 01 91 00.15 indicates that the Government intends to procure the Commissioning Authority (CxA) under a separate contract. In our experience with similar Government projects, commissioning services are often procured through the General Contractor. If these services have not yet been procured and NAVFAC anticipates soliciting proposals directly, we would appreciate the opportunity to submit a proposal for consideration. Does the CxA firm follow the same procedures as the GC for submission of proposals?	Government procured Cx services for MIDLANT Projects are procured through Design IDIQs, not subcontracted through Construction Contracts. The government will provide independent (third-party) Cx services in accordance with 01 91 00.15 22, Total Building Commissioning issued via this Amendment to the contract documents. No proposals for Cx services will be accepted.
97	Attachment F- _Small_Business_Participation_Commitment			Does not having a SWAM certification automatically disqualify you from being selected for Cx Services?	Government procured Cx services for MIDLANT Projects are procured through Design IDIQs, not

					subcontracted through Construction Contracts. Qualifications are defined in the RFPs for those IDIQs. The Construction Contractor has responsibilities that may be subcontracted for verification and testing in accordance with the construction contract and the qualifications required therein, also described in the Solicitation for Construction Services as amended. Additionally, SWaM (Small, Women and Minority businesses), is a certification program in Virginia designed to enhance procurement opportunities for businesses in state-funded projects. This is not a state-funded project.
98		134920.00 10 RFI Shielding	2.6	Reference 13 49 20.00 10 - 2.6 which calls for power, data, and signal filters. However, only (4) power filters within Set 1 <i>[reference sheet EP401 which identifies (1) 150A, 480Y/277V, 3PH, 4W; (2) 500A, 480Y/277V, 3PH, 4W; & (1) 225A, 480Y/277V, 3PH, 4W]</i> and (6) power filters within Set 2 <i>[reference sheet EP401 which identifies (4) 120V, 20A, & (1) 277V, 20A, and EP702 which identifies (1) 225A, 480Y/277V, 3PH, 4W]</i> are shown. If any additional power or signal filters are required for Fire Suppression, Plumbing, HVAC Ductwork & Piping, HVAC Controls, Electrical, Fire Alarm,	Refer to General sheets for utility penetration plans, requirements and details. Fiber to be used for communication/control wiring for fire protection, HVAC, telecom, ESS, as indicated per discipline.

				Telecommunications, Outside Plant, etc., please identify size/location for each. Alternately provide a schedule with the quantity and sizes of any additional power, data, and signal filters or stipulate an allowance that all bidders can include.	
99		313116.13		Confirm soil treatment for termite is only at new slabs	Bid per construction documents.
100		Bid Form		Is there a CLIN / unit price for the micro piles on bldg. LP48 since there is one for the concrete piles on LP48A -- please confirm	A revised Bid Schedule/ Price Proposal is provided via Amendment. Please see Attachment H - Price Proposal Form rev1
101	Vol 2	Battery Charging Areas		Please indicate Lithium Battery Charging Rooms will be considered hazardous and all materials and equipment within these rooms are to be considered explosion proof? Are there any other rooms that require explosion proof materials and equipment?	Refer to hazardous location plans on Electrical EH series sheets
102	Vol 1	092900 Gypsum Board	3.4	Please clarify the required gypsum board finish at wallcovering locations— General Note C on AE101A–AE102B calls for Level 5 at WC areas, but Specification Section 092900 3.4 indicates Level 4 for wall coverings.	Follow the specification section for a level 4 finish. See amendment for updates to Vol 1 sheets AE101A-AE102B removing General Note C. Traditional Type II wall coverings not on this project (Attachment P222_1737012_Drawings_volume I_Rev 001_SIGNED)
103	Vol 1	092900 Gypsum Board	3.4	Please confirm the required finish level for all gypsum board walls, partitions, and ceilings. Spec Section 092900 3.4 states Level 5 unless otherwise specified, but	Level 5 finish not required. Please see Amendment 0005 Continuation Sheet and attachment "P222_1737012_09 29

				the drawings (General Note C on AE101A–AE102B) indicate Level 5 at walls receiving wall coverings. Is it the intent for all walls to receive Level 5?	00" for revised specification.
104		General		Please provide the full Geotechnical Report for this project.	Please see attachment "P222_1737012_Geotech Report"
105	Vol 2	SB101 A		Note 11 - confirm if the adjacent existing exterior CMU wall (not shown) will require demolition at the same openings.	Bid per construction documents.
106		Div 25 Cybersecurity		Please verify whether there is presently any site-wide UMCS (Utility Monitoring and Control System) in place at naval station Norfolk, and whether there is an obligation for the HVAC and utility usage data of this project building to be transmitted to other buildings.	Please refer to Vol-1 sheet M-801 AND VOL-2 sheet M-801 - DDC CONTROL SYSTEM ARCHITECTURE.
107		Div 25 Cybersecurity		Please furnish confirmation concerning the wireless (RF) alarm signal connection method from the Fire Alarm Control Panel (FACP) in the new building to the centralized base fire alarm supervising station or Emergency Operation Center (EOC). If that's the case, kindly verify whether there is an already established ATO (Authority to Operate) for the wireless communication network.	Please see Amendment 0005 Continuation Sheet and attachment "P222_1737012_28 31 76" for revisions.
108		Div 25 Cybersecurity		Kindly verify the absence of a base-wide Mass Notification System (MNS) at naval station Norfolk and confirm that the MNS for this building is locally managed, without any external communication.	Bid per construction documents.

109		Div 25 Cyberse curity		Please provide confirmation that the fire detection and alarm control system of this building has an impact rating of L-M-M for C-I-A (Confidentiality, Integrity, and Availability).	Bid per construction documents.
110		Div 25 Cyberse curity		Please confirm that active CCTV and PACS systems, including the associated PIT network, are not required within the scope of this project's commissioning.	Bid per construction documents.
111		Div 25 Cyberse curity		Please confirm the mission criticality rating for this project facility's aligns with the Mission Support Category.	Mission Critical
112		095100 Acousti cal Ceilings		Please confirm whether approved equivalent manufacturers are acceptable for the ACT panels and ACT suspension system.	Yes, other approved equivalent manufacturers with products of equal performance to the basis-of-design products are acceptable for the ACT panels and ACT suspension system.
113	SF521 Vol 2			Contract Drawing SF521 does not provide a list of testing requirements for the Vertical Lift Fabric Door Repairs. Please advise what testing is required for acceptance after the repairs are completed.	Bid per construction documents.
114	CS101, CS501	Tempor ary Guard Shack		Note 1 on CS101 provides information on a temporary guard shacks during construction. The guard shack is indicated as provided by government and installed by contractor and references detail A3/CS501. Detail A3/CS501 is pavement striping and signage detail. Please identify correct detail for temporary guard shack. Please clarify if guard shacks referenced on	Pleas see attachment "P222_1737012_Drawings_volume I_Rev 001_SIGNED"

				CS101 are related to the CUI plans for CSP, or a separate scope. Please clarify who is responsible for furnishing and installing these guard sheds.	
115	CS101	Note 18, note 26		Note 18 on CS101 indicates replacing disturbed flight line pavement markings. Please provide information on what scope is disturbed, or if contractor should include replacement of all flight line pavement markings adjacent to project. If replacing all adjacent flight line pavement markings is intent, please provide line of demarcation for scope.	Pavement markings disturbed by the demolition of pavement within the LOD must be restored. Refer to sheet CD101 for LOD.
116	CS101	Note 13, Note 19		Note 19 on CS101 indicates replacing disturbed P1027 fire lane pavement markings. Please provide information on what scope is disturbed, or if contractor should include replacement of all fire lane pavement markings adjacent to project referenced by note 13 and note 19.	Pavement markings disturbed by the demolition of pavement within the LOD must be restored. Refer to sheet CD101 for LOD.
117	ES101, TS701, ES601, T0001			Drawings are unclear as to what is to be assumed for new and existing conduits as it relates to the telecom runs. On ES101 the new telecom runs are not noted and indicate that these could be existing conduit with new fiber pulled through. But ES601 contradicts this as the schedule notes new 4" conduit. Please clarify the existing to remain scope and the new scope required.	TS701, Detail C1 is a diagram for cable only but new and existing conduits and MHs are denoted by grey (existing) and black (new). TS701 Details A2 and A4 show the new conduit. ES601 is a cable schedule. The 'N' denotes new cable.
118	ES101, TS701, ES601, T0001			TS701 appears to show a new telecom run from building W143 to LP48A to LP212 to GBDAA.	TS701, Detail C1 is a diagram for cable only but new and existing conduits and MHs are

				T001 Telecom Legend notes a “dark and solid indicates new item” but ES601 does not mirror TS701 nor does it note if we are to be running new conduit along the entire run per drawing TS701. Please clarify the existing to remain scope and the new scope required.	denoted by grey (existing) and black (new). TS701 Details A2 and A4 show the new conduit. ES601 is a cable schedule. The 'N' denotes new cable.
119		01 11 00	1.2	Specification 01 11 00, §1.2 Occupancy of Premises states 'Building(s) will be occupied during performance of work under this Contract.' Please advise to what extent occupancy during construction will be for approach, coordination, access, and sequencing.	No longer applicable. Please see revised drawings in this Amendment (attachments "P222_1737012_Drawings_volume I_Rev 001_SIGNED" and P222_1737012_Drawings_volume II_Rev 001_SIGNED")
120		01 50 00	3.2.2	Per 3.2.2, b. reasonable amounts of the utilities listed will be made available at the prevailing rates. There are no values listed for each utility. Please advise what the rates are for each utility.	Please see attachment "FY26 Naval Station Norfolk Utility Costs" in this Amendment.
121	AE103			Keynote 76 on AE103 calls for a fall arrest horizontal lifeline. Please advise if this should be a newly installed lifeline system, and please provide specifications if so.	The fall arrest horizontal lifeline is to be installed as part of the contract. Refer to specifications section 07 22 70 Standing Seam Metal Roof Anchor.
122	C1 & C3 / AE203, C1 & C3 / AE204, C5 & B5 / AE513 C1 & C2 / AE514			Advise if C5 / AE513, miter cornered IMP at outside corner of horizontal IMP, is indeed correct as AE200 series, elevation drawings, appears to depict "single piece" outside corner panels or CONT PREFINISHED MTL CORNER FLASHING (as shown on C1 / AE514), and other similar conditions at corners, such as B5 / AE513, and C1 & C2 / AE514, do not show miter cornered IMP.	C5/AE513 is the typical detail for horizontal IMP at an outside corner. C1/AE514 is the typical detail for vertical IMP at an outside corner. They are different conditions. Bid per construction documents.

123	SF100 series			Sheet SF103D does not exist, but is needed to align scope as shown on AD101D. Please advise if SF103D will be provided to bidders.	Bid per construction documents.
124		PPI Date		Please provide a 2 week extension for contractor PPI's to allow for subcontractor review of documents, amendments, and submission of questions.	Please see Amendment 0005; the proposal due date has been extended to 31 March 2026 at 2pm ET.
125		Sheet C-001		The Construction Phasing Note on Sheet C-001 states that Volume 2 work will not commence until Volume 1 work is completed and accepted by the Government. Please confirm that completion of Volume 1 Work and LP48A includes the ESS, A/V and FF&E Options as described in CLINs 0002, 0004 and 0006 if exercised by the government.	Please see revisions to attachment "P222_1737012_Drawings_volume I_Rev 001_SIGNED" and "P222_1737012_Drawings_volume II_Rev 001_SIGNED"
126		Attachment H Price Schedule	Bid Note "f" for ESS, FF&E and A/V	The Attachment H Price Schedule states that "If awarded, the FF&E, A/V and ESS modification will be awarded at least 6 months prior to the contract completion date. Please confirm that FF&E, A/V and ESS as described in CLINs 0002, 0004, and 0006 associated with Building LP48A will be awarded not later than 6 months before Contractor's anticipated turnover date for Building LP48A.	Confirmed. Bid per construction documents.
127		Construction Schedule		Please confirm if time must be allocated in the construction schedule for the government to relocate from the hangar to the annex building? If so, how many calendar days does the government anticipate for this relocation activity?	No longer applicable. Please see revised drawings in this Amendment (attachments "P222_1737012_Drawings_volume I_Rev 001_SIGNED" and P222_1737012_Drawings_volume II_Rev 001_SIGNED")

129		PL101B		The civil utility drawings indicate that the sprinkler system will be connected to the domestic water distribution system, but the sprinkler riser details do not include backflow preventers. Please confirm that backflow prevention is required on the sprinkler system in LP48A. Sheet PL101B indicates BFP-1 at the water service entry but there is no backflow preventor for the Fire Service on FX101B.	An RPZ type backflow preventer is required for the sprinkler system in LP48A per Specification 21 13 13: 2.5 and is shown on FX001 and FX101B in the Mechanical Room 129.
130		Attachment H Price Schedule	CLIN 0002	The Option Pricing for the A/V and FF&E are separated by building in different CLINs. Please confirm that CLIN 0002 Option Item No. 1 for providing Electronic Security System (ESS) is for both buildings LP48A Annex and LP48 hangar.	Confirmed. Bid per construction documents.
131		EP121B	Note 9	The CDL Antenna System on the roof of LP-48 Hangar is noted as GFGL (REF: EP131). Please confirm that the GPS Antenna located on the Roof of the LP-48A Annex is also GFGL.	GPS platforms are CFCL. See details on structural sheets as referenced
132		CSP	Clearance Requirements	The CSP indicates the Construction Security Coordinator (CSC) shall be a Secret cleared U.S. Citizen. Since there are no other requirements for personnel to have a secret clearance, nor any classified documents, to reduce burden we request the requirement for the CSC to have a Secret clearance be removed. If the CSC must have a Secret Clearance will the Government consider proposals to meet solicitation requirements and be eligible for award for contractors that do not possess a facility	For key personnel with employers that do not possess a facility clearance, they will need to be vetted by NAVFAC security. NAVFAC security will need to provide us with cleared personnel lists.

				clearance, but represent that they have eligible employees using a Limited Access Authorization to meet the Security clearance requirements for the CSC? If so will the Government (1) process Limited Access Authorizations (LAAs) for key personnel whose employer does not possess a facility clearance and (2) allow the CSC to perform their duties while the CSC clearance information is verified via DISS?	
133		Solicitation	CUI Requirements	DFARS 252.204-7012, incorporated by reference in the solicitation, defines a “covered contractor information system” as “an unclassified information system that is owned, or operated by or for, a contractor and that processes, stores, or transmits covered defense information.” DFARS 252.204-7012 defines “covered defense information” as “unclassified controlled technical information or other information, as described in the Controlled Unclassified Information (CUI) Registry at http://www.archives.gov/cui/registry/category-list.html, that requires safeguarding or dissemination controls ...” The specifications provided in the solicitation do not contain any markings, the drawings are marked unclassified and there are no specific CUI markings that would indicate the information requires further safeguarding or dissemination controls.	Please see section 17. Document Control “All finished-state documentation provided by or developed for the U.S. Government is considered Controlled Unclassified Information (CUI) and is accountable. CUI documents shall not be modified and/or all CUI markings shall not be removed for convenience. Documentation containing the following finished-state information falls into this category: a) Detailed locations of penetrations into the secure space for HVAC, electricity, plumbing, telecom, and computer networks, etc. b) Detailed locations of internal electrical switches, panels, covers, or circuit boxes. c) Detailed locations of installed security equipment. d) Physical and logical

				Therefore, please confirm that this contract is not subject to the implementation of NIST SP 800–171 controls included in DFARS 252.204-7012.	wiring or networking layouts.
134		Solicitation	CUI Requirements	Further to the above PPI, in order to reduce burden, increase small business participation and promote effective competition please confirm and remove DFARS 252.204-7012, 252.204-7019 and 252.204-7020 as they do not apply to this contract as the project information is not “covered defense information.	Please see section 17. Document Control “ All finished-state documentation provided by or developed for the U.S. Government is considered Controlled Unclassified Information (CUI) and is accountable. CUI documents shall not be modified and/or all CUI markings shall not be removed for convenience. Documentation containing the following finished-state information falls into this category: a) Detailed locations of penetrations into the secure space for HVAC, electricity, plumbing, telecom, and computer networks, etc. b) Detailed locations of internal electrical switches, panels, covers, or circuit boxes. c) Detailed locations of installed security equipment. d) Physical and logical wiring or networking layouts.
135		Solicitation	CMMC	DFARS 252.204-7021, incorporated by Full Text, section (f) requires the Contractor to flow down the substance of this clause in subcontracts. While Prime Contractors will flow down the clause in subcontracts as required by (f)(1) most	Please see section 17. Document Control “ All finished-state documentation provided by or developed for the U.S. Government is considered Controlled Unclassified Information (CUI) and

				subcontractors do not have a CMMC certificate or started self-assessment for even CMMC Level One. In order to promote effective subcontractor competition, increase small business participation, and reduce burden please provide relief by not requiring subcontractors to have a current CMMC certificate or current CMMC status prior to the Contractor awarding a subcontract as indicated in (f)(2).	is accountable. CUI documents shall not be modified and/or all CUI markings shall not be removed for convenience. Documentation containing the following finished-state information falls into this category: a) Detailed locations of penetrations into the secure space for HVAC, electricity, plumbing, telecom, and computer networks, etc. b) Detailed locations of internal electrical switches, panels, covers, or circuit boxes. c) Detailed locations of installed security equipment. d) Physical and logical wiring or networking layouts.
136		01 14 00	1.3.1.2.1	The Work Restrictions in Division 1 require the use of U.S Citizens for General Construction and Finish Work of the secure area. The CSP only requires U.S. Citizens for the "finishing work". Please confirm that U.S Citizens are only required for the "finishing work".	Per CSP Section 21. Citizenship Requirements "In accordance with U.S. Government policy, the design and construction of P-222 shall be accomplished by U.S. Companies using U.S. persons, as per the Technical Specifications for Construction and Management of Sensitive Compartmented Information Facilities for ICD/ICS 705 Version 1.5.1. This document and other relevant references are available on the NAVFAC Directives and Guidance". Note: U.S. persons may be permitted provided that they are U.S.

					person(s) and meet eligibility requirements as defined in 8 U.S.C. 1101(a)(20) or who is a protected individual as defined by 8 U.S.C. 1324b(a)(3) and provide proof of eligibility. This does not guarantee approval by the SSM/SSO as each individual will be reviewed and approved according to the CSP.
137		Solicitation		The CSP requirement that all materials used on this project shall only be purchased through US suppliers/vendors appears to conflict with FAR 52.225-11 Buy American Materials under Trade Agreements. Please confirm that U.S. suppliers and vendors can procure materials in accord with FAR 52.225-11.	Per CSP section 19. Material used on this project shall only be purchased through US suppliers/vendors.
138		Site Access		In formulating our site logistics plans, base access and laydown requirements, are there any alternative or additional base access gates, laydown areas or logistics deliveries areas available for GC use?	Bid as shown, base access, laydown requirements and additional base access gates will be discussed at Preconstruction Kick-Off meeting with the award winning contractor.
139	Drawing	M601		Please Verify Flow rate	Pls see M-601 in revised drawings attachment "P222_1737012_Drawings_volume II_Rev 001_SIGNED" included in this Amendment.
140	Drawing	M601		Please Fan Horse Power	Pls see M-601 in revised drawings attachment "P222_1737012_Drawings_volume II_Rev 001_SIGNED" included in this Amendment.

141	Drawing	M601		Please provide more specification for blowdown pump assembly separator	Pleased see M-601 in revised drawings attachment "P222_1737012_Drawings_volume II_Rev 001_SIGNED" included in this Amendment.
142				We are unable to identify any work associated with the following specifications in the Drawings. Please confirm that the these Specifications are not applicable to this project: 1) 03 42 13.00 10 PLANT-PRECAST CONCRETE PRODUCTS FOR BELOW GRADE CONSTRUCTION 2) 09 62 38 STATIC-CONTROL FLOORING 3) 12 22 00 CURTAINS AND DRAPES 4) 12 24 13 ROLLER WINDOW SHADES 5) 13 34 20 PREFABRICATED STEEL BUILDINGS	12 24 13 ROLLER WINDOW SHADES: Bid per construction documents. See Amendment continuation sheet; 03 42 13.00 10 PLANT-PRECAST CONCRETE PRODUCTS FOR BELOW GRADE CONSTRUCTION is deleted from the project. 09 62 38 STATIC-CONTROL FLOORING is deleted from the project. 12 22 00 CURTAINS AND DRAPES is deleted from the project. 13 34 20 PREFABRICATED STEEL BUILDINGS specification is replaced in it's entirety.
143	AD101C	Drawin g set 02		Will the Designer of Record provide the necessary structural engineering support after contract award to substantiate the concrete pour-back design and confirm trench invert depths for new ILDFA trenches, at no additional cost to the contractor?	DOR will not provide. Unclear what engineering would be needed. Trench is detailed on Structural. Bid per construction documents.
144	3/3/2026	Drawin g set 02		Should the ILDFA bidder include a cost allowance in its proposal to cover third-party structural engineering required to validate and complete the pour-back design for both	Provide complete system. Bid per construction documents.

				the new and existing trench scope?	
145	3/3/2026	Division 08 DESIGN NOTES / S001 AE601		Advise UFC 4-010-01 Level of Protection required on the project as callouts and statements such as "EXTERIOR DOOR ASSEMBLIES, INCLUDING THE FRAME AND ANCHORAGE INTO ROUGH OPENING, MUST BE IN COMPLIANCE WITH CURRENT UFC 4-010-01 AT / FP REQUIREMENTS." on General Notes H and I / AE601 (LP48) and General Notes J / AE601 (LP48A), and "Curtain Wall assembly must meet the antiterrorism performance criteria specified in UFC 4-010-01" on Specification Section 08 44 00 - 1.9.1 does not the address the specific level of protection required on the project.	Bid per construction documents.
146	FX102			FX102 keynote #1 refers to the use of an one pipe penetration through the secure boundary for sprinkler protection. This mentions installation of the pipe penetration per detail C4/GI202. This detail seems not to be in the set. Could you provide the detail.	Please refer to B1/GI202 for penetration of secure boundary detail with sprinkler piping.
147	MH101B			(MH101 B) - Provide detail for battery charging exhaust hood.	Exhaust Hood length and depth as shown and noted on MH101B. Provide a 22.5 degree taper from hood edges to centered duct connection. Provide mounting bracket at each of the hood's four corners. Hood's bottom edge is to be 4".

148	MH101B			(MH101 B) - Confirm the lead acid battery shop exhaust duct is galvanized and not 316 SS.	All battery rooms (106,108, & 109) shall be 316 Stainless Steel
149	SF521, dwg set 01	41 22 13.15		Please provide information on the LP-48's existing-to-be-modified bridge cranes such as their: rope lengths, diameter of ropes, number of parts of rope (number of sheaves in the block and how many times it goes up and back), and dimensions of the hoist drum.	Information not available. Bid per construction documents.
150	AE101A, AE101B, A3/AE411	Drawin g set 02		Please provide specifications for helmet hookboards and steel storage shelving units for lithium batteries. Please clarify if these are part of the Government Estimated Price for FF&E or if these are required by the CM separately.	Bid steel storage shelving per construction documents. For helmet hookboards, provide 7-hook Coat/Hook Rack, such as item #2008-D in Smooth Plate Aluminum by Pit Products or equal.
151	AE111C	11 66 00	2.1.9	Regarding the divider curtain per specification section 11 66 00 - 2.1.9, feedback from the subcontractor vendor indicates that the minimum length for a section of curtain and frame is 15'. Drawing AE111C indicates two sections of curtain that are 12'-11 1/2" and 10'-5 1/2" in length respectively. Please provide direction if an alternate system shall be carried for these sections of curtain and curtain track as they cannot be furnished and installed as drawn and specified.	There are manufacturer's / fabricators that can produce the length indicated. Bid per construction documents.
152	CS505			CS505 details the fence foundations for the deadman and typical fence post foundations. Please clarify if the contractor is to assume multiple layers of existing onsite asphalt and concrete paving to core and cut through to	Demolition and geotech sheets indicate required information. Bid per construction documents.

				install the fence footings and deadman footing. Subcontractor feedback indicates that different areas of the base may include multiple layers of asphalt and concrete paving that incur additional costs to cut through in order to install the foundations per this detail. These potential obstructions may be small enough in nature not to fall under the obstruction removal CLIN, but still impact costs and schedule for installing fence foundations.	
153	CS505			CS505 details the fence deadman foundation. Please indicate if the deadman footing should be backfilled with concrete, onsite fill, imported structural fill, or other methods.	Deadman footings are in a paved area. Requirements for earthwork under such conditions are provided in specification section 31 23 00.00 20.