

STATEMENT OF WORK

1. Objective/Requirements

- 250-Ton Hydra-Set Complete Functional Test, Proof-Load and Calibration

2. Characteristics, Scope, and Specs

- The contractor shall perform the following duties:
- Complete Functional test, Proof-load and Calibration of one (1) Model DHS-250R System.
- Perform static structural proof test at 200% (1,000,000 lb.) with the piston rod fully extended.
- Static hydraulic system proof test at 125% (625,000 lb.) with the piston rod at mid stroke.
- 10-point calibration for accuracy within .5% of full load scale.
- Complete Functional hoisting and rotation test at 250,000 lbs. This test includes hanging the Hydra Set with a load of 250,000 lbs., rotation both directions of the Hydra Sets load, the full 12-inch stroke (checking the linear travel function), verifying the 250,000 weight to be within the .5% calibration standard, plus or minus 2500 lbs.
- One hour hang test with a 250,000 lbs. load.
- Physical check of external leakage.
- Physical check of internal leakage.
- Calibration test report.
- Certificate of Conformance

3. Place of Performance

Contractor Facility

4. Period of Performance

Six week after arrival of the hydra-set at Contractor Facility