



Table 4-1			
PCB Sampling			
P-1112 Power Plan Resiliency Improvements			
Portsmouth Naval Shipyard, Kittery, ME			
Sample No.	Sample Location	Description of Material	Total PCB Content (mg/kg)
PCB-01	Saltwater Room	White Brick Wall	1.370
PCB-02	Saltwater Room	Green Brick Wall	1.160
PCB-03	Saltwater Room	White Brick Wall (Opening)	4.090
PCB-04	Saltwater Room	White Brick Wall	0.511
PCB-05	Saltwater Room	Black Foundation Coating	ND
PCB-06	Saltwater Room	Red Brick Wall	3.400
PCB-07	Saltwater Room	White Brick Wall (Opening)	2.130
PCB-08	Saltwater Room	Red Concrete Floor	3.510
PCB-09	Saltwater Room	Blue Concrete Wall	2.160
PCB-10	Saltwater Room	White Crane Wall	6.170
PCB-11	Saltwater Room	Red Crane Rail	2.660
PCB-12	Maintenance Room	Red Concrete Floor	1.290
PCB-13	Maintenance Room	Blue Concrete Wall	1.230
PCB-14	Maintenance Room	Blue Metal Doorframe	2.170
PCB-15	Maintenance Room	White Concrete Wall	1.530

Asbestos Containing Material Bulk Sample Results			
P-1112 Power Plan Resiliency Improvements			
Portsmouth Naval Shipyard, Kittery, ME			
Sample No.	Sample Location	Description of Material	Percent and Type of Asbestos
01A	Saltwater Room	Wall Paint	No Asbestos Detected
01B	Saltwater Room	Wall Paint	No Asbestos Detected
01C	Saltwater Room	Wall Paint	No Asbestos Detected
01D	Saltwater Room	Wall Paint	No Asbestos Detected
01E	Saltwater Room	Wall Paint	No Asbestos Detected
02A	Saltwater Room	Floor Leveler	No Asbestos Detected
02B	Saltwater Room	Floor Leveler	No Asbestos Detected
02C	Saltwater Room	Floor Leveler	No Asbestos Detected
03A	Saltwater Room	Floor Sandy Debris	No Asbestos Detected
03B	Saltwater Room	Floor Sandy Debris	No Asbestos Detected
03C	Saltwater Room	Floor Sandy Debris	No Asbestos Detected
04A	Saltwater Room	Condensate Pipe Insulation	No Asbestos Detected
040B	Saltwater Room	Condensate Pipe Insulation	No Asbestos Detected
04C	Saltwater Room	Condensate Pipe Insulation	No Asbestos Detected
05A	Saltwater Room	Condensate Pipe Wrap	No Asbestos Detected
05V	Saltwater Room	Condensate Pipe Wrap	No Asbestos Detected
05C	Saltwater Room	Condensate Pipe Wrap	No Asbestos Detected
06A	Maintenance Room	Door Frame Caulk	No Asbestos Detected
06B	Maintenance Room	Door Frame Caulk	No Asbestos Detected
06C	Maintenance Room	Door Frame Caulk	No Asbestos Detected
07A	Exterior Saltwater Room	Brick Mortar	No Asbestos Detected
07B	Exterior Saltwater Room	Brick Mortar	No Asbestos Detected
07C	Exterior Saltwater Room	Brick Mortar	No Asbestos Detected
08A	Exterior Saltwater Room	Foundation Mastic	No Asbestos Detected
08B	Exterior Saltwater Room	Foundation Mastic	No Asbestos Detected
08C	Exterior Saltwater Room	Foundation Mastic	No Asbestos Detected

1. EXISTING SALTWATER ROOM IS CONSIDERED A HISTORIC STRUCTURE. CONTRACTOR SHALL COORDINATE ABATEMENT OPERATIONS AND METHODOLOGIES WITH PWD CULTURAL RESOURCE MANAGER OR POINT OF CONTACT.
2. REFER TO SHEET H-102 FOR ADDITIONAL SAMPLING IN B72 AND B242.

HAZARDOUS MATERIALS NOTES:

- 1) THE FOLLOWING SPECIFICATIONS APPLY:
 - a) SECTION 02 82 00.00 22 - ASBESTOS REMEDIATION
 - b) SECTION 02 83 00.00 22 - MANAGEMENT OF LEAD, CADMIUM, AND CHROMIUM (VI) DURING RENOVATION, DEMOLITION, CONSTRUCTION, REMOVAL AND ABATEMENT
 - c) SECTION 02 84 33 - REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBS)
- 2) THERE IS THE POTENTIAL FOR HAZARDOUS MATERIALS WITHIN THE PROJECT SCOPE OF WORK AREA INCLUDING ASBESTOS, HEAVY METALS, POLYCHLORINATED BIPHENYLS AND OTHER HAZARDOUS OR REGULATED MATERIALS.
- 3) OBTAIN PERMITS AND LICENSES REQUIRED FOR THE MANAGEMENT, REMOVAL AND TRANSPORT OF HAZARDOUS MATERIALS TO INCLUDE ASBESTOS CONTAINING MATERIALS (ACM), LEAD, CADMIUM AND CHROMIUM (VI) CONTAINING PAINT AND DUST, AND POLYCHLORINATED BIPHENYL (PCB) CONTAINING MATERIALS AND DEBRIS IN ACCORDANCE WITH THE SPECIFICATIONS, LOCAL, STATE AND FEDERAL REGULATIONS. DISPOSAL OF HAZARDOUS WASTE IS BY THE GOVERNMENT.
- 4) REMOVE EXISTING ASBESTOS CONTAINING MATERIALS IN ACCORDANCE WITH THE SPECIFICATIONS, FEDERAL, STATE AND LOCAL REGULATIONS. DISPOSAL OF HAZARDOUS MATERIAL IS BY THE GOVERNMENT.
- 5) EXISTING PAINT COATINGS WERE FOUND TO CONTAIN LEAD, CADMIUM AND CHROMIUM (VI) (LCC). MANAGE LCC PAINT IN AREAS INDICATED IN ACCORDANCE WITH SECTION 02 83 00.00 22 AND APPLICABLE STATE AND FEDERAL REGULATIONS. DISPOSAL OF HAZARDOUS MATERIAL IS BY THE GOVERNMENT
- 6) DESIGNATED MATERIALS HAVE BEEN FOUND TO CONTAIN GREATER THAN 2 PARTS PER MILLION (PPM) BUT LESS THAN 50 PPM POLYCHLORINATED BIPHENYLS. REMOVAL AND DISPOSAL OF THESE MATERIALS MAY REQUIRE SPECIAL HANDLING AND DISPOSAL IN ACCORDANCE WITH SECTION 02 84 33 REMOVAL AND DISPOSAL OF POLYCHLORINATED BIPHENYLS (PCBS) AND SECTION 01 57 19.00 22 TEMPORARY ENVIRONMENTAL CONTROL.
- 7) DISPOSAL OF HAZARDOUS MATERIALS WILL BE BY THE GOVERNMENT. THIS INCLUDES BUT IS NOT LIMITED TO MATERIALS CONTAINING >1% ASBESTOS, >50 PPM PCBS, AND PAINT CHIPS CONTAINING HEAVY METALS ABOVE THE RCRA LIMIT. DISPOSAL OF CONSTRUCTION AND DEMOLITION MATERIALS, INCLUDING THOSE COATED WITH PAINT CONTAINING <50 PPM PCBS AND/OR HEAVY METALS ABOVE TSCA LIMITS WILL BE BY THE CONTRACTOR. CONTRACTOR RESPONSIBLE FOR CONDUCTING ANY REQUIRED WASTE CHARACTERIZATION SAMPLING IN ACCORDANCE WITH SECTION 01 57 00.

Architectural plan view of a building. The building consists of a central horizontal rectangular section. A smaller rectangular section is attached to the top edge of the central section. A solid black rectangular area is located on the right side of the central section. To the right of the central section, there is a complex structure with multiple rectangular protrusions. A small circle is located above the right side of the central section. A north arrow is located to the right of the building, pointing upwards, with the text "PLAN NORTH" above it.

$1/8" = 1'$

A graphic scale bar for a drawing. It is a horizontal line divided into alternating black and white segments. Above the bar, the numbers 8, 4, 0, 8, 16, and 24 are marked. Below the bar, the word "scale" is written under the first segment, and "feet" is written under the last segment. The bar represents a total length of 24 feet.