

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE OF PAGES 1 44	
2. AMENDMENT/MODIFICATION NO. 0008		3. EFFECTIVE DATE 21-Apr-2025		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable)	
6. ISSUED BY CODE COMNAVFACSYSCOM WASHINGTON 1314 HARWOOD ST WASHINGTON DC 20374		N40080		7. ADMINISTERED BY (If other than item 6) CODE			
				See Item 6			
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X		9A. AMENDMENT OF SOLICITATION NO. N4008025R9500	
				X		9B. DATED (SEE ITEM 11) 13-Mar-2025	
						10A. MOD. OF CONTRACT/ORDER NO.	
						10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer ☐ is extended, ☒ is not extended.							
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) N40080-25-R-9500- Design-Build (DB)/Design-Bid-Build (DBB) Indefinite-Delivery/Indefinite-Quantity (IDIQ) Multiple Award Construction Contract (MACC) for Large Scale U.S. Military Projects, Locations in Washington D.C., Maryland, and Virginia PLEASE SEE SF30 BLOCK 14 CONTINUATION PAGE							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: _____ EMAIL: _____			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
_____ (Signature of person authorized to sign)				BY _____ (Signature of Contracting Officer)		21-Apr-2025	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION SF 30 - BLOCK 14 CONTINUATION PAGE (SF 30)

The following have been added by full text:

0008

The purpose of this amendment is to:

1. Provide revisions to design documents in accordance with noted PPIs
2. Provide PPI responses

1. Revisions to Specification Sections and Drawings:

PPI #19, #474 – See Revision to sheet CU103
 PPI #213 – See Revision to Sheet S-111A and S-111C
 PPI #387 – See Revision to Spec 31 62 51
 PPI #387, #405 – See Revision to Sheet S-302
 PPI #419, #420 – See Revision to Spec 03 30 00
 PPI #429, #497 – See Revision to Spec 41 22 13.15
 PPI #440 – See Revision to Sheet S-101A and S-101D
 PPI #472 – See Revision to Spec 33 40 00

2. PPI Responses:

#	Reference			Inquiry	Government Response
	Page	Section	Para		
19	CU105, CU103			Please provide the point of demarcation (POD) with ASUS for the sanitary sewer line exiting the plan southeast side of the building that goes to the 6,000 gallon oil water separator on CU105. The manhole immediately before the oil water separator on CU105 does not include any notes that it is provided by ASUS, whereas the manhole north of the oil water separator on CU103 notes "Provided by ASUS", but no POD is indicated.	Bid per RFP Drawing CU118 and See Amendment 0008 for revised CU103.

57	Page 4 of 6	Section 11 01 50	2.1	Paragraph 2.1 of Section 11 01 50 for the Interior Fall Protection System says the system will be "as illustrated on the structural drawings", but we are having trouble finding where this information is located. Please provide layout and sections of the interior fall protection system.	There is no interior fall protection system required for this project. Specification section 11 01 50, Interior Fall Protection Systems, can be disregarded.
59	Page 7	Section 08 44 00	1.4.1	The source for the Curtain Wall in section 1.4.1 of 08 44 00, states that all components will be by one manufacturer or fabricator, however, it does not specify a specific BoD or manufacturer. The exterior materials legend on AS617 mentions the aluminum curtain wall frames and doors will be by Kawneer. Please confirm that the curtain wall product can be open shop as long as it meets or exceeds the requirements shown in the specifications and not just Kawneer.	Confirmed, Manufacturers are acceptable as long as they meet all of the requirements of Section 08 44 00 – CURTAIN WALL AND GLAZED ASSEMBLIES and the details in the drawings including shapes and sizes of the system members.
63	S-101G; MH402			The Line Shack mechanical drawing MH402 shows a roof exhaust fan (EF-5) and a roof hood (RH-5). The structural drawings on S-101G do not show any roof frames for these items. Will frames be required similar to B1/S-505? Please clarify.	Confirmed; roof frames will be required for these items per B1/S-505.
69	GC101			GC101 shows acceptable haul routes when on base, which gates will construction traffic be permitted to use and what restrictions apply to these gates (truck inspections etc...)?	Construction traffic/deliveries must use Gate 1.
84		32 13 14.13	1.1	Reference specification section 32 13 14.13 - Concrete Paving for Airfields and Other Heavy Duty Pavements, specifically section 1.1. This section reads that the concrete pavement will be paid for per a unit price in the contract. The bid form does not include a section for unit price for concrete paving. Please update this specification	Unit pricing within Spec 32 13 14.13 should be disregarded.

				section to exclude the unit price methodology for concrete paving.	
85	CS102, CS510			Reference drawing CS102, Key Note 15 that labels at Traffic Barrier W-Beam and drawing CS510 that provides details for the Traffic Barrier W-Beam. Will a specification section be provided for the Traffic Barrier W-Beam?	No specification will be provided. Reference MDOT SHA Specification Sections 605 and 606.
107	GC102			General notes on GC102 note that Buildings 2372 and 669 cannot be demolished until new Sonobuoy Storage Facility, part of separate contract is functional. Please identify when the Sonobuoy Storage Facility will be complete so offerors can identify this in our schedule and price the demo and follow-on work accordingly.	Anticipated availability is February, 2026
108	GC102			General notes on GC102 note that Building 619 cannot be demolished until new Hazmat Storage Facility, part of Separate Contract is functional. Please identify when the Hazmat Storage Facility will be complete so offerors can identify this in our schedule and price the demo and follow-on work accordingly.	Anticipated availability is February, 2026
109	GC102			General notes on GC102 note that Building 314 & 315 cannot be demolished until new Air Ops Storage Facility, part of Separate Contract is functional. Please identify when the Air Ops Storage facility will be complete so offerors can identify this in our schedule and price the demo and follow-on work accordingly.	Anticipated availability is February, 2026
111	GC101			Is the contractor permitted to set up an on site portable batch plant? If so, please indicate where this space would be provided.	Batch plant may be set up within designated area of disturbance on site. Alternate area is available at recycling center near project site but will require separate permitting with unknown

					timelines. An on site batch plant will also require coordination with the base for the location and running utilities for power and water.
114	S-101D, E & F, P101D, E and F			The ILDFA floor trench drain system shown on S-101D, S-101E, S-101F is not shown on plumbing plans P-101D, E and F. There is only (1) 10" OW connection at SE corner of hangar shown on P-101F. There will be additional underslab pipe to tie into the drains shown on S-101D, S-101E and S-101F. Can you please shown this underslab pipe needed? The ILDFA contractor will only provide the ILDFA trench drain to be set by the concrete contractor, so additional pipe from the trench to this tie in point shown on P-101F is needed. Please show this pipe which can be completed under the plumbing scope of work.	Bid per RFP. The piping from the ILDFA trenches to the 10" OW connection at the southeast corner of the hangar is intended to be designed by the ILDFA supplier/installer. If the ILDFA supplier/installer will not do this, the general contractor is still responsible for this work. No revisions to the plumbing drawings will be provided.
115	S-101D, E and F. P-101D, E and F			There is a hangar door trench drain shown on S-101D, E and F. This is not shown on the plumbing plans P-101D, E and F. Where does this trench drain tie into for plumbing waste? Is it the 4" OW shown? Can you show the laterals that will tie the drench drain to this 4" pipe?	The trench drain on the inside of the hangar doors is shown on the plumbing drawings. There are 4 floor drains located at the low points of the trench drain and connected with a 4" line that runs to the oil-water separator.
117	P-101D			P-101D: Note 3 "3" PCW DN to Safespill Floor System Flush Connection w/ BV, Coordinate with Floor System Provider Prior to Installation". Can the design please show the PCW to the connection point on P-101D so all Contractors are aware of the location and pick up the scope required?	Refer to Government Response to PPI #114.
118	13 50 00	1.3.2		Spec 13 50 00-1.3.2 notes "Refer to Basis of Design in the Construction Drawings" for drainage trench. Please provide.	Bid per RFP. The basis of design is provided on the structural sheets S-101 through S-101F.

119	CU102 & CU103			There is roughly 584' of site gas line shown on the plans (CU102 and CU103) and it is noted "by others". A gas meter and regulator is shown on P-101A as well. Please verify the Contractor is not to include cost for this for this new gas line on site along with the gas meter and regulator. No specifications or details for this site gas line are provided in the bidding documents. If we are to carry cost, please provide an allowance on the bid form.	See Utility Note 24 of sheet GI002
120	Detail B1/P-501			Detail B1 on P-501 shows the gas meter. Please indicate that the gas meter is by others. Where is the plumbing contractor to pick up gas on this detail?	Refer to Government Response to PPI #119. The gas meter and associated valves is intended to be provided by the contractor.
129	AE-409A	A4		Within room A14 there is a coiling counter door, details shown on AE-409A. Please confirm that SHH/tube steel shall be used at either side of the jamb to support this door. Please provide tube steel details.	Bid per RFP. The coiling counter door A23C is intended to be supported from the cold former metal framing, which is a delegated design, see specification 05 40 00. This also applies to door B33C in room B11.
130	AE112			Rooms A17, A18, B10, C25, C26, C27, C28, C29, and C32 have ACT ceilings with a 6" perimeter trim. Please confirm per Spec 09 51 00 2.4 that all corner radius' are to be 18 inch radius.	Confirmed
132		12 00 01.00	1.1	Reference specification section 12 00 01.00 1.1 and the bid form CLIN 0009. Please confirm the Government estimate for FF&E includes the cost for FF&E design, as design is not part of the HAR Percentage. If final FF&E design costs are not included, and are the responsibility of the Prime Contractor, please provide direction as to where these costs are to be carried.	Design for the FFE needs to be under the base contract. HAR is for coordination by the KTR after award of the FFE.
134	2680 OF 3186	32 13 13.06	1.4.1	Portland Cement Concrete Pavement specification references providing a batch	Refer to Government Response to PPI #111

				plant, please identify on drawings location for this batch plant.	
135	CD012			Drawing CD102 shows demolition of existing overhead power lines. Please clarify what scope is required of the Contractor and what will be performed by the Utility company.	SMECO removes the lines as they are the purveyor of the utility. KTR to work with SMECO.
143	General			Please confirm if Naval Air Station Patuxent River base has a stockpile of soil that can be utilized for the surcharge, or if this is Contractor Means & Methods to source the soil.	Means and methods. Bid per RFP.
155	Page 1	Spec Section 071700	Bentoni te WP	Please say where the bentonite waterproofing is.	Bid per Construction Documents. Refer to AE415.
157				Are substitutions allowed from specified manufacturers shown on the Material Legends?	Confirmed, as long as compliance is achieved with aesthetic and technical requirements.
158	Page 3	Spec Section 102113	2.2	Spec Section 102113 for Toilet Compartments provides details for Stainless Steel Sheet (Finish 2) and Solid Polyethylene Panels (HDPE) (Finish 5). However, there are no indications for either in the drawings. Please clarify which material is needed for the Toilet Compartments.	Bid per construction documents. Refer to the Enlarged Floor Plans.
159				Please provide locations for exterior and traffic signage. VOL 1 CS511 and CS512 show a Stop sign, reserved parking sign, and Building Sign, but no locations on the drawings.	See CS111-CS112 for sign locations
160	VOL 2 AE511			In Vol 2 AE511, the drawing shows reference to the heavy duty wire mesh partition at L Shack Storage D14, but there is no reference to the wire mesh on the floor plans. Please provide location along with full elevations for the wire mesh partition needed.	Bid per the construction documents. Refer to AE101D.
161	VOL 1 S313			In Vol 2 AE121, note 6 provide the location for the manufactured canopy system and VOL 1 S-313 shows a cut	Bid per the construction documents. Refer to AE207.

				detail of the canopy, but not the entire canopy. Please provide an enlarged drawing of the canopy system with full size and elevations.	
171				Please provide manufacturers and model numbers for accessories listed on the MISC ITEMS LEGEND on AE401, AE402, AE406, and AE407.	Bid per RFP and refer to specification for requirements
173	AE101E			Is the resinous flooring to line the trench drains?	No.
174	AE110 and AE111			Will the Aircraft Jacking Point (keynote 4) require painted markings? Please confirm marking/symbol to be applied.	No.
175	AE615 and AE616	99713.27		Room Finish Schedule AE615 notes requirements for high performance coatings on structural steel to follow 099713.27. PT-2 HP on Interior Materials Legend (AE616), is noted as High Performance Coating and to follow 099713.27. Confirm high performance coatings (PT2-HP) is NOT required at ceiling/roof framings. Ceiling paint is noted as PT2, PT2-E and would follow 099000 and Div 5 Ferrous and non ferrous paint table.	Confirmed. Refer to the drawings and the UFGS 09 97 13.27 - HIGH PERFORMANCE COATING FOR STRUCTURAL STEEL notes on the Room Finish Schedule sheets AE614 & AE615. Note "c" specifically refers to coating all "primary and secondary" structural members in the hangar bay, including all parts the hangar doors with the 09 97 13.27 specified coatings. The hangar bay steel roof joists are "secondary" members and will be coated with the 09 97 13.27 specified coatings. Only the steel deck in the hangar bay is allowed to be coated with the field applied primer / paint as specified per 09 90 00 - PAINTS AND COATINGS.
181	TS101	Drawing s Volume 3 of 3	Drawin g Notes	Please confirm that all work identified in Drawing Notes 4, 5 & 6, as referenced on TS101, is not to be included in this solicitation.	Bid per RFP
184	TS101	Drawing s Volume 3 of 3		Please confirm that the UG Telecommunication distribution from CMH 10.7 to CMH 10.9.2 as shown on Sheet TS101 is utilizing existing conduits and that no new conduits are to be	Confirmed.

				installed between those communication manholes.	
185	TS101	Drawing s Volume 3 of 3		Please confirm that Manhole #11 as identified on Sheet TS101 is an existing manhole.	Confirmed.
186		Price Proposal Form	Line Item 0007	Option Item No. 6 states to provide the Electronic Security System (ESS) in accordance with the drawings and specifications. However, no ESS specification could be located. Please provide an Electronic Security System (ESS) specification.	The TY drawings are for Pathway infrastructure ONLY. No devices, wiring, or equipment are part of this contract.
190		32 13 13.06	2.3.1	In Spec Section 32 13 13.06 2.3.1, it references a batch plant, but no location could be identified in the drawings. (A) Is a batch plant required? (B) If required, is there a designated and/or preferred location for this batch plant within the site limits?	Refer to Government Response to PPI #111
193		09 67 23.16	1.4.5.5	Spec Section 09 67 23.16 1.4.5.5 Qualifications of Coating Contractor calls out for the coatings installer to be certified to SSPC QP 8 and should also be certified to SSPC QS1. These certifications are for companies that perform high performance coatings for tank linings, etc., and not companies that install resinous floors. Please clarify that these certifications are not required for this project.	Bid per RFP.
194	Specifications	01 30 02.00 22	1.3	Specification section 01 30 02.00 22 1.3 states that the Government AV budget on the Bid Schedule/Price Proposal Form for the AV Planned Modification is \$43,800 and does not include the Contractor's HAR. However, the Price Proposal Form provided in Amendment 0002 does not show the AV Option as a Planned Modification with the Government Budget. Please confirm that the AV Option	See Revised Attachment H.

				on the Price Proposal should be revised to include the Government AV Budget and Contractor's HAR.	
196	L-501	Drawing s Volume 1 of 3	C1,A1 & C2/ L501	Sheet L-501 Planting Details C1, A1 & C2 call for a 3" deep mulch layer. Spec section 32 93 00, Section 2.7 Mulch lists both Intert Mulch Materials and Organic Mulch Materials. Please confirm Organic Mulch Material is acceptable where shown in L-501 Planting Details C1, A1 & C2.	Confirmed - Organic Mulch is to be used where shown in L-501 Planting Details C1, A1 & C2.
200	L-101	Drawing s Volume 1 of 3		Sheet L-101 Detail A4 provides a detail for Tree Protection. However, no location for this Tree Protection could be found on the drawings. Please confirm that this Tree Protection on L-101 is not required.	Confirmed.
201	CS505	Drawing s Volume 1 of 3	1/CS50 5	Detail 1/CS505 shows the fence fabric height as 10'-0" max. Please confirm the desired height of the fence fabric as well as the total height including Fence Top.	Confirmed - 10' Fence with 1' top.
202	CS102	Drawing s Volume 1 of 3		Sheet CS102 calls out for a "Fence with Slats." However, no detail could be located. Please provide a detail for the type of fencing.	Confirmed. Detail 1 CS501 fence detail. See note 2.
203	CS103	Drawing s Volume 1 of 3		Sheet CS103 shows a gate at the dumpster pad / enclosure. However, no detail could be located for the gate. Please provide a detail for dumpster enclosure gate.	Bid per RFP. Detail 1 CS501 fence detail. See note 2.
204	S-100	Drawing s Volume 1 of 3		Sheet S-100 identifies soil improvements (aggregate piers or rigid inclusions) to be installed underneath footings and mat foundations. Please confirm that soil improvements (aggregate pier or rigid inclusions) are only required underneath the footings and mat foundations and not required underneath the entire building slab.	Bid per RFP. See sheet S-100 for required locations of soil improvements.

205	CU105	Drawing s Volume 1 of 3		Sheet CU105 identifies a 6,000 gallon Oil Water Separator Tank. Sheet GI001 states that ASUS will construct any water or wastewater utilities at or downstream of their point of demarcation. Please clarify that this Oil Water Separator Tank will be procured and installed by ASUS.	Bid per RFP. See point of demarcation on CU103/ CU118.
206	CU105	Drawing s Volume 1 of 3		Sheet CU105 identifies a sanitary sewer manhole adjacent to the 6,000 gallon Oil Water Separator Tank. Sheet GI001 states that ASUS will construct any water or wastewater utilities at or downstream of their point of demarcation. Please clarify that this sanitary sewer manhole will be procured and installed by ASUS.	Bid per construction document RFP. See point of demarcation on CU103/ CU118.
207	L-101 & L102	Drawing s Volume 1 of 3		Sheet L-101 shows (5) Bioretention Areas with callouts to enlarged views which are shown on Sheets L-103 & L-104. Sheet L-102 shows Bioretention HGR-BR-4 & Bioretention HGR-BR-5, however, no additional detail or enlarged views are provided. Please provide details for Bioretention HGR-BR-4 & Bioretention HGR-BR-5.	Bid per construction documents. HGR BR-4 and BR-5 are grass lined bioretention areas as indicated by the grass pattern hatch on sheet L-102.
209	MH102E	Mechanical		There appears to be a plan page missing from the mechanical drawing set. The rooftop equipment layout for Area E is not shown. Please confirm if Mechanical HVAC Roof Plan – Area E (MH102E) is available, and if so, provide the missing sheet for our review.	Bid per construction documents. There is no mechanical scope indicated on that section of the roof, thus the exclusion of that section of the roof from the mechanical set of documents. No information is shown and thus no sheet will be provided.
210	Spec. Section 23 82 00.00 20	Mechanical	2.2.1 a. vs. 2.3	Spec Section 23 82 00.00 20, Paragraph 2.2.1.a states to use 16-gauge aluminum-clad steel between burners and vacuum pumps. However, Spec Section 2.3 says flue vents should be UL 441-listed and made from galvanized,	Bid per RFP. Specification section 23 82 00.00 20 Paragraph 2.2.1 describes the radiant tubing material, not flue vent piping.

				aluminum, or stainless steel. Please clarify which flue vent material is acceptable between the infrared radiant heaters and the vacuum pumps.	
211	Spec. Section 23 82 00.00 20	Mechanical	2.3	Please clarify the acceptable flue vent material for the positive pressure section running from the vacuum pumps to the roof termination. -Spec Section 23 82 00.00 Paragraph 2.3 calls for UL 441-listed flue vent made of galvanized steel, aluminum, or stainless steel. -Sheet MH101C Keynote calls for the use of the vacuum pump manufacturer's vent kit. -However, the vacuum pump manufacturer's vent kit may not be available for this application. Please confirm that a factory-made, UL 441-approved double-wall flue vent—such as DuraVent DuraStack—is acceptable for the positive pressure flue vent from the vacuum pumps to the roof.	Confirmed. If the manufacturer's vent kit is not available, contractor must provide a manufacturer approved material and ensure the assembly will be UL 441-listed.
213	S-111A; S-311			Between D & E on the low roof there is an L3x3 "X" bracing indicated, and there is a detail cut to B1/S-311. This detail shows the "X" bracing to be L2x2. Please clarify which is correct.	The "x" bracing angles can be L2x2x1/4 as indicated in detail B1/S-311. The angle sizes in the plan views indicate the angles along the bottom of deck. See revised sheet. This occurs on column-line 9.6 between V and W as well.
214	Specification 26 56 20			Clarify where airfield and heliport lighting and visual navigation aids are required.	Bid per RFP. Refer to sheet ES101 for Airfield Electrical Site Plan
215	Detail A1/E-502			Provide BOD for Floor box.	Refer to specification 26 20 00, 2.4.1 and drawing E-002 for floorbox performance requirements. Bid per RFP.
217	07 27 10	07 27 10		What are the minimum manufacturer warranty requirements for the Air Barrier on this project?	Bid per construction documents. No project warranty is required. Paragraph 1.5, SD-02 only refers to the manufacturers warranty for a system if chosen for use by the

					successful GC to create the Air Barriers as prescribed in the drawings.
219	A4/AE501	07 95 00		In reference to the roof expansion joint (Detail A4 on AE501), which graphically shows an Emseal RoofJoint, please provide the specifications and design requirements for this PVC expansion joint cover system, as most manufacturers do not offer an exact equivalent.	Bid per construction requirements. Refer to section 07 95 00 for the specifications and design requirements. The contractor is responsible for providing what is specified or to provide a proposed substitution that is considered equivalent.
223		Section 41 22 13.15	1.2.m and 1.3.1.1	Paragraph 1.2.m in section 41 22 13.15 lists General Purpose Service and Hazardous under the Operating environments. Paragraph 1.3.1.1. says the crane is to both be General Purpose Service and also Hazardous for the full height of the crane. Please confirm if the entire crane is to operate in a Hazardous environment.	Confirmed.
225		Section 11 94 11	1.3.1	Would it be acceptable for the Fall Protection Contractor to hire an outside PE for stamping submittals?	Confirmed.
227		AE003 - AE005 & 07 27 10		The air barrier plans identify five envelopes for this building. Envelope 5, which includes Hangar Bays 1 & 2, is noted as requiring "Visual Inspection Only" for the AVB. Please provide clarification on what the visual inspection entails, including specific criteria that must be evaluated during the inspection. What are the defined standards or guidelines that must be followed per product (drwalls, panels, etc.) to determine compliance.	Bid per construction documents. Refer to 07 27 10, 1.1 SUMMARY. The entire building air barrier system, including the hangar bay, is the responsibility of the contractor. Only the hangar bay is not required to be pressure tested.
228		AE003 - AE005 & 07 27 10		For Envelope 5 (Hangar Bays 1 & 2), where the AVB is designated for "Visual Inspection Only," please confirm who is responsible for conducting the inspection. Should this be performed by the contractor, a third-party inspector, or another entity?	Refer to government response for PPI #227

				Additionally, please clarify if any documentation, reporting, or approvals are required as part of this inspection process.	
229		09 51 00		Please confirm all the radius perimeter trim (Axion). inside and outside corners around the acoustical ceiling tiles are all typical 18" per the specs?	Refer to Government response to PPI #130
230	A4/AE-511, B3/AE-413 C1/AE-505	05 54 00		Will light gauge metal framing be typically required to support the insulated metal panels and/or fabricated wall panels?	Bid per RFP.
231	C2/S-337			Column line/Letter indicators are missing from some of the structural drawings. Please provide updated drawings to reflect which column line/letter is being referenced in the details?	Bid per construction drawings. Detail C2/S-337 is intended to be used on multiple grid-lines.
232	A4/AE-409a			Please confirm the interior partition framing is not the structural support for the coiling counter door? Is there supposed to be an HSS member for the jamb support?	Refer to Government Response to PPI #129
235		28 00 00		CLIN 0007 Option 6 calls for Electronic Security System, (IDS, AC, VSS) however no spec was provided. Please confirm this spec will be issued.	Refer to Government Response to PPI #186
239		13 50 00	2.8.1	Specification 13 50 00 2.8.1 references a containment tank for the ILDFA system. The drawings do not schedule or show a containment tank. Please confirm if a containment tank is required. If required, please provide specifications, including size, material, manufacturer, and model, and location for the tank.	Containment tank is NOT required.
240	FX101A	13 50 00		FX101A references a booster pump for the ILDFA system. This pump is not shown or scheduled on the mechanical or plumbing drawings. Please confirm if this booster pump is required, and provide specifications for the pump.	The ILDFA pump will be provided by the ILDFA manufacturer.

245	AE402	B1, C1		The detail B1, C1/AE402 calls out a plastic end filler panels and sloped tops around the lockers but does not reference a product type. Please advise what material this should be.	Bid per construction documents. Refer to Section 10 51 26 - PLASTIC AND CELL PHONE LOCKERS, paragraph 2.3.7 and 2.3.8.
246	AE101	Room Schedule		The Room Schedule on AE101 references both rooms A17 and B10 as OP2 OFF/OPEN OFF as the room name. Please confirm that the Option 2 relates to the Translucent Panels and insulated metal panels and should not impact the interior of the office space.	Confirmed
252	CG501			Please confirm if the diversion fence is all that is needed to separate the site from the existing taxiway. Please confirm if additional MOT or protection is required for the demo and proposed work in the existing taxiway.	Bid per construction documents. See GC102-104.
253	AE617			The exterior materials legend states that the the Metal Wall Louvers are to receive a "Color to match - FWP1 fabricated wall panel (refer to comment)". The comment states that the color will be a custom color as required. Please confirm that the louver color to be the Kynar 500/Hylar 5000, #1760 Limestone to match the FWP1 panels.	Confirmed
254	AE617			Please provide Clarification on Translucent Wall Panels Frame (TP1) Color - it is noted that the color for the translucent wall panels frame (TP1) is listed as "Custom color as required." However, it seems the baseline color is established to match FWP1. Please confirm whether the custom color is acceptable, provided the cost and lead time remain consistent with FWP1. Otherwise, this may create discrepancies when evaluating values and scheduling the work.	Confirmed - the TP1 frames color shall match the FWP1 wall panels.

260		Section 41 22 13.15		Section 2.2.5 states, "Provide runway and support structure for under running crane of rolled steel shapes conforming to CMAA 74 OR patented track conforming to MHI27.1." Question, section C4/S-380 shows a patented track runway beam. Is patented track required?	No, detail C4/S-380 only shows a schematic runway beam.
261		Section 41 22 13.15		Section 2.3.2.2 states, "The load block sheaves must be constructed of non-sparking materials." Section 2.3.2.5 states, "Provide steel sheaves." Confirm the sheaves are steel or non-sparking materials (bronze).	Bid per construction documents
263		Section 41 22 13.15		Section 2.4.8.1 Runway Conductor Bar System. The spec indicates a conductor bar system that can cause spark. Please confirm this is accurate given the environment has been classified in section 1.3.1.1 as NEC Class I, Division II. If the conductor bar system is deemed unacceptable, please confirm a festoon system is required with non-sparking equipment (stainless steel track, bronze trolley wheels, neoprene cables, etc.)	Yes, crane will operate in an hazardous environment. Festoon system must be non-sparking.
264		Section 41 22 13.15		Section 2.4.8.2 Bridge Conductor System. Please confirm that the festoon track system should be standard equipment or non-sparking (stainless steel track, bronze trolley wheels, neoprene cables, etc.)	Refer to Government Response to PPI #263
266		28 00 00		What components of CLIN 0007 - Electronic Security System are GFGI? No Specification was issued.	Refer to Government Response to PPI #186
267	TS101			Ref TS101 Telecom Site Plan - Site plan seems to reference Phase 1 work, Please confirm these pathways and fiber are already installed. Please confirm telecom pathways in this project's scope are identified as 'phase 2'.	Keynotes 1,2,& 3 are all a part of phase I. All other keynotes are part of Phase II. Keynote 5 it is 100 PR and the splice point is in CMH 10.9.1

271	T-403			T-403: Details A1 and C1 for comm room A16 do not match. Detail C1 shows 4 cabinets but 3 of them are labeled Rack; however, keynote 2 calls out cabinets. Detail A1 only shows 2 racks and 1 cabinet. Please clarify.	Detail C1 has one cabinet and 3 4-post racks. Third rack is for future growth.
274	ES201			Provide size of electrical ductbank located at the plan south west corner of the hanger. Clarify purpose of this ductbank.	Bid per construction drawings. Feeder to Line Shack. See sheet E-111G for location of power distribution equipment. See sheet E-602 for equipment connections.
276	B5 & A3/AE415 and B2/S304			Geotextile waterproofing and hydrophilic waterstops are shown at only two locations, the Access Stair and Access Floor section (refer to B5 & A3/AE415 and B2/S304), Please clarify if these are the only areas intended to receive underslab waterproofing.	Confirmed
278	A3/E-510			Sheet E-510 detail A3 appears to be a cast in place ductbank manhole. Please confirm that all utility structures can be pre-cast in lieu of cast-in-place.	Confirmed
280	GC104			After surcharge and compaction are complete, are wick drains required to be capped or grouted in order to abandon them in place?	Bid per RFP. Submit with pre-consolidation plan
281	AE001	Toilet Accessory Mounting Height Schedule		The Toilet Accessory Mounting Height Schedule on sheet AE001 has a note that states "All toilet accessories listed above may not be in contract." Please confirm which items are not included in the contract, if any.	The Toilet Accessory Mounting Height Schedule is a standard schedule and the contractor is responsible for confirming accessory quantities.
283		32 31 00		Please provide a specification section for the canopy and turn stiles at exterior fencing, per sheet CS509.	Bid per RFP Detail 1 on CS509
285				It appears splash blocks at intermediate roof levels are intended to be 24" x 48" PVC applied to roof to act as extra protection in lieu of a traditional splash block. are the only true "concrete type"	Confirmed

				splash blocks the two detailed at the Line Shack building in detail C4/AE101G, with no others being required at grade/base of hangar.	
287				Confirm if roller shades are required at Room B21 as indicated in detail name on C2/ AE504. Note head detail at B21 on Elevation B1/AE605 shows section C1/AE 502 which shows no window shade. RCPS on AE112 B does not indicate a Note 4 at B21. Please confirm no shade is required for the 4' x10.25' section exterior window of B21 lobby.	Confirmed
294		07 95 00		Please provide detail of expansion joints where they occur in exterior corrugated metal "MWP" at back side of parapets, i.e. at column line "C" and "9.6". Is it only expansion joint on back side of parapet intended to be the expansion joint within the roof system, with the corrugated metal panels stopping short at joint, with no other expansion joint within the MWP metal panel system.	The expansion joint CFMF along Grids B & C shown in Section Detail A4/AE501 extends and terminates into Grid 9.
296		09 77 20		Although Specification 09 77 20 Fiberglass Reinforced Wall Panels was included, none have been found. Please confirm locations and extents if required.	Refer to B26 JAN on the ROOM FINISH SCHEDULE on sheet AE614 and the INTERIOR MATERIAL LEGEND on sheet AE616.
298	AE615/Price Proposal Form	1.1 Contract Line Items		Bid Option 4 indicates a 5-coat fuel resistive system in lieu of a 3-coat system. However, AE615 indicates LS1 to receive FRRF2 in the base bid with no bid option for FRRF1. Please clarify.	No Bid Option in LS1 - provide scheduled finish.
299				Confirm no ladder or crossover type steps transitions are required where walkpad systems at low roof occur at / over expansion joints.	Confirmed
300				Many of the interior expansion joints show a flat or angled aluminum expansion	Covers in spaces with ceilings will terminate at the ceiling horizontal covers.

				joints "cover" over the expansion "joint", i.e. see details A1 and A2 on sheet AE101A. Please confirm "height" above finished floor that these aluminum "covers" extend to. Some areas where they occur have ceilings, some areas are exposed structure. Is there a standard height that the aluminum cover runs?	Covers in spaces with no ceilings will extend up full height.
301		10 53 01	1.3	Spec 10 53 01 Manufactured Canopy, based on para 1.3 of spec , seems to relate to the canopy of the main entry shown in detail A2, A3/AE303. Please provide adequate details and information on roof system and related structure (columns, beams, decking) which occurs above the turnstile area in detail 1 on CS509.	The turnstile area canopy is completely separate from the main entry canopy. Refer to the Civil drawings and specifications.
304	Geotechnical Report	316251		The drawing series GR701 thru GR705 provides borings data but no geotech report has been provided. Please provide the geotechnical report.	See amendment 0007
305	AE101A,B,C,D & F			The architectural drawings do not provide a partition type for multiple exterior rooms. Are these intended to be exposed to structure? Please clarify the intended exterior partition types in rooms A09, A10, A11, A12, A16, B32, C14, C16, D10, & F11.	All partition types are indicated - refer to all Area Plan sheets and all Enlarged Plan sheets.
307	CS-104			There may be areas were exterior bollards desired but not called out or tagged, i.e. two at Line Shack door on CS-104. Please confirm these should be tagged as bollards.	See Government Response to PPI #425
308	FX001			Reference FX001, Fire Protection Note 7. This notes reads: Provide draft curtains in accordance with UFC 4-211-01, such that a single draft curtain area does not exceed 7,500 sq ft and shall extend from wall to wall and be supported by the building structure. UFC 4-211-01,	Draft curtains are shown and detailed on structural drawings.

				section 3-3.1.10 Draft Curtains requires to provide draft curtains per NFPA409 and does not indicate a clear size or material for the curtains, rather indicates how to calculate their size. There is not enough information in the drawings and support documentation provide pricing for this scope. Please provide a complete design and specifications of the draft curtains to be included per FX001, Fire Protection note 7.	
310	Bid Option #5			Site Plan CS104 and CS105 clearly shows what happens if Bid Option # 5 is accepted, how are these plans, and associated landscaping plans impacted if the option is not accepted. Impacts to fencing - How the perimeter fence is to be configured if Option is not taken. Impacts to Landscaping - what occurs in that area is only sod/turf. How the fencing is to be without the sliding gate to ensure the apron remains secured once the existing fence is removed for access to the taxiway. How is asphalt shoulder configured	If Bid Option is not accepted, termination of fence has been added to CS104-105. No change to landscaping or pavement shoulder.
312	S-308, P-101D, E and F			Reference S-308, P-101D, E and F. Detail A1 on S308 calls for a PVC pipe that connects the hangar gates doors trench with the main entrance hangar trench. This pipe is not shown in the P drawings. Please confirm this pipe is needed and what is the spacing between the pipes along the approx 300 ft of trench.	One pipe is required for each rail pit that's located in plan.
315	DWG GC 102,GC103			General notes on dwgs GC102, 103 define descriptive phasing of elements of the project - are we to follow these phases in strict order as stated or can we have the flexibility to have phases of work run concurrent with others (other than those	Bid per RFP Phasing on GC102-103, CG003 and CG111-CG134

				already mentioned to be concurrent)?	
343	n/a	23 09 00		Please confirm if J&A No. N40040-24-J&A-003 applies to this project and if the BAS is required to be JCI Metasys.	Confirmed.
344	CS103			Please advise if contractor is to furnish and install mobile barricade or if responsibility lies with government.	Bid per RFP. "MOBILE BARRICADE PROVIDED BY GOVERNMENT" per sheet CS101 and CS103
346	CU503	Note 1		For the Pre-Engineered pump station, please confirm ASUS will be responsible for the structure as well.	Bid per RFP. See point of demarcation on CU103
348	E-001	Note 18		Drawing E-001/General Note 18 states that all EMT must be factory painted. Please confirm this is a requirement for the entire project.	Bid per RFP.
349	AE124, AE416, AE502, AE503, AE506			Please provide more details about the sheet metal material and gauge/thickness for the following items: Drawing No. AE124, Detail C4, "Weathercap". Drawing No. AE416, Detail C1, "Prefinished brake metal base flashing trim", "Continuous prefinished 10"x10" metal gutter", "Extended prefinished flashing below gutter", "Cleats", "Prefinished 8"x8" metal downspouts". Drawing No. AE416, Detail C4, "Prefinished rake flashing and continuous cleat". Drawing No. AE502, Detail A1, "Prefinished overflow conductor head", "Scupper MFRS metal thru wall flashing to backside of parapet". Drawing No. AE503, Detail C1 "Prefinished metal coping", "Continuous cleat", "L flashing drip". Drawing No. AE506, Detail C3 "Prefinished Eave Flashing and continuous cleat".	Refer to 07 60 00, Table 1 for SHEET METAL WEIGHTS, THICKNESSES, AND GAGES.

350	AE 121			there is a roof area indicating a 1" per foot structural slope along with 1" per foot crickets. Please confirm whether this is correct or advise of any necessary corrections.	Confirmed.
352		09 51 00		Please confirm all the radius perimeter trim (Axiom), inside and outside corners around the acoustical ceiling tiles are all typical 18 inches per specs?	Refer to Government response to PPI #130.
353	A4/AE-511, B3/AE-413, C1/AE-505	54 00 00		Will light gauge metal framing be typically required to support the insulated metal panels and/or fabricated wall panels?	No, Bid per RFP.
354	C2/S-337			Column line/letter indicators are missing from some of the structural drawings. Will these drawings be updated to reflect which column line/letter is being referenced in the details?	See PPI response #231.
355	A4/AE-409a			Confirm the interior partition framing is not the structural support for the coiling counter door. We suggest this to be HSS/tube steel at either side of the jamb.	Refer to Government Response to PPI #129
357	N/A			In reference to RFI 39, please confirm ASUS will be responsible for the storm piping and trench drain under the concrete apron, and the 6000 gallon oil water separator tank.	No, Bid per RFP, Contractor responsibility.
383				Please confirm the surcharge material is only to be installed after the building and apron area has been graded to subgrade, and that any fill materials required to get building pad or apron area to subgrade are not to be considered part of the surcharge load.	Bid per RFP. 5' Deep Surcharge Material above finished grade as shown on GC104
387		31 62 51		Please provide the following information regarding the aggregate pier/rigid inclusion scope: 1. CPT reports and raw CPT data (if not included in the geotechnical report).	1. See amendment 0006. 2. See the last sentence in section 1.1 of specification 31 62 51, "Individual column loads will not be provided to the contractor. 3. See amendment 0008 4a. See

				2. Dead and live loads for column locations, linear loading for strip footings, and sustained bearing pressures for mat foundations. This information is required for settlement design to mitigate differential settlement concerns. 3. All uplift requirements and their respective locations. 4. Clarification on design responsibility: a. Can the ground improvement engineer of record be responsible for the design? b. Will depth, diameter, and spacing be determined by the ground improvement engineer of record? c. Can the ground improvement engineer of record determine the required number of modulus tests? 5. Bottom stabilization is based on the "tamper" aggregate pier method. If an alternative method is used for design and installation, can the bottom stabilization testing requirement be waived?	section 1.6.4 of specification 31 62 51. 4b. A minimum of two modulus tests should be performed. Additional tests can be selected by the engineer-of-record of the ground improvements. See amendment 0008. 5. No
389	Amendment 3, Pg 2			As stated in the site walk presentation, please confirm that the PPI deadline is Tuesday 4/15, 4 days after the site walk.	Bid per RFP.
393	41 22 13.15	2.3.2.2 and 2.3.2.5		Section 2.3.2.2 states that the load block sheaves must be constructed of non-sparking materials, whereas section 2.3.2.5 states that steel sheaves are to be provided. Please clarify if the sheaves are to be steel or non-sparking materials (i.e. bronze).	Bid per RFP
395	41 22 13.15	2.4.8.1		Section 2.4.8.1 Runway Conductor Bar System. The spec indicates a conductor bar system that can cause spark. Please confirm this is accurate given the environment has been classified in section	Bid per RFP

				1.3.1.1 as NEC Class I, Division II. If the conductor bar system is deemed unacceptable, please confirm a festoon system is required with non-sparking equipment (stainless steel track, bronze trolley wheels, neoprene cables, etc.)	
400	CS508			For the box frame gate on drawing CS508 please provide the following: 1) Specified wind load? 2) Will the gate need PE stamped drawings for wind load? 3) What is the required infill material? 4) Confirm if the gate is a mill finish?	Bid per RFP. Wind loads are prescribed on sheet S-001. Gate finish per 32 31 13 Infill per manufacturer recommendations compliant with CS508 and 32 31 13"
402	GC104 General Note 1			Due to the significant depth and quantity of wick drain installation, please confirm that wick drain installation duration is not included within the 801 day project duration.	Bid per RFP.
403	08 11 13	2.1.1.2		The Steel doors and Frames specification states which doors are to be level 3 Extra Heavy Doors in section 2.1.1.2. In it, it lists door B13B. Door B13B is not listed on the door schedule AE601. Please confirm there is no door B17B.	Bid per RFP.
405	S-301	C1		Per sheet S-301 detail C1 tension rods should be embedded in the rammed aggregate piers. How far into the rammed aggregate piers do the tension rods need to extend and how are they to be embedded?	See revised sheet S-302 in amendment 0008.
407		Section 41 22 13.15		Is the bridge crane to be single girder or double girder? A few documents indicate SG and another DG	Bid per RFP; prescribed crane requirements must be met.
408		Section 41 22 13.15		Please verify the number of bridge cranes expected. Seen a few things that indicate 1 and other that possibly indicates 2.	Confirmed; only 1 crane is required.
409		Section 41 22 13.15		Section 41 22 13.15 sub section 2.3.8 says wheels to be made of Forged steel then says provide wheels of non	See Specification Section 41 22 13.15 in amendment 0008.

				sparkling material. Which is actually required?	
410		Section 41 22 13.15		Section 41.22.13.15 sub section 2.4.1 provide motors painted to manufacturer's standard to "wash Down" service. Will there be an additional standard for this or just what our manufacturer recommends?	Bid per manufacturer recommendations in RFP.
412		Telecom municati ons		Please confirm that network switches, programming and integration of the network (classified and unclassified) will be GFGL.	Confirmed.
414	09 6723.16	3.9.6		Specification 09 67 23.16 - 3.9.6 Indicates to apply MPI 209. MPI 209 can not be found and there is no MPI 209. Please provide desired inclusion in lieu of MPI 209	Bid per RFP.
415	AE601	A13B, C18A, C22B, and F16A		The door schedule on AE601 lists door A13B, C18A, C22B, and F16A to receive a interior steel door frames but are listed to receive exterior steel door leaves. Please confirm the intent for doors A13B, C18A, C22B, and F16A are an interior frame with exterior leaves or provide updated frame/leaf types for the corresponding openings.	Confirmed; provide doors and frames as scheduled.
416	09 29 00	3.3		Specification 09 29 00 3.3.1 Indicated level 5 finish to be at all walls to receive eggshell finish. PT-1 is the majority of the room finishes and is indicated to be eggshell. Is it the intent to have level 5 finish at all these locations? Since level 5 comes with a pricing premium can Level 4 be provided at the room finishes in lieu of Level 5 per the specification?	Bid per finish level as specified in RFP.
417	31 00 00	3.1		Specification 31 00 00 states to strip topsoil to a depth of 4" where indicated. The boring logs show that there are some areas that have 6" of topsoil. Please confirm that all 6" of topsoil can be stripped in these areas.	Confirmed; bid per RFP.

418		03 30 00	2.3.1.2 A & B	Concrete materials the only cementitious materials are Portland Cement and Fly Ash. Due to limited availability of fly ash is granulated ground blast furnace slab (New-Cem) acceptable? Percentages up to 70% are requested by Contractor's for use with Mass Concrete.	Bid per RFP; granulated ground blast furnace slab is not acceptable.
419		03 30 00	3.5.8 B	Sand-plates are referenced for bar supports for reinforcing support for slabs cast on ground and or similar surfaces "slabs on grade" where vapor retarder is to be provided. Please confirm bar and mesh support accessories must have sand plates.	Sand plates should not be used. See specification 03 30 00 in amendment 0008.
420		03 30 00	3.6.2 E	Specifications note the use of fiber reinforcing as additive, but such an additive is not noted on the plans or in any other schedule-based locations in the specifications. Please confirm there are no fiber additives required in concrete in the Hanger Structure? If, required please provided guidance as to type of fiber and dosage rate required. Fibers are often either a primary or secondary additive on other projects depending on designer's requirements.	Fiber additives should not be used in this project. See specification 03 30 00 in amendment 0008.
421		03 30 00	3.11.1.1 A	a. Specifications note 1,200 sqft pour size limits bounded by formed construction joints. Please confirm the limit as stated applies and is not a general goal. Formed bulkheads required are a significant cost driver on this project and such a restriction will impact the projects schedule. If this requirement only applies to specific slab on grade thicknesses, please provide further guidance. The project has 5", 6", 8" and 14" slabs on grade with significant secondary sawing of "control and construction" joints shown in the design in plan	See specification 03 30 00 in amendment 0008.

				view on S-101A for the Hanger Structure. b. Please confirm that this constraint is not applicable to the 14" hangar slab on grade.	
422	S-002			Please provide a grout specification omitted for structural related base plate grout for the Hanger Structure. Nothing is referenced regarding grout as a material in Section 03 30 00 - Cast in Place Concrete.	See section 2.4.2 in specification 03 30 00 in amendment 0008.
423	C1/S-306 and A!,B4/S-308			Please confirm that's secondary pours shown are not structural grout material but are un-reinforced fill concrete no secondary reinforcing additives "fibers" are required.	Confirmed; the secondary pours to create the slopes within the trenches are unreinforced concrete.
424	B1, B2, B3, C2, C3/S-501			a. Smooth blanks are required in slabs on grade by design. Please confirm if smooth blank dowels for shown in section for slabs on grade construction and control joints can have sheared ends or "must be provided with saw cut ends.	Confirmed; the ends of the smooth dowels need to be cut clean with no deformation within the bar.
425	CS-104			There may be areas were exterior bollards desired but not called out or tagged, i.e. two at Line Shack door on CS-104. Please confirm these should be tagged as bollards.	Bid per RFP; bollards are tagged on CS-104.
426	FX001			Reference FX001, Fire Protection Note 7. This notes reads: Provide draft curtains in accordance with UFC 4-211-01, such that a single draft curtain area does not exceed 7,500 sq ft and shall extend from wall to wall and be supported by the building structure. UFC 4-211-01, section 3-3.1.10 Draft Curtains requires to provide draft curtains per NFPA409 and does not indicate a clear size or material for the curtains, rather indicates how to calculate their size. There is not enough information in the	Bid per RFP; refer to structural drawings for additional information on the draft curtains.

				drawings and support documentation provide pricing for this scope. Please provide a complete design and specifications of the draft curtains to be included per FX001, Fire Protection note 7.	
427	AE617			The Exterior Materials Legend on AE-617 shows the MWP as 4" x 36" which conflicts with the Specifications Section 07 42 13 Metal Wall Panels, and the details on Drawings A-502 and A-503 etc. Please confirm the Exterior Materials Legend is NOT correct.	The MWP3 panels will be 7/8" X 16".
428	Bid Option #5			Site Plan CS104 and CS105 clearly shows what happens if Bid Option # 5 is accepted, how are these plans, and associated landscaping plans impacted if the option is not accepted. Impacts to fencing - How the perimeter fence is to be configured if Option is not taken. Impacts to Landscaping - what occurs in that area is only sod/turf. How the fencing is to be without the sliding gate to ensure the apron remains secured once the existing fence is removed for access to the taxiway. How is asphalt shoulder configured	Refer to Government Response to PPI #310
429	412213.15	1.3.1.1	1	Crane spec section 412213.15-1.3.1.1 states the NEC class as I and Division as II but does not state the NEC Group letter designation, which is required to price the crane. Please advise the correct group designation	See specification 41 22 13.15 in amendment 0008.
430	S-308, P-101D, E and F			Reference S-308, P-101D, E and F. Detail A1 on S308 calls for a PVC pipe that connects the hangar gates doors trench with the main entrance hangar trench. This pipe is not shown in the P drawings. Please confirm this pipe is needed and what is the spacing	Confirmed; pipes are necessary per drawings.

				between the pipes along the approx 300 ft of trench.	
432	Spec 110150			Spec 11 01 50 calls for Interior Fall Protection Systems but drawings do not reflect intended system. "System will be designed for three users per line, one line each over fuselage and wings as illustrated on the structural drawings." is called out in the Specification. Please confirm this requirement is 3 lines per plane for a total of 6 lines in H1A and H1B. Please confirm if F11 has any Fall Protection Requirements.	Specification section 11 01 50 does not apply to this project.
433	DWG GC 102,GC103			General notes on dwgs GC102, 103 define descriptive phasing of elements of the project - are we to follow these phases in strict order as stated or can we have the flexibility to have phases of work run concurrent with others (other than those already mentioned to be concurrent)?	Bid per RFP Phasing on GC102-103, CG003 and CG111-CG134.
440	S-101D			Sheet S-101D has a spread footing with a call-out of F6x11 at column line intersection D/8. The footing schedule on sheet S-302 and the footing details on sheets S-302 and S-303 do not list footing type F6x11, please provide sizing, reinforcement, etc. for footing type F6x11.	See revisions to sheets S-101A and S-101D in amendment 0008.
445		33000	1.6.6.1	Please remove the professional engineer license for the Quality Manager.	Bid per RFP.
446		33000	1.6.6.1	What is the role of the Quality Manager? Are they the same person as the QC Manager? Are they to review submittals? Do they need to be on site to observe reinforcement and concrete pours? Please clarify this role.	Bid per RFP. The quality manager indicated in specification 03 30 00 is intended for the concrete construction only.
448	FX001 & FX501			On both drawings, there is a mention of underground fire protection piping to be	Bid per RFP. FX001 note 31 indicates that the fire water entrance (beginning 5ft

				stainless steel. Is all of the underground service piping to be stainless steel? If no, please provide a explanation of how much pipe will need to be stainless steel.	outside the building) must be stainless steel. All other underground piping is ductile iron as indicated on civil drawings.
451	M-roof drawings			Regarding all RTU's located on the roof, please provide a drawing showing all required condensate piping.	Bid per RFP.
452	M-Drawings			Since fire & fire / smoke dampers are not shown, please confirm they will not be required for this project.	Confirmed; All fire rated walls on project are 1-hour rated and will not require fire or fire/smoke dampers.
453	M-Drawings			Please provide a drawing, showing all exterior piping requiring heat trace.	Heat trace will not be required for any exterior piping.
454	CS508			What is the specified wind load?	See sheet S-001 for the wind load requirements.
455	CS508			Will the gate need to be PE stamped for wind load?	Confirmed.
456	CS508			What is the required infill?	Bid per RFP; see CS508 and specification 32 31 13.
457	CS508			Is the gate just mill finish?	Bid per RFP; See specification 32 31 13.
458				Please provide the geotechnical report for the project.	See Amendment 0007
460	Sheet CD104			Note 3 on this sheet requires the contractor to reimburse the Navy Forestry Account in the appraised amout of the timber. What is the appraised amount?	See PPI 064.
461	Sheet CS102			There is a reference for a Landside Asphalt - For Trucks in the turn around area near the bottom of the sheet. There is no detail for this reference and no delineation of the extent of this paving section. Can this be provided?	Bid per RFP; see Keynote 1 on sheet CS102.
462	Sheet CU105			The 6,000 Gal Oil/Water Separator Tank is listed as part of the contract. Where is the termination point after the tank for the contract?	Bid per RFP; see sheet CU103.
464	Sheet CG 127 & 128			These sheets call for a split casing protection on the existing fuel line. Can a detail be provided for this?	Bid per RFP; see sheet CU504.
465	Sheet CG103, CG203 & CG554	Sheet CG203 Detail 3		Downspouts are shown as 8" PVC going into a cleanout connected to 12" RCP Pipe.	Use fitting compliant with Detail 5 on sheet CG551.

				How are these dissimilar materials to be connected?	
466	Sheet CG554			The trench drain shown on the Detail 2 calls for a preformed trench drain. There is no specification for the trench drain. Can this item be better described as to what you are requiring?	Bid per RFP; See specification 33 40 00.
467	Sheet CG554			On Detail 2, the concrete for the trench drain is to be 4,500 psi concrete. Is this the correct concrete for this application?	Confirmed; bid per RFP.
468	Sheet CG554			In Detail 2, it appears that the right side of the trench drain has a hinge. Is this a hinge and if so, are all the grates to be hinged or are the hinged grates in a certain location?	Bid per RFP. A hinge is not required.
469	Sheet CG554			Detail 3 shows a cut-off trench with a compacted clay impermeable barrier. What impervious value is the clay?	Bid per RFP; see detail 3/CG554.
470	17	32 13 14.13	2.1.1.2	Profilograph Testing is required for the apron. Usually, Profilograph Testing is performed on long runs of pavement. Due to the short length and width of the apron, can this requirement be waived?	Use the profilograph method for all longitudinal testing, except for paving lanes less than 200 feet in length.
472	8	33 40 00	2.3.9	This specification is calling for a DIN Class D grate for the trench drain. This classification is not rated for the weight shown on Detail 2, Sheet CG554. What classification is to be used?	See revised specification 33 40 00 in amendment 0008.
473				The RFP is requesting Small Businesses to bid on the solicitation. However, due to the price range for the past experience project requirements, Small Business cannot meet these requirements and won't have the capabilities to provide pricing for such a large project. How are Small Businesses interested in participating in this solicitation supposed to respond for consideration?	Bid per RFP.

474	CD103	N/A	N/A	On the northwest side of CD103 there is a 24" RCP storm drain pipe that appears to be in dark line weight as to be demolished. However, this storm drain pipe is not tagged to be demolished. Please confirm pipe is to be demolished	See revised sheet CD103 in amendment 0008. Is this the same doc as PPI#19?
475	D1-D4/AE403, B4/AE615	N/A	N/A	For TOILET #B23, Elevations D1 through D4 on drawing AE403 notes "Porcelain Tile Pattern "A" (B4/AE615)" - Please confirm the pattern shown on elevation B4/AE615 is the intention for Toilet #B23. We recommend elevations D1-D4/AE403 depict the pattern that is noted.	Confirmed - install the tile per B4/AE615 on the elevations D1-D4/AE403.
476	Addendum 1, Att. E and G	N/A	N/A	Please verify that Attachment E is to be used for the Seed project (P691) and Attachment G is to be used for the full MACC contract.	No, Bid per RFP.
477	IN101D, IN101F, AE615	N/A	N/A	For DOOR POCKETS #D13 and #F18, please confirm the flooring finish is ONLY CONC1 per the Floor Finish Plans or if it's FRRF2 AND CONC1 per the Room Finish Schedule. If we are to follow the Room Finish Schedule, please accurately depict the extent of both the CONC1 and FRRF2 on the Floor Finish Plan.	The Room Finish Schedule and the Floor Finish Plans are correct. See note 9 on IN101D, IN101E, & IN101F for transition location. Bid per RFP.
478	N/A	02 82 00	N/A	The Certified Industrial Hygienist for Asbestos Remediation seems to required to be certified as a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer. Is it satisfactory if the IH company holds all of these credentials, but not held by one, single individual?	All the credentials referenced do not need to be held by the same individual.
479	N/A	02 82 00	N/A	The CIH for Asbestos Remediation is required to be appropriately licensed in the State of Maryland as a Project Monitor. Maryland does not have a project monitor license,	Follow all requirements for the State of Maryland for asbestos remediation.

				can you clarify this requirement?	
483	RFP, Page 10 & Page 21	N/A	N/A	Page 10 of the RFP shows a NAVFAC Command Wide Goal goals for additional SBE classifications (i.e. HUB Zone, SDVOSB, VOSB, SDB, WOSB). Page 21 does not provide any solicitation specific goals for these other classifications. Please provide goals for additional SBE classifications for the MACC and Seed Project.	Bid per RFP Program Goals on Page 10.
490	AE614, AE615, AE616	09 69 13	N/A	Sheet AE615 shows the floor finish for Room RACK STO #F14 to be RAF1, ESD1, and CONC1, with the ESD1 product listed on sheet AE616 and referenced in spec 09 69 13; please confirm the same ESD1 product used for that location is the same product used at other locations where ESD1 is the only floor finish shown (example: SIL LAB #F11)	Confirmed. Room Rack Sto #F14 is primarily RAF1 with CONC1 below and ESD1 on the perimeter. RAF1 and ESD1 have the same finish and must match per AE616.
491	AE112A	09 51 00	N/A	Please confirm all the radius perimeter trim (Axiom), inside and outside corners around the acoustical ceiling tiles are all typical 18 inches per specs?	Refer to Government response to PPI #130
492	S-337	N/A	N/A	Column line/letter indicators are missing from some of the structural drawing details. Please provide an updated/marked-up set of drawings that provide consistent column line/letter reference for all details where necessary? (Example Detail C2/S-337)	Bid per RFP; Detail C2/S-337 is intended to be used on multiple grid-lines.
493	AE-409a	N/A	N/A	Confirm the support for the coiling counter door is structural steel and not interior partition framing as shown.	Refer to Government Response to PPI #129
494	AE101A, B, C, D, E, F	N/A	N/A	Several walls throughout the floor plans do not have the type labeled. Please provide an updated drawing with all partition types called out or provide a basis to assume partition types without call outs.	Bid per RFP; All partition types are indicated - refer to all Area Plan sheets and all Enlarged Plan sheets.

495	AE409A, AE101A, AE101B	N/A	N/A	Rooms A14 and B11 reference the same elevation C1 on sheet AE409A, C1/AE409A only references room A14; please provide an elevation for room B11 or update C1/AE409A so that it references both rooms A14 and B11	Bid per RFP; OP2 OFF / OPEN OFF #A17 references C3/AE409 - OP2 OFF / OPEN OFF #B10 references C1/AE409.
496	S-009	41 22 13.15	1.3.1.1	Bridge Cranes: Section 1.3.1.1 identifies the explosion proof environment as NEC Class I, Division II. Please identify the Group (e.g. Group A (Acetylene), B (Hydrogen), C (Ethylene), or D (Propane))	Group D.
497	S-009	41 22 13.15	1.3.1.2	Bridge Cranes: Will you accept a 30 FPM hoist speed? Section 1.3.1.2 identifies the maximum hoist speed as 60 FPM and the minimum as 40 FPM. This range requires a custom hoist that standard hoist suppliers will not provide. Alternatively please provide a custom hoist manufacturer that will provide a hoist with speeds in the specified range.	Confirmed; a hoist speed of 30 FPM is acceptable. See revision to specification 41 22 13.15 in amendment 0008.
503	N/A	41 22 13.15	N/A	Section 2.4.8.1 Runway Conductor Bar System. The spec indicates a conductor bar system that can cause spark. Please confirm this is accurate given the environment has been classified in section 1.3.1.1 as NEC Class I, Division II. If the conductor bar system is deemed unacceptable.	Confirmed.
504	N/A	41 22 13.15	N/A	Bridge Cranes: Please confirm a festoon system is required with non-sparking equipment (stainless steel track, bronze trolley wheels, neoprene cables, etc.)	Confirmed.
505	N/A	41 22 13.15	2.4.8.2	Section 2.4.8.2 Bridge Conductor System. Please confirm that the festoon track system should be standard equipment or non-sparking (stainless steel track, bronze trolley wheels, neoprene cables, etc.)	Confirmed.

510	N/A	02 82 00	N/A	The Testing Laboratory selected for the sampling, analysis, and reporting of airborne concentrations of asbestos fibers, is required to be AIHA accredited. Can this requirement be waived if 2 consecutive passing PAT rounds are provided?	No - Bid per RFP
511	N/A	02 82 00	N/A	The persons in the Testing Laboratory selected for the sampling, analysis, and reporting of airborne concentrations of asbestos fibers, are required to be proficient by inclusion on the AIHA Asbestos Analysis Registry (AAR) for PCM analysis. Could this instead be satisfied by PAT proficiency and NIOSH 582 training?	No - Bid per RFP
512	N/A	02 82 00	N/A	A Lead Project Designer is required to develop and sign the Lead Compliance Plan. Would CIH credentials and demonstrated experience qualify in lieu of the project designer since this project is not being performed in a home or child occupied facility and any plan would be designed to satisfy OSHA requirements, not EPA and HUD?	No - Bid per RFP
513	CS508		N/A	Please specify wind loading for airfield dual slide gate across the apron. Will this loading require a PE Stamp?	See sheet S-001 for wind loading requirements.
514	CS508	N/A	N/A	Please refer to sheet CS508. What is the required infill pattern/design for the gate?	Infill per manufacturer recommendations compliant with CS508 and 32 31 13
531	SF1442	N/A	N/A	The estimated projects for this MACC are estimated to be between \$15M and \$1B. Would the Government consider a Stipend with the larger Design Build solicitations?	Bid per RFP. Specific project requirements will be issued on a task order level basis.
535	N/A	N/A	N/A	Is the government considering any future task orders on this MACC that would require offerors to hold an active facility clearance at time of submission?	Bid per RFP.

536	N/A	N/A	N/A	There is significant concern about availability from local ready-mix operations resulting in concrete loads taking longer than 30 minutes to reach the job site, as well as being unable to support high productions. Is the contractor permitted to set-up an on-site portable concrete batch plant to produce concrete that will consistently meet the specifications for the Apron concrete pavement? Will NAVFAC provide a site for this on the base, or directly on the job site? Please advise.	Refer to Government Response to PPI #111
540	General	General		Is there existing stockpiled soil/dirt available on the base for use in surcharge operations?	No.
542	General	General		There is concern about availability from local ready-mix operations resulting in concrete loads taking longer than 30 minutes to reach the job site, as well as being unable to support high productions. Is the contractor permitted to set-up an on-site portable concrete batch plant to produce concrete that will consistently meet the specifications for the Apron concrete pavement? Will NAVFAC provide a site for this on the base, or directly on the job site? Please advise.	Refer to Government Response to PPI #111
545	TS101			Sheet TS101: Drawing Notes 1,2, and 3 appear to be included in this project? If so, Please give separate point to point destinations for each of the copper and fiber under note 1. The way it is currently written is confusing. Please give a start and end point for note 5. Also, give a pair count for note 5, it is missing.	Keynotes 1,2,& 3 are all a part of phase I. All other keynotes are part of Phase II. Keynote 5 it is 100 PR and the splice point is in CMH 10.9.1
556		08 71 00		Specification 08 71 00 depicts select items "By Access Control" as well as signal(ing) to intrusion detection system.. Since no Division 28	Refer to Government Response to PPI #186

				specifications are provided (other than 28 31 76 Interior Fire Alarm and Mass Notification System) it appears no security scope of work is to be included in this contract. Confirm all security (Video, access control, and intrusion detection) are GFGI and not to be included in this contract.	
557	TY501			Sheet TY501 have general overview of security components. What is the desired manufacturer(s) of video, access control and Intrusion systems?	Refer to Government Response to PPI #186
558	TY Series	Division 28		TY Series drawings show locations for electronic security scope but the Specifications do not show the actual spec for the Division 28 ELECTRONIC SECURITY SYSTEMS (ESS) portion. Confirm electronic security scope is GFGI.	Refer to Government Response to PPI #186
559	TY Series			TY Series drawings: Please define the responsibilities of security contractor with regards to provision, installation, programming, testing security equipment and cable on this project.	Refer to Government Response to PPI #186
560	TY Series			TY Series drawings: Please clarify if this contract is to provide and install network switches associated with security devices (i.e. IP cameras, access control panels, intrusion panels, etc.). Is there a desired switch manufacturer to maintain continuity with existing network?	Refer to Government Response to PPI #186
561	TY Series			TY Series drawings: Will any of the new security devices be connecting to an existing security system?	Refer to Government Response to PPI #186
562	TY Series			TY Series drawings: Please specify the desired warranty period for security (Video, access control, and intrusion detection) devices	Refer to Government Response to PPI #186

563	TY Series			TY Series drawings: Please specify testing, commissioning, and procedures for the video, access control and intrusion systems.	Refer to Government Response to PPI #186
564	TY Series			TY Series drawings: If Specifications for Division 28 Security ESS is provided will an extension for RFI submission period be granted?	Refer to Government Response to PPI #186
567		27 41 00	2.3.1.a and 2.3.1.f	Section 27 41 00-2.3.1, a. indicates that the flat panel display will be used for both local presentation and video conferencing. Section 2.3.1, f. references a room PC that will be used for web conferencing. Is the “video conferencing” referenced in Section 2.3.1, a. the same as the “web conferencing” referenced in Section 2.3.1, f?	Yes
568		27 41 00	2.3.1.f	Section 27 41 00-2.3.1, f calls for pendant microphones. May other microphone styles, such as flush or surface-mount ceiling microphones be used that incorporate similar technology as that described in Section 2.3.1, f?	No
569	T-111 and T-113	27 41 00	2.3.1	Section 27 41 00-2.3.1: Several wireless technologies are called to include a wireless keyboard and mouse, a wireless presentations gateway, and a wireless touch panel. However, the drawings illustrate that Conference Rooms A18 and C28 will both receive a SIPR and Unclass drops. Will wireless devices be permitted in these rooms that also have a SIPR drop?	No
572		27 41 00		Will all the AV devices in the conference room be of the same classification level?	Yes
573		27 41 00		If the AV devices in each conference room are to be of different classification levels, is the intention that any device, regardless of classification, may be sent to	Yes

				different monitors, as desired, and seen at the same time?	
579				In order to allow appropriate time for document review for all subcontractors, including small business subcontractors, please consider a (1) week extension of the PPI deadline of 04/11/25. Small business subcontractors have reached out directly to request more time to process the drawings and specifications.	Bid per RFP.
586	CU101			Page CU101 indicates a "DIRECTIONAL BORE FIRE SUPPRESSION LINE UNDER MILLSTONE ROAD". Please confirm this scope is by the contractor and that it can be performed during working hours while the road is operational and actively used.	See point of demarcation on CU102
587	CU104			Page CU104 indicates to protect fuel line in place. Is the intent of the documents to provide this protection with the casing only as detailed on CU504? Prior to installation of casing shown on CU504 please provide details for protection requirements for existing fuel lines.	See GC102, install casing pipe in phase 2D
592	General			Based on subcontractor market feedback, major key subcontractors and material/equipment suppliers are requesting a 2-3 week extension. Please consider a due date extension to allow for sufficient time for the subcontractors to provide bid proposals.	Bid per RFP.
599	Specifcation 03 30 00 1.7			Per Specification Section 03 30 00 1.7 – Please list concrete operations that 100% outside air ventilation is required 24 hours per day? It is assumed that this will not be required on this project.	Bid per RFP
603	S-305			Per drawing S-305 detail, please confirm the floor trench for the ILDFA will be furnished and installed by	Bid per RFP

				others and not to be included in the contractors bid price?	
606	CU101/CU115			Per CU101/CU115 – Please confirm what the existing 14” waterline services to assess the utility shut down and approach to this tie-in and provide the limit of time this utility can be shut down to make the tie in?	See point of demarcation on CU102
607	CU115			Per Note on CU115 – Please define exact scope bidders are to assume to be included by contractors for the new Water and Sewer utilities as note on CU115 can be interpreted that all work will furnish and installed by ASUS and coordinated by KO for this project and these costs should not be included in the bid?	Reference point of demarcation for all utilities on CU101-119
610	01 14 00 Work Restrictions			There is concern about availability from local ready-mix operations resulting in concrete loads taking longer than 30 minutes to reach the job site, as well as being unable to support high productions. Is the contractor permitted to set-up an on-site portable concrete batch plant to produce concrete that will consistently meet the specifications for the Apron concrete pavement? Will NAVFAC provide a site for this on the base, or directly on the job site? Please advise.	Refer to Government Response to PPI #111
612	Oil-Water Seperator			Could a DAF (Dissolved Air Flotation) unit be an approved alternative for the oil-water seperator?	Bid per RFP
618		274100	2.3	Bid Specifications Section 27 41 00, 2.3.1, a. and Section 27 41 00, 2.3.1, f. Section 2.3.1, a. indicates that the flat panel display will be used for both local presentation and video conferencing. Section 2.3.1, f. references a room PC that will be used for web conferencing. Is the “video conferencing”	Yes

				referenced in Section 2.3.1, a. the same as the “web conferencing” referenced in Section 2.3.1, f?	
619		274100	2.3	Bid Specifications Section 27 41 00, 2.3.1, f. Section 2.3.1, f calls for pendant microphones. May other microphone styles, such as flush or surface-mount ceiling microphones be used that incorporate similar technology as that described in Section 2.3.1, f?	No
620	T-111, T-113	274100	2.3	Drawings T-111 and T-113 Several wireless technologies are called for Section 2.3.1, to include a wireless keyboard and mouse, a wireless presentations gateway, and a wireless touch panel. However, the drawings illustrate that Conference Rooms A18 and C28 will both receive a SIPR and and Unclass drops. Will wireless devices be permitted in these rooms that also have a SIPR drop?	No
623		274100		Will all the AV devices in the conference room be of the same classification level?	Yes
624		274100		If the AV devices in each conference room are to be of different classification levels, is the intention that any device, regardless of classification, may be sent to different monitors, as desired, and seen at the same time?	Yes
630	Solicitation			Recent Government policies are creating significant uncertainty and/or fluctuation in construction material costs that is increasing risk to both the Government and Offerors. To help mitigate this risk, and in lieu of using an Economic Price Adjustment clause, we request the Government revise the proposal acceptance period to 30 days after receipt	Bid per RFP.

				of offers. If the Government is unable to make an award within 30 days we recommend the Government issue an amendment, seven (7) calendar days before the end of the proposal acceptance period, to extend the proposal acceptance period an additional 30 days and request revised proposals based solely on market conditions. The Government can continue to issue amendments to extend the proposal acceptance period in 30 day increments as needed until it is able to make an award. While this creates some additional administrative burden, this approach will reduce risk to both the Government and Offerors while always providing the Government awardable proposals.	
633	GC-104			The General Notes on drawing GC-104 require a 5ft surcharge for an estimated 3mos across the entire building pad. The detail note at the bottom of the sheet requires the Contractor's Geotechnical Engineer to confirm design and extent of surcharging to mitigate underlying compressible soil layers. We request that the Government remove this requirement, allowing all offerors to bid the project based on the surcharge assumptions indicated in the General Notes.	Bid per RFP
634	Specifications	32 13 14.13		Confirm the use of third party testing and 2025 batch plant testing data for submittals for Airfield Paving	Bid per RFP. Per Spec 32 13 14.13 1.4.1.e and Table 17
635	Specifications	32 13 14.13		Confirm flexibility in the finishing method for airfield paving as air screed may not be the best method.	Bid per RFP Spec 32 13 14.13 3.5
638	Solicitation			We respectfully request a short extension to the RFI submission deadline to ensure	Bid per RFP.

				a complete and technically sound proposal. Several of our key trade partners—whose input is essential for identifying design concerns and verifying constructability—have experienced delays in their review due to the complexity of the project documents and the need to coordinate with manufacturers and suppliers regarding system-specific requirements, including aircraft fire suppression, hangar door systems, and utility infrastructure unique to aircraft maintenance operations. Allowing additional time would enable a more thorough evaluation of the plans and specifications and incorporate information gleaned from the site visit, ensuring all pertinent RFIs are submitted prior to bid. This would minimize post-award clarifications or change orders and support a more accurate, efficient, and cost-effective outcome for NAVFAC.	
641	24	04 20 00	3.7.2	Paragraph 3.7.2 CONCRETE MASONRY UNIT SURFACES says to "perform cleaning in accordance with the approved cleaning procedure demonstrated on the mock-up." Paragraph 1.3.1.5 says "Perform cleaning procedures on the mock-up and obtain approval of the Contracting Officer prior to cleaning the building." The method of cleaning is not mentioned in the plans or specs. Please provide the desired method of cleaning for exposed concrete masonry unit veneer.	Per 3.7.2 - Clean with a proprietary masonry cleaning agent specifically recommended for the color and texture by the concrete masonry manufacturer and manufacturer of the cleaning product.
647	CD100, CS100, CG100, CU100			Please provide the combined Cx101 thru Cx105 overall site plans for the CD100 Overall Existing Condition and Demolition, CS100 Overall	Bid per RFP

				Site Plan, CG100 Overall Grading and Drainage, and the CU100 Overall Utility Plan.	
648		00 21 00		Section 00 21 00 under Small Business Subcontracting Plan Information reads that the Small Business Subcontracting Plan is based on the proposed MACC NTE Value. Please confirm that the Factor 5 Small Business Participation Commitment Document is also based on the proposed MACC NTE value.	Confirmed.
649				Are there specific targets for Prime Contractors to adhere to, as it relates to Minority, Woman owned, or disadvantage business who wish to participate	Bid per RFP.

(End of Summary of Changes)