

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE OF PAGES 1 19	
2. AMENDMENT/MODIFICATION NO. 0011		3. EFFECTIVE DATE 06-May-2025		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable)	
6. ISSUED BY CODE COMNAVFACSYSCOM WASHINGTON 1314 HARWOOD ST WASHINGTON DC 20374		N40080		7. ADMINISTERED BY (If other than item 6) CODE		See Item 6	
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X		9A. AMENDMENT OF SOLICITATION NO. N4008025R9500	
				X		9B. DATED (SEE ITEM 11) 13-Mar-2025	
						10A. MOD. OF CONTRACT/ORDER NO.	
						10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer ☐ is extended, ☒ is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) N40080-25-R-9500- Design-Build (DB)/Design-Bid-Build (DBB) Indefinite-Delivery/Indefinite-Quantity (IDIQ) Multiple Award Construction Contract (MACC) for Large Scale U.S. Military Projects, Locations in Washington D.C., Maryland, and Virginia PLEASE SEE SF30 BLOCK 14 CONTINUATION PAGE							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: _____ EMAIL: _____			
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 06-May-2025	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION SF 30 - BLOCK 14 CONTINUATION PAGE (SF 30)

The following have been added by full text:

0011

The purpose of this amendment is to:

1. Revise Solicitation
2. Provide revisions to design documents in accordance with noted PPIs
3. Provide PPI responses

1. Revise Solicitation

Section 00 21 00 – Instructions
INSTRUCTIONS TO PROPOSERS

TO:

1.3.5 The intent of this contract is that all IDIQ Contractors participate in pre-proposal conferences and site-visits and submit proposals on each task order. Contract awardees will be expected to submit a proposal for all Task Order Requests for Proposal (RFP) received from the Government. However, in the event a MACC awardee is unable to submit a proposal on a particular RFP, the contractor is required to notify, in writing, the Contracting Officer who issued the RFP and the ACO for the basic contract within five working days from receipt of the RFP. **Awarded Offerors are expected to propose to the maximum extent possible over the duration of the IDIQ. Frequent proposal withdrawals from the same firm may result in non-renewal of the option period.**

2. Revisions to Specification Sections and Drawings:

Note: Revised Specification and Drawing Sheets issued by way of an amendment to N4008025R9500 are available via restricted access through PIEE. If an offeror has an issue retrieving the revised documents, they are instructed to contact the Contract Specialist, Molly Lawson at molly.e.lawson.civ@us.navy.mil in order to receive the documents via DoD Safe.

PPI #078 & 128 – See Amendment 0009 for Revision to specification section 32 13 14.13

PPI #087 – See Revision to specification section 31 00 00

PPI #156, 291 – See Revision to specification section 10 51 26

PPI #162, 163, 180, 181, 182, 183, 184, 185, 241, 267, 268, 367, 545, 546, 549, 577, 628

– See Revision to drawing TS101

PPI #163, 272, 372, 549, 555 – See Revision to drawing T-601

PPI #163, 369, 549 - See revision to drawing T-603

PPI #166 – See revision to specification section 01 11 00

PPI #176, 297 – See Revision to drawing AE615
 PPI #187 – See Revision to specification section 22 00 00 and drawing P-502
 PPI #189 – See Revision to Sheet M-605
 PPI #208 – See Revision to drawing FA001
 PPI #216 – See Revision to drawing AE402
 PPI #218 – See Revision to specification section 08 33 13
 PPI #220 – See Revision to specification section 26 56 20
 PPI #232 – See Revision to drawing AE100, AE101a, AE101b, 409a
 PPI #249 – See revision to drawing AE601
 PPI #270, 364, 365, 551, 552, 553, 366, 551, 576, 627 – See Revision to drawing T-001
 PPI #271, 370, 554 – See Revision to drawing T-403
 PPI #288 – See Revision to drawing AE411
 PPI #291 – See Revision to drawing AE101G
 PPI #295 – See Revision to drawing AE617
 PPI #341 - See Revision to specification section 07 42 63
 PPI #342 - See Revision to specification section 07 42 13
 PPI #345 – See Revision to Sheet CU506
 PPI #368 – See Revision to drawing T-116
 PPI #376 – See Revision to drawings AE201, AE202, AE204, AE606
 PPI #575, 626 – See Revision to drawing T-112, T-113
 PPI #191, 443 – See Revision to drawing CS508
 PPI #555 – See Revision to drawing T-602

3. PPI Responses:

#	Reference			Inquiry	Government Response
	Page	Section	Para		
20	GC104			For the wick drains indicated on GC104: 1) Will a specification be provided for Wick Drains? 2) Will a pre-consolidation plan be required? 3) Besides the settlement plates indicated on GC104 will vibrating wire piezometers and inclinometers be required?	1. No, Bid per RFP 2) Yes, Bid per RFP GC104 and 3) Not required but may be used, Bid per RFP.
66	GC102	n/a	n/a	Per drawing GC102, Building demolition under Phase 1A for buildings 2372, 669, 619, 314, and 315 cannot be demolished until new facilities, which are part of separate contracts, are functional. Please provide guidance as to when the offers shall expect ability to demolish existing buildings per Phase 1A.	The Offerors can expect that buildings 2372, 669, 619, 314 and 315 will be in use until 15 January 2026. This is the earliest date that they may be vacant and available for demolition after removal of furniture and other contents by the demolition Contractor.
78	CD101			For the fire suppression line that crosses Millstone Road and continues north to its tie in point please confirm all tree removal, asphalt sawcutting and patching on CD101 will be performed	Confirmed. Bid per RFP.

				under ASUS's contract with the government.	
81	CU104, CU105			Please confirm the 2" sanitary sewer force main w/ 8" casing under the concrete apron is to be by the contractor and not by ASUS.	Confirmed, work referenced is to be completed by contractor as per RFP.
87	CU504	31 00 00	2.6	Reference specification section 31 11 00, section 2.6 - Pipe Casing. This specification references you to drawing CU507. 1) Please provide drawing CU507 2) Is this specification section applicable to the fuel line casing shown on CU504? If so there is conflicting information (ASTM requirements, protective coatings) 3) If this specification section is not applicable to the fuel line casing provide specification section applicable to fuel line casing shown on CU504.	Amendment 0008 - 1) Specification section 31 00 00 2.6 should reference CU501 and CU504, not CU507. 2) It is applicable to CU501 and CU504. Specification will be revised. 3) See response to 2) Refer to revised specification section 31 00 00 to be re-issued.
128		Div 30 Specifications		Specification sections 31 00 00, 31 05 19.13, 32 01 16.17, 32 01 19.61, 32 12 15.13, 32 12 16.16, 32 13 14.13, 32 16 19, 32 17 23, and 33 40 00 have have various items that note "will be paid for at the contract unit price", but the Price Proposal Form provided in Amendment 0002 does not have unit prices for these Division 30 specificaiton items. Please confirm these unit prices are not required to be submitted.	Confirmed. Specifications have been revised to reflect Lump Sum payment. No change necessary to 32 01 19.61. Refer to revised specification 31 00 00 to be re-issued.
131	1	01 91 00.15	1.2	Specification section 01 91 00.15 1.2 CxC states the Commissioning Provider (or Commissioning Firm, terms are to be interchangeable as noted within this section) is hired by the government, where as 01 91 00.15 1.1 states the Prime Contractor is to employ the services of an independent Commissioning Firm. Please confirm that the independant commission firm is hired and paid by the Government as noted in 01 91 00.15.	Confirmed
138	A1 & C3, S-152F			Enlarged plan of Antenna platform indicates a total of 4 fall protection D-Ring attachments. Please confirm if this is full extent of the D-Ring Fall protection attachmetns. If not, please provide drawing showing full extent.	Yes, drawing S-152 shows all the fall protection attachments. Bid per RFP.
156	Page 5	Spec Section 105126	2.6.1	Spec Section for Plastic and Cell Phone Lockers, paragraph 2.6.1 says "Provide twelve (12) bank patron door charging lockers as shown on drawings for cell phones and other mobile devices..." However, VOL 2, drawing AE403,	Seven (7) pairs of cell are required. Refer to revise specification 10 51 26 to be reissued

				detail A3 shows 14 columns of 6-tier cell phone lockers, or 7 pairs. Please confirm the correct amount of cell phones lockers required for this project.	
162	TS101			Are notes 1,2, and 3 included in this project? If so, Please give separate point to point destinations for the for the copper and fiber under note 1. The way it is currently written is unclear. Please provide a start and end point associated with note 5.	See the updated drawing notes panel on the revised Sheet TS101 to be re-issued.
163	TS101 T601 T603			There is a conflict between drawings TS101, T601, and T603 on which manhole the 100 pair into P691 comes from. Please clarify.	See revisions to sheets TS101, T-601, and T 603 to be re-issued.
164		27 10 00		The rack elevation drawings show no vertical wire managers on the racks or in the equipment cabinets. Please clarify in vertical cable mangers are required or not.	Vertical wire managers are required, for 4-post racks and the cabinets.
165		27 10 00		Please confirm who is responsible for splicing the new copper cables to the existing splice cases in the manholes?	Verizon
166		01 11 00	1.2.2	Specification section 01 11 00 1.2.2 references the building will be occupied during construction - please clarify extent and for what durations	Building will not be occupied during construction. Refer to revised specification section 01 11 00 to be re-issued.
170		096723.13 & 096723.15		Confirm SSPC QP8 certification will be required for project. Will a portfolio of equal projects and reference from the manufacturer suffice for qualification. The BOD product does not require the SSPC QP8 or SSPC QS1 certification.	Refer to Government Response to PPI #639.
176	AE615 and AE616			Confirm H2A, HGR Bay #2 ceiling finish is EXP STR PT2, it appears to be missing the numeric identification on the Room Finish Schedule.	Confirmed - finish will be EXP STR PT2. See revision to drawing AE615 to be re-issued.
180	TS101	Drawings Volume 3 of 3	Drawing Notes	Please confirm that all OSP cabling fiber, as shown on TS101, is to be procured and installed by the local service provider (Verizon).	Contractor to provide and install fiber optic cabling to all buildings. Tie points to Verizon fiber to be coordinated during construction.
181	TS101	Drawings Volume 3 of 3	Drawing Notes	Please confirm that all work identified in Drawing Notes 4, 5 & 6, as referenced on TS101, is not to be included in this solicitation.	Bid per RFP
182	TS101	Drawings Volume 3 of 3	Scale	The provided scale on Sheet TS101 appears to be incorrect. Please provide a corrected scale.	See Revised drawing TS101 to be re-issued.

183	TS101	Drawings Volume 3 of 3		Please confirm that the underground Telecommunication distribution from CMH 10.7 to CMH 10.4.3 as shown on Sheet TS101 is utilizing existing conduits and that no new conduits are to be installed between those communication manholes.	New ductbank to be provided from CMH 10.7 to Hazmat storage. New ductbank to be provided from CMH 10.4.3 to sonobuoy storage bldg. Refer to Revised Sheet TS101 to be re-issued.
184	TS101	Drawings Volume 3 of 3		Please confirm that the UG Telecommunication distribution from CMH 10.7 to CMH 10.9.2 as shown on Sheet TS101 is utilizing existing conduits and that no new conduits are to be installed between those communication manholes.	Confirmed.
185	TS101	Drawings Volume 3 of 3		Please confirm that Manhole #11 as identified on Sheet TS101 is an existing manhole.	Confirmed.
187	P502 & P-904	Drawings Volume 2 of 3	Detail C4/P502 and Drawing Note 1 on sheet P904	In the drawings, Sheet P-502 Detail C4 shows the wall mounted hose reels for the compressed air drops. However, the spec section 22 00 00 section 2.11 Air Compressors does not mention any details about the compressed air drops or hose reels. (A) Can a specification for the hose reels be provided with a basis of design? (B) How long are the hose reels required to be at each compressed air drop? (C) Is there any additional final connections or disconnects needed at each hose drop?	Provide hose reel assembly complete with 100 foot hose rated for a minimum of 125 psig, ball stop, hose extension with air coupler, hose rollers, non-sparking ratchet pawl, and wall mount kit and required accessories. Refer to revised specification section 22 00 00 and drawing P-502 to be re-issued.
188	M-001	Drawings Volume 2 of 3	Mechanical General Note 1	Sheet M-001 Mechanical General Note 1 states that HVAC work must be coordinated with other trades. (A) Will BIM be required for clash detection from Mechanical Contractors? (B) If BIM is required, what Level of Design (LOD) will be required?	The construction documents do not require the contractor to perform clash detection using BIM.
189	M-605	Drawings Volume 2 of 3	Ductwork Construction and Leakage Testing Table	On sheet M-605 in the Ductwork Construction and Leakage Testing Table, the remarks column indicates Remark 1. However, it appears that Remark 1 is missing from this sheet and table. Could the Government please provide Remark 1 information?	Remark 1 was added to the Ductwork Construction and Leakage Testing Table Schedule. Refer to revised drawing M-605 to be re-issued.
191	CS508	Drawings Volume 1 of 3	Detail 2	Sheet CS508 Detail 2 regarding the foundation for the sliding gate on the apron indicates a 1'-2" apron pavement section. However, Detail 4 on sheet CS501 indicates a 12" apron pavement section. Please confirm the thickness of the airfield concrete section.	Refer to revised drawing CS508 to be re-issued.

193		09 67 23.16	1.4.5.5	Spec Section 09 67 23.16 1.4.5.5 Qualifications of Coating Contractor calls out for the coatings installer to be certified to SSPC QP 8 and should also be certified to SSPC QS1. These certifications are for companies that perform high performance coatings for tank linings, etc., and not companies that install resinous floors. Please clarify that these certifications are not required for this project.	Refer to Government Response to PPI #639.
208	FA001	Drawings Volume 2 of 3		Drawing FA001, Note 68, says “the secure area (CAT/SIL) must be provided with its own remote FA/MNS control panel (RFMCP).” FA-series drawings don’t appear to identify RFMCP quantities or locations, and drawing G-104 shows 5 different “secure areas”. Please clarify required number and approximate locations of RFMCP unit(s).	The secure area RFMCP is no longer a requirement.
216	08 71 00	Set 23 and Set 24		The Door Hardware specification states that Sets 23 and 24 for doors B20A and B20B require door operator bollards. Bollards are not shown on AE101B for doors B20A or B20B. Please advise where these will be located.	Refer to revised drawing AE402 to be re-issued.
218	E-111A, E-111B	Section 08 33 13	3.2.1	Paragraph 3.2.1 of section 08 33 13 calls for motorized operation of the coiling counter doors. Drawings E-111A and E-111B do not show power to these doors (openings A23C and B33C). Please verify if these doors are to be manual or motorized.	Refer to revised specification 08 33 13 to be re-issued.
220	Specification 26 56 20	1.4.2.a		Approved Airport Lighting Equipment document link does not work. Provide missing document.	Refer to revised specification section 26 56 20 to be re-issued.
232	A4/AE-409a			Please confirm the interior partition framing is not the structural support for the coiling counter door? Is there supposed to be an HSS member for the jamb support?	Refer to Government Response to PPI #129, Refer to revised drawing AE100, AE101a, AE101b, 409a to be re-issued.
237		27 41 00		For CLIN 0008 Option for AV Systems - Please confirm base bid is to include the concept AV package listed in Spec Sect 27 41 00 and current floor plans. Please note that the system description only lists a Large Conference Room, shall this description apply to conf. A18, B22 and C28? If separate and unique functionality is required, please issue updated specification.	Refer to Government Response to PPI #566, Amendment 0009

241	TS101			Site plan shows phase 1 fiber. Please confirm the phase 1 scope is already in place. Please confirm sheet note 4, 144 strand OS2 should be included in this contract. Additionally, What site fiber will Verizon provide and what fiber is the contractor responsible for?	The 144 fiber cannot be installed until the hangar entrance room has been built. The 144 extend from the hangar to building 435. Yes the fiber run is a part of this contract. See revisions to sheet TS101 to be re-issued.
249	AE601			The door schedule on AE601 lists room B31A & B35A to receive a single interior door but states that both shall also receive a D2 double steel door frame. Please confirm both frames should be a S2 frame in lieu of the D2 frame.	Refer to revised drawing AE601 to be re-issued.
267	TS101			Ref TS101 Telecom Site Plan - Site plan seems to reference Phase 1 work, Please confirm these pathways and fiber are already installed. Please confirm telecom pathways in this project's scope are identified as 'phase 2'.	Keynotes 1,2,& 3 are all a part of phase I. All other keynotes are part of Phase II. Keynote 5 it is 100 PR and the splice point is in CMH 10.9.1
268	TS101			Please confirm what fiber Verizon will install on TS101 telecom site plan and what is by the contractor.	Verizon will will splice in the contractor provided copper feeds.
270	T-001			T-001: The description of the Type S outlet asks for D1 jack to be red, D2 to be orange, and does not state the color for D3. Is this jack unclassified and black? According to symbol note 2 all jacks should match the fiber cable color. Please clarify Type S description.	Refer to revised drawing T-001 to be re-issued.
271	T-403			T-403: Details A1 and C1 for comm room A16 do not match. Detail C1 shows 4 cabinets but 3 of them are labeled Rack; however, keynote 2 calls out cabinets. Detail A1 only shows 2 racks and 1 cabinet. Please clarify.	Detail C1 has one cabinet and 3 4-post racks. Third rack is for future growth. Refer to revised drawing T-403 to be re-issued.
272	T-601			There is a conflict between Detail B1 on T-601 and Detail C2 on T-602. Fiber types and counts do not match. Copper pair counts do not match. Please clarify.	Each comm room receives a 25PR CAT3 backbone cable. Rooms a16,c30,c31 receive 48STD OS2 & 48 OM3 fiber. Rooms B16 & C20 receive 24 STD OS2 & 24 OM3. Refer to revised drawing T-601 to be re-issued.
277				Telecommunications ductbank (labeled CU) on CU102 notes to reference telecommunications plans for details. Telecom site utility plant TS101 does not shown this ductbank. Provide details	Bid per RFP. Refer to TS501

				of ductbank or confirm this is not in scope.	
288				Detail B3 on sheet AE411 makes reference to fabricated wall panels FWP3, the Exterior Material Legend on AE617 makes no reference to FWP3. Please confirm "color" for FWP3 panels.	Refer to revised drawing AE411 to be re-issued.
290		08 71 00		Hardware set 23.0 and 24.0 both indicate manufactures bollards for auto door operators. Please confirm a total of two bollards are anticipated, one bollard in floor of Lobby B21, between opening B20B and B22A, and one bollard on exterior of building.	Refer to Government Response to PPI #216.
291		10 51 26		Plastic lockers occur in many different areas. Some areas either elevate or schedule porcelain tile base under the lockers, i.e. B3/AE407; B2/AE408. Please clarify the "construction of the locker base" in which the applied finish base is applied for each condition, as well as areas which may only require metal material base by the locker manufacturer, i.e. line shack, i.e. C2/AE101G.	Refer to revise specification 10 51 26 and drawing AE101G to be reissued
292	Price Proposal Form	1.2 General Bid Notes		Price Proposal Form, General Bid Note C. indicates that CLINS 0002 - 0007 has a 365 day expiration from time of award. However, for CLINS 0008 and 0009, there is no expiration date given. Please limit the time period for those CLINS to the same 365 days at maximum	Bid per RFP
295				Please confirm paint color for FWP3 and associated trims that occur at Hangar doors. FWP3 is not listed on Exterior Material Legend on sheet AE617	Refer to revised drawing AE617 to be re-issued.
297	AE615			The Room Finish Schedule - Areas D-G indicates that Corridors D12 & F17 apply to Bid Option 4, apply FRRF1. However, the base bid floor coating is CONC1, not the 3-coat fuel resistive flooring, FRRF2. Please confirm if this is correct.	See revision to drawing AE615 to be re-issued.
309	AE617			The Exterior Materials Legend on AE-617 shows the MWP as 4" x 36" which conflicts with the Specifications Section 07 42 13 Metal Wall Panels, and the details on Drawings A-502 and A-503 etc. Please confirm the Exterior Materials Legend is NOT correct.	Refer to Government Response to PPI #342, Amendment 0010
341	AE-617	07 42 63	2.1.4	Section 07 42 63 Fabricated Wall Panel Assemblies is listing a FWP3 however	Delete the reference to FWP3. Refer to revised

				the Exterior Materials Legend on AE-617 does not show a color selection for this panel. Please provide color selection for FWP3.	specification section 07 42 63 to be re-issued.
345	CS503	Detail 4		Detail says if existing structures are not aircraft rated, please replace with rated structures. Please advise if and what structures are rated or unrated and if unknown, what should be assumed by bidders.	Include replacement structures or structure reinforcement in bid price. Refer to revised drawing SU506 to be re-issued.
351	Spec 26 35 43, E-111B, E-111D, E-111F		Spec paragraph 2.1.1.7	Specification UFGS 26 35 43 paragraph 2.1.1.7 POWER OUTPUT states "Provide a frequency converter rated at 312KW at unity power factor." Electrical Drawings E-111B, E-111D and E-111F all have NEW WORK KEYNOTES that state, "GFGI 400HZ 45KVA CONVERTERS.....". 1. Are the converters to be contractor furnished or confirm they are Government Furnished & Government Installed? 2. If the converters are to be contractor furnished, can you confirm if they are to be 312KW per the specification or 45 KVA per the electrical drawings.	1. 45KVA converters are Government Furnished & Government installed for the Hangar Converters. 2. the spec is for the (2) 312KVA converters for the SIL Lab 400Hz distribution. Refer to A3/E-401 for the converter locations. Refer E-602 (A,5) for the one-line information on 312KVA converters.
364	T-001			Symbol for SIPRNet standard WAO requires 2 strand OM3 to three jacks per faceplate. D1 is defined as Red, and D2 is defined as orange, please provide the color requirement for D3.	Refer to Government Response to PPI #270.
365	T-001			Symbol for SIPRNet standard WAO requires 2 strand OM3 to three jacks per faceplate. Please confirm that a single 6 strand cable is not acceptable and that the requirement is three 2-strand cables.	The revised symbols call for STANDARD WORK AREA OUTLET (WAO), SIPRNET; REQUIRES 2 STRAND OM3 MULTIMODE FIBER OPTIC MIC CABLE TO EACH OF THREE JACKS PER FACEPLATE. TERMINATE EACH JACK WITH A DUPLEX LC CONNECTOR. FIRST JACK WILL BE RED FOR D1 ICON, SECOND JACK WILL BE ORANGE FOR D2 ICON, THIRD JACK WILL BE YELLOW D3 ICON. LEAVE 4TH PORT BLANK FOR FUTURE CABLING. PROVIDE (2) 1"

					CONDUITS FROM EACH LOCATION TO NEAREST CLASSIFIED BASKET TRAY. DEVICES WITH A BOX AROUND THEM INDICATES A FLOOR BOX LOCATION SEE ELECTRICAL DWGS FOR BOX LOCATIONS Refer to revised drawing T-001 to be re-issued. Refer to government response to PPI #270.
366	T-001			Symbol for Top Secret standard WAO requires one 6-strand cable and also references three 2-strand OM3 to three jacks per faceplate. Please confirm the cabling requirements for the Top Secret WAOs.	A single six strand for Top secret WAO is acceptable. Refer to revision to drawing T-001 to be re-issued
367	TS-101, TS-501			The key notes on sheet TS-101 do not call for 3-Cell Fabric Duct as the details on sheet TS-501 do. Please confirm that the new sections of two-way and four-way communications ductbanks will require (1) 3-Cell Fabric Duct in (1) conduit. Please also confirm the size of the Fabric Duct.	3-cell fabric duct required in one conduit. the 4-inch 3 cell fabric ducts. Refer to revised drawing TS101 to be re-issued.
368	T-116			The U and S outlets within this area state they are to terminate in COMM B16 and COMM A16 respectively. COMM C20 and COMM C30 are much closer. Please confirm the origination point for these outlets.	Keynote 2 shall apply to these WAO. Refer to revised drawing T-116 to be re-issued.
369	T-401, T-603			The Voice Riser Diagram on sheet T-603 shows CAT6 cables running from the Building Entrance Protector to a voice patch panel mounted in a rack. The Enlarged Plan for MDF C14 does not show a copper patch panel in the racks. Please confirm these cables need to be installed and the quantity if so.	Wall mounted 110 blocks in Room C14. Refer to revised drawing T-603 to be re-issued.
370	T-403			Racks 1-3 are shown with the dimensions of a cabinet despite being labeled as racks. Please confirm these are supposed to be cabinets and not two-post racks.	Racks are 4-post racks. Along with a single cabinet. Refer to revised drawing T-403 to be re-issued.
371	T-501	Detail C1		Are the LC connectors at the WAO and at the Telecommunications Rooms required to be keyed in addition to their respective color or does the Government only desire the adapters to be colored with non-keyed connections?	LC terminations on both ends. The keyed and respective colors are required on both ends.

372	T-601, T-602			The backbone cabling on T-601 shows only singlemode fiber optic cable and 25 pair Category 3 cable. The backbone diagram on T-602 shows 48 strand multimode and singlemode cables and 50 pair Category 3 cables. Which diagram is correct?	Each comm room receives a 25PR CAT3 backbone cable. Rooms a16,c30,c31 receive 48STD OS2 & 48 OM3 fiber. Rooms B16 & C20 receive 24 STD OS2 & 24 OM3. Refer to revised drawing T-601 to be re-issued.
373	Spec 27 10 00		2.4.4	The specifications state to provide patch cords for patch panels. Please confirm patch cords are not required for the WAO side of fiber optic cables.	Patch cords are required on the WAO side. For bidding purposes provide 1 meter patch cords at the WAO per port.
374	Spec 27 10 00		2.4.4	Please provide the length for required patch cords and quantity calculations (1 per port, one per WAO, etc.)	Refer to Government Response to PPI #373.
375	Spec 27 10 00		2.4.4	If connections are required to be keyed, will the patch cords need to be keyed-to-keyed, or keyed-to-non-keyed?	Refer to Government Response to PPI #371.
376	AE204			On Drawing AE204, East and West Elevations, the translucent panels are graphically shown extending beyond the north wall of the hangar. This appears to be a modeling error. On Elevation D2/ AE606 East Elevation of the translucent panels, it is noted in the overall dimension that there are to be 24 EQ. 5'-0" wide vertical panels. This adds up to 120'-0". However the dimensions shows a different dimension. Please confirm what is shown on AE204 is not correct and confirm that the translucent panels are to be 24 EQ. 5'-0" wide vertical panels.	Refer to revised drawings AE201, AE202, AE204, AE606 to be re-issued.
411		General		Is there site specific badging or training requirements?	See spec section 00 14 00. Yes, the Contractor will need to coordinate with the Airfield Manager for access to an active taxiway. The Contractor will need to obtain two way radios to communicate with the air traffic control tower during movements on the airfield. The Contractors employees will need to be trained in the use of the radios and means to communicate with the tower.

417	31 00 00	3.1		Specification 31 00 00 states to strip topsoil to a depth of 4" where indicated. The boring logs show that there are some areas that have 6" of topsoil. Please confirm that all 6" of topsoil can be stripped in these areas.	Confirmed; bid per RFP. Refer to revised specification section 31 00 00
486	N/A	01 57 19	1.8	FAR 52.236-7 states Contractor will be responsible for all permits at no additional cost to Government. Can government provide a list of anticipated permits and fees each bidder should include to ensure equivalent pricing basis between bidders	No. Bid per RFP.
545	TS101			Sheet TS101: Drawing Notes 1,2, and 3 appear to be included in this project? If so, Please give separate point to point destinations for each of the copper and fiber under note 1. The way it is currently written is confusing. Please give a start and end point for note 5. Also, give a pair count for note 5, it is missing.	Keynotes 1,2,& 3 are all a part of phase I. All other keynotes are part of Phase II. Keynote 5 it is 100 PR and the splice point is in CMH 10.9.1 Refer to revised drawing TS101 to be re-issued.
549	TS101, T601, and T603			There is a conflict between drawings TS101, T601, and T603 on which manhole the 100 pair into P691 comes from. Please clarify.	See revisions to sheets TS101, T-601, and T-603 to be re-issued.
550		27 10 00		Section 27 10 00: The rack elevation drawings show no vertical wire managers on the racks or in the equipment cabinets. Please clarify if vertical cable managers are required or not.	Refer to Government Response to PPI #164
551	T001			Sheet T-001: Regarding the Type U outlet, the connector type does not match the second note under the symbol description. Please clarify.	All connections are to be LC. See revision to drawing T-001 to be re-issued.
552	T001			Sheet T-001: The description of the Type S outlet asks for D1 jack to be red, D2 to be orange, and does not state the color for D3. According to symbol note 2 all jacks should match the fiber cable color. Please redefine Type S description.	Refer to Government Response to PPI #270
553	T001			Sheet T-001: The description of the Type T outlet asks for D1 jack to be red, D2 to be orange, and does not state the color for D3. According to symbol note 2 all jacks should match the fiber cable color. Please redefine Type S description. Also, the description asks for 3 each 2-strand fibers and 1 each 6-strand fiber. Which is it?	Refer to Government Response to PPI #270
554	T403			Sheet T-403: Details A1 and C1 for comm room A16 do not match. Detail	Detail C1 has one cabinet and 3 4-post racks. Third

				C1 shows 4 cabinets but 3 of them are labeled Rack; however, keynote 2 calls out cabinets. Detail A1 only shows 2 racks and 1 cabinet. Please clarify	rack is for future growth. Detail A1 has (2) 4-post racks & (1) cabinet. Refer to revised drawing T-403 to be re-issued.
555	T601 & T602			There is a conflict between Detail B1 on T-601 and Detail C2 on T-602. Fiber types and counts do not match. Copper pair counts do not match. Please clarify.	See revisions to sheets T-601 and T-602 to be re-issued.
571	T-111, T-112, & T-113	27 41 00	2.3.1	The keynotes (T-111 Keynote 3, T-112 Keynote 3, T-113 Keynote 2) in the drawings call for conduit from the tables in the conference rooms to the wall monitors. However, the system description in Section 27 41 00, 2.3.1 makes no mention of any device at the table that may need to be seen on the monitors. Is AV connectivity required for any devices at the table which may need to be seen on the monitors? If so, what connectivity is required (for example: two HDMI connections, etc.)?	AV Specification 27 41 00 applies to pathway infrastructure only. System design and equipment not in CM scope.
574	T-111, and T-113	27 41 00	2.3.1	Sheets T-111 & T-113: The drawings depict three TV units in Conference Room A18 and Conference Room C28. However, the system description in Section 2.3.1 only mentions one display. Will the two additional displays be stand-alone displays or is it expected that they will be integrated with overall AV system such that content may be viewed on any of the three displays, as desired?	Refer to Government Response to PPI #571.
575	T-112 & T-113			Lobby B21 (Drawing T-112) and Security C25 (Drawing T-113) are both shown as receiving a CATV drop, but they do not seem to show the symbol for the TV. Are TV Displays also required at these drops?	TV drops are required. Refer to revised drawing T-112 to be re-issued.
576	T-001			Sheet T-001: Regarding the outlet descriptions. Is the cable to be a 6 strand Fiber to the outlet or individual 2 strand fibers? Can you also please provide/confirm Icon colors for each of the (3) 2-port adapters.	Individual 2 strand per faceplate port. Refer to revised drawing T-001 to be re-issued.
577	TS-001			Sheet TS-001: Please provide clarification on the OSP cabling Scope of work. Confirm if both the 144F OS2 & 100pr. PE89 cables are in the SOW, per TS101 it is unclear, reference Drawing Notes "Hangar (Phae II Scope) (Not Part Of This Contract). If the these cables are in the SOW can a revised	See the updated drawing notes panel on the revised Sheet TS101 to be re-issued.

				rawing be provided to confirm the end point for each from EF/TER/MDF C14.	
578				The civil drawings note that demolition can not begin until operations is moved to buildings being built outside of our scope. Provide a date that we will have full control of the site to perform the work.	Please refer to Government Response to PPI #066
585	CU101			Page CU101 indicates a "DIRECTIONAL BORE COMMUNICATION DUCT BANK UNDER MILLSTONE ROAD". Please confirm this scope is by the contractor and that it can be performed during working hours while the road is operational and actively used.	Horizontal directional drilling (HDD) is permitted for communication infrastructure by UFC 3-580-01, Informational and Communications Technology Infrastructure, dated 21 NOV 2024. Per the UFC, conduits installed under roads by means of HDD must be of sufficient depth to clear existing utilities and meet the H-20 load ratings. Yes, the Contractor is required to install the communications line under Millstone Road as indicated on Vol. 1 drawing sheet CU101. Yes, the work can be performed during working hours while the road is operational and actively used.
594	GR-705			Terracon GeoModel on Drawing GR705 shows borings A-1/A-2/H-1/SWM13 through SWM-19 having ground water observed within 10 below existing grade. Please confirm expected gallon-per-minute dewatering system needed to allow for new utility and building foundation construction. In addition, please confirm that a ground water treatment system is not required prior to discharge?	Contractor to determine. Means and methods.
596	GC-102			Per page GC102 - Please confirm buildings Phase 1A (Notes 1A1/1A2/1A3) do not temporary controls to allow public access within the construction fence work area until the (3) separate contracts are complete per General Notes Phase 1A. Confirm what site utilities services these	Refer to Government Response to PPI #066.

				buildings will require waiting for the (3) separate contracts to finished.	
597	Specification 01 11 00.1.7			Per Specification Section 01 11 00.1.7 Salvage Materials & Equipment. In order to account for the cost please provide a list of salvaged materials that will remain the property of the government	Refer to Government Response to PPI #554
598	Specification 01 14 00			Per Specification Section 01 14 00 Work Restrictions – Please confirm that concrete readymix delivery trucks will be allowed to deliver concrete between the 6:30AM-8AM and 3:30-5PM peak traffic hours.	No, the Contractor should not plan to deliver concrete during peak traffic hours (0630-0800 / 1530-1700), except in limited amounts with great effort on the part of the Contractor to coordinate delivery access requirements with base Security.
604	01 11 001.6			Per Specification Section 01 11 001.6 – Please provide durations the NMCI contractor will need by building to account for project schedule/general requirements.	Bid per RFP.
605				Please confirm cost to use the eCMS required system that contractors and/or subcontractors will need to pay NAVFAC to use? Please confirm that an information sharing system like Procore will not be allowed to be used on this project?	No cost to the KTR to use eCMS. Only eCMS is being allowed to be used by the construction team.
607	CU115			Per Note on CU115 – Please define exact scope bidders are to assume to be included by contractors for the new Water and Sewer utilities as note on CU115 can be interpreted that all work will furnish and installed by ASUS and coordinated by KO for this project and these costs should not be included in the bid?	Reference point of demarcation for all utilities on CU101-119. Refer to RFP
609	Specification 01 91 00 & 01 91 19			Please confirm the Construction Manager is meant to provide the Building Enclosure Commissioning Provider (BECxP) & Testing Agency services (such as Pressure Testing) described in section 01 91 19 Building Enclosure Commissioning. Please confirm other Commissioning Agencies/Providers described in Sections 01 91 00.15 and 01 91 00.15 20 are hired directly by the Government.	Refer to Government Response to PPI #131
611				Please confirm US Citizenship is not a requirement of contractor employees.	Confirmed

622	T-111, T-112, T-113	274100	2.3	Bid Specifications Section 27 41 00, 2.3.1 The keynotes in the drawings call for conduit from the tables in the conference rooms to the wall monitors. However, the system description in Section 27 41 00, 2.3.1 makes no mention of any device at the table that may need to be seen on the monitors. Is AV connectivity required for any devices at the table which may need to be seen on the monitors? If so, what connectivity is required (for example: two HDMI connections, etc.)?	Refer to Government Response to PPI #571.
625	T-111, T-113	274100	2.3	Bid Specifications Section 27 41 00, 2.3.1 The drawings depict three TV units in Conference Room A18 and Conference Room C28. However, the system description in Section 2.3.1 only mentions one display. Will the two additional displays be stand-alone displays or is it expected that they will be integrated with overall AV system such that content may be viewed on any of the three displays, as desired?	Refer to Government Response to PPI #571.
626	T-112, T-113			Drawing T-112 and T-113 Lobby B21 (Drawing T-112) and Security C25 (Drawing T-113) are both shown as receiving a CATV drop, but they do not seem to show the symbol for the TV. Are TV Displays also required at these drops?	Refer to Government Response to PPI #575
627	T-001			Drawing T-001 Regarding the outlet descriptions. Is the cable to be a 6 strand fiberto the outlet or individual 2 strand fibers? Can you also please provide/confirm Icon colors for each of the (3) 2-port adapters.	Refer to Government Response to PPI #576
628	TS101			Drawing TS101 Please provide clarification on the OSP cabling Scope of work. Confirm if both the 144F OS2 & 100pr. PE89 cables are in the SOW, per TS101 it is unclear, reference Drawing Notes "Hangar (Phae II Scope) (Not Part Of This Contract). If the these cables are in the SOW can a revised drawing be provided to confirm the end point for each from EF/TER/MDF C14.	144 OS2 extend from bldg Bldg 534 to new hangar. 100 PR extend from Manhole 10.9.1 to new hangar. Refer to revised drawing TS-101 to be re-issued. Refer to Government Response to PPI #163.
629	Specifications	01 20 00	1.6.2 (a)	Section 01 20 00 Par. 1.6.2 (a) includes FAR 52.232-5(b) regarding payment for	Bid per RFP.

				materials stored offsite. We recommend the following addition to the spec (excerpt below) to meet the intent allowing payments for offsite stored material and mitigate issues with our subcontractors: "Payment for materials that are stored offsite is authorized by the contracting officer if the Contractor furnishes evidence (e.g., paid invoice, bill of sale) that the contractor has acquired title to such material and that the material will be used to perform this contract per FAR 52.232-5(b)(2). "	
632	Specs. pg. 501/503	01 78 30	1.1	The 2009 A/E/C CAD Standard, Release 4.0 (ERDC / ITL TR-09-2) is referenced. Would NAVFAC consider using A/E/C CAD Standard, Release 6.0 or newer (ERDC / ITL TR-12-6) that may better align with the available Revit templates on the CAD BIM Center?	Confirmed
639	09 67 23.15	09 67 23.15 - Fuel Resitive Resinous Flooring, 3-Coat System	1.1	Section 09 67 23.15 Fuel Resistive Resinous Flooring, 3-Coat System requires all contractors to be SSPC QP8/QP5 and should also be SSPC QS 1 certified. According to SSPC.org, there are only 8 contractors in the entire country that are SSPC QP 8 certified. These requirements significantly limit other highly-qualified contractors who have recently completed similar hangar projects for NAVFAC. This will also substantially increase the cost of the epoxy resinous flooring scope. Please consider removing these certification requirements.	SSPC QP8 certification not required.
640	09 67 23.16	09 67 23.16 - Fuel Resitive Resinous Flooring, 5-Coat System	1.1	Section 09 67 23.16 Fuel Resistive Resinous Flooring, 5-Coat System requires all contractors to be SSPC QP8/QP5 and should also be SSPC QS 1 certified. According to SSPC.org, there are only 8 contractors in the entire country that are SSPC QP 8 certified. These requirements significantly limit other highly-qualified contractors who have recently completed similar hangar projects for NAVFAC. This will also substantially increase the cost of the epoxy resinous flooring scope. Please consider removing these certification requirements.	Refer to Government Response to PPI #639.
645	01 91 00			Building Commissioning 01 91 00.15 is given for Building Commissioning. Section 01 91 00.15 20 Total Building Commissioning is also given. Systems	Refer to Government Response to PPI #131

				to be commissioned listed in both contradict with each spec. For instance, 01 91 00.15-1.15 lists HVAC, Lighting, Service Hot Water systems, Utility Monitoring and Control Systems, Metering and Sub-Metering and Automatic Receptacle Control 01 91 00.15 20-1.4 lists HVAC, Building Automation System, Lighting Systems, Power Distribution Systems, Service Water Heating Systems, plumbing systems and Natural gas and propane Systems. Please clarify which specification is to be used	
649	09 67 23.13 / AE614-AE617			Specifications have a section for 09 67 23.13 Standard Resinous Flooring. However, the drawings do not appear to call for any standard resinous flooring. Please confirm all resinous flooring is either a 3-coat or 5-coat system for specification sections 09 67 23.15 & 09 67 23.16.	Section 09 67 23.13 Standard Resinous Flooring is not used.
650	AE616			On interior finish legend AE616, there is a note next to the 5-coat epoxy floors and base calling for "Bid Option 4". Please confirm this is now to be for Bid Option 5.	Confirmed

(End of Summary of Changes)