



**DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 72 AIR BASE WING (AFMC)
TINKER AIR FORCE BASE OKLAHOMA**

02 April 2026

MEMORANDUM FOR AFSC/PZIOC (ATTN: Sara Hinds)
THROUGH: 72 ABW/CEN

FROM: 72 ABW/CEED
Tepa Companies

SUBJECT: Amended Solicitation Documents
Project: WWYK250003 – Relocate Fire Alarm Circuit, O106-062, B3001
Reference: Memo, 12 March 2026, Request for Solicitation

1. During the PreBid Site Visit; it was discovered that some of the Conveyors in the original Design have been demolished. Request an amendment be prepared to incorporate the following changes to the solicitation package previously sent to your office:

AMENDED DRAWING WWYK250003_AMD1 DWGS - MODIFIED AS FOLLOWS:

SHEET G-101: GENERAL NOTES 6.

The purpose of this project is to remove / relocate the fire alarm and mass notification systems from the conveyor as well as remove / relocate the fire sprinkler piping supported by the conveyor structure. The contractor will install new/relocated alarm and sprinkler material in a code compliant manner within the scope of work area. New signs will also be provided and installed next to or near existing signs in the scope of work area. The signs will not be connected to the primary power circuits under the scope of this project, only provided and mounted in the appropriate locations.

SHEET F-100: FIRE ALARM AND SPRINKLER NOTES, EXIT SIGNS

1. Locate and provide new Exit signs in the scope of work area next to or near existing signs. Exit signs shall be provided with battery backup. The new Exit signs will not be connected to power circuits to energize the units. The government will be providing the materials and labor to energize the signs at a later date. The government will provide the EMT and power circuits to the new signs that the contractor provides and installs. The government will be wiring, energizing and testing the signs outside the scope of this project at a later date.
3. The contractor is not responsible for the demolition of the existing signs. The government will demolish the existing Exit signs and wire / energize new contractor installed signs after the demolition of the conveyor at a later date, outside the scope of this project.

SHEET F-100: FIRE ALARM AND MASS NOTIFICATION DEMOLITION NOTES

2. The building fire alarm system outside the project area shall remain operational or authorized outage at all times. Supervise fire protection impairments in accordance with UFC 3-601-02. No fire alarm devices shall be demolished until the building occupants have been removed from that portion of the building or fire watch in place.

SHEET F-100: FIRE ALARM AND MASS NOTIFICATION GENERAL NOTES

1. Modify the existing Fire Alarm and Mass Notification system as indicated on the contract documents, as evidently intended and in accordance with NFPA 70, NFPA 72, UFC 3-600-01 with change 6, and Tinker AFB Fire Protection Standards. The drawings are diagrammatic in nature and indicate general arrangements of systems and work, but do not include all interconnections between other systems. Provide conduit, back boxes, raceway and wiring as required to accomplish the functions intended and required by code.
2. Coordinate work with that of other trades so as to avoid conflicts. Resolve conflicts prior to rough-in. Failure to provide such coordination prior to work being installed shall not be cause for additional compensation to the contractor, and may result in rejection of the work.
9. Not used
14. Not used

SHEET F-100: SPRINKLER SYSTEM GENERAL NOTES:

16. Modified System. Construction and (Shop) Drawings must be prepared by an individual that has obtained National Institute for Certification in Engineering Technologies, Fire Alarm Systems, Level III Certification, at a minimum. the QFPE must review the shop drawings, and materials submittals. The shop drawings must bear the review stamp of the QFPE prior to submitting the fire sprinkler shop drawings to the government.
17. Submit Shop Drawings and product data to the government for review, in a manner as required per NFPA 13 and UFC 3-600-01. Submit equipment data sheets for a complete installation of the fire sprinkler system. Approved shop drawings, testing plans, and data sheets are required prior to commencement of work. The fire sprinkler system submittal shall be a complete package, partial submittal will not be accepted.

SHEET F101: - FIRE ALARM AND SPRINKLER COMPOSITE PLAN
FIRE/MASS NOTIFICATION CONTROL
PANEL SCHEDULE

- a. Existing FCI-72
- b. Future location of fire alarm network node control panel
- c. Existing FCI 7100
- d. Existing FCI E-3 (installed on fiber network)
- e. Existing Siemens MXL
- f. Existing FCI E-3
- g. Existing FCI E-3
- h. Existing Simplex 4004
- i. New Fiber Optic Patch Panel for Fire and Mass Notification Network. Contractor to provide the patch panel and terminate the fiber into and out from the patch panel to maintain the continuity of the fiber optic network. Terminating and programming these panels to the network will be under a separate contract.
- j. Existing FCI 24
- k. Existing Simplex 4004
- l. Existing FCI
- m. Existing FCI 24
- n. Existing FCPS-24FS8
- o. Existing HPF-24-24S8
- p. Existing HPF-24S8
- q. Existing HPF-24S8
- r. Existing HPF-24S8
- s. Existing FCPS-24FS6
- t. Existing SIMPLEX 4100U

CONVEYOR SECTIONS FOR GOVT COORDINATION

1. H87 - 087 (PHASE 1, 23E092)
2. G82 - G87 (PHASE 2, 23E094)
3. C87 - G87 (PHASE 3, 23E095)
4. K77 - K81 (PHASE 4, 23E096)
5. J81 - 081 (PHASE 5, 23E103)
6. D81 - J81 (PHASE 6, 23E104)
7. D87 - D92 (PHASE 7, 23E105)
8. I95 - 095 (PHASE 8, 23E106)
9. 099 - 0105 (O-P 1 OF 6, 24E026)
10. 095 - 099 (O-P 2 OF 6, 24E027)
11. 091 - 095 (O-P 3 OF 6, 24E028)
12. 087 - 091 (O-P 4 OF 6, 24E029)
13. 081 - 087 (O-P 5 OF 6, 24E030)
14. 071 - 081 (O-P 6 OF 6, 24E031)
15. TO BE DETERMINED
16. TO BE DETERMINED

SECTIONS PRIORITIES IN ORDER

1. SECTION 15
2. SECTION 9
3. SECTION 10
4. SECTION 11
5. SECTION 12
6. SECTION 13
7. SECTION 14
8. SECTION 8
9. SECTION 7
10. SECTION 3
11. SECTION 2
12. SECTION 1
13. SECTION 5
14. SECTION 6
15. SECTION 16
16. SECTION 4

SHEET F-102: FIRE ALARM AND SPRINKLER COMPOSITE PLAN GENERAL NOTES

1. This sheet identifies the conveyor location requiring re-routing of the life safety systems currently installed on the conveyor platform. All fire alarm, mass notification, and fire sprinkler systems are to be uninstalled from the conveyor and reinstalled with supports connecting to the roof deck steel. New signs are to be installed only with no operational wiring or EMT. Existing signs shall remain in their current location in their current status.
2. Before removing any electrical conduit, conductors, or devices, ensure and verify that the circuit is properly de-energized.
3. The intent is to disconnect the fire alarm circuits and fire sprinkler drops to demolish the overhead conveyor. Re-route systems cabling and drops to the bottom of roof truss steel above the conveyor platform.
4. Provide red EMT of $\frac{3}{4}$ " inch minimum with compression fittings for all new fire alarm raceway. Existing red EMT may be reused if it is like new condition. All new EMT shall be factory painted red and $\frac{3}{4}$ " inch minimum.
5. New circuit and piping route shall be along the lower roof truss steel supports above the current conveyor platform.
6. Fire sprinkler branch lines and supporting hangers may be uninstalled and reinstalled or demolished, as needed for code compliance.
7. Existing FCI-E3 network fire alarm located on the second level next to O-P aisle. The second level is open to the aisle, located at column O-94/95 on the second level.
8. Existing class A circuits may be converted to class B per the equipment manufacturer's instructions in accordance with NFPA 72. Do not abandon any fire alarm, mass notification circuits or raceway.
9. Perform a pre-test of the alarm and sprinkler systems impacted by the relocation of circuits prior to beginning work. Deficiencies identified during the pre-test will not be the responsibility of the contractor to correct if issue remains during the final acceptance test.
10. Perform an acceptance test for all affected alarm and sprinkler systems in accordance with NFPA 13 and 72, upon the completion of work. Contractor will correct deficiencies not identified on the pre-test.
11. Submittals are required. Accurate record drawings (as-builts) are required to be provided by the contractor as a close-out submittal.
12. Provide work in compliance with referenced codes and standards.

SHEET F-103: FIRE ALARM AND SPRINKLER PLAN AREA - "A"
CONVEYOR SECTIONS SHOWN IN PLAN

SHEETS NOTES

1. Not Used.
2. Not Used.
3. Not Used.
4. Not Used.
5. Demolish fire alarm circuit and install new at roof steel.
6. A) Demolish fire alarm circuit and install new at roof steel.
B) Demolish fire sprinkler cross main from conveyor and install new with supporting hangers attached to roof steel.
C) Demolish sprinkler drop to dock box office and install new to dock box office with support hangers attached at roof steel.
7. A) Demolish and cap 5 sprinkler branch lines.
B) Install sprinkler and drop at column C-93 hangers, should be anchored at roof steel.
8. A) Uninstall the fire alarm audio-visual circuit serving the dock box office. reinstall off of conveyor.
B) Install 2 Exit Signs.
C) Demolish fire sprinkler branch line and cap at the isolation valve located at the white house.
9. Demolish fire alarm circuit and install new at roof steel.
10. A) Not Used.
B) Demolish fire alarm circuit and install new at roof steel.
11. Demolish fire alarm circuit and install new at roof steel.
12. A) Demolish fire alarm circuit and install new at roof steel.
B) Not Used.
13. A) Not Used.
B) Demolish fire alarm circuit and install new at roof steel.
14. A) Not Used.
B) Demolish fire alarm circuits and install new at roof steel.
15. A) Demolish fire system branch lines at sprinklers from below conveyor Mezzanine and cap cross main.
B) Demolish fire alarm circuit to dock box office and install new with supports from roof steel.
C) Not Used.
16. Demolish fire sprinkler supply main off of the conveyor and reinstall above the conveyor at roof steel to supply the office space.

SHEET F-104: FIRE ALARM AND SPRINKLER PLAN AREA - "B"
CONVEYOR SECTIONS SHOWN IN PLAN

1. Not Used.
2. Not Used.
3. Not Used.
4. Not Used.
5. Demolish fire alarm circuit and install new at roof steel.
6. A) Demolish fire alarm circuit and install new at roof steel.
B) Demolish fire sprinkler cross main from conveyor and install new with supporting hangers attached to roof steel.
C) Demolish sprinkler drop to dock box office and install new to dock box office with support hangers attached at roof steel.
7. A) Demolish and cap 5 sprinkler branch lines.
B) Install sprinkler and drop at column C-93. Hangers should be anchored at roof steel.
8. A) Uninstall the fire alarm audio-visual circuit serving the dock box office. Reinstall off of conveyor.
B) Install 2 Exit signs.
C) Demolish fire sprinkler branch line and cap at the isolation valve located at the White House.
9. Demolish fire alarm circuit and install new at roof steel.
10. A) Not Used.
B) Demolish fire alarm circuit and install new at roof steel.
11. Demolish fire alarm circuit and install new at roof steel.
12. A) Demolish fire alarm circuit and install new at roof steel.
B) Not Used.
13. A) Not Used.
B) Demolish fire alarm circuit and install new at roof steel.
14. A) Not Used.
B) Demolish fire alarm circuits and install new at roof steel.
15. A) Demolish fire system branch lines at sprinklers from below conveyor mezzanine and cap cross main.
B) Demolish fire alarm circuit to dock box office and install new with supports from roof steel.
C) Not Used.
16. Demolish fire sprinkler supply main off of the conveyor and reinstall above the conveyor at roof steel to supply the office space.

2. The points of contact for this project are:

- a. Bash Jimoh, Project Manager. PH: 582-4828
- b. Jake Miller, Construction Inspector. PH: 734-9807
- c. Joshua Wheeler, CSAG Program Manager. PH: 582-4826
- d. Billy Deal, Contracting Officer Representative (COR). PH: 739-4975

WHEELER.JOSHUA.
JERROD.160761334

Digitally signed by
WHEELER.JOSHUA.JERROD.16076
13342
Date: 2026.04.03 14:07:49 -05'00'

2

JOSHUA WHEELER
CSAG Program Manager
72d Civil Engineering Directorate (Tepa)

KOUEMO.AR
AUD.NGASSE
U.1269207600

Digitally signed by
KOUEMO.AR
ASSEU.1269207600
Date: 2026.04.03
14:12:13 -05'00'

ARNAUD KOUEMO
CSAG Section Chief
72d Civil Engineering Directorate

01 Attachment(s):

- 1. Amended Drawing

cc:

Project folder