



DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 72 AIR BASE WING (AFMC)
TINKER AIR FORCE BASE OKLAHOMA

24 March 26

MEMORANDUM FOR AFSC/PZIOC (ATTN: Sara Hinds)
THROUGH: 72 ABW/CENM

FROM: 72 ABW/CEED
Tepa Companies

SUBJECT: Pre-Bid RFI Responses
Project: WWYK250003, - Relocate Fire Alarm Circuit, O106-O62, B3001

Reference: Memo, 03 March 2026, Pre-Bid RFIs, Relocate Fire Alarm Circuit, O106-O62, B3001

1. This office reviewed the referenced RFIs for the subject project and provided answers below. Please forward to the contractor(s) for their use in preparing proposals.

(1) Request for information. What is the expectation for hydrostatic testing requirements for this project?

- a. 200 psi (or 50 psi in excess of system working pressure if above 150 psi) for 2 hours
- b. Working pressure for 2 hours
- c. 24-hour visual test with no sign of leakage

Government Response: The pre-test & Inspection and post-test & Inspection will both be hydrostatic tests for 2 hours at system working pressure per NFPA 13.

(2) Request for information. What are the sprinkler calculation requirements for this project since we will only be resupplying 3-4 existing sprinklers?

Government Response: The fire sprinkler scope of work is to remove sprinkler drops from the conveyor system that is to be demolished. A few relocations may be required, but that will be below the 10 sprinkler per system threshold to require calculations. Therefore, no fire sprinkler calculations are required.

(3) Request for information. Please provide as-builts for the existing sprinkler systems involved in this project.

Government Response: There is no comprehensive as-builts exist for the fire alarm or fire sprinkler systems in building 3001.

- (4) Request for information. Will the fire sprinkler work be able to be performed during normal business hours or will it be after-hours and weekend work?

Government Response: The contractor will have the ability to make accommodations to work after hours and on weekends with Government approval.

- (5) Request for information. Will it be acceptable to shut down the aisle between columns O/107 to O/111 during demolition of the existing sprinkler system? Forklift traffic and pedestrian traffic walking through during demolition will create a hazard.

Government Response: Aisles will be eligible for closure through the Tinker AFB outage request process and Government approval.

- (6) Request for information. What days and times are fire alarm testing currently allowed within B 3001?

Government Response: Testing is allowed throughout the day. Fire Alarm testing signs will need to be placed in designated areas during testing. Contractor shall follow the Tinker AFB Outage Request Procedure.

- (7) Request for information. Please provide the correct submittal register

Government Response: The project submittal register provided is only for Division 0 and Division 1. All other submittal registry edits will come from the contractor's Designer of Record during the contractor's design process.

- (8) Request for information. Please provide the relevant as built drawings per SOW 5.4.

Government Response: No comprehensive as-builts exist for the fire alarm or fire sprinkler systems in building 3001.

- (9) Request for information. Where coverage is to be added to another panel, will extending FA wiring via a terminal strip/box be acceptable?

Government Response: As per Amendment #1, no panels are to be demolished and no new panels are to be provided. The adjusted scope of work is to remove or relocate the alarm and sprinkler systems from the overhead conveyor in the designated areas, and to install exit signs without wiring them for operation.

- (10) Request for information. Drawing F-100 Exit Signs, note 3 states “contractor is not responsible for the demolition of the existing exit signs.” Drawing F102, General Note #1 states “All exit signs, FA, MNS and fire sprinkler systems are to be uninstalled from the conveyor and reinstalled with supports connecting to the roof deck steel”.

Government Response: Drawing F-102 has changed in Amendment #1. Exit signs are not required to be uninstalled. New Exit signs are required to be installed but not wired or energized. Tinker AFB personnel will complete the demolition of old exit signs and wiring the new exit signs at a later time. Contractor is only to provide and install new exit signs, unenergized. No 120-volt circuits are required to be provided by the contractor for exit signs.

- (11) Request for information. Emergency batteries have a shelf life of approximately one year without being energized before they will not operate. Please confirm that the contractor will not be required to replace the factory installed emergency battery.

Government Response: Exit sign back-up batteries and fire alarm panel secondary power batteries are not be required to be replaced.

- (12) Request for information. Clarification. This project is only for Relocate Fire Alarm Circuits, not Design of Mass Notification.

Government Response: This project does not require the design of a complete new fire alarm / mass notification system or a new fire sprinkler system. This project is to remove fire protection and life safety systems from the overhead conveyor and to provide new exit signs next to or near the existing exit sign locations. All work shall comply with the referenced codes and standards. All work shall be documented on contractor's field drawings for submittal at the end of the project.

- (13) Request for information. Will the Government provide information on devices and location of existing circuits for (E) Siemens MXL. And (K) Simplex 4004?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (14) Request for information. If FA raceways are in EMT that is NOT painted red, may it be reused or does it need to be replaced with Red?

Government Response: Fire alarm EMT shall be $\frac{3}{4}$ inch and factory painted red. Do not reuse existing EMT if it is less than $\frac{3}{4}$ inch or if it is not factory painted red.

- (15) Request for information. Drawing F-101, (L) Existing FCI to Remain, Is the manufacturer FCI E3?

Government Response: As per Amendment #1, no panels are to be demolished and no new panels are to be provided. The adjusted scope of work is to remove or relocate the alarm and sprinkler systems from the overhead conveyor in the designated areas, and to install exit signs without wiring them for operation.

- (16) Request for information. Drawing F-101, There are 6 notification panels listed (N-S), can you tell us what fire alarm panels control/key/trips them.

Government Response: No comprehensive as-builts exist for the fire alarm or fire sprinkler systems in building 3001.

- (17) Request for information. Drawing F-101 (I) New Fiber Patch Panel. Please confirm the contractor is to install the patch panels, fiber optic, terminations and testing in the three (3) locations shown.

Government Response: The contractor will be installing fiber optic cabling to the three panel locations and terminating into a fiber patch panel at each respective location. The contractor will not be providing any new fiber terminations into fire alarm panels; Only maintaining the existing fiber terminations for Panel "D" as shown in the plans. Panel "D" is currently connected to the fiber optic network and shall remain on the fiber network at the end of the project.

- (18) Request for information. Please confirm if the contractor is to connect panel(s) (F) and (G) to the patch panels (I) shown at their location.

Government Response: Contractor is to provide the fiber optic cable and patch panels located at Panel "F", "G" and "B" locations. Contractor to terminate fiber to the patch panels to be located at Panel "F", "G" and "B" locations. Panel "D" is currently terminated into the fiber network and shall remain connected and operational at the end of the project. For Panel "F", "G", and "B" locations, provide fiber patch panels and terminate fiber into the patch panel but do not connect fire alarm panels to the patch panels for these three locations.

- (19) Request for information. During site visit it was stated that (T) Simplex 4100U was to be Demo but the schedule said to remain, please clarify the scope requirement.

Government Response: The Simplex 4100U is to remain unchanged unless it has circuits installed on the overhead conveyor. It and other panels are only shown to identify that they are in the scope of work area.

(20) Request for information. (H) Simplex 4004 is to be supervised by (B) new FCI-E3 and cross trip. Is the Simplex panel able to provide general alarm and trouble contacts this contract will need.

- a. If not, will the contractor need to contract with Simplex to provide and program the needed contacts or will the Government provide this?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

(21) Request for information. The Panel Schedule states (B) to provide Fiber Optic Network Node to be installed in this project. Please confirm if all existing panels that are not networked will need Fiber Optic Network Node.

Government Response: Contractor is to provide the fiber optic cable and patch panels located at Panel "F", "G" and "B" locations. Contractor to terminate fiber to the patch panels to be located at Panel "F", "G" and "B" locations. Panel "D" is currently terminated into the fiber network and shall remain connected and operational at the end of the project. For Panel "F", "G", and "B" locations, provide fiber patch panels and terminate fiber into the patch panel but do not connect fire alarm panels to the patch panels for these three locations.

(22) Request for information. Drawing F-101, is the Fiber cable (SM) single mode or (MM) Multimode?

Government Response: Contractor to comply with the manufacturer's requirements for FCI-E3 fiber optic networks. The contractor's Designer of Record will need to identify the specific needs based on the FCI fire alarm manufacturer's requirements.

(23) Request for information. Drawing F-101, how many strands does the fiber need to have?

Government Response: Contractor to comply with the manufacturer's requirements for FCI-E3 fiber optic networks. The contractor's Designer of Record will need to identify the specific needs based on the FCI fire alarm manufacturer's requirements.

- (24) Request for information. Please confirm that all existing FCI conventional panels circuits are to be monitored with addressable modules from a new FCI-E3 panel? Or will existing devices need to be changed to addressable devices?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm systems. Amendment #1 also removed the new fire alarm control panel.

- (25) Request for information. (C) Existing FCI 7100 devices are clip mode (old protocol) would on these panels need to be changed to a newer protocol device?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm systems. Amendment #1 also removed the new fire alarm control panel.

- (26) Request for information. How many nodes are currently open on the network?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, consolidation of fire alarm systems. Amendment #1 also removed the new fire alarm control panel.

- (27) Request for information. What size conduit /raceway will the new fiber optic cable need to be?

Government Response: Per the Tinker AFB fire protection standard, all EMT used for fire alarm systems is required to be ¾ inch minimum and factory painted red.

- (28) Request for information. Will inter duct need to be installed in the fiber optic EMT raceway?

Government Response: Contractor to comply with the manufacturer's requirements for FCI-E3 fiber optic networks. The contractor's Designer of Record will need to identify the specific needs based on the FCI fire alarm manufacturer's requirements

- (29) Request for information. Will the contractor be required to submit lane outages during construction?

Government Response: The contractor will need to follow the Tinker AFB procedure for all requested outages.

- (30) Request for information. Specification section 26 05 48 .00 10 Seismic Protection for Electrical Equipment, in review of the SOW and drawings, please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (31) Request for information. Specification section 26 08 00 Apparatus Inspection and Testing. The SOW and drawings do not indicate panelboards and electrical equipment. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (32) Request for information. Specification section 26 20 00 Interior Distribution System. The SOW and drawings do not indicate panelboards and electrical equipment. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (33) Request for information. Specification section 26 23 00 Low Voltage Switchgear. The SOW and drawings do not indicate switchgear and electrical equipment. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (34) Request for information. Specification section 26 28 01.00 10 Coordinated Power System Protection. The SOW and drawings do not indicate new panelboard or switchgear that will need to have studies completed. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (35) Request for information. Specification section 26 29 23 Variable Frequency Drive Systems Under 600V. The SOW and drawings do not indicate VFD's. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (36) Request for information. Specification section 26 32 14.00 10 Diesel-Generator Set, Stationary 15-300KW, Standby Applications. The SOW and drawings do not indicate generators. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (37) Request for information. Specification section 26 36 00.00 10 Automatic Transfer Switch and By-Pass/Isolation Switch. The SOW and drawings do not indicate ATS and electrical equipment. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (38) Request for information. Specification section 26 41 00. Lightning Protection System. The SOW and drawings do not indicate lightning protection or work outside of the building. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (39) Request for information. Specification section 26 42 14.00 10. Cathodic Protection System (Sacrificial Anode). The SOW and drawings do not indicate cathodic protection is required for work outside of the building. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (40) Request for information. Specification section 26 56 00 Exterior Lighting. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (41) Request for information. Specification section 26 56 20.00 10 Airfield and Heliport Lighting and Visual Navigation Aids. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (42) Request for information. Specification section 28 31 33.00 19 Fire Alarm Reporting System, Radio Type. The SOW and drawings do not indicate any work associated with providing a new Monaco Transceiver. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (43) Request for information. Specification section 33 71 02 Underground Electrical Distribution. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (44) Request for information. Specification section 26 51 00.1.4 Submittal. Please confirm the submittal required by this section are only those referencing exit lights and no other product data, test reports or certificates are required.

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (45) Request for information. Drawings F-101, Where is the Monaco Transceiver that the new FCI-E3 Panel B is to report to located?

Government Response: As per Amendment #1, no panels are to be demolished and no new panels are to be provided. The adjusted scope of work is to remove or relocate the alarm and sprinkler systems from the overhead conveyor in the designated areas, and to install exit signs without wiring them for operation.

- (46) Request for information. For all existing panels that are to remain and are associated with this scope of work, please confirm that all are in good working order and in need of no repair, parts or working components.

Government Response: As a requirement of this project, the contractor shall perform a pre-test of all impacted existing systems prior to commencing any work. This pre-test identifies the existing condition and performance of the existing systems. Deficiencies identified during the pre-test will NOT be the contractor's responsibility to repair. Any new deficiencies not identified in the pre-test will be the contractor's responsibility to repair.

- (47) Request for information. For all existing panels that are to remain, please confirm that the existing batteries are in good working order and are not to be replaced under this scope of work.

Government Response: Exit sign back-up batteries and fire alarm panel secondary power batteries are not be required to be replaced.

- (48) Request for information. Drawing G-101, General Note 6 and stated at the site visit the purpose of this project is to remove the fire alarm from the conveyor system. Drawing F-102, General Note 16 states to provide a code compliant fire alarm and mass notification within the scope of work area. Please confirm if note 16 is correct and required by this project.

Government Response: This project does not require the design of a complete new fire alarm / mass notification system or a new fire sprinkler system. This project is to remove fire protection and life safety systems from the overhead conveyor and to provide new exit signs next to or near the existing exit sign locations. All work shall comply with the referenced codes and standards. All work shall be documented on contractor's field drawings for submittal at the end of the project.

- (49) Request for information. Clarification. This project is only for Relocate Fire Alarm Circuits, not Design of Mass Notification.

Government Response: This project does not require the design of a complete new fire alarm / mass notification system or a new fire sprinkler system. This project is to remove fire protection and life safety systems from the overhead conveyor and to provide new exit signs next to or near the existing exit sign locations. All work shall comply with the referenced codes and standards. All work shall be documented on contractor's field drawings for submittal at the end of the project.

- (50) Request for information. Will the Government provide information on devices and location of existing circuits for (E) Siemens MXL. And (K) Simplex 4004. Can the existing conduits be used or need to be replaced with Red.

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (51) Request for information. (L) Existing FCI to Remain, Is this an FCI E3?

Government Response: As per Amendment #1, no panels are to be demolished and no new panels are to be provided. The adjusted scope of work is to remove or relocate the alarm and sprinkler systems from the overhead conveyor in the designated areas, and to install exit signs without wiring them for operation.

- (52) Request for information. There are 6 notification panels listed, can you tell us what fire alarm panels control them.

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (53) Request for information. Clarification. (I) New Fiber Patch Panel. Is the contractor to provide the equipment for the E3 panels on this contract and terminate and program on future contract.

Government Response: The contractor will be installing fiber optic cabling to the three panel locations and terminating into a fiber patch panel at each respective location. The contractor will not be providing any new fiber terminations into fire alarm panels; Only maintaining the existing fiber terminations for Panel "D" as shown in the plans. Panel "D" is currently connected to the fiber optic network and shall remain on the fiber network at the end of the project.

- (54) Request for information. During site visit it was stated that (T) Simplex 4100U was to be Demo but the schedule said to remain. Please clarify if it is to remain or be demolished.

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (55) Request for information. H) Simplex 4004 is to be supervised by B and cross trip. If Simplex is unable to provide general alarm and trouble contacts will the contractor need to hire Simplex to provide and program or will the Government provide this.

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (56) Request for information. The Panel Schedule states (B) to provide Fiber Optic Network Node to be installed in this project. The question is don't all (I) that are not networked need Fiber Optic Network Node?

Government Response: The contractor will be installing fiber optic cabling to the three panel locations and terminating into a fiber patch panel at each respective location. The contractor will not be providing any new fiber terminations into fire alarm panels; Only maintaining the existing fiber terminations for Panel "D" as shown in the plans. Panel "D" is currently connected to the fiber optic network and shall remain on the fiber network at the end of the project.

- (57) Request for information. Is Fiber cable (SM) single mode or (MM) Multimode?

Government Response: Contractor to comply with the manufacturer's requirements for FCI-E3 fiber optic networks. The contractor's Designer of Record will need to identify the specific needs based on the FCI fire alarm manufacturer's requirements.

- (58) Request for information. Will the existing FCI conventional panels device need to be changed to addressable?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel. No conventional devices are required to be changed to addressable devices as a part of this project, unless directed to do so by the Contractor's Designer of Record.

- (59) Request for information. (C) Existing FCI 7100 devices are clip mode that would need to be changed to a newer protocol device?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel. No conventional devices are required to be changed to addressable devices as a part of this project, unless directed to do so by the Contractor's Designer of Record.

- (60) Request for information. How many nodes are open on the network?

Government Response: The government does not have any as-built information for those systems. The scope per Amendment #1 removed the demolition, relocation, and consolidation of fire alarm panels. Amendment #1 also removed the new fire alarm control panel.

- (61) Request for information. Will the Government provide an Environmental survey?

Government Response: Yes, as necessary.

- (62) Request for information. Is the 'bottom of the roof steel' mentioned in the notes referring to the bottom of the roof decking or the bottom of the bar joists?

Government Response: Bottom of bar joist or lower chord of roof truss, and above crane level. Do not attach anything directly to the bottom of the roof deck since that will cause roof leaks.

- (63) Request for information. The drawings represent section 15 with a mezzanine area below the conveyor. Is there any work between the two?

Government Response: During the pre-bid walk, conveyor section 15 was identified to have fire alarm circuits and sprinklers removed and reinstalled per the scope of the project. Conveyor Section 15 and the corresponding Mezzanine will be demolished by the government and this project is to remove / relocate life safety systems.

- (64) Request for information. The submittal register provided does not address specification Sections that pertain to this project. Will this be corrected?

Government Response: The contractor's designer of record is responsible for determining the project specifications per the references provided. Division 0 and Division 1 specifications are provided.

- (65) Request for information. Clarification. This project is only for Relocate Fire Alarm Circuits, not Design of Mass Notification.

Government Response: Duplicate inquiry.

- (66) Request for information. Will the Government provide information on devices and location of existing circuits for (E)Siemens MXL. and (K) Simplex 4004. Can the existing conduits be used or need to be replace with Red.

Government Response: Duplicate inquiry.

- (67) Request for information. (L) Existing FCI to Remain, Is this an FCI E3

Government Response: Duplicate inquiry.

- (68) Request for information. There are 6 notification panels listed, can you tell us what fire alarm panels control them.

Government Response: Duplicate inquiry.

- (69) Request for information. Clarification. (I) New Fiber Patch Panel. Is the contractor to provide the equipment for the E3 panels on this contract and terminate and program on future contract.

Government Response: Duplicate inquiry.

- (70) During site visit it was stated that (T) Simplex 4100U was to be Demo but the schedule said to remain.

Government Response: Duplicate inquiry.

- (71) Request for information. (H) Simplex 4004 is to be supervised by B and cross trip. If Simplex is unable to provide general alarm and trouble contacts will the contractor need to hire Simplex to provide and program or will the Government provide this.

Government Response: Duplicate inquiry.

- (72) Request for information. The Panel Schedule states (B) to provide Fiber Optic Network Node to be installed in this project. The question is don't all (I) that are not networked need Fiber Optic Network Node.

Government Response: Duplicate inquiry.

- (73) Request for information. Is Fiber cable (SM) single mode or (MM) Multimode.

Government Response: Duplicate inquiry.

- (74) Request for information. Will the existing FCI conventional panels device need to be changed to addressable.

Government Response: Duplicate inquiry.

- (75) Request for information. (C) Existing FCI 7100 devices are clip mode that would need to be changed to a newer protocol device.

Government Response: Duplicate inquiry.

- (76) Request for information: How many nodes are open on the network.

Government Response: Duplicate inquiry.

- (77) Request for information. What is the expectation for hydrostatic testing requirements for this project?

- a. 200 psi (or 50 psi in excess of system working pressure if above 150 psi) for 2 hours
- b. Working pressure for 2 hours
- c. 24-hour visual test with no sign of leakage

Government Response: Duplicate inquiry.

- (78) Request for information. What are the sprinkler calculation requirements for this project since we will only be resupplying 3-4 existing sprinklers?

Government Response: Duplicate inquiry.

- (79) Request for information. Please provide as-builts for the existing sprinkler systems involved in this project.

Government Response: Duplicate inquiry.

- (80) Request for information. Will the fire sprinkler work be able to be performed during normal business hours or will it be after-hours and weekend work?

Government Response: Duplicate inquiry.

- (81) Request for information. Will it be acceptable to shut down the aisle between columns O/107 to O/111 during demolition of the existing sprinkler system? Forklift traffic and pedestrian traffic walking through during demolition will create a hazard.

Government Response: Duplicate inquiry.

- (82) Request for information. What days and times are fire alarm testing currently allowed within B 3001?

Government Response: Duplicate inquiry.

- (83) Request for information. Please provide the correct submittal register

Government Response: Duplicate inquiry.

- (84) Request for information. Please provide the relevant as built drawings per SOW 5.4.

Government Response: Duplicate inquiry.

- (85) Request for information. Where coverage is to be added to another panel, will extending FA wiring via a terminal strip/box be acceptable? Or is all new wiring required

Government Response: Duplicate inquiry.

- (86) Request for information. Drawing F-100 Exit Signs, note 3 states "contractor is not responsible for the demolition of the existing exit signs." Drawing F102, General Note #1 states "All exit signs, FA, MNS and fire sprinkler systems are to be uninstalled from the conveyor and reinstalled with supports connecting to the roof deck steel".

Government Response: Duplicate inquiry.

- (87) Request for information. Emergency batteries have a shelf life of approximately one year without being energized before they will not operate. Please confirm that the contractor will not be required to replace the factory installed emergency battery

Government Response: Duplicate inquiry.

- (88) Request for information. Clarification. This project is only for Relocate Fire Alarm Circuits, not Design of Mass Notification.

Government Response: Duplicate inquiry.

- (89) Request for Information. Will the Government provide information on devices and location of existing circuits for (E) Siemens MXL. and (K) Simplex 4004?

Government Response: Duplicate inquiry.

- (90) Request for information. If FA raceways are in EMT that is NOT painted red, may it be reused or does it need to be replaced with Red?

Government Response: Duplicate inquiry.

- (91) Request for information. Drawing F-101, (L) Existing FCI to Remain, Is the manufacturer FCI E3?

Government Response: Duplicate inquiry.

- (92) Request for information. Drawing F-101, There are 6 notification panels listed (N-S), can you tell us what fire alarm panels control/key/trips them.

Government Response: Duplicate inquiry.

- (93) Request for information. Drawing F-101 (I) New Fiber Patch Panel. Please confirm the contractor is to install the patch panels, fiber optic, and terminations and testing in the three (3) locations shown.

Government Response: Duplicate inquiry.

- (94) Request for information. Please confirm if the contractor is to connect panel(s) (F) and (G) to the patch panels (I) shown at their location.

Government Response: Duplicate inquiry.

- (95) Request for information. During site visit it was stated that (T) Simplex 4100U was to be Demo but the schedule said to remain, please clarify the scope requirement.

Government Response: Duplicate inquiry.

- (96) Request for information. (H) Simplex 4004 is to be supervised by (B) new FCI-E3 and cross trip. Is the Simplex panel able to provide general alarm and trouble contacts this contract will need. If not, will the contractor need to contract with Simplex to provide and program the needed contacts or will the Government provide this?

Government Response: Duplicate inquiry.

- (97) Request for information. The Panel Schedule states (B) to provide Fiber Optic Network Node to be installed in this project. Please confirm if all existing panels that are not networked will need Fiber Optic Network Node.

Government Response: Duplicate inquiry.

(98) Request for information. Drawing F-101, is the Fiber cable (SM) single mode or (MM) Multimode?

Government Response: Duplicate inquiry.

(99) Request for information. Drawing F-101, how many strands does the fiber need to have?

Government Response: Duplicate inquiry.

(100) Request for information. Please confirm that all existing FCI conventional panels circuits are to be monitored with addressable modules from a new FCI-E3 panel? Or will existing devices need to be changed to addressable devices?

Government Response: Duplicate inquiry.

(101) Request for information. (C) Existing FCI 7100 devices are clip mode (old protocol) would on these panels need to be changed to a newer protocol device?

Government Response: Duplicate inquiry.

(102) Request for information. How many nodes are currently open on the network?

Government Response: Duplicate inquiry.

(103) Request for information. What size conduit /raceway will the new fiber optic cable need to be?

Government Response: Duplicate inquiry.

(104) Request for information. Will inter duct need to be installed in the fiber optic EMT raceway?

Government Response: Duplicate inquiry.

(105) Request for information. Will the contractor be required to submit lane outages during construction?

Government Response: Duplicate inquiry.

(106) Request for information. Specification section 26 05 48 .00 10 Seismic Protection for Electrical Equipment, in review of the SOW and drawings, please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(107) Request for information. Specification section 26 08 00 Apparatus Inspection and Testing. The SOW and drawings do not indicate panelboards and electrical equipment. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(108) Request for information. Specification section 26 20 00 Interior Distribution System. The SOW and drawings do not indicate panelboards and electrical equipment. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(109) Request for information. Specification section 26 23 00 Low Voltage Switchgear. The SOW and drawings do not indicate switchgear and electrical equipment. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(110) Request for information. Specification section 26 28 01.00 10 Coordinated Power System Protection. The SOW and drawings do not indicate new panelboard or switchgear that will need to have studies completed. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(111) Request for information. Specification section 26 29 23 Variable Frequency Drive Systems Under 600V. The SOW and drawings do not indicate VFD's. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(112) Request for information. Specification section 26 32 14.00 10 Diesel-Generator Set, Stationary 15-300KW, Standby Applications. The SOW and drawings do not indicate generators. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(113) Request for information. Specification section 26 36 00.00 10 Automatic Transfer Switch and By-Pass/Isolation Switch. The SOW and drawings do not indicate ATS and electrical equipment. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(114) Request for information. Specification section 26 41 00. Lightning Protection System. The SOW and drawings do not indicate lightning protection or work outside of the building. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(115) Request for information. Specification section 26 42 14.00 10. Cathodic Protection System (Sacrificial Anode). The SOW and drawings do not indicate cathodic protection is required or work outside of the building. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(116) Request for information. Specification section 26 56 00 Exterior Lighting. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(117) Request for information. Specification section 26 56 20.00 10 Airfield and Heliport Lighting and Visual Navigation Aids. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(118) Request for information. Specification section 28 31 33.00 19 Fire Alarm Reporting System, Radio Type. The SOW and drawings do not indicate any work associated with providing a new Monaco Transceiver. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(119) Request for information. Specification section 33 71 02 Underground Electrical Distribution. The SOW and drawings do not indicate work outside of the building. Please confirm this is not applicable and not required.

Government Response: Duplicate inquiry.

(120) Request for information. Specification section 26 51 00.1.4 Submittal. Please confirm the submittal required by this section are only those referencing exit lights and no other product data, test reports or certificates are required.

Government Response: Duplicate inquiry.

(121) Request for information. Drawings F-101, Where is the Monaco Transceiver that the new FCI-E3 Panel B is to report to located?

Government Response: Duplicate inquiry.

(122) Request for information. For all existing panels that are to remain and are associated with this scope of work, please confirm that all are in good working order and in need of no repair, parts or working components.

Government Response: Duplicate inquiry.

(123) Request for information. For all existing panels that are to remain, please confirm that the existing batteries are in good working order and are not to be replaced under this scope of work.

Government Response: Duplicate inquiry.

(124) Request for information. Drawing G-101, General Note 6 and stated at the site visit the purpose of this project is to remove the fire alarm from the conveyor system. Drawing F-102, General Note 16 states to provide a code compliant fire alarm and mass notification within the scope of work area. Please confirm if note 16 is correct and required by this project.

Government Response: Duplicate inquiry.

2. The points of contact for this project are:
 - a. Bash Jimoh, Project Manager. PH: 582-4828
 - b. Jake Miller, Construction Inspector. PH: 734-9807
 - c. Joshua Wheeler, CSAG Program Manager. PH: 582-4826
 - d. Sara Hinds, Contracting Officer Representative (COR). PH: 505-506-9723

BASH JIMOH
Project Manager
72d Civil Engineering Directorate (Tepa)

BILLY DEAL
Mechanical Engineer/COR
72d Civil Engineering Directorate

02 Attachment(s):

1. Amendment 1 Drawing
2. Design Narrative Amendment 1

cc:

Project folder