

DATE: 07/17/2024

PROJECT # 25MO16CN
MAXIMO # 5422382

TITLE: GENERAL BUILDING PAINTING AND FLOORING PROJECT

ATTACHMENTS: Paint Specifications, Flooring Specifications

SCOPE OF WORK:

The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

General Description

The responsibility of the contractor is to prep and paint the following buildings listed in the project area description according to the general requirements. All measurements are for reference only and are to be field verified by contractor. The point of contact for access to the building is listed below in the project area descriptions.

Detailed Requirements and Specifications

- 1.) General Requirements (As applicable for all Buildings listed in the Project Area Description)
 - a. Repair all cracks, holes, and damaged surfaces to provide a solid foundation for painting. If there are significant repairs needed (greater than 50 S.F.), it shall be noted below in the project area description.
 - b. Clean and treat mold and mildew areas for finish coating application.
 - c. Apply interior / exterior finish surfacing compound as appropriate to any damaged surfaces to match surrounding finishes.
 - d. All finish colors shall match as close as possible the existing colors unless otherwise noted in the project area description section.
 - e. Replace any damaged or rotten trim boards, siding, or moldings, as quantified in the work area descriptions. Replace any loose, damaged, or missing caulking and glazing compound on windows, doors and other surfaces on the interior and exterior.
 - f. Secure any loose trim boards, siding, or moldings that are not damaged or rotten.
 - g. All repaired surfaces will be primed with latex KILZ 2 or equivalent unless otherwise noted in the project area description section.
 - h. All metal surfaces shall have (2) coats of latex direct to metal semi-gloss finish paint applied unless otherwise noted in the project area description section.
 - i. All interior wall surfaces shall have (2) coats of eggshell / satin finish latex paint applied unless otherwise noted in the project area description section.
 - j. All wood trim and doors shall have (2) coats of semi-gloss latex finish paint applied unless otherwise noted in the project area description section.
 - k. All wood trim with natural finishes shall be sanded for finish appearance and (2) coats of polyurethane finish coat shall be applied areas unless otherwise noted in the project area description section.
 - l. All exterior masonry surfaces shall have (2) coats of Loxon masonry coating or equivalent applied unless otherwise noted in the project area description section.
 - m. All EFIS finishes shall have (2) coats of Semi-gloss latex finish paint unless otherwise noted in the project area description section.
 - n. All high bay areas shall have (2) coats of a high gloss coating applied to provide maximum illumination of the work areas unless otherwise noted in the project area description section.
 - o. Apply KILZ 2 or equivalent primer sealer and (2) coats of mildew resistant latex semi-gloss finish paint to all previously painted surfaces in the bathroom areas unless otherwise noted in the project area description section.
 - p. Due to inadequate adhesion of previously painted finishes additional scrapping and preparation shall be required for all wood, masonry and metal surfaces.
 - q. No roof surfaces are to be painted unless otherwise noted in the project area description.

- r. Cover all furniture, possessions, and building components as required protecting them from damage during accomplishment of interior and exterior painting. The contractor shall be responsible for the removal and resetting of all furniture. This includes any required disassembling and reassembling of furniture.
- s. The contractor shall provide a storage container on site to store furniture and other large items to keep them from being damaged during the work process. If work can be completed with furniture items in the center of the room and properly covered to ensure they are not damaged, then there is no need for a container to be utilized.
- t. Remove and reinstall all electrical/data switch and receptacle covers, to insure all previously painted surfaces are repainted.
- u. Paint over existing painted stenciled signage and replace with newly painted stenciled signage with the same lettering or numbering.
- v. Repaint all exposed piping and piping insulation. Stencil proper markings on piping.
- w. Clean all over-spray, drips, splatters and spills resulting from accomplishing this project from all surfaces as appropriate.
- x. Previously painted concrete floors shall be painted with Sherwin Williams Rexthane I Floor paint or equivalent. Concrete sealer shall be applied (Ardex Sealer) or equivalent prior to floor painting. The floors shall be clean dry and dull prior to all applications.
- y. No glass surfaces are to be painted unless otherwise noted in the project area description area.
- z. Special scheduling shall be required on all the buildings listed below. Approximately ¼ of the work areas shall be available for paint at one given time. It is the responsibility of the contractor to coordinate a schedule with the point of contact for each building.
- aa. The statement that all surfaces tested positive or negative for lead paint means that all surfaces are to be assumed as positive or negative as listed in the project area description section of this scope.
- bb. The intent of this project is not to abate the lead paint. The intent is only to remove the lead paint to the extent necessary to prep for a new coat of paint.
- cc. All paint and prep work shall comply with the attached painting and coating specifications as applicable.

2.) Project Area Description

- a. Building S960 is a structure located behind S962 on Michael Rd.
 - i. Paint all previously painted steel posts, trusses, rafters and supports for structure.
 - ii. Paint to match existing color.
 - iii. The point of contact for access to the building is Mike Osterlund at 910-451-3090.
- b. Building S962 is a structure located on Michael rd.
 - i. Paint all previously painted steel posts, trusses, rafters and supports for shelter attached to back of building.
 - ii. The point of contact for access to the building is Mike Osterlund at 910-451-3090.
- c. Building 1069 is a control bldg. located at 201 on Holcomb Blvd.
 - i. Paint all previously painted interior surfaces.
 - ii. Paint all previously painted interior surfaces.
 - iii. The building tested negative for lead in all areas tested throughout the exterior and interior of the building.
 - iv. Paint color PPG Willow Springs PPG1007-1 or equivalent.
 - v. The point of contact for access to the building is SSGT Pounds at 910-450-9280.
- d. Building FC280 is a Field Maintenance Bldg. located on Gonzalez Blvd
 - i. Install Non-skid epoxy floor in engine dyno bays.
 - ii. The point of contact for access to the building is Cpl. Albright727-992-9386.
- e. Building 1039 is the Brig located in Hadnot Point on Turret Street.
 - i. Remove existing carpet and 6" vinyl cove base in rooms 153B, 142, 144, 145, 105,107,136, 124, 128B.
 - ii. Prep and seal concrete.
 - iii. Install Tarkett Tarkett Crafted Plank Provence PECF2131 or equivalent and new 6"vinyl cove base.
 - iv. Paint all previously painted hatches (metal doors), cells, railings, stairwells and window frames within the facility to match existing color.

- v. Paint rooms DB100a, D148, D153A, D153B and Master Control Room.
- vi. Paint color to Sherwinn Williams Olympus White SW6253.
- vii. The point of contact for access to the building is Gene Rued 910-451-7457
- f. Building FC375 is a Motor Transport Facility located on Mchugh Blvd.
 - i. Remove all drywall in motorpool dispatch office.
 - ii. Install new ½” drywall.
 - iii. Paint all new drywall.
 - iv. Paint color PPG Commercial White PPG1025-1 or equivalent.
 - v. The point of contact for access to the building is Lcpl Marcus A. Ramirez at 531-401-4969.
- g. Building 60 is Admin. Office/Joint Reception center located at Hadnot Point on Lucy Brewer Ave.
 - i. Remove existing carpet and install new carpet tiles though out room 226.
 - ii. Carpet shall be Tarkett Abrasive Action Winter Gray 19103 carpet tiles or equivalent.
 - iii. The point of contact for access to the building is Andrew Hart at 910-451-6737.
- h. Building FC330 is a Enlisted Marines Club located on Gonzalez Loop.
 - i. Paint all previously painted white border around building on exterior and front driveway canopy.
 - ii. Paint color PPG Commercial White PPG1025-1 or equivalent.
 - iii. The point of contact for access to the building is Robert Steinsberger at 276-233-2005.
- i. Building TT19 is a Youth Center located on Iwo Jima Blvd.
 - i. Paint all previously painted interior surfaces excluding gymnasium.
 - ii. Refinish all wood doors.
 - iii. The paint color shall be Sherwinn Williams Olympus White SW3562.
 - iv. The point of contact for access to the building is Sarah Williams at 910-450-1422.
- j. Building HP5 is a SIM TELEX EX building located on Post Lane.
 - i. Paint all previously painted interior surfaces.
 - ii. Paint color shall be Sherwinn Williams Unique Gray SW 6260 or equivalent.
 - iii. The point of contact for access is Staff Sgt Turner at 910-415-1118.
- k. Building A71 is a SIM Maintenance OPS building located on NC 172.
 - i. Remove existing carpet and VCT in rooms 10N-51, 86, 52, 45, 47, 48, 128, 2, 25, 26, 35, 36, 39, 40, 41, S4, H&S Co, Carrier Planner, S1, S6, Supply Officer, Bldg A72 Boat Office, 237, 224.
 - ii. Seal all floors with Install Tarkett Winter Gray 19103 Carpet Tiles and new Vinyl Cove Base
 - iii. The point of contact for access is SSGT K.E. Hunt at 910-440-7732.
- l. Building 111 is a Battalion Squadron Headquarters located on B St.
 - i. Remove existing carpet and vct.
 - ii. Seal floor with Ardex floor sealer or equivalent.
 - iii. Install Tarkett Abrasive Action Winter Gray 19103 carpet tiles or equivalent.
 - iv. The point of contact for the building is Jeffrey Hayden at 585-694-9450

SUBMITTALS: The contractor shall submit the manufacturer’s product specifications including all technical data for all material being used in process. Contractor shall make electronic copies of all submittals, include the approved submittal sheets, and provide two (2) CD’s/DVD’s containing all submittals for project and should be marked ‘Complete Submittal Package’ must include contract numbers.

SPECIAL SCHEDULING AND ACCESS: See point of contact identified in the project area descriptions.

SPECIAL CONDITIONS: As identified.

HAZARDOUS MATERIALS: Where there is lead present. The intent is to only scrape and encapsulate the lead present. The contractor shall submit a hazardous materials plan for all lead work.

ENVIRONMENTAL: As identified.