

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE	OF	PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0004		3. EFFECTIVE DATE 03/17/26	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (if applicable) 26-0400		1	4	
6. ISSUED BY CODE		7. ADMINISTERED BY (if other than Item 6) CODE	See Item 6					
NAVFAC Mid-Atlantic Resident Officer in Charge of Construction 1107A Birch Street Camp Lejeune, NC 28547-2521								
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)			(X)	9A. AMENDMENT OF SOLICITATION NO.				
			X	N40085-26-R-9016				
				9B. DATED (SEE ITEM 11) 02/24/26				
				10A. MODIFICATION OF CONTRACT/ORDER NO.				
				10B. DATED (SEE ITEM 11)				
CODE			FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS								
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☒ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.								
12. ACCOUNTING AND APPROPRIATION DATA (if required)								
13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.								
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).							
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
	D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.								
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) 26-0400, Roof Repairs Buildings HP51, HP53, HP55, HP57, HP255, and HP265 Amendment 0004, Answer Request for Information.								
The time and date for receipt of proposals remains unchanged.								
This amendment should be acknowledged when your proposal is submitted. Failure to acknowledge the amendment may constitute grounds for rejection of a proposal.								
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.								
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)					
15B. CONTRACTOR/OFFEROR			15C. DATE SIGNED			16B. UNITED STATES OF AMERICA		
(Signature of person authorized to sign)			(Signature of Contracting Officer)			16C. DATE SIGNED		
NSN 7540-01-152-8070 Previous edition unusable			STANDARD FORM 30 (REV. 10-83) Prescribed by GSA FAR (48 CFR) 53.243					

CONTINUATION SHEET

QUESTION 1: There are 21 total barracks out for bid at the same time this project is bid. Is it possible that the bid due dates can be spaced out over the fiscal year so that all 21 buildings are not awarded at the same time? If that is not an option, can the government consider delaying the award of each project with a 4 to 6 week delay between each project award? This will help with the assignment of manpower required for each scope of work. This will also help with the internal load placed on Government personnel to get all projects awarded and started.

ANSWER 1: No, the due dates cannot be changed.

QUESTION 2: Note 10 on Bldg HP53 states to “Remove existing antenna, prepare for new roof as per detail 1/A6. There is no note to reinstall existing or install a new antenna. Is the intent to remove the antenna and not reinstall? Is the intent to remove and reinstall the existing antenna? Or is the intent to remove and install a new antenna? If new is required, what is the basis of design of the antenna?

ANSWER 2: Intent is to remove and not reinstall.

QUESTION 3: Roof Key Notes on the HP50’s Buildings Note 9 “Remove existing dormers down to existing roof deck”. Is the intent of this note to demo the dormer over builds down to the existing roof deck or is the intent to only remove the asphalt Shingles and felt down to the roof deck?

ANSWER 3: Intent is to DEMO the Dormer over build down to the existing roof deck.

QUESTION 4: Roof Key Note 07 on the HP 50s Bldgs “Remove existing Exhaust Fan, Replace with new Exhaust Fans. Location and Quantity are Approximate. Contractor to verify”. It has been our experience that the roof mounted exhaust fans are often actual motorized fans mounted on a roof curb, but we have also seen the fans mounted in the ductwork below the roof deck in the mechanical chase with just a “Roof Hood” mounted on a roof curb. Is the intent to replace the roof equipment whether its an actual fan or hood? Or is the intent to replace the fan even if it is installed in the attic or mechanical chase below?

ANSWER 4: Intent is to replace the roof equipment whether it’s an actual fan or hood.

QUESTION 5: Note 2 under General Requirements on 255 & 265 “Remove existing Lightning Protection If Applicable”. There are no notes to reinstall the existing lightning protection. Is the intent to leave the Lightning protection off the building? Is the intent to reinstall the existing lightning protection? Is the intent to install new lightning protection? If new lightning protection is required, please provide design requirements.

ANSWER 5: Intent is to remove lighting protection and not reinstall.

QUESTION 6: Drawing A6 Typical Roof Detail on the HP50's Buildings "Install R 30 Spray Insulation 48" wide entire perimeter of the building". Is the Spray Insulation Blown loose fill insulation or is the Spray insulation Spray "Foam" insulation?

ANSWER 6: Insulation is blown loose fill insulation.

QUESTION 7: Note 9 under General Requirements for Building 255, 265 states "Install panel clips as per the manufactures recommendation for a 150 mph Wind in accordance with the Uniform Building Code for North Carolina". Panel clip spacing based on the Wind Uplift Calculations takes into consideration the pull-out strength of the roof deck substrate. Does the Government know if the plywood roof decks are 5/8" plywood or 3/4" plywood?

ANSWER 7: As per Sheet DTL1, General Requirement #12, All measurements shall be field verified by contractor prior to Bid.

QUESTION 8: During our site visit we noticed some differences regarding the downspouts on the 6 different buildings. Buildings HP-255 and 265 show the downspouts dropping out of the bottom of the gutters, running down the parapet wall about 2 feet and turning back into and through the existing parapet wall piping the rainwater back into the building into pvc piping installed in the attic. Our experience over the last 10 to 15 years has included provisions in the contract drawings to provide 6"x6"x1 /4" Steel Downspouts to channel the water out of the building down and tying into a rain leader below grade. The Tubular Steel provides protection of the downspout from potential damage that could crush or bend the typical light gauge aluminum downspouts. I have included a typical Tubular Steel DS detail from a project we are doing now here at Camp Lejeune.

ANSWER 8: At buildings HP255 and HP265, Government wishes to have 6 inch by 6 inch by a quarter inch steel downspouts as per enclosed Downspout Detail drawing. Provide at each existing downspout location. Note: in lieu of steel pipe outlet connecting to drain pipe, provide 4 inch galvanized steel pipe outlet at 4 inch above existing grade and concrete splash block at each outlet.

QUESTION 9: Buildings HP-51 , 53, 55, and 57 have light gauge metal downspouts that drop out of the bottom of the gutter down to a splash block or tied into a rain leader.

ANSWER 9: Leave new downspouts as designed. Note: as per drawings on HP51 and HP55 have splash blocks and HP53 and HP57 tie into existing piping.

QUESTION 10: On Buildings HP-255 and 265, there is currently no work included in the scope of work to do anything with the existing gutters and downspouts other than to clean them. Does the government want to leave the downspouts turning back into the attic space or are 6x6 tubular steel downspouts needed on these 2 buildings.

ANSWER 10: At buildings HP255 and HP265, Government wishes to have 6 inch by 6 inch by a quarter inch steel downspouts as per enclosed Downspout Detail drawing. Provide at each existing downspout location. Note: in lieu of steel pipe outlet connecting to drain pipe, provide 4 inch galvanized steel pipe outlet at 4 inch above existing grade and concrete splash block at each outlet.

QUESTION 11: On Buildings HP-51, 53, 55, and 57 the scope of work is to remove and provide new gutters and downspouts with light gauge metal downspouts down to splash blocks on the ground. The Tubular Steel provides protection of the downspout from potential damage that could crush or bend the typical light gauge aluminum downspouts. Does the government want to leave the new downspouts as designed running down the exterior of the building to splash blocks or are 6x6 tubular steel downspouts needed on these 4 buildings.

ANSWER 11: Leave new downspouts as designed. Note: as per drawings on HP51 and HP55 have splash blocks and HP53 and HP57 tie into existing piping.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

