

STATEMENT OF WORK

LOAD BANK TESTING OF EMERGENCY POWER SUPPLY SYSTEMS AND FUEL QUALITY TESTING

GREAT PLAINS AREA INDIAN HEALTH SERVICE LOCATIONS:

BELCOURT, ND

EAGLE BUTTE, SD

FT. THOMPSON, SD

FT. YATES, ND

KYLE, SD

LOWER BRULE, SD

MOBRIDGE, SD

McLAUGHLIN, SD

PINE RIDGE, SD

RAPID CITY, SD

ROSEBUD, SD

SISSETON, SD

WAGNER, SD

WANBLEE, SD

FEBRUARY 2025

Table of Contents

1. Project Description	3
2. Scope of Work (SOW):	4
3. Period of Performance.....	6
4. Contractor Responsibilities	6
5. Government Responsibilities	7
6. Records/Data	7
7. Quality Assurance	7
8. Deliveries or Performance	7
9. Payments to the Contractor	8
10. IHS Personnel	8
11. Invoice Format	8
12. Authority	9
Appendix A – Generator Information and Location	10
Appendix B – Bid Schedule	11
Appendix C – Report of Inspection, Testing, & Maintenance Form	12
Appendix D – Contract Performance Evaluation	14

STATEMENT OF WORK

Load Bank Testing of Emergency Power Supply Systems and Fuel Quality Testing
Great Plains Area
Belcourt & Ft. Yates, ND, Eagle Butte, Ft. Thompson, Kyle, Lower Brule, McLaughlin,
Mobridge, Pine Ridge, Rapid City, Rosebud, Sisseton, Wagner & Wanblee, SD

1. Project Description

- A. Title:** Load Bank Testing of Emergency Power Supply Systems and Fuel Quality Testing
- B. Location:** This service is to be provided at multiple locations: Belcourt & Ft. Yates, ND, Eagle Butte, Ft. Thompson, Kyle, Lower Brule, McLaughlin, Mobridge, Pine Ridge, Rapid City, Rosebud, Sisseton, Wagner & Wanblee, SD.
- C. Period of Performance:**
1. **Base Year** (Date of Award – 12/31/2026)
 2. **First Option Year** (1/1/2027 – 12/31/2027)
 3. **Second Option Year** (1/1/2028 – 12/31/2028)
 4. **Third Option Year** (1/1/2029 – 12/31/2029)
 5. **Fourth Option Year** (1/1/2030 – 12/31/2030)
- D. Description:** The purpose of this contract is to conduct annual load bank testing and fuel quality testing of the Emergency Power Supply Systems (EPSS) at various facilities in the Great Plains Area Indian Health Service, which includes locations in North Dakota and South Dakota. It is essential to perform these inspections and tests as required by code to maintain continued accreditation from the Centers for Medicare and Medicaid Services and the Joint Commission for our facilities.
- E. Background:** The code requirements are deemed essential for achieving the minimum level of reliability and performance, especially when life safety electrical power needs are concerned.
- F. Related Documents**
1. This SOW and any other standard government or IHS documents are included and considered a part of this contract.
 2. NFPA 70, National Electrical Code, 2012 Edition
 3. NFPA 110, Standard for Emergency and Standby Power Systems, 2010 Edition
 4. NFPA 99, Standard for Healthcare Facilities, 2012 Edition
 5. NFPA 101, Life Safety Code, 2012 Edition
- G. Common Acronyms or Definitions**
1. IHS – Indian Health Service
 2. CMS – Centers for Medicare & Medicaid Services
 3. CO – Contracting Officer
 4. COR – Contracting Officer's Representative

5. PO – Project Officer
6. IGCE – Independent Government Cost Estimate
7. RFI – Request For Information

2. Scope of Work (SOW): Perform an annual load bank and fuel quality test of the emergency generators located at selected Great Plains Area facilities. The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

A. Load Bank Test.

1. Pre-startup inspection.
 - a. Check fuel tank level.
 - b. Check coolant level.
 - c. Check engine oil level.
 - d. Connect the load bank to the output of the generator.
2. Generator startup.
 - a. Start the generator by simulating a normal power failure from a “cold start” by use of the test switch on the automatic transfer switch or by disconnecting the normal power supply to EPSS.
 - b. Allow the generator to reach normal operating temperature.
 - c. Watch and listen for any potential problems or abnormal noises.
 - i. If any problems are identified, do not proceed with the test and notify the PO and Facility Manager of the problem.
3. Load transfer (Annual).
 - a. Transfer the load to EPS.
 - b. Increase the load until each leg carries at least 50 percent of the maximum continuous rated load of the generator.
 - c. Record the time and the running time meter (RTM) reading to “start” the 90-minute load bank test.
 - d. Check and record the AC voltage, frequency, and amperage of each leg.
 - e. Check and record initial oil pressure and water temperature.
 - f. Monitor the generator for overheating, listen for unusual noises, and record the AC voltage, frequency, and amperage of each leg, along with the oil pressure and water temperature every 15-minutes of runtime while maintaining a load of at least 50 percent for a minimum running time of 30 continuous minutes.
 - i. If a problem develops, shut the generator down quickly to minimize damage and notify the PO and Facility Manager of the problem.
 - g. Increase the load until each leg carries at least 75 percent of the maximum continuous rated load of the generator.

- h. Record the time and the RTM reading immediately after the 75 percent load is applied. This time indicates the “start” of the final 1-hour runtime at 75 percent to complete the 90-minute load bank test.
 - i. Continue to monitor the generator for overheating, listen for unusual noises, and record the AC voltage, frequency, and amperage of each leg, along with the oil pressure and water temperature every 15-minutes of runtime while maintaining a load of at least 75 percent for a minimum running time of 60 continuous minutes.
- 4. Load Transfer (3-Year/4-Hour).
 - a. Transfer the load to EPS.
 - b. Increase the load until each leg carries at least 30 percent of the maximum continuous rated load of the generator.
 - c. Record the time and the running time meter (RTM) reading to “start” the 4-hour load bank test.
 - d. Check and record the AC voltage, frequency, and amperage of each leg.
 - e. Check and record initial oil pressure and water temperature.
 - f. Monitor the generator for overheating, listen for unusual noises, and record the AC voltage, frequency, and amperage of each leg, along with the oil pressure and water temperature every 15-minutes of runtime while maintaining a load of at least 30 percent for a minimum running time of 180 continuous minutes.
 - i. If a problem develops, shut the generator down quickly to minimize damage and notify the PO and Facility Manager of the problem.
 - g. Increase the load until each leg carries at least 75 percent of the maximum continuous rated load of the generator.
 - h. Record the time and the RTM reading immediately after the 75 percent load is applied. This time indicates the “start” of the final 1-hour runtime at 75 percent to complete the 4-hour load bank test.
 - i. Continue to monitor the generator for overheating, listen for unusual noises, and record the AC voltage, frequency, and amperage of each leg, along with the oil pressure and water temperature every 15-minutes of runtime while maintaining a load of at least 75 percent for a minimum running time of 60 continuous minutes.
- 5. Post-test procedure.
 - a. Remove the loads gradually after the test, and allow the generator to run under light load for 1-hour.
 - b. Remove all loads 5 to 10 minutes before shutting the generator down.
 - c. Return the test switch to normal and reestablish the normal power supply.
 - d. Place the unit in automatic operation.

B. Fuel Quality Test.

1. Obtain an individual fuel sample from each generator fuel tank.
 - a. Perform fuel quality tests on each sample using appropriate ASTM standards.

C. Additional Facility Requirements.

1. The contractor shall comply with the requirements of the hospital's Facility Manager and clean up after themselves, including any tools and equipment needed to complete the testing.

3. Period of Performance.

A. Base Year (Date of Award – 12/31/2026)

1. The annual load bank test shall be performed at ALL facilities within 60 days from the Notice to proceed or 365 (+/- 30) days after the 2025 load bank test, whichever comes first.
2. The fuel quality test shall be performed at ALL facilities at the same time as the annual load bank test.

B. First Option Year (1/1/2027 – 12/31/2027)

1. The annual load bank test shall be performed at ALL facilities 365 (+/- 30) days after the 2026 load bank test.
2. The fuel quality test shall be performed at all facilities at the same time as the annual load bank test.

C. Second Option Year (1/1/2028 – 12/31/2028)

1. The 4-hour load bank test shall be performed at ALL facilities 365 (+/- 30) days after the 2027 load bank test.
2. The fuel quality test shall be performed at all facilities at the same time as the annual load bank test.

D. Third Option Year (1/1/2029 – 12/31/2029)

1. The annual load bank test shall be performed at ALL facilities 365 (+/- 30) days after the 2028 load bank test.
2. The fuel quality test shall be performed at all facilities at the same time as the annual load bank test.

E. Fourth Option Year (1/1/2030 – 12/31/2030)

1. The annual load bank test shall be performed at ALL facilities 365 (+/- 30) days after the 2029 load bank test.
2. The fuel quality test shall be performed at all facilities at the same time as the annual load bank test.

4. Contractor Responsibilities

- A.** Contractor personnel performing the testing/inspections shall possess appropriate credentials from a certifying organization, such as the National Fire Protection Association (NFPA 101, 99, 70, 110), Emergency Generator Service Association (EGSA), Licensed Electrician (Master or Journeyman), and American Society for Testing and Materials (ASTM). Supporting documentation for credentials shall be submitted with the bid proposal.
- B.** Following notice to proceed, the contractor shall submit a proposed inspection schedule to the Project Officer for approval. The schedule shall include facility locations, the date of planned inspections, and the name of each technician to perform each inspection. The contractor shall notify the Project Officer immediately concerning any scheduling changes. The contractor shall notify each Facility Manager a minimum of 72 hours before performing a service.

- C. Failed component replacement and repairs will not be included within the contractor's responsibilities unless the failure of components is the result of the contractor's activities. However, the contractor is invited to provide recommendations resulting from the contracted service to the Facility Manager and the Project Officer. Any repair, service, or part not included within this contract will require a separate procurement from the local Service Unit before the repair, service, or part can be performed, installed, or ordered. Invoices without a corresponding procurement number will not be paid.

5. Government Responsibilities

- A. The Facility Manager shall provide access to all necessary areas of the facility.
- B. Post-Award Meeting: One post-award meeting shall be conducted before the start of the project to establish schedule and provide necessary contact information for local facility managers.

6. Records/Data

- A. Following completion of the testing, reports shall be completed for each facility. All testing data shall be recorded on the attached applicable "RECORD OF INSPECTION, TESTING, & MAINTENANCE" forms or another form approved by the Project Officer. Reports shall be electronically completed utilizing a fillable PDF form provided by IHS. A copy of each report shall be provided to the Project Officer for documentation purposes. This documentation shall be provided no later than 20 workdays following the completion of the final site visit.
- B. The contractor shall submit one package, after all sites have been visited, containing one invoice that includes all the locations to the Project Officer itemizing the service performed at each site. The invoice shall include the contract number, facility name, type of service performed at each facility, date of service for each facility, and payment amount per facility. The reports shall accompany the invoice. Individual invoices shall not be submitted to the locations within the contract.

7. Quality Assurance

- A. Facility Managers will submit vendor evaluations to the Project Officer upon completion of each site visit, see attached sample. Successful contract completion will be determined by the timely submission of schedules, reports, and invoices. Accuracy of schedule and information in reports will also be taken into consideration. Thorough completion of services as indicated in the contractor tasks, vendor evaluations, and in general will also be considered when evaluating the successful completion of the contract.

8. Deliveries or Performance

- A. Place of Performance/Hours of Operation
 - 1. Sites to receive service are Belcourt (ND), Eagle Butte (SD), Ft. Thompson (SD), Ft. Yates (ND), Kyle (SD), Lower Brule (SD), Mobridge (SD), McLaughlin (SD), Pine Ridge (SD), Rapid City (SD), Rosebud (SD), Sisseton (SD), Wagner (SD), and Wanblee (SD).
 - 2. Inspection and testing shall be completed between the hours of 8:00 AM and 5:00 PM, M-F, unless otherwise approved by the Project Officer. No testing and maintenance shall be performed on a national holiday unless approved by the Project Officer.

9. Payments to the Contractor

- A. The Government will pay the Contractor a fixed price, as indicated below, which will constitute full compensation for all Contractor professional and incidental services, travel expenses, and materials necessary to furnish the complete project as required and specified in this SOW.
- B. Progress payments will be paid following acceptance by the Government of that particular schedule item and a properly submitted and approved invoice.

10. IHS Personnel

Contracting Officer's Representative (COR)

Contact information will be provided to the eventual awardee.

Any change in COR designation will be documented by the Contracting Officer in writing.

11. Invoice Format

Invoice Processing Platform (IPP)

Invoices submitted under any award resulting from this solicitation will be required to utilize the Invoice Processing Platform (IPP) in accordance with HHSAR 352.232-71, Electronic Submission and Processing of Payment Requests.

IPP is a secure, web-based electronic invoicing system provided by the U.S. Department of the Treasury's Bureau of the Fiscal Service, in partnership with the Federal Reserve Bank of St. Louis (FRSTL).

Respondents to this solicitation are encouraged to register an account with IPP if they have not already done so. If your organization is already registered to use IPP, you will not be required to re-register- however, we encourage you make sure your organization and designated IPP user accounts are valid and up to date.

The IPP website address is: <https://www.ipp.gov>

If you require assistance registering or IPP account access, please contact the IPP Helpdesk at (866) 973-3131 (M-F 8AM to 6PM ET), or IPPCustomerSupport@fiscal.treasury.gov

Should the contractor feel that use of the IPP would be unduly burdensome, their response to this solicitation should include an explanation of this position for a determination by the contracting officer.

12. Authority

- A. No person other than the Contracting Officer has authority to bind the Government with respect to this contract.
- B. No action or omission of any government employee or representative other than the Contracting Officer shall increase or decrease the scope of this contract or shall otherwise modify the terms and conditions of this contract.
- C. In no event shall any of the following be effective or binding on the Government or imputed to the Contracting Officer with respect to this contract:
 - 1. An understanding or agreement between the Contractor and anyone other than the Contracting Officer;
 - 2. A purported modification or change order issued by anyone other than the Contracting Officer;

3. A promise by anyone other than the Contracting Officer to provide additional funding or make payments; or
4. An order, direction, consent, or permission from anyone other than the Contracting Officer to:
 - a. Incur costs in excess of a specified estimated cost, allotment of funds, or other ceiling; or
 - b. Expend hours in excess of a specified level of effort.

Appendix A – Generator Information and Location

Generator	Manufacturer	Engine	Model	Generator Size	# of ATS
Belcourt #1	Onan	Cummins	300DFCB	300 KW	6
Belcourt #2	Onan	Cummins	300DFCB	300 KW	
Eagle Butte #1	Cat	CatC32	SR4B-GD	1000 KW	5
Eagle Butte #2	Cat	CatC32	SR4B-GD	1000 KW	
Ft. Thompson	Generac	Generac	SD200	200 KW	1
Ft. Yates #1	Kohler	Perkins	100R0ZP81	100 KW	2
Ft. Yates #2 *	Kohler		50REZGC	50 KW	
Kyle *	Onan	Ford	70ENL32811E	70 KW	1
Lower Brule	MTU	John Deere	DS00150D6SPAK0574	150 KW	1
McLaughlin #1 *	Onan	Cummins	GGHH-8826847	100 KW	2
McLaughlin #2 *	Kohler		50REZGC	50 KW	
Pine Ridge #1	Onan	Cummins	350DFCC	350 KW	4
Pine Ridge #2	Onan	Cummins	350DFCC	350 KW	
Rapid City #1	Cummins	Cummins	DFEK*2190176	500 KW	2
Rapid City #2	Cummins	Cummins	DFEK*2190176	500 KW	
Rapid City #3	Cummins	Cummins	DFEK*2190176	500 KW	
Rosebud #1	Onan	Cummins	500DFYG31397E	500 KW	4
Rosebud #2	Onan	Cummins	500DFYG31397E	500 KW	
Sisseton #1	Onan	Cummins	DFLC-5744883	1250 KW	6
Sisseton #2	Onan	Cummins	DFLE-5744884	1500 KW	
Wagner	Onan	Cummins	350DFCC	350 KW	4
Wanblee	Onan	Cummins	DGFA-5765088	150 KW	1
YRTC *	Generac	Generac	95A03325-S	100 KW	1

*** Generator uses propane fuel / natural gas. Modify fuel system maintenance services from NFPA standards accordingly.**

**NO PRICING
INFORMATION IS
REQUIRED FOR
THIS SOURCES
SOUGHT NOTICE.**

Appendix C – Report of Inspection, Testing, & Maintenance Form

Report of Inspection, Testing & Maintenance of Emergency and Standby Power Systems

Type of Load Bank: ☐ Annual 90-Minute ☐ 3-Year Combined 4-Hour Date: _____

Company Name: _____

Street Address: _____

City: _____ State: _____ Zip: _____

Phone: _____ Fax: _____

Technician Name: _____

Name of Property: _____

Street Address: _____

City: _____ State: _____ Zip: _____

Phone: _____ Fax: _____

Designated Representative: _____

Gen #1 Manufacturer: _____ Gen Model: _____

Gen Spec: _____ Gen S/N: _____ Gen CPL: _____

Engine Model: _____ Engine S/N: _____

Fuel Type: ☐ Gasoline ☐ Diesel ☐ LPG ☐ CNG

Rated KW: _____ Rated KVA: _____ Hour Meter: _____

Gen #2 Manufacturer: _____ Gen Model: _____

Gen Spec: _____ Gen S/N: _____ Gen CPL: _____

Engine Model: _____ Engine S/N: _____

Fuel Type: ☐ Gasoline ☐ Diesel ☐ LPG ☐ CNG

Rated KW: _____ Rated KVA: _____ Hour Meter: _____

Gen #3 Manufacturer: _____ Gen Model: _____

Gen Spec: _____ Gen S/N: _____ Gen CPL: _____

Engine Model: _____ Engine S/N: _____

Fuel Type: ☐ Gasoline ☐ Diesel ☐ LPG ☐ CNG

Rated KW: _____ Rated KVA: _____ Hour Meter: _____

ATS #1 Model: _____ Spec: _____ S/N: _____

ATS #2 Model: _____ Spec: _____ S/N: _____

ATS #3 Model: _____ Spec: _____ S/N: _____

ATS #4 Model: _____ Spec: _____ S/N: _____

ATS #5 Model: _____ Spec: _____ S/N: _____

ATS #6 Model: _____ Spec: _____ S/N: _____

TECHNICIAN'S SIGNATURE: _____ DATE: _____

Cover Sheet

Rev: _____

Appendix C – Report of Inspection, Testing, & Maintenance Form

GREAT PLAINS AREA INDIAN HEALTH SERVICE

□ ANNUAL LOAD BANK TEST REPORT

❑ 4-HOUR LOAD BANK TEST REPORT

Facility: _____

Date: _____

Generator ID#: _____

Model #: _____

NAMEPLATE DATA

KW: _____

KVA: _____

PF: _____

VOLTS: _____

AMPS: _____

HZ: _____

For an annual load bank, generator shall be exercised with supplemental loads at not less than 50% of the EPS nameplate kW rating for 30 continuous minutes and at not less than 75% of the EPS nameplate kW rating for 1 continuous hour for a total test duration of not less than 1.5 continuous hours.

For a 4-hour combined load bank, generator shall be exercised with supplemental loads at not less than 30% of the EPS nameplate kW rating for 3 continuous hours and at not less than 75% of the EPS nameplate kW rating for 1 continuous hour for a total test duration of not less than 4 continuous hours.

Load Rate 30%: _____ (kW) = 30% of Nameplate Data

Load Rate 50%: _____ (kW) = 50% of Nameplate Data

Load Rate 75%: _____ (kW) = 75% of Nameplate Data

[illegible]

Technician: _____

(Print)

Signature: _____

Appendix D – Contract Performance Evaluation

Great Plains Area Generator Load Bank and Fuel Testing Performance Evaluation

To be completed by the Facility Manager after inspection

Facility Name: _____

Date:_____ Contractor Rep onsite:_____

1.	Overall Evaluation	Poor	Average	Good	Excellent
2.	Performance	Poor	Average	Good	Excellent
3.	Quality of Services	Poor	Average	Good	Excellent
4.	Workmanship	Poor	Average	Good	Excellent
5.	Knowledge	Poor	Average	Good	Excellent

Comments:This image shows a blank sheet of white paper with horizontal ruling lines. The lines are evenly spaced and extend across the width of the page. There are no margins, text, or other markings on the paper.