

1. Manufacturer Information

- Are the existing transformers from a specific manufacturer? If not, is there an approved method for confirming nameplate data (e.g., provided documentation or site access), or should this be determined during the inspection phase? **ABB manufactures the Transformers; however, we customized them with high voltage plug adapters, auxiliary circuits, and built-in secondary containment surrounding the transformer. This is NOT a standard commercial off the shelf item.**

2. Condition / Known Deficiencies

- Are there any known issues beyond standard wear (e.g., oil leaks, insulation degradation, connector failures), or should this be treated strictly as a full inspection and repair effort? **This should be treated as a full inspection and repair; each transformer could require additional individual repairs if identified.**

3. On-Site vs. Off-Site Work

- We understand the units will be transported to the contractor's facility for repair—are there any anticipated constraints on turnaround time or staging at JRRF? **There are no known anticipated constraints, if necessary, staging can be done on-site with an escort.**

4. Testing & Reporting Expectations

- Beyond the listed dielectric, turns ratio, and insulation testing, are there any preferred reporting formats or additional diagnostic expectations? **There is no standard format for reports. Also include required oil test sampling and PCB certificate.**

5. Equipment Identification / Site Access

- Is there an approved method for confirming the manufacturer and nameplate data of the existing transformers (e.g., site visit or provided documentation), or should this be assumed as part of the inspection phase? **See Question one.**