

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE	OF	PAGES
2. AMENDMENT/MODIFICATION NO.		3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (if applicable)		1	3	
AMENDMENT NO. 0005		03/19/26		26-0400				
6. ISSUED BY		CODE	7. ADMINISTERED BY (if other than Item 6)		CODE			
NAVFAC Mid-Atlantic Resident Officer in Charge of Construction 1107A Birch Street Camp Lejeune, NC 28547-2521		N40085				See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)	9A. AMENDMENT OF SOLICITATION NO.			
				X	N40085-26-R-9016			
					9B. DATED (SEE ITEM 11) 02/24/26			
					10A. MODIFICATION OF CONTRACT/ORDER NO.			
					10B. DATED (SEE ITEM 11)			
CODE								
FACILITY CODE								
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS								
☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☒ is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.								
12. ACCOUNTING AND APPROPRIATION DATA (if required)								
13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.								
CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).							
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
	D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.								
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) 26-0400, Roof Repairs Buildings HP51, HP53, HP55, HP57, HP255, and HP265 Amendment 0005, Answer Request for Information.								
The time and date for receipt of proposals remains unchanged.								
This amendment should be acknowledged when your proposal is submitted. Failure to acknowledge the amendment may constitute grounds for rejection of a proposal.								
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.								
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)				
15B. CONTRACTOR/OFFEROR				15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED
(Signature of person authorized to sign)				(Signature of Contracting Officer)				
NSN 7540-01-152-8070 Previous edition unusable								
STANDARD FORM 30 (REV. 10-83) Prescribed by GSA FAR (48 CFR) 53.243								

CONTINUATION SHEET

QUESTION 1: The RFP dated 2/24/2026 has listed 6 barracks that need new roofs to include demo of the existing roofs, metal fascias and soffits and installing new standing seam metal roofs, fascias and soffits. The Contract completion date is shown as 360 days after award. There are typically 60 days needed after the award to hold the Preconstruction conference, issue a Purchase Orders and get Admin and Technical submittals in, and approved to allow procurement of materials needed to start work. This only leaves 300 calendar days to complete all 6 buildings to include punch out and final inspections. $300/6 = 50$ calendar days per building. Actual workdays estimating 5 workdays a week leave only about 40 workdays to complete all scopes on each building to avoid completing late and incurring LDs. Our Experience with the 3-story barracks with this scope of work which includes fascias and soffits will require a minimum of 4 months per building taking into consideration inclement weather and other mitigating factors. Will the Government consider increasing the time allowed to do all 6 buildings to a minimum of 720 days?

ANSWER 1: The government will increase the time allowed to complete all six buildings to 720 days. HP51, HP53, HP55, and HP57 must be completed prior to HP255 and HP265.

QUESTION 2: 20M060CN Roof Repairs-Buildings HP255-HP265 SOW & 26M020CN BEQ HP51-HP53-HP55-HP57 Roof Repairs SOW – on sheet A1 General Note #23 states “Contractor shall review asbestos inspection survey before commencing work”. We don’t see where survey is provided in the RFP to be able to identify any asbestos containing materials to be demolished with the roof. Will this be provided?

ANSWER 2: See uploaded ACM Reports.

QUESTION 3: 20M060CN Roof Repairs-Buildings HP255-HP265 SOW & 26M020CN BEQ HP51-HP53-HP55-HP57 Roof Repairs SOW – on sheet A1 under Hazardous Materials – Notes: #2 states if found contractor to abate asbestos if found. If we are to include abatement we must be able to verify type and quantity to be removed to estimate accurately. Will the asbestos surveys be provided?

ANSWER 3: See uploaded ACM Reports.

QUESTION 4: Plans set states to remove and replace permanent fall protection. Does the replacement fall protection system/connections need to be identical to the old system/connections?

ANSWER 4: See attached Specification Section 11 24 24.

QUESTION 5: In the SOW note 2 it says remove existing lightning protection if applicable but no where does it say to reinstall with existing or even new LPS. If it exists should we reinstall?

ANSWER 5: Intent is to remove lighting protection and not reinstall.

QUESTION 6: Has site laydown area for the contractor been identified?

ANSWER 6: Information will be provided after award.

QUESTION 7: In several documents including Combined Div 01 DBB SPECS, 01 11 00 para 1.2 and 01 14 00 para 1.2 special scheduling is “as described in the attached project description”. Is there a separate attachment with that title that describes preferred phasing in detail?

ANSWER 7: Information will be provided after award.

QUESTION 8: Combined Div 01 DBB SPECS 01 31 23.13 20 para 1.6.1 we note that the schedule, daily reports and many other documents are considered CUI and our internal process discusses handling of **government designated** CUI within our company to ensure that we maintain our current CMMC certification level and continue to progress to the next level by the November deadline. Are we as contractors authorized to apply the CUI designation to the documents?

ANSWER 8: CUI designation is not required for eCMS submission.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

SECTION 11 24 24

PERMANENT HORIZONTAL FALL PROTECTION, METAL ROOFING
08/20

PART 1 GENERAL

1.1 DESCRIPTION

Standing Seam Metal Roofing (SSMR) fall protection to be used in all SSMRs with slopes greater than 3/12.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

UNITED FACILITIES GUIDE SPECIFICATIONS (UFGS)

07 61 15.00 20 Aluminum Standing Seam Roofing

UNIFIED FACILITIES CRITERIA (UFC)

UFC 3-301-01 Structural Engineering: Fall Prevention and Protection

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A10.32 Personal Fall Protection Used in Construction and Demolition Operations

ANSI Z359.1 Safety Requirements for Personal Fall Arrest Systems, Subsystems and Components

OCCUPATIONAL SAFETY AND HEALTH ORGANIZATION (OSHA)

1926.502 Fall Prevention Systems and Criteria and Practices

1.3 DEFINITIONS

Roof sloping (#/12) refers to the number of inches a roof rises in height for every 12 inches, as measured horizontally from the edge of the roof to the centerline.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

For fabrication showing the complete fall protection system. Layout drawings of each system in relation to the supporting structure indicating the locations of properly labeled components.

SD-03 Product Data

Manufacturer's data and product information indicating the sizes, descriptions, capacities, test certifications, and other descriptive data showing in sufficient detail that the product complies with the contract requirements.

SD-07 Certificates

Installer's Certification

SD-08 Manufacturer's Instructions

Maintenance Procedures: Including parts list and maintenance requirements for all equipment.

Operation Procedures: Indicating proper use of equipment for safe operation of the systems.

1.5 QUALITY CONTROL

After fall protection system is installed, the manufacturer's authorized representative shall inspect and operate the system and make any final adjustments. The manufacturer's authorized representative shall issue a certificate attesting to the system's design and installation, and formally submit to the USG

1.6 QUALIFICATIONS

- a. Furnish proof of installer's certification approval by manufacturer in the form of the installer's current certificate issued by the manufacturer.
- b. Provide a designer's qualification statement.

1.7 WARRANTY

- a. Provide lifetime manufacturer warranty
- b. Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Design, furnish, install, and certify a complete and useable permanent fall protection system, inclusive of all components, appurtenances, fasteners, end stops, carriages, and equipment necessary for safety of maintenance

workers.

Submit horizontal life line and anchorage connector systems for approval by the designer of record and the installation public works group's cognizant architect or designated fall protection expert. The chosen fall protection system must be compatible with the Base Exterior Architectural Plan, low-maintenance, designed for service in harsh coastal conditions, and compliant with ANSI/ASSP Z359 requirements. The following proprietary systems would meet government requirements, but other options may be proposed by the contractor, subject to final approval by the government:

- 1) 3M Capital Safety Roofsafe Rail System
- 2) Miller ShockFusion Horizontal Lifeline Roof System
- 3) Kee Safety KeeLine Engineered Lifeline Solution

2.1.1.1 Design Requirements

- a. Design must be performed, signed, and sealed by a Professional Engineer from the manufacturer experienced in the design of horizontal lifeline fall arrest systems. Submit qualifications of engineer.
- b. Design must provide for access from the roof hatch (where provided) to the roof ridge, allowing for continuous worker tie off to reach the ridge line. For buildings without a roof hatch, design must provide for access from the roof eave (at an acceptable location) to the roof ridge, allowing continuous worker tie off to reach the ridge line. D-rings are acceptable for ascent and decent parallel to standing seams, or propose alternative method.
- c. Low profile and architecturally pleasing systems are preferred, and will be evaluated higher than more obtrusive designs.
- d. Concealed fasteners are preferred.

2.1.1.2 Performance Requirements

- a. System must be able to accommodate three (3) users at a time.
- b. All fall protection anchorages must be designed for a minimum 3,100 lb nominal live load capacity. Anchorages, including any supporting structure, must be designed to allow future replacement of the horizontal lifeline system or anchorage connectors regardless of the required capacity of the chosen horizontal lifeline system or anchorage connectors. Anchorages that support two or more independent horizontal life line spans at a single point must be designed for the combined load effects of the horizontal life line systems in accordance with ANSI/ASSP Z359.6.

2.2 FINISHES

- a. Choice of finishes in powder coated or anodized aluminum alloy are preferred.
- b. Color must comply with the MCBCL Base Exterior Architectural Plan (BEAP) and the USG Architect. Submit color samples for approval.

2.3 TESTS, INSPECTIONS, AND VERIFICATIONS

After fall protection system is installed, the manufacturer's authorized representative shall inspect and operate the system and make any final adjustments. The manufacturer's authorized representative shall issue a certificate attesting to the system's design and installation, and formally submit to the USG.

PART 3 EXECUTION

3.1 INSTALLATION

Fall protection system shall be installed under the direction of manufacturer's authorized trained personnel.

3.2 INSPECTION

The manufacturer's authorized representative shall inspect and operate the system and make any final adjustments.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Demonstration

The manufacturer's authorized representative shall issue a certificate attesting to the system's design and installation, and formally submit to the USG.

3.3.2 Training

Train designated US Government personnel on-site regarding proper use of system.

-- End of Section --