

Q&A Solicitation 040ADV-25-R-0016 GPO – NARA 4th Floor Renovation

Q.1 Would it be possible to include site photos in the RFI responses?

RFI responses will be written.

Q.2 Can the Government confirm if the following document types are or would be count(ed) against the 120-page limit associated with this solicitation: cover, title page, table of contents, first page?

Cover, title, table of contents and first pages are NOT counted against the 120-page limit.

Q.3 For “graphic presentations, including tables” may offerors use 11x17 pages? If so, would each such page count as one or two pages against the 120-page limit associated with this solicitation?

Offerors may use 11x17 sheets for graphic presentations. Each 11x-17 will be counted as a single page.

Q.4 Volume 3: “The Offeror shall submit a comprehensive Quality Control/Quality Assurance (QC/QA) Management Plan.” Is the Government looking for a summary or a draft of a complete, post-award-type submittal? If the latter, these plans are often 50 pages or more; can the Government confirm if this Plan is excluded from the 120-page limit?

A full, post-award level plan is not required. Please adhere to the solicitation instructions.

Q.5 Volume 3: “The Offeror shall submit a comprehensive Safety Plan.” Is the Government looking for a summary or a draft of a complete, post-award-type submittal? If the latter, these plans are often 50 pages or more; can the Government confirm if this Plan is excluded from the 120-page limit?

See response to Q.4.

Q.6 Volume 3: “An Accident Prevention Plan (APP) is required for this contract and must be job site specific.” Is the Government looking for a summary or a draft of a complete, post-award-type submittal? If the latter, these plans are often 50 pages or more; can the Government confirm if this Plan is excluded from the 120-page limit?

See response to Q.4

Q.7 Volume 5: “The offeror’s proposal submission must include a minimum of three completed past performance questionnaires, but no more than five completed questionnaires, to enable proper evaluation. An offeror may submit other forms of past performance records as supplemental information, including CPARS. The supplemental information, however, may not be submitted in lieu of the PPQ form.” Would the Government reconsider and allow offerors to submit CPARS in lieu of new PPQ forms submitted directly to the Government? Such existing federal-form evaluations are designed for this purpose and would evaluate the relevant categories. Evaluators/references are often reluctant to complete new evaluations when existing evaluations are already available and have already been completed for this type of situation and purpose. In addition, over a multi-year look-back, references are very often no longer available. These are circumstances that are beyond an offeror’s control and that can impact proposal scores unnecessarily and an offeror’s ability to present its most recent and relevant work. Allowing such existing evaluations – in lieu of new PPQ forms – helps offerors provide the best experience information and most thorough proposals possible for the Government’s consideration. And because they would be evaluations on official, federal forms, they would still allow the Government to assess offeror past performance effectively.

Offerors must comply with all solicitation instructions. CPARS may be submitted as supplemental information; however, supplemental information cannot be used as a substitute for the required questionnaires.

Q.8 Volumes 1 and 6: Can the Government confirm if offerors should count the information applicable to these two Volumes against the 120-page limit associated with this solicitation?

Except for tables of content, the cover page, and the first page, all sheets will count against the 120-page limit.

Q.9 Please share the Sign In Sheet.

The Sign-In sheet was posted on 4/1/2026 in Amendment 040ADV-26-R-0016-C0001

Q.10 Please confirm if a single, duly qualified individual may ""triple hat" and serve as the project superintendent, QC Manager, and SSHO.

No. Key personnel roles shall be filled as specified and may not be combined.

Q.11 Is US Citizen mandatory at the Job site?

US Citizenship is not explicitly listed as a mandatory requirement for all labor; however, all personnel working on-site must be able to pass a rigorous federal background investigation to obtain a Public Trust Clearance.

Q.12 Please share the photos of the site visit.

RFI responses will be written.

Q.13 Are there FF&E requirements in this project?

According to the Sheet Index and Scope of Work (Sheet G-002), the project distinguishes between permanent construction and equipment through a phased approach. For Phase 1, there are no FF&E (Furniture, Fixtures, and Equipment) requirements; the scope is strictly for a "warm lit shell" and full MEP infrastructure. However, Phase 2 contains significant equipment requirements, specifically the furnishing and installation of the High-Density Mobile Shelving System in both the North and South wings, as well as three (3) specialized Dehumidifiers.

Q.14 Is there any amendment forthcoming with extension of bid date? Please advise.

Yes. The proposal submission due date will be extended.

Q.15 Can we use the original PPQ issued by the clients for the technical?

The technical volume imposes separate instructions. The PPQs exclusively apply to the past performance volume.

Q.16 Is Bid Bond or bonding capacity letter required for this solicitation?

Yes. A Bid Bond and Certificate of Insurance (COI) are required at time of award.

Q.17 Can we utilize the subcontractors experience for technical requirement?

Subcontractor experience is permitted for the technical volume.

Q.18 Is there any page limit for each factor, please advise?

No. The length of each volume is at the offeror's discretion.

Q.19 What are the access requirements to the building for the awardee contractor and its subcontractor personnel? Will we get a badge for the duration of the contract for every individual or day passes?

Please review Section H of the solicitation, specifically the following: Security Clearances, Badging Protocol, Badge Security, and Roster Management.

Q.20 Is the project required to be performed by US Citizens only?

See previous response.

Q.21 All work will be performed during normal business hours. What about selective demolition and features of work that generate noise?

All selective demolition, core drilling, powder-actuated fastening (Hilti guns), and heavy hammering that generate significant noise or vibrations must be performed after normal business hours or on weekends. The "After Hours" window is typically defined as 4:00 PM to 12:00 AM.

Q.22 Please provide contact information for the firms that are currently maintaining the fire alarm and sprinkler systems in the building.

Per Specification Section 284621.11, the awardee must coordinate all system shutdowns, "fire watches," and final tie-ins with the GPO Fire Marshal and the building's incumbent maintenance contractors. All work performed on these life-safety systems must be scheduled at least 48 hours in advance and will typically require oversight by the building's maintenance personnel.

Q.23 Are the 12" x 12" ceiling tiles free of asbestos?

The existing 12" x 12" and 1" x 1" spline ceiling tiles throughout the 4th-floor project area are classified as Asbestos-Containing Material (ACM). Both the tiles themselves and the adhesive mastic used to secure them have tested positive for asbestos. Additionally, the contractor is responsible for the full abatement and disposal of these tiles in accordance with 29 CFR 1926.1101. This work must be completed by a licensed abatement subcontractor under negative-pressure containment before any new MEP infrastructure or architectural finishes are installed in Phase 1.

Q.24 Has all the asbestos and lead paint been abated in the areas work is to be done?

Lead-based paint is present on several existing structural elements and masonry walls. Additionally, all costs associated with the testing, monitoring, removal, and legal disposal of these hazardous materials must be included in your proposal pricing for the Phase 1 CLINs.

Q.25 Is 3rd Party Testing required for communications cabling?

Yes, according to Specification Section 271500 (Communications Horizontal Cabling), third-party testing and certification are mandatory requirements for this project.

Q.26 Is it possible to get the permitting procedure for the building? Does any of the permitting have to go through other agencies like Historical Preservation groups, Washington DC Permit offices, etc?

Because this project is located on federal property, the building is generally exempt from the District of Columbia Department of Buildings (DOB) / DCRA permitting

process. You are not required to pull standard Washington DC building, electrical, or plumbing permits for work performed within the facility. However, project permitting is managed internally through the GPO Agency Support Operations Business Unit and the NARA Facility Manager.

Q.27 Will the contractor be given a manifest or material list for deliveries they are to sign for?

The Government will not provide a master manifest or material list for contractor-purchased items. The contractor is solely responsible for tracking their own orders, maintaining their own procurement logs, and verifying that all deliveries match their approved submittals and purchase orders.

Q.28 Specs say CAT6 UTP but next sentence says "Shielded Cable is specifically required for all ethernet applications within integrated automation (DCC) systems". Please clarify is it CAT6 UTP or CAT6 STP?

Where conflicting requirements are indicated, the more stringent requirement shall govern. Accordingly, provide shielded Category 6 (CAT6 STP) cable for all Ethernet applications within the integrated automation (DDC) systems.

Q.29 Who is to install the wire mesh cable tray, Electrical or low voltage contractor?

The Electrical Contractor is responsible for furnishing, installation, and structural support of the wire mesh cable tray system. This includes all threaded rod hangers, wall brackets, and intersections required to create a continuous pathway throughout the 4th-floor corridors and into the telecommunications rooms.

Q.30 Can the Wiremaid Pro-10 Series tray be substituted?

Per Specification Section 260536: The wiremaid Pro-10 Series is listed as a basis of design. Under federal procurement guidelines, you may propose a substitution, provided it is an "approved" equal.

Q.31 Would a LAN-Tek IV cable tester be an adequate substitute for a Fluke or Agilent tester?

Yes, the TREND Networks LANTEK IV-S (or IV series) is generally considered an adequate substitute and an "approved equal" to the Fluke DSX series or Agilent testers.

Q.32 Is there ethernet cabling requirement beyond the cameras noted on the drawings?

Security Control Panels: Ethernet drops are required for the DMP (Digital Monitoring Products) alarm panels and any secondary network-connected power supplies to allow for remote monitoring and head-end communication.

Card Readers and Door Controllers: some hardware uses specialized security cabling, all IP-based door controllers and any "intelligent" power controllers in the security closets require a CAT6 ethernet connection to the security VLAN.

Q.33 What is the delivery procedure to the building? Off-site inspection or setup with building security?

The contractor must submit a Delivery Request Form to the COR and the GPO Security Office at least two business days in advance of any major delivery.

Q.34 What devices are the Security Contractor responsible for furnishing and installing in HW-2 and HW-3 Door Hardware Sets? (Card Reader, Door Contact, REX Motion, REX Push Button. Electrified Hinge, Electrified locks).

Card Readers: Furnish and install at the exterior/entry side of the door.

Door Contacts (DPS): Furnish and install (typically recessed in the frame/door top).

Request-to-Exit (REX) Motion Sensors: Furnish and install on the secure side of the opening.

REX Push Buttons: Furnish and install (required specifically for HW-3 emergency override/egress compliance).

System Integration: All low-voltage wiring from these devices back to the Security Control Panel.

Q.35 Is there parking onsite available for contractors?

There is no reserved or dedicated on-site parking available for contractor or subcontractor personal vehicles. Contractors are permitted to park onsite in Lot 50 at a daily rate of \$9 if spots are available.

Q.36 Is the Security Contractor required to provide a new Server/NVR with Camera Licenses for the new cameras or are we to connect to an existing Recorder with camera licenses?

The Security Contractor is responsible for furnishing and installing the required professional-tier camera licenses. These licenses must be registered to the Government and coordinated with the GPO IT/Security department to ensure they are properly activated on the existing server.

Q.37 Is the security contractor required to provide a new DMP Alarm Panel or are we tying into an existing panel with Zone Expansion Modules? If using existing, what method of expansion is required? Model of existing Panel?

All new zones (door contacts, REX, etc.) must be fully supervised using the appropriate EOL resistors to match the existing system configuration. The contractor is responsible for all zone programming, including alphanumeric descriptors for each new point, coordinated with the Security Operations Center (SOC) naming standards.

Q.38 Page 41, Section L.3 Submission, Modification, Revision, and Withdrawal of Proposal Instructions, Item d references a different solicitation number. Please confirm the only solicitation number to be used for this pursuit is 040ADV-26-R-0016.

Solicitation No. 040ADV-26-R-0016 is the only solicitation number to be used for this pursuit.

Q.39 Section XI Key Personnel requests for the resumes of the Project Manager, Superintendent, Quality Control Lead and Safety Lead as part of the technical submission. The table and section H shows the key positions as Project Manager, Quality Control Lead, Safety Lead and Master Electrician. Which is correct?

The Superintendent was erroneously listed Section XI of the SOW. Section H and Section L outline the correct list of the key personnel: Project Manager, Quality Control Lead, Safety Lead and Master Electrician.

The corrected section,

XI. Key Personnel: The Government has designated the Project Manager, Quality Control Lead, and Safety Lead positions as key personnel. Each position shall be filled by one full-time equivalent(FTE) for the total duration of this project. The key personnel specified below are essential to the work being performed under this contract. All personnel shall possess the minimum education and experience identified in the table below. The Contractor shall follow the guidance outlined in Section H of this contract for the substitution of key personnel for the duration of this contract.

Q.40 Can any of the key personnels serve as duo-roles?

No. See previous response.

Q.41 Are there any hazardous materials removal on this project? If so, please provide the hazmat report.

As previously noted in the responses to Q.23 and Q.24, the answer is yes. There are significant hazardous material abatement requirements for this project.

This report was uploaded as part of the original solicitation package on the SAM.gov posting (Attachment J.7: Hazardous Materials Survey Report.)

Q.42 Is shelving shown on drawing A303 part of the scope of work? If so, please provide the specification.

The detailed technical requirements for this equipment can be found in Specification Section 10 56 26 (High-Density Mobile Storage Units) and Section 10 56 13 (Metal Storage Shelving).

Q.43 Who is responsible for the third-party testing/inspections?

The General Contractor is responsible for hiring, coordinating, and paying for all third-party testing and inspection services required by the contract documents. These agencies must be independent of the contractor and approved by the Contracting Officer's Representative (COR) prior to performing work.

Q.44 What are the working hours?

Monday through Friday: 7:00 AM – 3:30 PM.

Q.45 Sheet A702 - Detail E6 notes that there is an add alternate for brick infill at Central shafts 1-10. This work is to include new doors. This alternate work is not noted in the RFP/Price schedule, and these doors are not shown on the door schedule. Please confirm that an alternate for the work shown on Sheet A702 - Detail E6 is to be

Base Bid vs. Alternate: While the architectural detail notes this as an "Add Alternate," the Government has determined that this work is not required for the functional completion of the NARA 4th Floor Renovation currently.

Q.46 Provide a cut section or detail for new drywall element at E5 & D5/A702

The drywall must extend from the finished floor through the suspended ceiling grid and terminate at the underside of the structural deck above.

Q.47 Wall type SOZ shown on A801 appears to indicate in-wall insulation but does not call it out. Please confirm insulation will not be used on wall type SOZ.

Wall Type SOZ is a specialized "Archival Partition" designed for acoustic separation and thermal stability:

- (1) Insulation Requirement: 3-1/2" thick Mineral Wool Sound Attenuation Fire Batts (SAFB).
- (2) Framing: 3-5/8" 20-gauge metal studs at 16" O.C.
- (3) Facing: 5/8" Type X Gypsum Board on both sides, extending slab-to-slab as defined in Q.46.

Q.48 Notes AD14 and AD15 on AD102 as well as notes AF23 and AF24 on A102 call for patching in Existing Mechanical Room A421 walls. Please advise on wall types being patched.

Based on the Existing Conditions Survey and the Architectural Demolition (AD) series drawings, the walls within and surrounding Mechanical Room A421 consist of two primary construction types. The patching required by the notes mentioned shall match these existing assemblies:

- (1) Concrete Masonry Unit (CMU) Walls: Where old piping, conduits, or ductwork are removed (per notes AD14/AD15), the contractor must infill the openings with matching CMU blocks.

- (2) Finish: The patch must be finished with a sand-finish mortar joint to match existing. In areas visible to the public or office staff, a skim coat of plaster or joint compound may be required to achieve a flush, paintable surface (per notes AF23/AF24).
- (3) Fire Rating: Because Room A421 is a mechanical shaft/space, these walls are part of a 2-hour fire-rated assembly. All patches must be fully grouted, and any remaining gaps must be sealed with UL-listed fire-stopping mortar or intumescent sealant.

Q.49 B4/A703 shows the lightweight concrete topping abutting the face of the furring wall that goes around the perimeter of the floor. Partition detail SOZ on A801, however, shows the concrete topping passing under the furring wall and abutting a piece of blocking. Please advise if the concrete topping is to abutt the face of the furring wall or pass under it.

The lightweight topping is non-structural. Mounting the furring wall directly to the structural slab provides a more stable substrate for the wall framing than mounting it on top of the topping material.

Q.50 Price schedule "J.6+-+Cost-Price+Proposal+-+Excel+NARA" includes 6 CLINs while the RFP-Section B includes 1 CLIN. Is this project to be priced as a single lump sum or broken into the 6 CLINs in the Excel Price schedule?

The project must be priced using the six-CLIN breakdown as provided in Attachment J.6 (Excel Price Schedule). While Section B of the RFP may show a single aggregate CLIN for administrative summary purposes, the detailed cost breakdown in the Excel document is mandatory for a responsive bid.

Q.51 The bid documents are broken into Phase 1 - Architectural and HVAC upgrades minus the dehumidifier work and Phase 2 - Installation of high bay storage systems and dehumidifiers. The CLINs in the Price Schedule do not appear to align with the phasing in the Bid documents. Is this project to be priced as a single lump sum or priced

Phase 1 (Abatement, Demo, HVAC Upgrades): This work should be distributed across CLIN 0001 (Abatement/Demo) and CLIN 0002 (Infrastructure/MEP).

Phase 2 (High-Density Storage & Dehumidifiers): The storage systems should be captured under CLIN 0004, while the dehumidification units and their specialized integration fall under the remainder of CLIN 0002.

While the final award will be a Firm-Fixed-Price (FFP) contract, the Government requires the "lump sum" for each CLIN to be backed by the detailed line items in the Excel sheet.

Q.52 Elevations D5 and E5 on A702 show a type wall "S" surround at Stair 2 and 3 which is to receive P-1 as the finish. The Partition Plan (A801) does not show a type "S" wall. Please provide a detail for an "S" wall. Provide a cut section of elevations D5 and E5 on A702.

The omission of the "S" wall designation on Drawing A801 is acknowledged. For bidding purposes, provide a wall assembly consistent with the adjacent partition types shown on A801, configured as required to receive finish P-1 as indicated on A702.

A detailed wall type designation and associated section/cut detail for the "S" wall will be provided by amendment. No additional compensation will be provided for coordination of this condition.

Q.53 Please advise on base and head condition requirements for wall types shown on A801 especially for the head condition at the brick arches.

Base and head conditions for the wall types shown shall be as detailed on the drawings and specified in the contract documents. At locations where wall heads occur adjacent to or beneath existing brick arches, provide framing and attachment as required to accommodate the existing conditions while maintaining the design intent. The Contractor shall field verify all existing conditions and coordinate installation accordingly.

Q.54 Please confirm radius track is to be used where walls run perpendicular to brick arches.

Where new walls intersect or occur perpendicular to existing brick arches, provide framing as required to accommodate the existing curved conditions. This shall include the use of radius track where necessary to achieve proper fit and alignment with the existing conditions. The Contractor is responsible for field verification of existing conditions and coordination of framing to meet the design intent.

Q.55 Regarding the acoustical ceiling tiles in Restroom A401, drawings call for 2x2 tile (A201) and specifications call for 2x4 tile (095113 2.3.J). Please confirm 2x2 ceiling tile is to be used.

In the event of a discrepancy between the drawings and specifications, the specifications shall govern unless otherwise directed.

Accordingly provide acoustical ceiling tile in Restroom A401 in accordance with Specification Section 095113, Paragraph 2.3.J, which indicates 2'-0" x 4'-0" ceiling tile. The drawings will be clarified by amendment if required.

Q.56 Partition Plan A801 shows a vapor barrier between the two layers of gyp board for partition type SOZ. Section 2.2 of 072100 lists multiple vapor barriers (retarders). Please confirm that it is to be the "Fire-Retardant, Reinforced-Polyethylene Vapor Retarders" listed in 2.2.B that is to be used. Reference E2/A703.

Provide vapor retarder for Partition Type SOZ in accordance with Specification Section 072100, Paragraph 2.2.B. Install the vapor retarder at the location indicated on the drawings and in accordance with the manufacturer's recommendations and specification requirements. No deviation is authorized.

Q.57 Partition types 1S, 2S, and SO indicate that acoustical insulation is only to be used with the "A" option. That option does not appear to be used. Please confirm acoustical in-wall insulation is not used.

As the "A" option is not indicated for these partition types in the contract documents, acoustical in-wall insulation is not required for these assemblies.

Provide partition construction in accordance with the wall types as scheduled and detailed. No additional acoustical insulation shall be included unless otherwise directed by amendment.

Q.58 Openings A401B and A402C (openings for Stair 1 and 2) are called out as having a type "F" door in the Door Schedule on A801. No type F door, however, is shown - only type A and B. Please provide an elevation for door type F.

The reference to Door Type "F" for Openings A401B and A402C is acknowledged. The corresponding door type is not currently defined in the contract drawings.

For bidding purposes, provide a door and frame assembly consistent with the performance requirements indicated for these openings, including fire rating, hardware, and finish requirements as applicable to stair enclosures.

A detailed elevation and specification for Door Type "F" will be provided by amendment. No additional compensation will be provided for coordination of this condition.

Q.59 Please advise who is to furnish the security/electrified hardware: DFH contractor or security contractor?

Unless specifically identified otherwise in the contract documents, all door hardware, including electrified hardware associated with door assemblies, shall be furnished and installed under Division 08. The security contractor shall provide and coordinate connections, devices, and system integration associated with the electronic security system as specified. The Contractor is responsible for coordination between trades to ensure a complete and fully functional installation.

Q.60 Please advise if the general contractor is to provide permanent cores and keys.

Unless otherwise indicated, the General Contractor shall provide permanent cores and keys as part of the door hardware package. Keying shall be coordinated with the Government's keying requirements and existing system, if applicable. Final keying schedule and quantities will be provided or approved by the Government prior to installation. Temporary construction cores may be used during construction and shall be replaced with permanent cores at Substantial Completion. The Contractor is responsible for coordination to ensure a complete and functional keying system.

Q.61 Please advise if there is preferred vendor for permanent cores / keying and if the contractor is to key this space to integrate with the rest of the building.

The Government does not designate a preferred vendor for permanent cores and keying unless specifically identified in the contract documents. The Contractor shall coordinate all keying with the Owner to ensure compatibility and integration with the existing building keying system. This includes providing cores, keys and keying arrangements consistent with the Government's established standards. Final keying requirements, including system type and keying schedule, will be provided or approved by the Government prior to installation. The Contractor is responsible for ensuring the furnished system is fully compatible with the existing facility.

Q.62 Hardware Sets HW-1 and HW-2 on A801 call for a bottom flush bolt; however, a bottom flush bolt is not called out on the Hardware Schedule. Please advise on manufacturer and style for this hardware item.

The requirement for a bottom flush bolt as indicated in HW-1 and HW-2 is acknowledged. Where a bottom flush bolt is required for paired doors, provide a standard, heavy duty concealed or surface mounted flush bolt compatible with the specified door and frame assembly.

Manufacturer and style shall be in accordance with the basis of design hardware manufacturers listed in the specifications for Division 08.

Final selection shall comply with applicable code requirements and be coordinated with the approved hardware submittal. The drawings and hardware schedule will be clarified by amendment if required.

Q.63 Hardware Sets HW-1 and HW-2 on A801 call for a dustproof strike; however, a dustproof strike is not called out on the Hardware Schedule. Please advise on manufacturer and style for this hardware item.

The requirement for a dustproof strike as indicated in HW-1 and HW-2 is acknowledged. Where required, provide a standard dustproof strike compatible with the specified flush bolt and door/frame assembly.

Manufacturer and style shall be in accordance with the basis of design hardware manufacturers listed in the specifications for Division 08.

Final selection shall comply with applicable code requirements and be coordinated with the approved hardware submittal. The drawings and hardware schedule will be clarified by amendment if required.

Q.64 Hardware Sets HW-1 and HW-2 on A801 call for an astragal; however, an astragal is not called out on the Hardware Schedule. Please advise on manufacturer and style for this hardware item.

The requirement for an astragal as indicated in HW-1 and HW-2 is acknowledged. Where required for paired doors, provide an astragal compatible with the specified door and frame assembly.

Manufacturer and style shall be in accordance with the basis of design hardware manufacturers listed in the specifications for Division 08.

Final selection shall comply with applicable code requirements and shall be coordinated with the approved hardware submittal. The drawings and hardware schedule will be clarified by amendment if required.

Q.65 Hardware Set HW-1 on A801 calls for an acoustic door seal; however, a door seal is not called out on the Hardware Schedule. Please advise on manufacturer and style for this hardware item.

The requirement for an acoustic door seal as indicated in HW-1 and HW-2 is acknowledged. Where required, provide a complete acoustic sealing system, including perimeter seals and door bottom seal, compatible with the specified door and frame assembly.

Manufacturer and style shall be in accordance with the basis of design hardware manufacturers listed in the specifications for Division 08.

Final selection shall meet the acoustic performance intent of the assembly and comply with applicable code requirements and shall be coordinated with the approved hardware submittal. The drawings and hardware schedule will be clarified by amendment if required.

Q.66 Hardware Set HW-1 on A801 calls for an automatic threshold seal; however, automatic threshold seal is not called out on the Hardware Schedule. Please advise on manufacturer and style for this hardware item.

The requirement for an automatic threshold seal as indicated in HW-1 is acknowledged. Where required, provide an automatic door bottom seal compatible with the specified door and frame assembly.

Manufacturer and style shall be in accordance with the basis of design hardware manufacturers listed in the specification for Division 08.

Final selection shall comply with applicable code requirements and shall be coordinated with the approved hardware submittal. The drawings and hardware schedule will be clarified by amendment if required.

Q.67 Regarding the key control system, please confirm if a key control cabinet is required for this project. If so, please indicate type (e.g. wall mounted, portable etc.)

A key control cabinet is not specially identified in the contract documents.

Accordingly, key control is not required for this project unless directed otherwise by amendment.

The Contractor shall provide keys and keying in accordance with the specified keying requirements and coordinate with the Government for final key control procedures.

Q.68 Please advise if a key lock box or key control system software listed in the specifications are required for this project?

A key lock box and key control system software are not specifically identified as required deliverables in the contract documents.

Neither a key lock box nor key control system software is required for this project unless otherwise directed by amendment.

The Contractor shall comply with all specified keying requirements and coordinate with the Government regarding key control procedures.

Q.69 Specifications list coordinators and carry-open bars for door pairs. Please confirm these are required as they are not called out in the Hardware Schedule or the Hardware Set.

For bidding purposes, provide hardware in accordance with the hardware sets as shown on the drawings. Door coordinators and carry open bars are not required unless specifically indicated in the hardware sets or required to meet code or life safety requirements.

The Contractor shall ensure all door assemblies are complete and code compliant. The contract documents will be clarified by amendment if additional hardware is required.

Q.70 Door gasketing and metal protective trim units are called out in specifications, but not in the Hardware Sets. Please confirm if they are to be used. If so, please advise on which openings.

For bidding purposes, provide hardware and accessories in accordance with the hardware sets as shown on the drawings. Door gasketing and metal protective trim units are not required unless specifically indicated in the hardware sets or where necessary to meet code, fire rating, or performance requirements of the door assembly. The Contractor shall ensure all door assemblies are complete and code compliant. The contract documents will be clarified by amendment if additional requirements are identified.

Q.71 May "Klimak" be added to list of acceptable manufacturers for Custom Factory Fabricated Air Handling Units?

Requests to add manufacturers shall be submitted in accordance with the "substitutions" or "or equals" provisions of the specifications. Approval of alternate

manufacturers will be evaluated for compliance with the specified performance, quality, and basis of design requirements.
For bidding purposes, provide equipment from the listed acceptable manufacturers.

Q.72 May "Neptronic" be added to the list of acceptable manufacturers for Humidifiers?

Requests to add manufacturers shall be submitted in accordance with the "substitutions" or "or equals" provisions of the specifications. Approval of alternate manufacturers will be evaluated for compliance with the specified performance, quality, and basis of design requirements.
For bidding purposes, provide equipment from the listed acceptable manufacturers.

Q.73 May "Neptronic" be added to the list of acceptable manufacturers for Reverse Osmosis Water Piping for Humidification?

Requests to add manufacturers shall be submitted in accordance with the "substitutions" or "or equals" provisions of the specifications. Approval of alternate manufacturers will be evaluated for compliance with the specified performance, quality, and basis of design requirements.
For bidding purposes, provide equipment from the listed acceptable manufacturers.

Q.74 May "Climate by Design International (CDI)" be added to the list of acceptable manufactureres for Indoor Mechanical Dehumidication Units?

Requests to add manufacturers shall be submitted in accordance with the "substitutions" or "or equals" provisions of the specifications. Approval of alternate manufacturers will be evaluated for compliance with the specified performance, quality, and basis of design requirements.
For bidding purposes, provide equipment from the listed acceptable manufacturers.

Q.75 Who is the existing switchgear manufacturer?

The existing main switchgear and the distribution panels were manufactured by Square D (by Schneider Electric).

Q.76 Where is the 3rd floor electric room and switchboard USG12A located in relation to the work area?

Switchboard USG12A is located in Room A-320 on the 3rd Floor of Building A. This electrical room is located exactly one story (one level) directly below the NARA 4th-floor project footprint.

Q.77 Please provide the Edwards fire alarm system point of contact for the building.

The Contractor shall coordinate all fire alarm system work with the Government and the building's designated fire alarm service provider. Contact information will be provided after award.

Q.78 Please provide telecommunication device plans or confirm there is none beyond what is shown on TN301.

No additional telecommunication device plans are included in the contract documents beyond what is shown on Drawing TN301.

Provide telecommunications work in accordance with the requirements and information indicated on TN301 and the applicable specifications.

Q.79 Confirm if there is existing cable tray for contractor use for telecom cabling or will conduit be required from each device to the IDF room.

The Contractor shall field verify the presence and condition of any existing cable tray systems and coordinate their use where suitable. Where existing cable tray is not available or not suitable for use, provide conduit from each device to the IDF room as required to complete the installation.

The Contractor is responsible for providing a complete and code compliant telecommunications pathway system in accordance with the contract documents.

Q.80 Please advise who the existing DDC System vendor/contractor is for the building.

The Contractor shall coordinate all work with the Government and the building's designated controls provider to ensure compatibility and integration with the existing system. Contact information will be provided after award.

Q.81 Does this project require DC First Source labor?

Not applicable for federal government contracts.

Q.82 On A1/A703 it is noted “Existing Pipe with New Pipe Insulation”. Please confirm the extent of existing to remain piping that is to receive new pipe insulation.

Provide new pipe insulation on existing piping where indicated on the drawings and where insulation is removed, damaged or required to meet current code and specification requirements.

The Contractor shall field verify the extend and condition of existing piping and include all work necessary to provide a complete and compliant installation.

Q.83 Keynote AF03 on A101 states that access doors shall be provided at existing pipe valve locations and coordinate with MEP drawings. Please confirm that access doors for existing valves are only required at the four (4) locations shown on A101.

The four (4) locations shown on a101 are identified for reference, however, access doors are not limited to only those locations. Provide access doors at all existing valve locations within the project work area where access is required and where walls or ceilings are being modified or constructed.

The Contractor shall coordinate with the MEP drawings and field verify all valve locations to ensure proper access is provided.

Q.84 Specification 220523-3.2.E.1 references press end connections for valves located in copper piping systems 2” and smaller. Please confirm that press end connections are acceptable to use.

Provide press type connections in accordance with the specified requirements and manufacturer’s recommendations. All materials, installation methods, and fittings shall comply with the contract specifications and applicable codes.

Q.85 Specification section 224100-2.2.C.2 C 3 requires a flood control system for ASSE 1013 RPZ backflow preventers. A flood control system is not indicated on M1402 (note 39). Is a flood control system required for ASSE 1013 RPZ backflow preventers? If so, should the flood control system connect to the BMS or be a cellular?

For bidding purposes, comply with the requirements of the specifications. Provide a flood control system for ASSE 1013 RPZ backflow preventers in accordance with Section 224100.

Connection and monitoring requirements shall be as specified. If not explicitly defined, coordinate with the building systems to provide a complete and functional installation. Final integration requirements (BMS or other) will be confirmed after award.

Q.86 Specification section 224216.13-2.3.C references chrome plated pipe or tubing for lavatory supplies. Please advise if flexible supplies can be utilized in lieu of the chrome plated pipe or tubing.

For bidding purposes, provide chrome plated pipe or tubing in accordance with the specifications. Any proposed substitution shall be submitted in accordance with the contract provisions for substitutions and will be subject to approval.

Q.87 Please advise if sleeves are required for core drilled penetrations for mechanical and plumbing piping.

For core drilled penetrations, sleeves shall be provided where required to maintain fire resistance ratings, allow for proper sealing, and protect the building construction. Where sleeves are not specifically required by specifications or applicable codes, core-drilled penetrations may be sealed in accordance with the specified firestopping and sealing requirements. The Contractor is responsible for ensuring all penetrations are properly detailed, sealed and code compliant.

Q.88 Specification section 230518-3.1.B.2 references escutcheons for existing piping. Please confirm that escutcheons for existing piping that is exposed in finished spaces should receive an escutcheon.

Provide escutcheons in accordance with the specifications to ensure a complete and finished appearance.

The Contractor shall coordinate installation to match adjacent finished and maintain compliance with the contract documents.

Q.89 Specification section 230529-2.3.A.1.7 states that metal framing systems for HVAC supports shall be hot-dipped galvanized. Please advise if pre-galvanized or electro-galvanized metal framing systems are acceptable in lieu of hot-dipped galvanized.

For bidding purposes, provide hot dipped galvanized metal framing systems in accordance with the specifications. Any proposed substitution shall be submitted in accordance with the contract provisions for substitutions and will be subject to approval.

Q.90 Drawings M1102 and M1103 indicate work to be performed on level 3. Please confirm the following: Work shown on the 3rd floor can occur during normal working hours & Confirm that the space below the new work will be cleared of existing items.

Work on the third floor shall be performed in accordance with the contract requirements for working hours. Unless otherwise restricted in the contract documents, normal working hours may be utilized.

The space below the work area is not guaranteed to be cleared of existing items. The Contractor shall coordinate with the Government regarding access, protection of existing conditions, and any required relocation of items.

The Contractor is responsible for providing all necessary protection measures and coordination to safely perform the work.

Q.91 Detail 6 on S200 is a duct hanger detail indicating adhesive anchors attached to brick and noted not to exceed 250 pounds. Specification section 233113-3.4.C does not require adhesive anchors for building attachments for metal ducts. Confirm that adhesive anchors are not required for building attachments.

For bidding purposes, provide attachments in accordance with the details shown on the structural drawings where specific conditions are indicated. Adhesive anchors shall be used where required by the details or where necessary based on existing conditions.

Q.92 Specification section 230548.13-3.2.K.3 states that pipe risers shall utilize a resilient guides and anchors. This isolation system is typically used in buildings with multiple floors where the resilient support is installed at the lowest level and guides are installed at the midpoint and roof line to compensate for expansion in the piping system. The risers for this project travel only a single floor. Please confirm that resilient guide and anchor isolation system is NOT required for this project.

For this project, where pipe rises are limited to a single floor, a full resilient guide and anchor isolation system as typically applied to a multi-story risers is not required.

Provide supports and anchorage appropriate for the piping configuration in accordance with the specifications and manufacturer's recommendations.

Q.93 The vibration isolation schedule shown in specification section 230548.13 (page 14) indicates a FC-1 (neoprene piping flexible connection) should be provided at fan coil units. Detail H on M1501 does not indicate flexible connectors on the piping to fan coil units. Please advise if a neoprene flexible piping connection is required at fan coil units.

For bidding purposes, comply with the requirements of the specifications. Provide neoprene flexible piping connections at fan coil units in accordance with the vibration isolation schedule.

The contract documents will be clarified by amendment if additional detail is required.

Q.94 Specification 230700-3.12 states that all supply duct exposed in conditioned spaces shall receive 1" thick board insulation. Per A201 Archival Storage A401 and A402 is exposed. Please confirm that all supply ductwork in these areas is to receive 1" thick board insulation.

Rooms A401 and A402 are identified as conditioned spaces with exposed ductwork. Accordingly, provide 1" thick board insulation on all exposed supply ductwork in these areas in accordance with the specifications.

The contract documents will be clarified by amendment if additional detail is required.

Q.95 Specification section 232116-3.1.C states to install balancing valves and flow meter fittings at each branch connection to return main. Balance valves on the return branch connection to the main are not shown on the drawings (reference M1103 at column line 12 for example). Please advise if balance valves on return branch piping connections to mains are required.

For bidding purposes, comply with the requirements of the specifications. Provide balancing valves and flow meter fittings at each return branch connection to the main as specified.

The contract documents will be clarified by amendment if additional detail is required.

Q.96 Specification section 232116-3.2.D states to install test ports adjacent to DDC temperature sensors and control valves in hydronic piping for device verification. Test

ports are not indicated on the piping details at control valves (reference B/M1501, C/M1501, H/M1501, and A/M1502). Please advise if test ports are required at

For bidding purposes, comply with the requirements of the specifications. Provide test ports at locations adjacent to DDC temperature sensors and control valves as specified.

The contract documents will be clarified by amendment if additional detail is required.

Q.97 Specification section 232500 outlines the HVAC water treatment requirements for the closed loop systems. The work included in this project has connections to existing chilled and heating hot water systems. Please confirm that the owner will be responsible for adding chemicals for the new system and the contractor is only responsible for flushing chemicals.

For bidding purposes, the Contractor shall be responsible for providing a complete water treatment scope in accordance with the specifications. The Government is not responsible for providing initial chemical treatment for the new or modified systems.

Q.98 Specification section 232533.13-2.5.A and 3.9.B.2 states that RO distribution piping shall be pharmaceutical grade welded stainless steel. Please advise if schedule 40 type 316 stainless steel with socket weld fittings can be utilized in lieu of pharmaceutical grade welded stainless steel for RO distribution piping.

For bidding purposes, provide pharmaceutical grade welded stainless steel piping in accordance with the specifications. Any proposed substitution shall be submitted in accordance with the contract provisions for substitutions and will be subject to approval.

Q.99 Per A401, Tremco Vulkem OC 810 waterproofing is to be applied beneath Sherwin Williams Hybri-Flex EB epoxy flooring in Mech Room 2 and Mech Room 3. Vulkem OC 810, however, should not be applied below the Hybri-Flex EB as this may cause compatibility issues. Please confirm it is acceptable to use Sherwin Williams Resuflor EOC as the waterproofing layer ILO Vulkem OC 810.

For bidding purposes, provide materials as specified in the contract documents. Sherwin Williams Resuflor EOC is not currently listed as an acceptable substitute. Requests for substitution shall be submitted in accordance with the contract provisions for substitutions.

Q.100 Per A401 finish schedule, VB-1 is listed as "match GPO Standard" but is not called out in specification section 096513 . Please provide specification for the existing Vinyl Base (VB-1).

Final selection shall be coordinated with and approved by the Government.

Q.101 Please confirm substitute floor tile is permitted in lieu of Daltile. Please provide suitable substitution products and substitution form, if permitted.

Substitutions are not pre-approved. For bidding purposes, provide the basis of design product as specified.

Requests for substitution shall be submitted in accordance with the contract provisions for substitutions after award.

Q.102 Specification section 102800 outlines all the private-use washroom accessories but does not specify the showerhead/hose listed on G104 detail A1 nor does it list in on A601 Plumbing and Restroom Accessories Schedule. Please confirm if the shower head and hose is to be CFCI or OFCI and specification.

For bidding purposes, include the showerhead and hose as part of the construction scope. Provide a commercial-grade assembly suitable for the application, coordinated with the plumbing drawings and specifications. The Contractor shall ensure a complete and code compliant installation.

Final product selection will be confirmed by amendment or during submittal review.

Q.103 During the site walk, it was observed that a significant amount of existing equipment and supplies stored within the work area. Please confirm that these items will be removed prior to the renovation and contractors are not to include costs to relocate or remove these items.

Removal or relocation of existing equipment and materials will be coordinated with the Government; however minor relocation or coordination necessary to perform the work shall be included in the Contractor's scope.

Q.104 During the site walk, it was observed that a number of the locations shown on sheet S101 as a crack appeared to be a concrete spall that will require additional remediation in order to receive a new epoxy flooring. Are bidders to bid the documents as is and spalled concrete will be handled as a change?

Bidders shall base their pricing on the contract documents as issued.
Any additional unforeseen concrete spalling beyond what is indicated in the contract documents will be addressed in accordance with the contract provisions.

Q.105 Please confirm if we are required to submit the excel file of pricing sheet, or if a PDF version of it is sufficient.

Offerors shall submit a Microsoft Excel workbook for the pricing sheet.

Q.106 Please confirm no bid bond is required.

Bid Bond and Certificate of Insurance (COI) are required at time of award.

Q.107 For evaluations purposes, are only projects in the \$1M - \$5M range relevant for submission? Or please confirm if other values would be equally rated if they have similar scope.

Offerors should determine the relevant range based on the general construction scope.
All submitted projects will be evaluated in accordance with the criteria outlined in the solicitation

Q.108 To less burden on government contacts, may we please submit previously completed PPQs?

Yes. Customer references may resubmit previous questionnaires that meet the recency and relevancy standards in Section M

Q.109 If all previously completed PPQs are not allowed, what about ones that were submitted for GPO?

See previous response.

Q.110 If we are not allowed to submit previously completed PPQs, are Gov contacts allowed to forward previously completed ones in lieu of completing new ones? We are trying to lessen the request on Gov contacts to complete evaluations for the same projects over and over.

See previous response.

Q.111 The solicitation instructed to include a Sol number in our RFI subject line that does not coordinate what is provided on SAM. Please clarify Sol number.

The solicitation number is 040ADV-26-R-0016. The SAM.gov Notice ID is the same.

Q.112 Page 38 of 46 Key Personnel- The Government has designated the Project Manager, Quality Control Lead, Safety Lead and Master Electrician positions as key personnel. Each position shall be filled by one full-time equivalent (FTE) for the total duration of this project. QUESTION: Please confirm if a full-time project superintendent is required in lieu of a full-time project manager?

A full-time Project Manager is required, as defined in the solicitation and shall not be replaced by a Superintendent.

Q.113 Please confirm that the Safety Representative (SSHO) is a full-time staff member as well.

The SSHO is designated as key personnel and shall be provided as a full-time staff member for the duration of the project.

Q.114 Section 1.6 GPO Furnished Products para A. Could you provide a list and quantity of GPO furnished products for contractor installation.

For bidding purposes, do not include Government furnished products unless specifically identified. The Government will provide information on furnished products and quantities after award.

Q.115 Existing Switchgear USG-12A Spare Breakers.

a. During the 3/24/26 site walk, it was noticed that existing switchgear USG-12A contains spare 1600A rated breakers. Per 100% construction bid drawing E1601(electrical one-line) dated 5/30/25, Special Note #1 shows the installation of breakers to match existing manufacturer and AIC rating. Is it permissible to utilize the existing spare 1600A rated breakers in lieu of the qty. 3, new breakers as indicated E1601/ Special Note #1?

For bidding purposes, provide new breakers as specified. Use of existing spare breakers is not authorized unless approved through a formal submittal or modification after award.

Q.116 New Lighting Control Zoning Question Archival Storage “A” & “B”

a. 100% construction bid drawing E1501/Detail 5 (Diagram-Room Lighting Control System) shows multiple choices for Type “WS” wall station controls. There are qty. 4 “WS” controls in Archival Storage “A” (room A401) and qty. 4 “WS” controls in Archival Storage “B”(room A402) per E1201 “Electrical Lighting New Work Plan”.

a. We are assuming that the “single space with dimmable lights in single zone” option should be utilized for bid purposes in lieu of the other single space options shown for controls within Archival Storage “A” (ZONE) & “B” (ZONE). Please confirm E1501/Detail 5 single space with dimmable lights in single zone option is to be utilized for “WS” connectivity within each Archival Storage “A” & “B” zones or provide preferred multiple zone information within Archival Storage “A” & “B”. Please additionally refer to E1702 “Lighting Control Intent Schedule”.

For bidding purposes, provide lighting controls for Archival Storage Rooms A401 and A402 as a single space with dimmable lights in a single zone. Configure the “WS” wall station controls accordingly for each room.

Final zoning and control sequences will be confirmed during submittal review in coordination with the Lighting Control Intent Schedule.

The contract documents will be clarified by amendment if additional requirements are identified.

Q.117 Spec 28 46 21.11-1.9-A “Quality Assurance/Installer Qualifications” Questions

a. Spec 28 46 21.11-1.9-A.1 & 2 require personnel to be trained and certified by manufacturer for installation of units and the installation to be supervised by a NICET Level III technician. Do these requirements apply to the installation of all fire alarm conduit/boxes/wiring or just the fire alarm devices & panel terminations (fire alarm parts from manufacturer)?

These requirements do not apply to the installation of raceway, conduit, boxes, and general wiring infrastructure, which may be performed by qualified electrical personnel in accordance with applicable codes and specifications.

Q.118 Reference DDC Control System for HVAC - specification section 230923.1.5.A: Please provide a list of specific items included in “GPO supplied network hardware, integration equipment, instrumentation and controls and integrated automated systems”.

For bidding purposes, assume that GPO furnished items are limited to those explicitly identified in the contract documents. The Contractor shall provide all other components necessary for a complete and fully functional DDC control system.

Q.119 Please clarify the name of the existing currently Fire Alarm manufacturer in the building.

The existing fire alarm system is an EST3 system. The Contractor shall coordinate all work to ensure compatibility with the existing system.

Q.120 SWGR USG-12A. Need to add breakers so need to know what it is.

To properly procure and install the required breakers for the NARA 4th Floor project, the following technical specifications for Switchboard USG-12A (located in Room A-320) must be utilized:

Below is Equipment Identification:

- Manufacturer: Square D (Schneider Electric).
- Model/Type: QED-2 Switchboard (Standard Front-Accessible).
- Bus Rating: 480/277V, 3-Phase, 4-Wire.
- Main Bus Capacity: 2000A (Contractor to verify via nameplate during site walk).

Q.121 Work is on the 4th floor and SWGR is on 3rd. Need location of SWGR USG-12A and pathway to new panels on 4th floor.

Switchboard USG12A is located in Room A-320 on the 3rd Floor of Building A. Feeders will exit the top of USG-12A in Room A-320 and transition through the structural slab into the 4th-floor plenum. All penetrations between the 3rd and 4th floors must be

sealed with a UL-listed 2-hour fire-stop system to maintain the integrity of the floor assembly.

Q.122 Please provide As Builts of the Fire Sprinkler System showing the work areas, the adjacent areas, and piping from the work areas back to the Fire Pump.

The Contractor shall field verify existing conditions and coordinate work accordingly. Any available record documents may be provided after award, if available.

Q.123 See Phase 1 Drawing FP001. This drawings shows results from a Fire Pump Test in 2022. This test indicates a failure of the pump to perform properly at 150% of the rated flow. Has this been corrected? Are we to include any work related to pump repairs? Is a more recent test report available? If yes, please provide a copy.

For bidding purposes, no work related to fire pump repair or replacement is included in this project.

Additional information will be provided by amendment if available.

Q.124 See Phase 1 Drawing FP001. General Note 1 states that the new system is to be designed as an Ordinary Hazard Group II Occupancy. This class will only protect storage up to 12 feet in height to the top of the storage. Per Drawing A702, the top of the shelves will 12'-3". Please confirm that the AHJ will accept a system design for an Ordinary Hazard Group II Occupancy.

The system shall be designed in accordance with the hazard classification indicated in the contract documents. The Contractor shall design the system to meet all applicable codes and coordinate with the AHJ for approval.

Any required changes will be addressed by amendment or during the submittal review process.

Q.125 See Phase 1 Drawing FP001. General Note 21 references Combustible Concealed Spaces. Please indicate if there are spaces of this type in the work area for this project, and if yes, where they are located.

The Contractor shall field verify existing conditions and identify any combustible concealed spaces within the work area. Provide fire protection in accordance with applicable codes and the contract requirements.

Q.126 See Phase 1 Drawing FP001. General Note 23. This note references Providing Inspection Reports for NFPA-13, 14, and 25. NFPA 14 is for Standpipe Systems. There is no Standpipe Work on this project. Please confirm this is not applicable. NFPA-25 is for Inspection, Testing, and Maintenance (ITM) of existing systems and generally does not apply to Construction Projects. Please state whether we are to perform any NFPA-25 ITM under this project. If yes, please indicate which tasks we are to perform.

For bidding purposes, do not include NFPA 25 ITM services beyond those required for system acceptance and commissioning of new or modified work in accordance with NFPA 13.

Q.127 See Phase 1 Drawing FPD101. What is the size of existing mains referenced in Drawing Notes 1 and 2?

The Contractor shall field verify the size and configuration of existing mains and coordinate all work accordingly.

Q.128 Will a Hazmat Report be provided? Some of the existing area has 1 x 1 ceiling tiles with exposed sprinkler pipe below that is to be demo'd. These tiles are likely asbestos.

Any suspected hazardous materials encountered shall be handled in accordance with applicable regulations and the contract provisions. This report was uploaded as part of the original solicitation package on the SAM.gov posting (Attachment J.7: Hazardous Materials Survey Report.)

Q.129 Security - Please provide parts list to include long part number for card readers.

For bidding purposes, provide equipment in accordance with the performance requirements and basis of design identified in the specifications. Final equipment selections shall be submitted for approval during the submittal process.

Q.130 Security - Please provide access control system manufacturer.

The Contractor shall provide a system in accordance with the specified performance requirements. Final manufacturer selection shall be subject to approval during the submittal process.

Q.131 Security - Please provide IT/LAN/Comm Closet locations

The Contractor shall coordinate with the Government to confirm exact locations and access requirements. Field verify all existing conditions.

Q.132 Security - Please provide Access Control and Intrusion Detection Systems panel locations

The Contractor shall coordinate with the Government to determine panel locations and field verify existing conditions to ensure proper installation.

Q.133 Is there a reclamation program in place at the GPO for fluorescent tubes or with the contractor be responsible for the disposal.

The Contractor shall be responsible for proper handling and disposal of fluorescent tubes in accordance with applicable federal and local regulations.

Q.134 Will the entire workspace be available throughout the project or will portions be occupied during the renovation?

The space may be partially occupied. Coordinate phasing and access with the Government.

Q.135 Do the existing to be demolished lighting fixtures contain PCBs?

PCB presence is not identified. Do not assume; handle per regulations if encountered.

Q.136 Are there ACM's present in the workspace?

ACMs are not identified. Do not assume, handle per regulations if encountered.

Q.137 Is lead present any finishes or paint within the jobsite.

Lead is not identified. Do not assume, handle per regulations if encountered.

Q.138 E1601 shows the installation of new breakers in USG-12A. All available spaces are currently filled with existing breakers labeled SPARE. Can these breakers be re-used?

Provide new breakers as specified. Reuse of existing spare breakers is not permitted unless approved after award.

Q.139 Please provide the approved submittal for USG-12A for reference. If this isn't available, please provide a photo of the "Shop Order Number" of the gear which should be located in the top corner of each gear section. If this isn't available, please provide photos of the model number of each SPARE breaker in USG-12A.

The Contractor shall field verify existing equipment and ratings to ensure compatibility with new work. No additional documentation or photos are available at this time.

Q.140 Have arc-flash and coordination studies been conducted for this new work or should the performing contractor account for this in their proposal?

The Contractor shall include arc flash and coordination studies as part of their scope in accordance with applicable codes and specifications.

Q.141 Where will door access controls need to be routed

Final routing will be determined during coordination and submittal review.

Q.142 Where will camera conduits need to be routed

Final routing will be determined during coordination and submittal review.

Q.143 Where will security conduits need to be routed

Final routing will be determined during coordination and submittal review.

Q.144 Specification SECTION 10 56 13 – METAL STORAGE SHELVING, PART 2 – PRODUCTS, Section 2.2 A-2. States, “Load Carrying Capacity per Shelf: 350 lb.” Section 2.2 A- 6. “Solid Type Shelves: Fabricated from steel sheet as follows: a. Steel Sheet Thickness, Nominal: 0.044 inch or greater as required for load carrying capacity per shelf.” (Which equates to a capacity of 650 pounds per shelf). Drawing S100- PLAN NOTES: 4 “Per NARA directive 36 lbs. average box weight used for design load of fixed shelving, 5 boxes per shelf for total = 180 lbs. What is the required load capacity performance criteria for each individual shelf?

The shelving system shall meet the specified minimum load carrying capacity of 350 lbs. per shelf in accordance with the specifications. Provide shelving that meets or exceeds the specified capacity requirements.

Q.145 In the lower LH corner of Storage A it appears there are (3) single-sided units blocking an elevator door. Is this correct?

The conflict is acknowledged. Shelving units shall not obstruct required access, including elevator doors. Coordinate layout.

The contract documents will be clarified by amendment if adjustments to the layout are required.

Q.146 Our pricing is tied to the U.S. Midwest Domestic Hot Rolled Coil Steel Index (CRU). Given the volatility of commodity markets, like steel, and the global economy in general, and given that delivery of part of this project is at least a year off, will an allowance be considered if there is a drastic increase in the price of steel? In other words, would the successful bidder be allowed to modify pricing to current market conditions based on the CRU Index 30 days prior to product shipment?

The Government will consider requests for economic price adjustments due to market volatility.

Q.147 Assuming we only clean the interior facing glass surface?

Provide cleaning as necessary to deliver a complete and finished installation in accordance with the contract documents.

Q.148 Assuming glass cleaning with only standard glass cleaners and standard cleaning methods?

Use manufacturer recommended methods. Standard cleaners are acceptable if no damage occurs.

Q.149 Assuming no existing glass replacement is necessary?

Replace glass as required to provide a complete and acceptable installation.

Q.150 What sealing will be required for the existing windows, glass to sash, sash to sash, frame to perimeter, or like all joints exposed to the interior?

Seal all required joints to achieve a complete weathertight installation per specs.

Q.151 Assuming no exterior window sealing is to be performed?

Provide sealing as required by the contract documents for a complete installation.

Q.152 It is assumed that the plexiglass will not carry a fire rating of any sorts ?

Provide materials in accordance with the contract documents, including fire rating requirements where applicable.

Q.153 The existing windows appear to be double / single hung type. Should the ones where keynote AF 02 is applicable be made inoperable as part of the sealing process?

Where keynote AF02 is applicable, provide sealing as required to meet the design intent.

Q.154 Please advise if the windows shown at the perimeter of the switch gear and mech. Atrium rooms are to receive the 3/8" dark gray plexiglass and prep work associated with Keynote AF 02.

Provide plexiglass only where keynote AF02 is indicated. Verify locations on drawings.

Q.155 Would the Gov't. look at other finish options, since the CRL clips will not be exposed to view?

Provide specified finishes. Substitutions require approval.

Q.156 Please elaborate on F Door Type (Phase 1)

For bidding purposes, provide a door assembly consistent with stair enclosure requirements, including applicable fire rating.

Detailed information will be provided by amendment or during submittal review

Q.157 Please confirm no doors/frames/hardware scope for phase 2

Doors, frames, and hardware work is associated with Phase 1. No doors/frames/hardware scope is identified for Phase 2.

Q.158 Please provide a copy of the Hazmat report. What are we considering to be ACM?

The Contractor shall not assume the presence or absence of ACM and shall handle any suspected materials in accordance with requirements. This report was uploaded as part of the original solicitation package on the SAM.gov posting (*Attachment J.7: Hazardous Materials Survey Report.*)

Q.159 Please provide site visit sign-in sheet.

The site visit sign-in sheet was posted on SAM.gov on 04/01/2026 under Notice ID 040ADV-26-R-0016-C0001

Q.160 Per Volume 4- Key personnel requirements, each position shall be filled by one full-time equivalent (FTE) for the total duration of this project. The key personnel specified are considered to be essential to the work being performed under this contract. Please advise if the QC Lead & SSHO are required to be on-site all times or just during definable feature of work?

QC Lead and SSHO are full-time. On site during active work including definable features.

Q.161 Please consider the acceptance of previously completed PPQs. If the client has already completed PPQs in the past, it becomes burdensome to complete multiple requests. We appreciate your consideration.

See previous response.

Q.162 Looks like majority of the ceiling needs to be accessed. Please confirm if the entire ceiling is going to be abated.

Extent of abatement is not defined as the entire ceiling. Provide abatement only where required by the contract documents and where hazardous materials are identified. This report was uploaded as part of the original solicitation package on the SAM.gov posting (Attachment J.7: Hazardous Materials Survey Report.)