



**DEPARTMENT OF THE AIR FORCE
86TH AIRLIFT WING (USAFE)**

05 March 2026

MEMORANDUM FOR RECORD

FROM: [REDACTED]

SUBJECT: ATF Large Area Maintenance Shelter (LAMS) Electrical Outlets Installation

1. General Description.

The contractor shall provide all labor, materials, equipment, supervision, and transportation necessary to install electrical outlets in the Large Area Maintenance Shelter (LAMS) supporting Air Transportation Function (ATF) cargo operations.

The purpose of this installation is to provide reliable electrical power for mission-essential equipment used in cargo processing operations, including pallet build up equipment, inspection tools, and operational support equipment.

The contractor shall ensure all work complies with the National Electrical Code (NEC/NFPA 70) for U.S. requirements and Verband der Elektrotechnik (VDE) standards for German electrical installations.

2. General Requirement.

2.1. The contractor shall perform all work under their own responsibility and provide qualified personnel capable of performing electrical installation work.

The contractor shall:

- Provide all required tools, equipment, and materials.
- Ensure all electrical installations comply with applicable U.S. electrical standards, German electrical codes, and base civil engineering regulations. This includes the NEC for U.S. requirements and VDE standards for German electrical installations.
- Ensure the work is performed in a safe and professional manner.
- Coordinate work activities with the designated government representative.

2.2. Special Requirements

The electrical outlets will be installed within the two LAMS utilized by the ATF for cargo staging, pallet build up, and equipment operations.

The installed outlets shall support equipment such as:

- Inspection equipment
- Cargo processing equipment
- Maintenance tools

The installation must ensure sufficient electrical capacity to support operational requirements while maintaining compliance with NEC for U.S. requirements and VDE for German requirements.

2.3. Electrical Installation Requirements

The contractor shall provide and install all materials necessary to support the installation of electrical outlets within the LAMS facility. All materials shall meet applicable electrical safety standards and be suitable for outdoor or semi-covered operational environments.

The electrical system shall include the following components:

- Electrical Distribution Components
 - Outer Distribution Panel

Brand: Steidle (or equivalent)

Quantity: 1 unit supporting both LAMS
 - Inner Distribution Panels

Brand: Spelsberg (or equivalent)

Quantity: 1 per tent (2 total)
- Circuit Protection Components
 - Inlets in Inner Distribution – B16A Fuse

Brand: Hager (or equivalent)

Quantity: 6 per tent (12 total)

- Main Fuse Inner Distribution – 63A

Brand: Hager (or equivalent)

Quantity: 1 per tent (2 total)

- Electrical Connection Components

-DIN Rail Terminal Blocks

Brand: Weidmuller (or equivalent)

German reference: Reihenklemme

Quantity: 18 per tent (36 total)

- Electrical Outlets

-Moisture-proof Electrical Outlets – 230V

Brand: Merten Aquastar (or equivalent)

Type: Weather resistant/ moisture protected outlets suitable for outdoor or semi-covered environments.

Quantity: 6 per tent (12 total)

3. Hours of Operation

3.1. Work Schedule

All work shall be performed during normal work hours between 08:00 and 16:00 Monday through Friday. No work shall be performed on German or American holidays.

U.S. Federal Holidays	Date	German Holidays	Date
New Year's Day	Jan 1, 2026	New Year's Day	Jan 1, 2026
MLK Jr Day	Jan 19, 2026	Good Friday	Apr 3, 2026
President's Day	Feb 16, 2026	Easter Monday	Apr 6, 2026
Memorial Day	May 25, 2026	Labour Day	May 1, 2026
Juneteenth	Jun 19, 2026	Ascension Day	May 14, 2026
Independence Day	Jul 3, 2026	Whit Monday	May 25, 2026

Labor Day	Sep 7, 2026	Corpus Christi	Jun 4, 2026
Columbus Day	Oct 12, 2026	German Unity Day	Oct 3, 2026
Veterans Day	Nov 11, 2026	All Saints Day	Nov 1, 2026
Thanksgiving Day	Nov 26, 2026	Christmas Eve	Dec 24, 2026
Christmas	Dec 25, 2026	Christmas Day	Dec 25, 2026
		New Year's Eve	Dec 31, 2026

3.2. Work Location

Large Area Maintenance Shelter adjacent to Building 3452 Ramstein Air Base. The work area is located within controlled and gated operational cargo facility. Contractor access to the site must be coordinated in advance with the ATF designated POC. Personnel and vehicles must comply with all installation access procedures and security requirements.

4. Completion Requirements.

4.1. Upon completion of installation, the contractor shall:

- Verify functionality of all electrical outlets.
- Ensure proper grounding and circuit protection.
- Remove all installation debris and equipment
- Notify the government representative for final inspection.

Work will be considered complete once the installation has been inspected and accepted by the government.

5. Point of Contact

5.1. [REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]

[REDACTED]