

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE 1 OF 7	
2. AMENDMENT/MODIFICATION NUMBER 0003		3. EFFECTIVE DATE 15 Apr 2026		4. REQUISITION/PURCHASE REQUISITION NUMBER See Continuation Sheet		5. PROJECT NUMBER (If applicable) P993/995	
6. ISSUED BY NAVFACSYS COM MID-ATLANTIC 9324 VIRGINIA AVENUE, NORFOLK NORFOLK, VA 23511-0395 UNITED STATES Brittany Cristelli, Email: brittany.n.cristelli.civ@us.navy.mil Telephone: 757-341-1978		CODE N40085		7. ADMINISTERED BY (If other than Item 6) SCD: PAS:		CODE	
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)				(X)		9A. AMENDMENT OF SOLICITATION NUMBER N4008526R0002	
				(X)		9B. DATED (SEE ITEM 11) 06 Mar 2026	
				()		10A. MODIFICATION OF CONTRACT/ORDER NUMBER	
				()		10B. DATED (SEE ITEM 13)	
CODE		FACILITY CODE					

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)
 See Section 00 70 00 - Conditions of the Contract

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)
N4008526R0002; DESIGN-BID-BUILD, P993/995 F35 SUSTAINMENT CENTER & COMPOSITE REPAIR FACILITY, MARINE CORPS AIR STATION, CHERRY POINT, NORTH CAROLINA

The proposal due date of 28 April 2026 remains unchanged.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) BRITTANY N. CRISTELLI	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA 	16C. DATE SIGNED 15 Apr 2026
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Section 00 20 00 - Instructions for Procurements

Miscellaneous text in this section has been added to:

The purpose of this amendment is to incorporate the following:

1. Revised Drawings for P993 (CUI - Not posted to SAM)
2. Revised Drawings for P995 (attached separately)
3. Revised Specifications for P993 (no attachments)
4. Revised Specifications for P995 (attached separately)
5. Additional Pre-Proposal Inquiry (PPI) responses (attached separately)

1. REVISED DRAWINGS FOR P993 (CUI - NOT POSTED TO SAM.GOV)

(P993) DWG C-002 - GENERAL NOTES

General Note 3 revised per Environmental Affairs (Jessica Guilianelli) to show accurate dates when tree clearing may not be performed.

(P993) DWG BB140 - HISTORIC BORING SITE LOCATIONS

Added attached sheet BB140 to show historic boring site location map.

(P993) DWG BB141 - HISTORICAL BORING LOGS

Added attached sheet BB141 to show historical boring logs from April 2020.

(P993) DWG BB142 - HISTORICAL BORING LOGS

Added attached sheet BB142 to show historical boring logs from April 2020.

(P993) DWG BB143 - HISTORICAL BORING LOGS

Added attached sheet BB143 to show historical boring logs from April 2020.

(P993) DWG CG107B - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2 - PARKING LOT & P995

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG107C - EROSION AND SEDIMENT CONTROL PLAN - PHASE 3

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG117B - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2 - P993 SITE & APRON

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG117C - EROSION AND SEDIMENT CONTROL PLAN - PHASE 3

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG123C - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2 & 3

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)." Sentence added to end of callout "with use of an erosion control blanket or placement of sod".

(P993) DWG CG128B - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG128C - EROSION AND SEDIMENT CONTROL PLAN - PHASE 3

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)."

(P993) DWG CG144B - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2 - TAXIWAY

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)." Sentence added to end of callout "with use of an erosion control blanket or placement of sod".

(P993) DWG CG144C - EROSION AND SEDIMENT CONTROL PLAN - PHASE 2 & 3

Keynote 18 added - "Rip rap outlet, see detail A4/C-508 (note: adjust configuration per field conditions)." Sentence added to end of callout "with use of an erosion control blanket or placement of sod".

(P993) DWG CG603 - STORM DRAIN STRUCTURE DATA TABLES

Edit made to Drainage Structure Table: C-STRM - Str. No. SU12 Type revised to "SUMH W/ BWT COVER".

(P993) DWG C-508 - DETAILS

Note added to indicate that Structure SU12 requires a bolted watertight ring and cover.

(P993) DWG C-509 - DETAILS

Revised pavement details per ProjNet comments from Ariana White (AECOM).

(P993) DWG C-510 - DETAILS

Revised Roadway Concrete Pavement section per ProjNet comments from Ariana White (AECOM).

(P993) DWG C-511 - DETAILS

Added C2 "Joint and Sealants" to this sheet.

(P993) DWG CT301 - AIRFIELD TYPICAL SECTIONS

Revised subbase materials for 18" select material subbase.

(P993) DWG CT302 - AIRFIELD TYPICAL SECTIONS

Revised subbase materials for 18" select material subbase.

(P993) DWG CU126 - UTILITY PLAN

Changed C-Fire-08 from 6" DIP to 12" DIP. This is the fire main connecting the 12" fire water loop to the Building P-993 fire riser room.

(P993) DWG CU202 - GRAVITY SEWER PROFILES

Changed fire water crossing at Sta. 18+19 from 6" DIP to 12" DIP.

(P993) DWG CU243 - FIRE WATER PROFILES

Changed C-Fire-08 Profile View from 6" DIP to 12" DIP.

(P993) DWG CU262 - ELECTRICAL PROFILES

Changed fire water crossing at Sta. 10+33 from 6" DIP to 12" DIP.

(P993) DWG CU640 - FIRE WATER DATA TABLES

Changed Fire Water Fitting F25 from 12" X 6" TEE to 12" X 12" TEE.

Changed Fire Water Valve F229 from 6" GATE VALVE to 12" GATE VALVE.

(P993) DWG SS102 - BRIDGE FOUNDATION LAYOUT

Added a bridge pile summary table to the sheet.

(P993) DWG SS128 - NORTH MSE WALL

Added a callout regarding the anticipated presence of unsatisfactory material beneath the MSE wall leveling pad.

(P993) DWG SS129 - SOUTH MSE WALL

Added a callout regarding the anticipated presence of unsatisfactory material beneath the MSE wall leveling pad.

(P993) DWG SS130 - BRIDGE WALL DETAILS

Added a callout and note regarding the anticipated presence of unsatisfactory material beneath the MSE wall leveling pad.

(P993) DWG A-140 - SECOND FLOOR PLAN - SUPPORT

Added RF shielding partition to interior of Secure Lobby 206.

(P993) DWG A-425 - SECOND FLOOR PLAN - SECURE BOUNDARY

Added RF shielding boundary to Secure Lobby 206. Fire alarm and electrical penetrations have shifted to south wall of ALIS Admin 210.

(P993) DWG E-001 - ELECTRICAL SYMBOLS, LEGEND, ABBREVIATIONS, AND NOTES

Added Electrostatic Dissipative Symbol (ESD) to the legend.

(P993) DWG E-107 - FIRST FLOOR HAZARDOUS AREA PLAN - BASE BID

Classified Storage 136 hatched for hazardous location.

(P993) DWG E-108 - FIRST FLOOR HAZARDOUS AREA PLAN - WITH BID OPTIONS

Classified Storage 136 hatched for hazardous location.

(P993) DWG EG105 - FIRST FLOOR GROUNDING PLAN - BAY AREA 1A

Keynote 10 abbreviation has been revised to "ESD".

(P993) DWG EG107 - FIRST FLOOR GROUNDING PLAN - BAY AREA 1C

Keynote 10 abbreviation has been revised to "ESD".

(P993) DWG EG108 - FIRST FLOOR GROUNDING PLAN - BAY AREA 1D

Keynote 10 abbreviation has been revised to "ESD".

(P993) DWG EG113 - FIRST FLOOR GROUNDING PLAN - SUPPORT AREA A

Keynotes 11, 12, 13, and 14 abbreviations have been revised to "ESD".

(P993) DWG EG115 - FIRST FLOOR GROUNDING PLAN - SUPPORT AREA C

Keynote 5 abbreviation has been revised to "ESD".

(P993) DWG EG121 - FIRST FLOOR GROUNDING PLAN - BAY AREA 2E

Keynote 10 abbreviation has been revised to "ESD".

(P993) DWG EG124 - FIRST FLOOR GROUNDING PLAN - BAY AREA 2H

Keynote 10 abbreviation has been revised to "ESD".

(P993) DWG EG129 - SECOND FLOOR GROUNDING PLAN - SUPPORT

Keynotes 6 and 7 abbreviations have been revised to "ESD".

(P993) DWG EL501 - LIGHTING DIAGRAMS AND DETAILS

Revised Detail A2 - Pendant Luminaire Mounting Details

(P993) DWG EP117 - FIRST FLOOR POWER PLAN - SUPPORT AREA C

Duplex receptacles for A/V have been relocated in office rooms 120 and 121.

(P993) DWG EP401 - ENLARGED ELECTRICAL ROOM PLANS

Switchboard A, Switchboard B, ATS-D1 and AEH-DP1 were moved to the south on the wall to make room for clearances. AEH-D1 was moved to the plan north on the same wall.

(P993) DWG TT100 - TELECOMMUNICATIONS - SITE PLAN- OVERALL

Revised and added back in the Lift Station conduit pathway and fiber connection.

Revised keynote #13 to change the size to 6-strand SM fiber.

(P993) DWG TT101 - TELECOMMUNICATIONS - SITE PLAN - OVERALL - BID OPTION PAINT BOOTH AREA C

Revised and added back in the Lift Station conduit pathway and fiber connection.

Revised keynote #13 to change the size to 6-strand SM fiber.

(P993) DWG TT130 - SECOND FLOOR TELECOMMUNICATIONS PLAN - SUPPORT AREA C/D

All the clouded rooms as indicated on the drawings have been revised to provide a Data Outlet, Junction Box, and the revised correct height.

(P993) DWG TT601 - TELECOMMUNICATIONS RISER DIAGRAMS

Revised the riser diagram to reflect the final number of Sunshades.

Revised keynote #5 reflects the number fiber cables to match the Sunshade final count.

(P993) DWG TA105 - SECOND FLOOR AV PLAN - OVERALL

Callouts have been updated for second floor offices alternate A/V plan.

(P993) DWG TA 407 - AUDIO VISUAL EQUIPMENT PLAN - TYPICAL OFFICE

Office - Second Floor Alternate A/V Plan added to sheet.

2. REVISED DRAWINGS FOR P995: (ATTACHED SEPARATELY)

(P995) DWG A-116 - ROOF PLAN

Replace sheet

(P995) DWG A-407 - ENLARGED PLAN AND SECTIONS - WALK-IN FREEZER

Replace Sheet

(P995) DWG A-111 - REFLECTED CEILING PLAN - AREA C

Correct reference Keynote #2 to reference Keynote #1

(P995) DWG S-202 - FRAMING PLAN - AREA A

Please replace "CB12" with "CB2" on column line 6 on Drawing S-202

(P995) DWG C-501 - SITE DETAILS

Revise keynote #4 to reference detail D1/C-501.

(P995) DWG CG-102 - PARTIAL SITE PLAN - AREA 2

disregard spot elevations 27.61' and 27.12'

(P995) DWG CU-101 - PARTIAL UTILITY PLAN - AREA 3 & 4

Revise Keynote #2 to read "Remove existing 2" blowoff, 2" gate valve, and MJ plug and connect to P-993 water stub with 6" x 2 1/2" MJ reducer."
Disregard keynote 15.

Revise Keynote #6 to read "6" DIP to remote FDC, C1/C-51

3. REVISED P993 SPECIFICATIONS: (NO ATTACHMENTS PROVIDED)

(P993) SECTION 28 08 10 ELECTRONIC SECURITY SYSTEM ACCEPTANCE TESTING

Remove specification in its entirety. Future amendment to be provided with updated hardware schedules

(P993) SECTION 28 10 05 ELECTRONIC SECURITY SYSTEMS ESS

Remove specification in its entirety. Future amendment to be provided with updated hardware schedules

(P993) SECTION 31 62 13.20 PRECAST PRESTRESSED CONCRETE PILES

Revised specification to require signed and sealed pile design calculations except for those piles supporting the taxiway bridge.

4. REVISED P995 SPECIFICATIONS: (ATTACHED SEPARATELY)

(P995) SECTION 08 11 16 ALUMINUM DOORS AND FRAMES

Replace Section, Change made to 3.7 Hardware Schedule to clarify Electronic Safety and Security requirements for doors. Change was made to HWS-1

(P995) SECTION 08 33 23 STEEL OVERHEAD COILING DOORS

Replace Section, Change made to 3.3 Hardware Sets to clarify Electronic Safety and Security requirements for doors. Change was made to HWS-3

(P995) SECTION 08 33 23 DOOR HARDWARE

Replace Section, Change made to 3.6 Hardware Schedule to clarify Electronic Safety and Security requirements for doors. Changes were made to HWS-6, HWS-9, HWS-10, HWS-12 and sets HWS-6A, HWS-10A, HWS-12A were added.

(P995) SECTION 41 22 13.15 BRIDGE CRANES, OVERHEAD ELECTRIC, UNDER RUNNING TROLLEY

Change the 1st sentence in paragraph 1.3.1.3 to read "Provide under running single girder electric bridge crane(s), with under running trolley mounted hoist, conforming to MHI MH27.1, CMAA 70, and CMAA 74 service class C, as applicable."

(P995) SECTION 42 15 00 INDUSTRIAL OVENS

Change paragraph 2.1.1 to read "Composite curing autoclaves have a minimum operating temperature of 800 F and pressure of 200 PSI. Equipment is constructed of carbon steel and stainless steel. Equip with vacuum systems to remove air and moisture from composite parts during curing. Provide heating and cooling systems to control ramp rates and maintain steady state temperatures. Autoclaves heat at a rate of 4 F per minute. Autoclaves cool at a minimum rate of 2 F per minute and a maximum rate of 8 F per minute. Equipment has a soak tolerance of 10 F. Provide thermocouple ports and vacuum ports. Vacuum ports are capable of automatically controlling vacuum level and venting based on a specified schedule. Controls follow set run schedules for ramp, soak and cooling operations at specified temperatures and temperature rates. Controls follow set pressure schedules and achieve pressurization and depressurization rates of 4 PSI minimum or higher. Cooling systems are active. Standalone vacuum pump and receiver are integrated with the control system. Furnish interior lighting."

(P995) SECTION 42 15 00 INDUSTRIAL OVENS

Change paragraph 2.1.2 to read "Composite curing ovens have a maximum operating temperature of 500 F, normal temperature of 350 F and minimum 75 F above ambient temperatures. Temperatures are uniform 10 F at 250 F and 350 F. Oven bodies are heavy tongue and groove panels with 0.036 inch, 20 gauge, painted carbon steel exterior skin and 0.036 inch, 20 gauge aluminized steel interior skin and ducts. Chamber wall composites incorporate industrial board insulation. Roofs, doors and base trim are 0.105 inch, 12 gauge steel. Vertical lift doors have viewing windows. Oven bodies attach to concrete slabs and have insulated floor panels. The heat rate is adjustable within the range of 0.1 to 5 F per minute. The cooling rate is 3 to 4 F per minute. Equipment has a soak tolerance of 10 F. Provide thermocouple ports and vacuum ports. Controls follow set run schedules for heating, soak and cooling operations at specified temperatures and temperature rates. Equipment features recipe control, manual control, data acquisition, reporting and post run data analysis functions. Cooling systems are active. Furnish interior lighting. A multi port vacuum manifold is located on each side of the oven, with each port fitted with a quarter turn isolating ball valve. A jack panel with multiple thermocouples is located on each side of the oven interior chamber."

(P995) SECTION 45 52 00 AEROSPACE X-RAY TESTING EQUIPMENT

Replace section. Numerous changes made for clarification to address multiple PPI's.

(P995) Section 41 22 13.15 BRIDGE CRANES, OVERHEAD ELECTRIC, UNDER RUNNING TROLLEY

Change the 1st sentence in paragraph 1.3.1.3 to read "Provide under running single girder electric bridge crane(s), with under running trolley mounted hoist, conforming to MHI MH27.1, CMAA 70, and CMAA 74 service class C, as applicable."

(P995) SECTION 42 15 00 INDUSTRIAL OVENS

Paragraph 3.8 Industrial Oven Schedule for AC-1, AC-2 and AC-3 in # 13 and #14 of each schedule delete the word "maximum" and replace with "minimum".

(P995) SECTION 25 08 11.02 20 RISK MANAGEMENT FRAMEWORK FOR HVAC/DDC FACILITY-RELATED CONTROL SYSTEM

Remove spec section in its entirety and any submittal requirements pertaining to this section from the P995 Submittal Register.

(P995) SECTION 26 29 23 ADJUSTABLE SPEED DRIVE (ASD) SYSTEMS UNDER 600 VOLTS

Delete paragraph 1.8.1 Spare Parts from the spec.

(P995) SECTION 22 00 00 PLUMBING, GENERAL PURPOSE

Delete paragraph 2.4.10 Precast Terrazzo Shower Floors from the spec.

5. PRE-PROPOSAL INQUIRY RESPONSES (ATTACHED SEPARATELY)

Section 00 73 00 - Supplementary Conditions

The following attachments were added:

Amendment 0003 Pre-Proposal Inquiries