

**STATEMENT OF WORK
VLSB 26-0076
B1130 REPAIR HVAC**

09 March 2026

SCOPE OF WORK:

This project is to make repairs to the existing heating, ventilation, air conditioning (HVAC) system in building 1130 annex. A retro commissioning by a third party was performed which revealed many issues with the system. The government has resolved many of the issues, but several critical items remain. This project will correct those outstanding items.

OCCUPANCY and ESCORT Notes:

1. All bathrooms will remain open and accessible to the users during construction.
2. Work will be conducted in one space at a time only to provide the least disruption to operations.
3. All other offices will remain occupied during the construction and power/network will remain functional.
4. The contractor will cover surfaces, equipment and office furniture when conducting work above the ceiling grid; all covering will be removed before departing the facility at the end of the day.
5. The contractor will clean the work area before departing the facility at the end of the day.
6. This project shall be completed by the specified calendar days in the RFP.
7. Escorts will be provided by the government when working in B1130.
8. Work hours – shall be 0700-1700 M-F. After hours work may be accomplished with schedule approved by government.
9. A Proposed Schedule for this project shall be submitted with the proposal to exhibit their understanding of the project schedule.

CLIN 01:

The contractor shall perform the following actions:

- Provide shop drawings of the HVAC system showing all equipment and material that will be installed and upgraded. The drawings shall be submitted to the government and approved by the government before any material is ordered.
- Replace all temperature, pressure, humidity, and air monitoring sensors on both air handlers.
- Replace the supply air fan bearing on air handler unit (AHU) 2.
- Replace the Belimo control valve controlling the air damper on computer room air conditioner (CRAC) 1.

- Disassemble ceiling grid where necessary to perform any above ceiling work. The ceiling tiles and grid assembly shall be reused so it shall not be discarded or damaged. Any damaged ceiling material damaged will be the contractors responsibility to replace.
- Replace all flex duct that supplies all variable air volume (VAV) boxes from the main branch supplies. Approximately 8 feet of flex duct shall be replaced at each VAV box in the annex on both floors. The flex duct shall be replaced with hard duct. The new ductwork shall be insulated according to industry standards.
- Replace both energy recovery ventilators (ERV) with dedicated outdoor air systems (DOAS) that are equipped with DX cooling coils and electric heating coils. DOAS-1, which supports AHU-1, shall have a minimum cooling capacity of 353MBH. DOAS-2, which supports AHU-2, shall have a minimum cooling capacity of 420MBH.
- Replace the 17 VAV boxes that are undersized by 10% or more as shown in Table 2 of the commissioning report (percentages greater than 100% are undersized). This will be VAV 1-03, 1-06, 1-08, 1-09, 1-10, 1-11, 1-12, 1-13, 1-14, 1-15, 1-19, 2-03, 2-04, 2-06, 2-09, 2-13, and 2-18. The new VAVs shall be sized based on the simulated airflow data from Table 2. The new VAVs shall include hot water reheat coils if it is replacing a VAV with hot water reheat coils.
- Install new isolation valves on the supply and return lines of all VAVs with hot water reheat.
- It is the contractor's responsibility to determine if the ductwork to and from these VAVs needs to be enlarged to accommodate the increased air flow. This includes any additional supplies and returns that are needed to support the new VAVs. Any enlarged ductwork shall be shown on the shop drawings.
- It is the contractor's responsibility to determine if the electrical infrastructure needs to be upgraded to support any of the new pieces of equipment. Any required electrical upgrades shall be shown in the shop drawings.
- All ceiling grid and tiles shall be reinstalled to original condition.
- Integrate any new equipment into the current building automation system.
- Perform a test and balance (based on UFGS 23 05 93) of the entire HVAC system. The system shall be balanced to meet the simulated air flow data of Table 2 from the commissioning report.

GENERAL REQUIREMENTS

ESCORTS:

The Contractor shall be responsible for the Coordination of escorts with the Govt.

1. A weekly request, listing the number of escorts and the time period they will be needed will be provided to the Govt, by 1500 Thursday of the week prior to the requirement.
2. The Govt shall not be liable for any delays caused by lack of communication and confirmation from the contractor regarding escorts.
3. The contractor shall discuss planned movement routes throughout the facility during each phase with the Govt for approval.

4. Standard hours of operation are 0730 – 1630 M-F, holidays and down-days as indicated by AFCENT and will be followed by the contractor.
5. If required a contractor may request additional hours or days as needed, however they are subject to denial if the government is unable to support.

EGRESS:

The Contractor shall be responsible for the generation of appropriate life safety plans and signage.

1. The Contractor shall generate updated Egress plans that reflect the new building design.
2. The Contractor shall install appropriate emergency exit signage to align with the updated egress plans.
3. The Contractor shall post the emergency exit guidance maps as required.

PHASING:

1. The building will remain occupied during all phases of work.
2. Temporary cooling is required for any outages.
3. The contractor will adhere to the phasing indicated in the attached document, Attachment 7 Phasing, any changes must be approved by the Govt.
4. Rough phasing description:
 - Phase 1:
 - A. Preform HVAC 2nd Floor
 - Phase 2:
 - B. Preform HVAC 1st Floor.
5. Phase 1 & 2 subcomponents may occur in any order required except for rooms 227-229, which must be completed entirely. However, if possible, with no effect to cost or timeline the Govt would prefer they occur in the order as indicated above.

CONSTRUCTION SCHEDULE:

1. Contract duration is 210 calendar days.
 - a. Mobilization – 15 calendar days
 - b. Construction – 150 calendar days
 - c. Close-out Documents – 45 calendar days

DESIGN:

No design is required. Shop drawings of any new material and equipment that is installed shall be provided.

NOTES:

Contract performance for shall start after the issuance of a NTP.

All material must be submitted to the government and approved by the government before it is ordered by the contractor.

Construction is not to begin until all long lead material is on site.

Any references to State Government, Federal Government, or Industry standards or specifications made herein shall form a part of this specification to the extent referenced thereto and all materials and workmanship under this contract shall comply with or exceed these standards and references. All referenced standards shall be the latest edition.

All manufactured equipment and products shall be new materials in good condition and installed as per manufacturer's latest printed instructions, unless specified otherwise herein.

The user is responsible for moving any government or personal property that may interfere with construction. If property cannot be moved (desks, tables, workbenches, etc.) it shall be protected by the user.

The Contractor shall pay particular attention to the government non-movable equipment/furniture and work around it. The contractor will be held accountable for any damage that occurs during construction.

The user is responsible for providing an escort if required at any point during construction.

Contractor shall take into account the special treatment of hazardous waste, as well as the environmental implications related to building demolition management (i.e. fluorescent lighting tubes, t-stats, etc.). Every effort shall be made to recycle eligible materials, and those not suitable, shall be disposed of off base in accordance with all (SCDHEC) South Carolina Department of Health and Environmental Control regulations.

Contractor superintendent cannot be quality controller (CQC) and safety (SSHO) at the same time. Meanwhile, contractor superintendent can be the SSHO. This project requires a full-time contractor superintendent and as needed CQC/SSHO.

Any refrigerant amounts removed or installed shall be documented and the information shall be provided to Shaw AFB.

If any submittal does not, in the opinion of the Contracting Officer, meet or exceed the requirements contained within this SOW, in the Shaw AFB Design Standards or in any referenced design guidance or nationally recognized code then it shall be considered to be unacceptable and returned to the Contract for correction and resubmission.

Ensure that any demolition, utility cut and capping, and debris removal service performed at Shaw AFB, South Carolina is completed in such a manner that will restore a neat and professional appearance of base areas.

The facility/area shall be cleaned in its entirety, including exterior areas, before being returned to the government.

FIRE PROTECTION:

The Contractor shall ensure that any area in the Facility which was modified meets all applicable Fire Codes. The Contractor shall ensure that all spaces are correctly sprinkled, to include redesign and replacement of sprinkler heads, fire mains, and mass notification systems as required.

FINAL ACCEPTANCE:

Once all construction work is done, a final walk through will be completed prior to acceptance. During this walk through any seen issues will be presented for rectification by the contractor. Once the contractor has completed them, a follow-up walk through will be completed. Any changes requested due to an error by the contractor shall be the financial responsibility of the contractor.

WARRANTY:

Contractor shall furnish a minimum one-year warranty against defects in material and workmanship starting on the beneficial occupancy date.

GENERAL INFORMATION:

The contractor shall provide all management, tools, supplies, equipment, labor, and applicable licenses and permits necessary to complete the requirements within. All work and designs shall be done in accordance with this Statement of Work and follow all specifications identified within; (UFC) Unified Facilities Criteria, Unified Facilities Guide Specifications (UFGS), the International Building Code (IBC), International plumbing code (IPC), South Carolina Department of Health and Environmental Control (SCDHEC), National Electrical Code (NEC), National Electrical Safety Code (NESC), National Fire Protection Association (NFPA), EPA 402-K-01-001 (2008), South Carolina Department of Transportation (SCDOT), South Carolina Department of Health and Environmental Control (SCDHEC) Shaw Air Force Base Design and Construction Standards, Change 2, 21 Aug 2018 and all other applicable codes. Contractor shall maintain and ensure ADA compliance within all areas being renovated and will indicate in the 65%, and 95% design drawings what the minimum standard for compliance is.

Contractor shall verify all dimensions, quantities and square footages. All dimensions, quantities and square footages included are approximations. Construction and demolition shall be in strict accordance with the Shaw Air Force Base Design and

Construction Standards. The information provided in this Statement of Work (SOW), the provided drawings, and the requirements of the Shaw Air Force Base Design and Construction Standards shall be determined to be the minimum standards required in this project.

The contractor shall video all areas in which work shall occur prior to starting work to include interior and exterior of the project site. UFC's take precedence over all standards, codes and Shaw AFB Design Standards and requirements that pertain to the work within this SOW.

During construction, the Contractor shall take care not to damage existing structures, etc. that will not be replaced as part of this contract. The Contractor shall be responsible for the repair of any damage caused by the Contractor to the facility or equipment during this project. Contractor shall be responsible for the temporary support of all devices as required to perform work. Any demolition work that needs to be accomplished to complete the contract is the responsibility of the contractor. All material shall be installed per manufacturers' recommendations. All items listed in the SOW are to be supplied and installed by the contractor unless otherwise noted. The contractor shall be responsible for removing and reinstalling or relocating any obstructions, utilities, or components that will impede the work to be accomplished in this SOW.

A pre-construction meeting will be held at Shaw AFB to include the Contractor and Government representatives. The Government shall set up this meeting, to be held on Shaw AFB, with the Contractor and Government representatives, to discuss all remodel requirements, as well as any other construction issues the Contractor may have. All finishes shall be presented to the project inspector as **one** submittal for selection and approval prior to installation. All material that could be discontinued shall be on-site, i.e. carpet and tile prior to starting project so there will be no difference in color.

Contractor shall use an approved hauling route to prevent interference with base operations. In order to prevent problems with traffic, noise, wear and tear on roads, or other problems having the potential to adversely affect health, safety, or the environment, the government reserves the right to regulate routes, intervals, delivery points, and times for hauling.

All debris hauled by the contractor shall be enclosed to prevent leaking, spilling, or blowing. The Contractor shall ensure all debris or dirt is promptly removed from any transportation route if such debris is spilled, blown, or leaked from hauling equipment and vehicles. The contractor shall remove all dirt and mud caused by tracks of hauling equipment within one hour of notification by the Government. All demolition debris collected by the contractor shall be housed dumpsters and covered at all times and disposed of in an authorized landfill or transfer station. No disposal or burning is allowed on base. The contractor shall provide the government inspector with an electronic copy of each dump receipt on the following workday by 0800 with the daily report.

PERMITS:

The contractor shall pay for and obtain any required permits. The contractor shall act in accordance with this Statement of Work, SCDHEC, Federal, and Shaw AFB guidelines.

The contractor must comply with environmental provisions.

ASBESTOS/LEAD BASED PAINT:

With the building being constructed in 2014 it is assumed there are no asbestos containing materials. Asbestos testing is not required.

WORKING CONDITIONS:

The Contractor shall take all precautions to ensure that his operations are conducted in a manner as to minimally interfere with the normal operations of the base and the safety and convenience of the base personnel. The contractor shall coordinate utility outages with the Civil Engineering Squadron (CE) service call and the user.

DAILY REPORTS:

The contractor shall provide the government with an electronic copy of each dump receipt along with the daily report by 0800 the following workday. All daily reports will be submitted in RAKEN format and shall include pictures of work performed for each day. Daily reports shall be submitted in .pdf with report number and date for the file name (ex. 001 June 02, 2023).

END OF STATEMENT OF WORK