

1. PRE-PROPOSAL INQUIRY RESPONSES:

Question #	Reference			Question	Government Response
	Page	Section	Paragraph		
151	Solicitation Page 13 of 50			The RFP for the P-993 F-35 Sustainment Center requires all contractors performing work on the project to hold CMMC Level 2 (Self). Currently, the vast majority of local and regional subcontractors, equipment suppliers, vendors and service providers – particularly those that qualify as SB - do not possess this certification, and estimates indicate it will take most companies 6–18 months to obtain it, with costs ranging from tens of thousands to hundreds of thousands of dollars per vendor. This requirement is especially burdensome on the local small-business community, many of whom do not have the resources necessary to pursue certification. As a result, the mandate is severely hindering the project’s ability to meet the Government’s 40% small-business participation target. Can the Government reduce the small-business participation target for this Opportunity from 40% to 20%?	PENDING RESPONSE
153				The documents provided do not appear to have analytical data for the water and soil conditions at either the P-995 or P-993 sites in terms of contamination. Is their analytical data that shows the actual constituents of concern and their concentration levels? type of contamination concentrations will affect what landfills the material can be disposed of and impact the analytical tests that will need to be performed.	PENDING RESPONSE
155	Solicitation , pages 11 and 15			On page 15 of the solicitation it states “ <i>The minimum required small business participation (i.e. work to be performed by small business as the prime contractor and/or work to be performed by small business subcontractors) is 20%. Offerors who are not able to meet the minimum total small business participation requirement of 20% (of the total contract value) shall provide a</i>	PENDING RESPONSE

				<i>detailed explanation why the minimum total small business participation requirement cannot be achieved.</i> The current CMMC Level 2 requirements for all subcontractor involvement create a barrier for the majority of local small businesses, as they have not previously encountered this requirement and do not have this certification. To obtain CMMC Level 2 certification takes approximately 8 months minimum and can be cost-prohibitive for many local small businesses, thereby eliminating them from consideration for subcontracting opportunities on this contract. On page 11 of the solicitation the anticipated magnitude of construction for this project is identified as “<i>over \$500,000,000</i>”. Considering that the majority of the scope of work is dedicated to P-993, which requires the CMMC Level 2 certification, the P-995 facility, which does not require the CMMC Level 2 certification, would need to carry the small business participation. The P-995 facility is significantly smaller in dollar value and will not be able to carry the small business participation requirement to allow Prime contractors to meet the 20% goal. Please revise the small business target goal to a more realistic 10%.	
156	Solicitation , page 51			On page 51 of the solicitation, paragraph (d) CMMC unique identifiers, states "The Offeror shall provide, in the proposal, the CMMC unique identifier(s) (CMMC UIDs) issued by SPRS for each contractor information system that will process, store, or transmit FCI or CUI during performance of a contract, task order, or delivery order resulting from this solicitation." However, there are no instructions in the submission requirements for where to include this information. Please confirm where this information is to be provided - in our Price Proposal Volume or Non-Price Proposal volume?	PENDING RESPONSE
157				P-995 does not have division 1 specifications. The understanding is that the P-993 Specifications will be used for both P-993 and P-995. Currently only contractors who have	PENDING RESPONSE

				CMMC level 2 may have access to the division 1 specifications. Please release a version of the P-993 specifications that can be provided to our subcontractors and suppliers who will not have CMMC level 2.	
160				Will the Compiled Geotechnical Report be provided to contractors? This is required to help delegated designs like the Water Tower Foundation.	Geotech report in its entirety will not be provided. Bid per boring information provided.
161	P-993	CU700, CU701, and C-524		Drawing CU700 includes a callout for detail C2/C-524 for the bypass connection. This detail C2 does not agree with the section view of the bypass connection shown on drawing CU701; the detail is for a below-grade connection, while CU701 shows an above-grade connection. Please confirm if the bypass connection will be installed below-grade per C2/C-524 or if an above-grade connection will be required.	Bypass connection is to be below grade per Detail C2/C-524. Sheet CU701 to be amended.
162	P-993	CG drawings and 33 40 00		The Specs for P993 (33 40 00 / 2.1.1.1) call out RCP pipe to be Class III and Class V. The Grading & Drainage plan sheets have Keynote #1 (RCP Culvert, Class V) pointing to certain RCP runs. The Grading & Drainage profiles specify Class V for pipes larger than 48", as well as the 15" crossing at the taxiway. The Storm Drain Pipe Schedule shows Class V for RCP pipes larger than 42". Keynote 1 is not identifying all pipes larger than 42" to be class V. Please confirm the pipe schedule will take precedence if the pipe class is not identified in the plan drawings. Please consider revising the plan drawings to align with the RCP pipe schedule.	The following runs of storm water pipe shall be Class V RCP: • 15" pipe connecting storm structure 74 to 75 • 15" pipe connecting storm structure 72 to 73 • 15" pipe connecting storm structure 96 to 97 • 15" pipe connecting storm structure 97 to 98 • 15" pipe connecting storm structure 98 to 99 • 15" pipe connecting storm structure 98 to 99 • 42" pipe connecting storm structure 23 to 23a • 42" pipe connecting storm structure 28 to 30 • 42" pipe connecting storm structure 23 to 23a • 42" pipe connecting storm structure 30 to 31 • 42" pipe connecting storm structure 31 to 32 • All 48" pipe • All 43" H x 68" W elliptical pipe Please note that Construction Keynote 1 will be re-written to say "RCP CULVERT, CLASS V WHERE NOTED ON

					PLAN.” The keynote in the plan view will be directed to culvert pipes.
163				Throughout the utility plan, keynotes, profiles, and schedules, stub-out/service sizes and their fittings do not correlate. Could we receive the correct sizes we should carry, or should we assume that, where discrepancies exist, the plan sheet keynotes take precedence? some examples: The water service going to the yard hydrate for both the Pump Station & the Telecom Node BLDG the profiles are showing 2" service line on Sheet CU232 and the telecom node BLDG Keynote on sheet CU115 is calling it 3/4" and the pump station CU700 is pointing out for a 3/4" RPZ indicating this could be a 3/4" Service line as well. W31 & W32 on the Schedule is calling for a 6" x 2" Service Saddle as well. please confirm if 2" service line or 3/4" service line. Is the Tapped Plug for where the 12" DIP Fire Main terminates 12"x2" with 2" Blowoff as shown on the profiles CU240 & CU 242 or 12"x4" with 4" Blowoff as shown in keynote 14 on sheet CU 116 & Keynote 4 on sheet CU 117?	Plans to be reviewed and corrected via addendum. Plan sheet keynotes can be assumed to take precedence. Water service for yard hydrants is 2". Blow-offs for 8" or less pipes are 2". Blow-offs for 10" or greater pipes are 4". Yes approximate quantities for fire and domestic water mains can be provided.
164				For CLINS 0001C & 0002C it is calling out to replace the undercut material with Imported Structural Fill or NCDOT #57 crushed Stone. NCDOT #57 crushed stone & Imported Structural Fill are two different materials with different commodity pricing. #57 Crushed stone make me assume it will be for an undercut of a utility trench and Imported structural fill makes me assume it would be for undercut for (pavement or building pad) subgrade which as well would be two separate prices. Please confirm which material contractors should assume for pricing purposes or provide separate CLINS for the different materials.	PENDING RESPONSE
165		01 91 00.15 & 01 91 00.15 22		Specification sections 01 91 00.15 Building Commissioning and 01 91 00.15 22 Total Building commissioning appear to contradict. The Total Building Commissioning states, "the Government has hired an	Confirmed. Government will hire independent commissioning firm

				Independent Commissioning Firm". please confirm what commissioning scopes that the Governments independent commissioning firm will perform and what scopes contractors will be required to perform.	
166		01 91 00.15 22	1.9.1	Paragraph 1.9.1 of specification 01 91 00.15 22 states, Commissioning Services must be provided for only the F-35 Aircraft Sustainment Center Hangar and COMMUNICATIONS NODE BUILDING, PV ARRAY, and the PUMP STATION Generator. Please confirm if this will be performed by the Governments independent Commissioning team. Are contractors required to perform commissioning on the P-995 Composite Repair Facility?	See response to PPI #165.
167		01 91 00.15	1.9.1.2	Section 01 91 00.15 paragraph 1.9.1.2 Commissioning Specialists. Should the Mechanical and Electrical Commissioning Specialists be employees of the Prime or subcontractor and under the direction of the CxC?	See response to PPI #165.
168		01 91 00.15	1.9.1.2	Section 01 91 00.15 paragraph 1.9.1.2 Commissioning Specialists. Can the Mechanical Commissioning Specialist have similar qualification requirements as the Electrical Commissioning Specialist? As it is written, the mechanical subcontractor may not be able to be certified by the agencies due to these agencies 3rd party restrictions on membership and certification (they cannot be equipment manufacturers, installers, or contractors to achieve these agency certifications). Can the Mechanical Commissioning Specialist qualifications be stated: "The technical work associated with mechanical systems to be commissioned must be performed by an engineering technician with five years of experience inspecting, testing, and calibrating mechanical and plumbing equipment, systems, and devices."?	See response to PPI #165.
169		23 08 00		Is the specification 23 08 00 intended for the GC/mechanical contractors' role and participation in the commissioning process and not the CxC?	GC, MC, and CxC will all need to participate in the commissioning process. Coordinate with commissioning authority.

170	P-993	CU700 & CU701		Please provide additional information regarding pump requirements for the new sanitary sewer lift station shown on drawing CU700 and CU701, including: a. Total Dynamic Head (TDH) b. Power requirements (spec lists 408V – please confirm) c. Type of pump (specs list several different types of pumps)	a. Flow - 380 gpm, TDH - 42 ft b. Power - 3 Ph, 460 V, 7.5 HP. Note that in future buildout 30 HP motors will be needed. C. Submersible Sewage Grinder Nonclog Pumps per Specification 33 32 16 Part 2.2. Xylem Flygt NP 3127 HT 3~ Adaptive 489 is basis of design.
171	P-993			Please confirm which gate should be utilized for delivery for abnormally long materials like the 85' Piles.	PENDING RESPONSE
175	MP102 thru MP107			Please provide mechanical pipe drawings showing the natural gas pipe layout.	Natural gas piping is shown on the plumbing sheets to align with natural gas piping being in division 22 specifications.
176	P-116, P-119, P-121, P-405, P-503, P-504			Is testing by a gas testing agency required for the Breathing Air pipe systems?	Breathing air systems shall be installed per specifications. No additional testing by the contractor for compliance is required.
177	P-118, P-505			Please specify the pipe and fittings materials and methods required for the nitrogen system in the building.	No nitrogen in project scope of work. Sheet P-505, Detail B1 reflects aluminum for the piping material.
178	P-995	07 84 00		Question 1: Given the project's firestopping scope (penetration types, quantities, and assembly ratings), does the Government / DFPE consider this project eligible for the Option (b) qualification pathway with AHJ approval, rather than the full Option (a) FM 4991 / UL Certified Firestop Contractor requirement? Question 2: If Option (a) remains required, can the Government confirm whether a waiver or substitution process is available given the regional unavailability of FM 4991- or UL-certified firestopping contractors? Question 3: For Option (b) eligibility, please confirm: (a) who serves as the AHJ for this Navy project for purposes of approving Option (b) qualifications, and (b) what documentation of manufacturer training and experience will be required for submission.	PENDING RESPONSE
179	P-993	08 91 00	2.2	the metal wall louvers specifications state, "Wall louvers must bear the AMCA certified ratings program seal	Confirmed. Project will require the listed AMCA ratings.

				for air performance and water penetration in accordance with AMCA 500-L and AMCA 511. The rating must show a water penetration of 0.20 or less ounce per square foot of free area at a free velocity of 800 feet per minute". Recent projects have been requiring AMCA 550 rating for louvers. Please confirm the project will require the listed AMCA ratings and not the AMCA 550 rating.	
180	P-993	CU702	A3	Please confirm the callout for the precast concrete vault is accurate on drawing CU702 detail A3. Drawings Cu220 and CU 620 identify structure IW04 as manhole.	IW04 is a rectangular vault per Sheet CU702. CU220 appears as manhole due to USACE AutoCAD Civil 3D style. Sheet CU620 Table with Structure IW04 to be amended from "IWMH" to "Vault".
181	P-993	CU702		Please confirm rim elevations for both the precast concrete wet well and precast concrete valve vault. Drawing CU-702, detail A3 shows wetwell rim elevation of 28.00 and precast vault rim elevation of 27.75. Drawing CU220 and CU620 show rim elevation of 27.50 for both IW04 (assumed valve vault -see question 1 above) and IW05 (wetwell).	Rim elevations on CU702 are correct. Precast wetwell rim = 28.00' and precast valve vault rim = 27.75". CU220 and CU620 to be amended.
182	P-993	CU702		OWS-02 is called out on drawing CU702 to be below grade. This depiction is also shown on drawing CU220. However, the detail on CU702 is shown with aluminum grating on the top of the oil water separator. This seems to indicate that the top of the oil water separator should be at or above grade. Please confirm the details of oil water separator OWS-02 relative to its installation (above grade or below grade).	Sheet CU702 Detail A1 is for OWS-03 shown on Sheet CU202 Profile C-SSWR-05. This sheet to be amended to show OWS-03 above-grade. OWS-01 and OWS-02 are below grade per mechanical sheets.
183	P-993 spec 1587	09 97 13.27	3.1	Paragraph 3.1 states, "Coat exterior surfaces to tank including steel roof, shell legs, stair, railing, and other exterior appurtenances." Please confirm if this specification is only applicable to the water tower.	PENDING RESPONSE
184	P-993	CU700		Drawing CU 700 has a callout for a 50' x 50' lift station pad. Please confirm this pad is a stone pad and not a concrete pad. Please confirm the depth of the pad and type of stone that will be used if required.	Stone pad. 4" ABC with weed block fabric topped with 2" NCDOT #57 stone.
185	P-993	CU-602		OWS-03 shows on the San Sewer line and details on page CU-602 but I have not located details for the OWS-01 &	For OWS-01 - See Sheet PS101, Detail A4/P-501, and P602 for details. See Sheet

				OWS-02 on the Industrial Waste line please advise where these drawings are located	CU220 Profile C-INDW-01 for profile. Profile label for OWS-01 to be amended from "OWS-02, SEE DETAIL ON A1/CU-702" to "OWS-01, SEE MECHANICAL DRAWINGS" For OWS-02 - See Sheet PS101, Detail A4/P-501, and P602 for details. See Sheet P-913 for riser diagram. Profile label on Sheet CU202 C-SSWR-03 for SS18 to be amended from "INV. IN 23.46, 4" S" to "INV. IN 21.31, 4" S" For OWS-03 - See Sheet CU702 for detail and Sheet CU202 C-SSWR-05 for profile. Profile label for OWS-03 to be amended from "OWS-4 SEE MECHANICAL DRAWINGS" to "OWS-03 SEE DETAIL A1/CU-702"
190	P-993_P-995	General		The RFP includes multiple delegated design requirements. Please confirm that the Contractor's delegated design responsibility is limited to developing systems consistent with the performance requirements identified in the contract documents. Further, if the delegated design process identifies additional system requirements, coordination items, or infrastructure upgrades (e.g., structural, electrical, mechanical, or architectural) beyond those indicated in the contract documents, please confirm that such impacts will be addressed as changes to the contract.	PENDING RESPONSE
194	Pages 51-52	Solicitation		Because this Contract appears to be the first project in the region requiring CMMC Level 2 (Self), the added burden is expected to increase vendor costs significantly and may extend the schedule as trade partners work through the certification process. This will present an extreme challenge for the SubK's in the Region and will drive up overall pricing due to limited competition, or only large business SubK's and/or non-regional, or only	PENDING RESPONSE

				far away SubK's being able to work it. To reduce these impacts, it is recommended that the Government and DOR identify which drawings and scope elements truly require CMMC Level 2 (Self) and package them separately, allowing broader vendor participation on remaining work. As written, the requirement is expected to drive pricing above budgeted levels and may jeopardize the proposed Period of Performance.	
195		P-993 Drawings		To help with Price and Schedule, would the Government consider limiting the "CUI" labeling of the P-993 Design Documents (and therefore the CMMC LVL 2 Requirement) to only those special areas or scopes that would warrant it?	PENDING RESPONSE
196	Pages 51-52	Solicitation and P-995 Drawings		As it stands the P-995 Drawings and Specifications are NOT labeled as CUI. The P-995 Specification does not have its own Division 01 Section and it is our understanding that the P-993 Specifications will be used for both P-993 and P-995. Currently only contractors who have CMMC Level 2 Certification may have access to the "global" Division 01 Specifications. Will the Government release an additional P-995 specific Division 01 Specification that can be provided to subcontractors and suppliers who will not have CMMC Level 2 (particularly those Small Businesses and Local/Regional Sub's/Suppliers that are currently challenged with Level 2)?	PENDING RESPONSE
197		P993 Drawing TY0001 and TY500s, and AM01 Rev. Bid Form		CLIN 0007, Option 5 for P993, in the AM0001 Rev. Price Schedule says "Electronic Security System (ESS) complete in accordance with the drawings and specifications but excluding work provided in another Priced line item." TY001 General Note 1 states, "provide infrastructure for the GFGI Electronic Security Systems (ESS)..." In addition, the TY 500 series of drawings labels the equipment as NIC (Not in Contract). Please confirm what scope is to be included in this CLIN.	The contract is limited to providing pathways that support Government Furnished Government Installed devices and cabling. The security devices and cabling will be provided under a separate contract.
198	28 10 05	TY001, and TY500s		The Government has provided specification section 28 10 05 for Electronic Security Systems ESS. TY001 identifies the ESS equipment	The contract is limited to providing pathways that support Government Furnished Government

				as GFGI. Please confirm this specification is provided for reference only and the Government will Furnish and Install the ESS equipment and contractors are only required to install the ESS infrastructure (backbone) that the Government will utilize for installation of ESS equipment and wires.	Installed devices and cabling. The security devices and cabling will be provided under a separate contract.
199	B3/P-504			Detail B3/P-504 added a second meter by BAS/DDC Contractor, in addition to gas meter by Gas Utility Company. Should this added meter be a iTron gas meter?	Intent of sub-metering is for remote monitoring. Gas sub-meter must have AMI capability.
200	C4/P-504 & P-702			Detail C4 on P-504 and P-702: What type of water meter is desired? Should this be a iTron meter? It is noted in 22 00 00-2.13 that an Encoded Radio Transmitter (ERT) shall be attached to each water meter register to report to base advanced meter infrastructure equipment.	Intent of sub-metering is for remote monitoring. Water sub-meter must have AMI capability.
201	MP134			Key note 1 on MP134 seems to be shown in the wrong area, should this note exist? Paint Booth Units are shown on MP133. On MP133, should the Keynote 1 be moved closer to Paint Booth Units?	Intent of keynote on this sheet is to apply to any rooftop equipment associated with the paint booth.
202	MP122			EF-06 and 07 are shown in Paint Booth 2 per MP122. No EF's are shown in Paint Booth 1 per MP121, should EF's be added?	EF-06 and EF-07 serve paint booth 1 & 2 hygiene area, refer to MH121, MH122, MH131, MH132.
203	CS401	AMD 1 - Price Form		CS401 shows a bid option for light duty asphalt in the parking lot spaces in lieu of the concrete paving in the base bid. Confirm that this option is to be carried in CLIN 0006, OPTION 4 for P993: Solar Array in Parking Lot including the canopy, structural and foundation system, complete in accordance with the drawings and specifications but excluding work provided in another Priced line item. The pavement is not mentioned in the description.	Correct, the light duty asphalt to be included in CLIN 0006.
204	F-501			Detail A1 on F-501 shows a SSA Dielectric Break. It is assumed this detail is applicable at the anticipated single penetration of a main going into the Secure Boundary area on F-106 (2nd floor). If this detail applied to every wall penetration in the secure area, please advise.	Detail is required at all security boundary penetrations. Walls within the secure boundary do not require dielectric break.

205		01 45 00	1.6.5	Provide a separate QC Specialist at the work site for each of the areas as listed in the Matrix listed below, who must assist and report to the QC Manager and who must have no duties other than their assigned quality control duties. These individuals or specialized technical companies are directly employed by the Prime Contractor and cannot be employed by a supplier or subcontractor on this project . The Contractor suggests that QC Specialists can be employed by a supplier or subcontractor. Please confirm this is acceptable.	Confirmed. QC can be employed by a supplier / subcontractor.
206		01 45 00	1.6.7	Provide Submittal Reviewers, other than the QC Manager or CxC, qualified in the disciplines being reviewed, to review and certify that the submittals meet the requirements of this Contract prior to certification or approval by the QC Manager. Each submittal must be reviewed by an individual with 10 years of construction experience. Each submittal must be reviewed by a registered architect or professional engineer. The contractor suggests that these submittal reviewers are allowed to be QC Specialists with the experience required under paragraph 1.6.5. Please confirm this is acceptable	PENDING RESPONSE
207		33 40 00	2.1.1.1	Specification 33 40 00 - 2.1.1.1 call out RCP pipe to be Class III and Class V. The Grading & Drainage plan sheets have Keynote #1 (RCP Culvert, Class V) pointing to certain RCP runs. The Grading & Drainage profiles specify Class V for pipes larger than 48", as well as the 15" crossing at the taxiway. The Storm Drain Pipe Schedule shows Class V for RCP pipes larger than 42". Could we get these documents to correlate and clearly show which RCP runs are to be Class III versus Class V?	See the response to question #182.
208		33 40 00	2.4.1	The Specs (33 40 00 / 2.4.1) include hydrostatic testing and leakage testing (33 40 00 / 3.7.3.1 and 3.8.3.1). RCP suppliers will not provide pricing or guarantee that RCP pipe will comply with these specifications due to RCP being concrete material. Could the RCP testing requirements be removed from the Specs?	Engineer of record does not object to the requested change subject to government approval.

209		Bid Form		For CLINS 0001C & 0002C it is calling out to replace the undercut material with Imported Structural Fill or NCDOT #57 crushed Stone. NCDOT #57 crushed stone & Imported Structural Fill are two different prices. #57 Crushed stone make me assume it will be for an undercut of a utility trench and Imported structural fill makes me assume it would be for undercut for (pavement or building pad) subgrade which as well would be two separate prices. Could we get clarification on which material for this CLINS to be priced with and for which application or create two separate CLINS?	PENDING RESPONSE
210		31 00 00		The only current recommendations on fill types appear to be within the Earthwork Specifications. While a geotechnical report has been provided, it does not include any recommendations from the Geotechnical Engineer. Could we receive recommendations from the Geotechnical Engineer on the geotechnical report provided?	Geotech report will not be released in its entirety.
211		Geotech Report		There are high quantities of SC, SC-SM, and uncontrolled fill on the project, particularly within the berm near the runway where the majority of cut is located. Can you confirm whether: These materials are suitable only as general fill in non-structural areas (e.g., beyond 5 feet from structural zones), and whether they meet surcharge requirements to be placed above the building FFE; or For bidding purposes, we should assume all excavated material can meet structural fill requirements, with separate CLINs established in the event that SC, SC-SM, and uncontrolled fill encountered in structural cut areas and utility trenches must be exported or placed in nonstructural areas and replaced with imported select fill?	Fill to be used in nonstructural area fill.
212	P-603			P-603: Question is in regards to the vacuum system. VS-02 to 09 requires an explosion vent per note 7. Please provide the Kst and PMAX values in order to size the explosion proof venting for the 8 separators that will be paried w/ the 960SCFM systems.	Combustible dust hazard analysis shall be performed as indicated in paint booth specification. Coordinate with paint booth vendor for Kst and Pmax values.

213	EP111			See EP111-Main Sprinkler Room H113. The power to the louver motorized dampers is not shown. Can you please revise to show power to the louvers?	Add circuit BL-M1:29 for both motorized dampers.
214	L-102			Please clarify if the wayfinding exterior signs on page L-102 should be included in the base bid for P993?	Yes they should be included in base bid.
215	CU005, CU115, CU630			Key Note 5 on CU115 calls for a 3/4" Water Service running near the Telecom Node Building. W30 appears to be a hydrant but the water table on CU630 W122 and W30 call for 2" fittings. CU005 shows a fire line running to the Node Building. Please confirm.	W30 is a yard hydrant with a 2" service line. Sheet CU115 Keynote 5 to be amended. Sheet CU630 Table with Fittings W29 and W30 to be amended. 6" fire line is for Hydrant F217.
216	CU004, CU 115			Key Note 5 on CU115 calls for a 3/4" Water Service running near the Telecom Node Building. CU004 does not show a domestic water service going to the Node Building. Please confirm.	CU004 to be amended to show 2" domestic water service to Telecom Node Building in black.
217	23 09 00			The building Controls is to be by JCI per 23 09 00 specifications. Section 1.10 of 23 09 00.00 22 notes Contractor Qualifications. Since the Controls/BAS package is to be by JCI, should section 1.10 Contractor Qualifications be removed?	Section 1.10 of 23 09 00. 00 22 does not need to be remove. If a JCI branch is awarded the project, they should have no issues complying.
218	23 09 00			The Controls specifications do no indicate if the controls package must be first tier subcontractor to the Prime (GC) Contractor. Please verify this firm must be first tier.	How the Controls package is awarded/bought/procured/etc. must abide to project's Contractual requirements. This is a non-technical question, so, since the BCS specification templates that we used do not have specific provisions for the Controls package subcontractor, I would suggest/request that it be "first tier sub", just to match requirements in other sections i.e., Div 26.
219	TY001			P993 TY001 states electronic security systems (ESS) are GFGI and contractor is responsible for infrastructure only. Bid form Option 5 states contractor is responsible for ESS. Please confirm that ESS is GFGI.	The contract is limited to providing pathways that support Government Furnished Government Installed devices and cabling. The security devices and cabling will be provided under a separate contract.
220	MP121 to MP123			A Paint Booth Contractor has indicated that Chilled Water (glycol mix) is required for cooling paint booth make-up air handling units. Are	Paint booth to be standalone equipment. Paint booth air handling equipment is not

				the current chillers sized for this? MP121 to MP123 does not reflect CW pipe going to Paint Booth Air Handling Units.	supported by the base building hydronic plant.
221		33 16 15	2.1.1	33 16 15 - 2.1.1 notes seismic Design Category C, but per structural plans, the Seismic Design Category is classified as B, which is typical for this area. Please verify 33 16 15 - 2.1.1 is to be Seismic Design Category B, not C.	Specification 33 16 15 Part 2.1.1 to be amended to Seismic Design Category B.
222		33 51 15		Specification 33 51 15 is given for site gas, but this site gas distribution pipe is by Piedmont not under this contract. Please remove this specification.	Confirmed.
223	09 90 00			09 90 00 requires all contractors and subcontractors applying industrial coatings identified in the Project Program to be SSPC QP 1 certified. This certification pertains to contractors specializing in complex industrial structures such as bridges, chemical plants, storage tanks, etc. Please consider removing this certification requirement for architectural coatings under 09 90 00 for any coating scope of work outside of hangar structural steel, exterior tank, and bridge.	See PPI #46
224		07 52 00, 07 61 15	1.8.2, 1.9	UFC 3-110-03 paragraph D-2.2 (General Contractor's Warranties [one to five years]) states the following: "Recently some government roof specifications call for a General Contractor's Watertight Warranty to add another method of ensuring a quality roof installation. Unless stated otherwise in the Scope of Work in the RFP, all permanent new construction and replacement roofs require a Five-Year General Contractor Bonded Watertightness Warranty. The scope of work in the RFP may waive the Bonding requirement, but if not specified, the Bonded five-year watertightness warranty is required. The required wording of the warranty will be provided in the applicable UFGS." Specification sections 07 52 00 paragraph 1.8.2 and 07 61 15 paragraph 1.9 both require a two-year installer warranty. Please confirm if these two-year installer warranties are to replace the need for a five-year general contractor bonded	Warranty information is an indicated in current UFGS. Bid as shown.

				watertightness warranty or clarify if both warranties are required.	
225	C-002			Will Land Use Control Plans be required for work with-in the projects LOD? Existing studies appear to place the project adjacent to, or possibly w/in OU1.	PENDING RESPONSE
226		01 57 19.01 20		01 57 19.0 20 - 1.1.1.1.5 notes to refer to 01 14 for permitting requirements when excavating into a groundwater table in a Land Use Control (LUC) area. 01 14 00 does not reference LUC requirement. Please confirm a LUC plan is not required, as this can take extensive approval time and impact schedule. Please remove this reference if there is not Operable Unio or Land Use Control Plan.	PENDING RESPONSE
227	BB100	31 00 00	2.2.2	The existing berm is a large source of fill material (≈135,000cy) that we plan on using for site fill. However, looking at the Geotech report's boring logs a good bit of the soil is SC and uncontrolled fill. The specification 31 00 00 - 2.2.2 Embankment Fill allows for materials classified as GW, GP, SW, SP-SM or in accordance with ASTM D2487. Are we able to utilize this existing berm soil in non-structural areas or do we need to plan on hauling it offsite and importing good material? Please confirm that we are to assume that this material is geotechnically suitable for reuse.	Berm to be used in non-structural areas
228		31 00 00	3.4.5	Spec 31 00 00 - 3.4.5 Structural Excavation calls for excavating the entire building footprint area and at least 5 feet beyond, to the deeper of 4 feet below existing grade or 2 feet below bottom of footings. Please remove this requirement as the building footprint is a very large area that is all in a fill area, also being loaded with a surcharge, and deep foundation piling is being installed under the foundation. By excavating an additional 4 feet below the existing grade for the building footprint, this is an additional ~50,000+ CY's of excavation. Please confirm that this over excavation is not required.	PENDING RESPONSE
229	P-601			Faucets and lavatories require power in the bathrooms. See P-601. This power is not reflected on EP drawings. Can you please revise the electrical	There are circuits shown for lavatory faucets. For example, see keyed note 5 on sheet EP118 which has the circuit

				power plans to show electrical requirements needed?	and references sensor detail A4/EP501 requirements.
230	CT301	31 00 00	3.4.5	Spec 31 00 00 - 3.4.5 Structural Excavation says, "For new pavement areas including exterior concrete pads, over-excavate to a minimum of 12 inches below bottom of new pavement/pad base course, scarify, moisture-condition, and compact to at least 95 percent. The pavement details on CT301 call for 12" satisfactory material. Please confirm that we are to assume that on-site material can be reused as satisfactory material. if the on-site material is found to be unsatisfactory, it will then go to the unit price CLIN 0001C.	Confirmed.
231	CU006			Confirm that the gas line will be run to the building meter (including the meter) by Piedmont Natural Gas and pricing is not to be carried by the GC.	Confirmed. Piedmont to install yard piping to building meter.
232	CG135B			CG135B shows that RCP culvert for the temporary stream crossing. Confirm that any water that is pumped for temporary work at the stream crossing is assumed to be clean water, and if this water is contaminated, it will fall to CLIN 0004 for treatment.	Confirmed. There is no indication that water is currently contaminated.
233	SS117			The bridge detail for intermediate diaphragm calls out the channel MC 18 x 42.7. The structural steel notes call for galvanized high strength bolts, nuts, washers, etc. Please confirm that all exposed steel is to only to be galvanized, not painted. If not, please provide the finish coating and painting specification requirements.	Yes, for the taxiway bridge diaphragms, the high strength bolts, nuts, washers, direct tension indicators, plates, bent plates, channels, and angles must be galvanized.
234	CT475			Sheet Keynote 1 on CT475 calls out the Navy Mooring Eye/Tiedowns to be provided at center of shown slabs per detail A1 on CT505. The mooring eyes are only indicated on the plans at the F-35 parking areas only. Please confirm that mooring eyes are not required at the center of all slab grids per the UFC requirements.	Mooring eyes are not required at the center of all slab grids per UFC, only the ones shown on the airfield jointing plans per direction from NAVFAC during design.
235	P-001			Plumbing plans do not indicate if natural gas pipe is to be painted, please clarify.	Install natural gas piping per specification 22 11 20. Piping shall be installed with a protective covering as indicated in section 3.4.
236	CU800			Keynote 1 on Sheet CU800 calls out the elevated storage tank. Will there be precast pile deep foundations required? If so, are the piles included	Due to tank manufacturer design differences, foundation design is delegated design by tank manufacturer. See Sheet

				in the unit price line item 0001D? Please provide foundation information to support the elevated storage tank.	CU800 General Note 3 and Specification Section 33 16 15 Part 2.1.3. Cost is typically carried by tank manufacturer.
237				Partial BOD P993 - Duration is noted to be 1,461 calendar days. Is there any requirement to complete the tie-in to Runway 05R, taxiway to bridge and the bridge in advance? If not, will NAVFAC accept a partial BOD for this completed work since it may support other projects like the Scuff & Refresh, and will also be very difficult to maintain the landscaping around an active runway?	PENDING RESPONSE
238	CU800			Please confirm who is responsible for the initial water filling of the 250,000-gallon tank.	Prime contractor or appropriate subcontractor is expected to draw water from existing firewater system for leakage testing. Temporary bypass pumping may need to be used due to construction sequencing. Contractor may coordinate direct fill by Owner if proposed fire water system has been placed in service.
239	CU801	09 97 13.16		General Note 3.H calls out exterior coating with orange & white checkerboard pattern. 09 97 13.16 is called out for interior coating of welded steel water tanks. Please provide painting specifications for the water tank exterior paint.	See Specification 09 97 13.27 Part 2.2.
240	Bid Form			Bid Form line Item 0001G is for Unit Price for P993 for demolition, excavation and disposal of buried concrete and debris greater than 1/2 cubic yard in size, encountered within planned excavation for 500 Tons. Line Item 0002D is for P995 for the same description for 100 CY. One is in Tons and the other is in cubic yards. Please change the unit for 0001G to CY.	P995 to be revised to similar units.
241		09 97 13.16		For interior and exterior coatings of the water tanks, the specs require a Certified Industrial Hygienist (CIH), a Certified Protective Coatings Specialist (PCS), and an SSPC QP 5, Level III QC Specialist Coating Inspector. Please clarify if these independent third-party specialists can be provided by the coating contractor, or if they must be first tier to the general contractor.	Independent third-party specialists can be provided.

242	FA-140			FA-140 shows explosion-proof devices in Class 1 Division 2 areas. Typically, Class 1 Division 2 areas do not require explosion-proof equipment. Please confirm Class 1 Division 2 areas do not require explosion-proof devices.	Explosionproof devices are required in the Class 1 Div 2 areas
243		Attachment F - Price Proposal Form		Attachment F - Price Proposal Form includes P993 FF&E, AV, and Collateral Equipment Options 0015 - 0022. Section 1.2, FF&E, AV & Collateral Equipment Bid Notes, is for CLINS 0017 through 0027 and item number 6, notes the FF&E, AV, and Collateral Equipment modifications will be awarded at least 6 months prior to contract completion date. No schedule extension will be granted if the modification is awarded at least 6 months prior to contract completion. FF&E, AV, and Collateral equipment, especially CLIN 0015 Collateral Equipment, CLIN 0016 Collateral Equipment for Paint Spray Booths Option, CLIN 17 Stacker Units, CLIN 18 Sun Shelters will take longer than 6 months to procure and install. Please confirm these items will be awarded at least 24 months prior to contract completion.	PENDING RESPONSE
244		Attachment F - Price Proposal Form & 01 30.02.00 22		Attachment F - Price Proposal Form CLIN 0022 is for AV Design Services Option Price to provide a Certified Technology Specialist - Design (CTS-D) per 01 30 02.00 22. This option per Notes section 1.2 on the Attachment F does not have to be awarded until 6 months prior to contract completion. Confirm this option will be awarded at time of contract award in order for the contractor to have enough time to complete the design, validation, and best value determination per 01 30 02.00 22	PENDING RESPONSE
245	A220 - A236	03 45 00		Please confirm if there is a basis of design for the for the inlaid brick at the precast wall panels	Basis of design will be provided to successful bidder
246	A220 - A236	03 45 00		Regarding the sandblasted finish areas of the precast wall panels, please confirm if the intent is for the concrete to be grey tinted or painted in the field. If these panels have a tint/pigmented mix, the mix cannot be altered within the same piece, so color variation within the same piece cannot	Precast elements must contain color admixture. Color must be warm off-white and ultimately approved by the Base Architect

				be achieved other than the difference in tone between medium and heavy sandblast. Also please verify if a silane sealer is required on the exterior face of the precast.	
247	A-005			Drawing A-005 calls to temporarily seal the hangar door opening for pressure testing of Zone 2 and Zone 4. The AB testing market has stated that it will be impossible to maintain a temporary seal on an opening that large. Please confirm if Zone 2 and Zone 4 can be changed to air barrier inspection only.	Hangar bays can be changed to inspection only.
248		10 60 10		Drawings for P993 currently show the exterior solar collector wall being removed from the scope of the project, however specification section 10 60 10 was provided. Please confirm that the exterior solar collector wall has been removed from the scope of the project.	Confirmed. Exterior solar collector walls have been removed from the project.
249		08 33 23	2.2.1.1, 2.2.7.2	Specification section 08 33 23 paragraph 2.2.1.1 calls for door curtains to be 304 stainless steel. Paragraph 2.2.7.2 also calls for either a baked-enamel or powder coat finish. Please confirm if the finish for the OHDs (08 33 23) should be stainless steel or baked-enamel/powder coat.	Confirmed. Exterior solar collector walls have been removed from the project.
250	MI801			MI801: Does the BCS need to physically connect to a main base wide utility monitoring building, or will it connect online/digitally? If there needs to be a conduit/cable connection, please provide the building it needs to connect to, and the route the connection should run (similar to the ductbank shown for comm connection to Building 137)	PENDING RESPONSE
251				Will the Government consider amending P993 Regulations to remove all civil drawings, including but not limited to sections General (G), Survey (V), Geotech (BB), Civil (C, CD, CS, CG, CU), Airfield(CT), and Airfield Electrical (EA) , from the CUI, on the basis that such drawings do not present a national security risk and are already appropriately regulated under existing civil and aviation authorities?	PENDING RESPONSE
252				Will the Government consider amending P993 Regulations to remove all civil specifications including but not limited to divisions 01, 32, 33, and	PENDING RESPONSE

				34 , from the CUI, on the basis that such drawings do not present a national security risk and are already appropriately regulated under existing civil and aviation authorities?	
253				If the contractor would like to consider a batch plant per the 32 13 14 specs, it would require an area of not less than 3 acres, with adequate access to power, water, and drainage. Can the Gov't confirm if power and water could be made available during construction?	PENDING RESPONSE
254				Please consider reducing the CUI label on drawings and specifications to the absolute minimum. A complete label of all drawings and specifications requires all subcontractors working on this project to obtain a CMMC Level 2 (self) certification. Currently there are only a few subcontractors that have this certification and the impacts to the project will be extensive if not adjusted.	PENDING RESPONSE
255	1/A-301 & A-501 thru A-303			Wall Type Detail Notes on drawings A-501 - A-503 call for wall framing to be extended to underside of deck above at all locations for bracing and also extend gyp bd to full height of walls. Gypsum partitions on 1/A-301 show some walls only going up to 16'H (including framing). Walls shown in 1/A-301 appear to be wall type D, which on A-502, shown gypsum partition going all the way to the deck. Please confirm if gypsum partitions and framing in 1/A-301 should only go up 16'H or up to deck.	See revised sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE D".
256	23 64 26			Looking at specification section 23 64 26 Chilled-Hot Water Piping Systems, Part 2 Products only schedule 40 black carbon steel piping is mentioned as an acceptable piping material to install. (Reference paragraph 2.2 Steel Piping) In similar projects we have installed type "L" copper in Heating hot water & Chilled water systems for piping 4" and smaller in diameter and used schedule 40 black carbon steel for piping larger than 4" diameter in size. Will type "L" copper be acceptable for use in this application for building P995?	Type L copper piping is acceptable for use in question. In Specification Section 23 64 26, change paragraph 2.2.1 to include "Above ground piping 4 inch and smaller must be Type L copper."
257		076114.0 0 20	1.7	UFC 3-110-03 paragraph D-2.2 (General Contractor's Warranties [one	Para 1.7 Modified to include 5-year warranty as stated.

				to five years]) states the following: “Recently some government roof specifications call for a General Contractor’s Watertight Warranty to add another method of ensuring a quality roof installation. Unless stated otherwise in the Scope of Work in the RFP, all permanent new construction and replacement roofs require a Five-Year General Contractor Bonded Watertightness Warranty. The scope of work in the RFP may waive the Bonding requirement, but if not specified, the Bonded five-year watertightness warranty is required. The required wording of the warranty will be provided in the applicable UFGS.” Specification section 07 61 14.00 20 paragraph 1.7 requires a two-year installer warranty. Please confirm if this two-year installer warranty is to replace the need for a five-year general contractor bonded watertightness warranty or clarify if both warranties are required	
258	A-502			Wall Type G for shower walls show 1/2" cementitious board on both sides, one for the 1/4" solid surface shower side, and the other for tile. There are no walls that would have solid surface one side and tile on the other. For clarity, since wall type G is not called out on the plans, please confirm that wall type G should only be used for shower-to-shower walls that separate each other.	See revised sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE G".
259	A-401 & A-403			Please confirm walls that lead from shower to toilet room (TOILET 105 & 112) which is a chase wall, would be wall type J.	Walls between showers and individual restrooms 105/106 & 111/112 (and which contain doors 105A and 112A) are correctly identified as WALL TYPE F. See revised sheet A-401 "ENLARGED RESTROOM PLANS AND DETAILS" plan A4/A-401 for clarifications on shower and chase wall type. See revised sheet A-403 "ENLARGED RESTROOM PLANS AND ELEVATIONS" plan C1/A-403 for clarifications on shower and chase wall type.
260	A-401 & A-403			Please confirm what wall type is required for shower back walls that are sitting on wall type B.	See revised sheet A-404 "ENLARGED RESTROOM ELEVATIONS AND SHOWER DETAILS" detail

					A5/A-404 "SHOWER SECTION" for revised wall detailing.
261	A-502 & A-404			Walls and soffits for showers shown on A5/A-404 says to extend walls and finishes to 6" above highest adjacent ceiling and brace to structure. Wall type G on A-502 shower walls show walls and finishes up to the deck. Please confirm the height for walls and finishes required for shower walls.	See revised sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE G".
262	A-502			There is no mention of STC rating requirements for walls shown on the drawings or specifications. Please confirm and/or provide information required for STC ratings regarding gypsum walls and ceiling, if any.	None required. Bid as specified.
263	ES101, ES701			Pad-mount transformers (T1-T4) locations on ES101 Site Plan vary from ES701 Site Electrical Riser Diagram. Please confirm what sequence is correct.	Sequence on ES101 is correct.
264	ES101, ES701			ES101 Plan Notes 1 states SW5 is provided by P-993 project but does not show SW4 as provided by P-993 project. ES701 states SW4 is provided by P-993 project but does not show SW5 as provided by P-993 project. Please confirm both SW5 and SW4 are provided by P-993 project.	Both are provided by P-993 project.
265		01 45 00	1.6.5	Provide a separate QC Specialist at the work site for each of the areas as listed in the Matrix listed below, who must assist and report to the QC Manager and who must have no duties other than their assigned quality control duties. These individuals or specialized technical companies are directly employed by the Prime Contractor and cannot be employed by a supplier or subcontractor on this project. The Contractor suggests that QC Specialists can be employed by a supplier or subcontractor. Please confirm this is acceptable.	PENDING RESPONSE
266		01 45 00	1.6.7	Provide Submittal Reviewers, other than the QC Manager or CxC, qualified in the disciplines being reviewed, to review and certify that the submittals meet the requirements of this Contract prior to certification or approval by the QC Manager. Each submittal must be reviewed by an individual with 10 years of construction experience. Each submittal must be reviewed by a	PENDING RESPONSE

				registered architect or professional engineer. The contractor suggests that these submittal reviewers are allowed to be QC Specialists with the experience required under paragraph 1.6.5. Please confirm this is acceptable	
267	ES701			Drawing ES701 shows the Cable Schedule Remarks and lists Existing Ductbank or New Ductbank. Cable #3 does not state if it is pulled through existing or new duct bank. Please confirm if duct bank for Cable #3 is Existing or New.	Duct bank from SW5 (through MH15, MH14 & MH11) to SW4 is provided as a part of the P-993 project. All other duct bank will be new and part of the P-995 project.
268		01 57 19		The Specs for P995 do not include Division 01. Division 01 is where the information would be for CLIN 0010. Could you provide the Division 01 portion of the P995 Specs, or should we refer to the P993 Division 01 Specs?	PENDING RESPONSE
269		33 40 00	2.4.1	The Specs (33 40 00 / 2.4.1) include hydrostatic testing and leakage testing (33 40 00 / 3.7.3.1 and 3.8.3.1). RCP suppliers will not provide pricing or guarantee that RCP pipe will comply with these specifications due to RCP being concrete material. Could the RCP testing requirements be removed from the Specs?	The specified test is performed at the plant or independent laboratory. Suppliers of the watertight connectors should be able to supply KTRs with results of their tests which conform to ASTM standards for watertight joints. The requirement remains in the specification. Bid as specified.
270		33 40 00	3.5.1	The Specs 33 40 00 / 3.5.1 require storm manholes and inlets to have booted connections. Precast suppliers will not quote this project with booted inlet connections for storm structures. Could the booted inlet connections be removed from the Specs?	There are products available which will meet the criteria set forth in the specification. The flexible, watertight connector conforming to ASTM C923 requirement remains in the specification. Bid as specified.
271	P-602			P-602: High Pressure Vacuum Schedule, please confirm what the vacuum is actually operating at?	The numbers in the schedule define the vacuum requirements.
272	ES101, ES701			ES101 shows all electrical duct bank from SW5 to T1 as new duck bank. ES701 Site Electrical Riser Diagram shows duct bank as existing, new, or unknown. Please confirm what duct bank is new and what is existing.	Duct bank from SW5 (through MH15, MH14 & MH11) to SW4 is provided as a part of the P-993 project. All other duct bank will be new and part of the P-995 project.
273	A220 - A236	03 45 00		Please confirm if there is a basis of design for the for the inlaid brick at the precast wall panels	Basis of design will be provided to successful bidder
274	A220 - A236	03 45 00		Regarding the sandblasted finish areas of the precast wall panels, please confirm if the intent is for the concrete to be grey and then painted in the field. If these panels will have a	Confirmed. Design does not require change of color. Variation will be achieved with level of sandblast

				tint/pigmented mix, the mix cannot be altered within the same piece, so color variation within the same piece cannot be achieved other than the difference in tone between medium and heavy sandblast. Please provide clarification	
275	T-001			T-001 ERCES (BDA) Note says that the contractor is provide a separate line item in their bid for complete installation and testing of an ERCES (BDA) system for this facility to comply with specification section provided. There is no specification section for an ERCES (BDA). Please provide specification section for this ERCES (BDA) system.	PENDING RESPONSE
276	M-502, M-001	23 07 00		For exposed rectangular duct, are we to install double-wall insulated duct, or do we install single wall rectangular duct with external insulation? Per drawing M-502 detail A1 we are to use a Thermosetting Resin Coated Fiberglass Duct Liner. (This detail indicates the insulation is located inside of the sheet metal duct like duct liner) Per spec section 23 07 00 page 28, it states that Insulation on exposed rectangular duct is to be rigid insulation. (indicates a product such as duct board) Are we to provide Thermosetting Resin Coated Fiberglass liner and exterior insulation such as duct board for the exposed rectangular ductwork? Typically, at MCAS Cherry Point and Camp Lejeune exposed rectangular duct has been installed as double-wall insulated duct as it is more presentable and durable in exposed areas. Will double wall rectangular duct be allowed for use in the exposed areas for this project?	All exposed ductwork to be double-wall insulated ductwork. Detail A1/M-502 to be omitted.
277		23 03 00		The specifications allow the use of type L copper for the heating hot water pipe system on 2" and smaller. Please confirm the use of type L copper for the chilled water pipe, on pipe sized 2" and smaller is acceptable.	Type L copper piping is acceptable for use in question. In Specification Section 23 64 26, change paragraph 2.2.1 to include "Above ground piping 4 inch and smaller must be Type L copper."
278		22 00 00		Please specify the pipe and fittings materials and methods required for the low pressure vacuum system.	304 SS piping and CF fittings will be used for the system. Para 2.1 revised in spec
279		22 00 00		Please specify the pipe and fittings materials and methods required for the high pressure vacuum system.	304 SS piping and CF fittings will be used for the system. Para 2.1 revised in spec

280	MP102 thru MP107			Please provide mechanical pipe drawings showing the natural gas pipe layout.	Final gas routing/sizing is dependent on requirements of delegated design. Use M-910 for bidding purposes.
281	P-116, P-119, P-121, P-405, P-503, P-504			Is testing by a gas testing agency required for the Breathing Air pipe systems?	Breathing air system must be certified by a third-party testing agency.
282	P-118, P-505			Please specify the pipe and fittings materials and methods required for the nitrogen system in the building.	Sheet P-505, Detail B1 reflects aluminum for the piping material.
283	I-602			Please provide grout GR-2 finish.	GR-1 to be used at all tile locations per finish legend. See revised drawing sheet I-602, Sheet Notes have been updated to match the finish legend.
284		25 10 10		Utility Monitoring and Control System UMCS Front End and Integration is not noted in div 25 specification like P993. Please provide div 25 10 10 UMCS spec if desired	Spec 25 10 10 has been provided.
285	I-102			Keynote 6 reads CFCI Flat Panel Display. Is this a TV? If so, should this be included in Option 22 for the AV Equipment HAR. If it's confirmed that the display is CFCI please provide specs.	Confirmed. Flat panel display sizes/descriptions can be found in the TA drawings in the elevations and the Display Schedule.
286	I-102			Please clarify that the furniture shown on the furniture schedule shown on I-102 is included in the Option 23 HAR for FF&E.	Line item 26/Option 24 covers 995 FF&E. Option 23 is for A/V only.
287				Please confirm if wall type K requires gypsum partition on top of CMU wall similar to wall types B & C.	None required. Bid as specified.
288	A3/A-304			A3/A-304 calls out furring wall type K. Wall type drawings do not include a furring wall type K. Wall type K on A-503 only calls for a 12'H CMU wall. Please confirm gypsum furring as 8" steel stud wall at 15'H is correct.	See previous response to PPI #121.
289	A-502			Wall Type E does not appear to be called out on the floor plans. Please confirm wall type E locations.	Confirmed that wall type E is no longer used.
290				Please confirm that wall tile is not required behind lockers.	Confirmed. Coordinate tile installation w/ approved locker installation.
291	A-501-A-503			Please confirm that CMU & gypsum walls above finished ceilings are not required to be painted.	See 09 90 00 PAINTS AND COATINGS, paragraph 1.1.2 Painting Excluded- Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic

					spaces, crawl spaces, elevator shafts and chases. Note that exclusion of finish painting does not exclude the requirement for full gypsum finishing as specified.
292	S-205			There are approximately five, (5) steel members between Columns 3-4 / H that are not sized. Please provide clarification as to the size and type of steel members these are.	The (5) roof joists between column lines 3 & 4, on and just north of column line H are to be 40LH08 joists.
293	I-602			Finish schedule calls out RES-2 resinous floor system. Finish plans and room schedule do not indicate RES-2. Please confirm RES-2 is not required or provide room locations.	RES-2 (ROTUNDA RED) is to be applied in "Main Corridor 101 & Back Corridor 130" per finish legend. RES-1 (WHITE) is to be applied at all other resinous flooring locations. See revised drawing sheet I-601, RES-1 & RES-2 have been swapped in the Finish Legend to coordinate with the finish plans. Rooms numbers for the Main Corridor and Back Corridor have also been updated in RES-2's Locaton column (Finish Legend). See revised sheet I-601 for adjustments to the flooring in room 125 and 150.
294	I-602			Finish schedule calls for the RES-1 to be Resuflor Performance HPS which is basically the thickness of the 3-coat fuel resistive resinous flooring system (around 30 mils thick). However, the spec calls for a 1/4" thick floor which is basically the thickness of the 5-coat fuel resistive resinous flooring system (250 mils thick). Please confirm if we should follow the drawing finish schedule or specifications.	09 67 23.13 - 2.2 calls out a two-component, high solids epoxy product - this matches Resuflor Performance HPS. Note also that products named in the Finish Schedule are not intended to replace or override specification requirements. See drawing sheet I-602 "SCHEDULES & LEGENDS", "SHEET NOTES", Note A., which states "FINISHES INDICATED ARE THE APPROVED BASIS OF DESIGN TO CONVEY COLOR, PATTERN, TEXTURE AND SALIENT CHARACTERISTICS ONLY. THE LISTING OF MANUFACTURER INFORMATION IS NOT INTENDED TO LIMIT THE SELECTION OF PRODUCTS PROVIDED BY OTHER

					MANUFACTURERS. PRODUCTS MEETING THESE CRITERIA WILL BE CONSIDERED AND MUST BE REVIEWED BY THE INTERIOR DESIGNER OF RECORD (IDOR) AND THE NAVFAC INTERIOR DESIGNER AND APPROVED BY THE CONTRACTING OFFICER."
					Bid as specified.
295		12 24 13		Section 2.1.2.1 calls for spring operated mechanisms. Spring-operated roller shades are not recommended for shades with a 140" drop due to limitations in control, performance, and long-term durability. Spring systems rely on internal tension to counterbalance the weight of the fabric. At increased heights—such as 140"—the amount of fabric on the roll becomes significantly greater, resulting in higher overall weight and larger roll diameters. This places added demand on the spring mechanism beyond its optimal operating range. As a result, several performance issues can occur: Inconsistent Positioning, Uncontrolled Movement, Limited Adjustability and Accelerated Wear. Because of this please clarify if clutch-operated or motorized systems for the shades is allowed.	Based on the limitations provided, clutch operated shades are acceptable. See adjustments to spec section 12 24 13 - 2.1.2 & 2.1.3, mechanisms now reflect chain and clutch.
296	MP401			Is a pulse type gas meter needed as well in addition to Piedmont gas meter for BMS System? See MP401	Correct, additional gas meter is to be provided to ensure communication/monitoring is available through the BAS.
297	M-711			A water meter is noted in detail A4 on M-711 for Domestic Water. This meter is not provided in the equipment schedule on P-601 and not shown on P-403 on the domestic line coming into the building. Please provide detail on water meter needed.	Requirements for water meters are provided in detail A4/M-711.
298	A-501			Wall Type Note #5 on A501 calls for all gypsum board to 5/8" abuse resistant per the specifications. Does abuse resistant gypsum board need to be installed on the walls above the CMU, Type B & C?	Confirmed. Bid as specified.
299	A-501			Wall Type Note #8 states " wall framing must be extended to the underside of the deck above at all	See revised drawing sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE D",

				locations for bracing unless otherwise noted. Extend gypsum board to full height of walls unless otherwise noted." Please confirm if the interior Wall Types D & F in Area E extend to the deck above?	"WALL TYPE F" and "WALL TYPE G" (revised stud overhead bracing).
300	A-501			Specification Section 092200 Supports for Gypsum Board section 2.1.1.2 calls for metal studs to be no thinner than .033-inch thickness. Can you please provide the metal stud gauge for all interior walls as it does not clarify the stud gauge just not thinner than .033?	Provide manufacturer's standard gauge that is 0.033 inches or more
301		45 52 00		Please provide additional specifications for the blade manipulator (rotation type).	See previous response to PPI #147. Specification revised for clarification.
302		45 52 00 and 41 22 14		Please provide travel requirements for the 2-ton internal bridge crane for the Aerospace X-Ray Testing Equipment.	Specification 45 52 00 revised for clarification.
303				To clarify, please confirm that RES-1 epoxy flooring is required under all major equipment in Autoclaves 130, honeycomb machining 133, x-ray 126, sanding booth 121.	Confirmed. The entire floor is epoxy resin in these locations.
304	P-001			Plumbing plans do not indicate if natural gas pipe is to be painted, please clarify if gas pipe is to be painted yellow.	All gas piping must be painted safety yellow.
305	A-307			Please confirm how and when the general contractor would be given notice for removal of "knock out panels" as we would need to coordinate multiple trades and scopes of work to remove and replace the exterior walls shown on A-307.	Cannot be defined. Demolition of temporary knockout panel and re-building of permanent knockout panels is dependent on eventual Large Autoclave procurement (Large Autoclave NIC). Bid as specified.
306				Please provide descriptions and/or details for how gypsum walls would actually need to be built and braced where walls are to go all the way up to deck.	See revised drawing sheet A-501 "WALL TYPE DETAILS" for revised "WALL TYPE B" and "WALL TYPE C" (revised stud walls to 6"). See revised drawing sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE D", "WALL TYPE F" and "WALL TYPE G" (revised stud overhead bracing). See revised drawing sheet A-502 "WALL TYPE DETAILS" for revised "WALL TYPE H" and "WALL TYPE J" (revised furring wall bracing).

					See revised drawing sheet A-503 "WALL TYPE DETAILS" for revised "WALL TYPE L" (revised furring wall bracing).
307		41.22 13.15		Please clarify if the bridge cranes need to be top running, or underhung cranes.	See previous response to PPI #6 in Amendment 0003
308		41.22 13.15	1.3.1.1	Please clarify length of runways for the cranes listed in paragraph 1.3.1.1.	Paragraph 1.3.1.1 indicates bridge spans, not runway lengths. Bid as specified.
309		Attachment F - Price Proposal Form		Attachment F - Price Proposal Form includes P995 FF&E, AV, and Collateral Equipment Options 0023 - 0027. Section 1.2, FF&E, AV & Collateral Equipment Bid Notes, is for CLINS 0017 through 0027 and item number 6, notes the FF&E, AV, and Collateral Equipment modifications will be awarded at least 6 months prior to contract completion date. No schedule extension will be granted if the modification is awarded at least 6 months prior to contract completion. FF&E, AV, and Collateral equipment, especially CLIN 0023 Composite Oven and CLIN 0024 Collateral Equipment will take longer than 6 months to procure and install. Please confirm these items will be awarded at least 24 months prior to contract completion.	PENDING RESPONSE
310		Attachment F - Price Proposal &		Attachment F - Price Proposal Form CLIN 0027 is for AV Design Services Option Price to provide a Certified Technology Specialist - Design (CTS-D) per 01 30 02.00 22. There is no 01 30 02.00 22 for P995. This option per Notes section 1.2 on the Attachment F does not have to be awarded until 6 months prior to contract completion. Confirm this option will be awarded at time of contract award in order for the contractor to have enough time to complete the design, validation, and best value determination per 01 30 02.00 22	PENDING RESPONSE
311	A-102	41.22 13.15 and 41 22 23.19		Please clarify in the Main Corridor 125, if we need to have a bridge crane in this room, or 2 2-ton under running monorail hoists which has been called out in spec 41 22 23.19.	Corridor 125 only includes the monorail hoist specified in section 41 22 23.19 MONORAIL HOISTS.
312	A-116, A-504			The Roof Plan (A-116) of P995 currently does not show any permanent fall protection to be installed. A Fall protection guide rail system is shown on P993 at the roof	Equipment maintenance occurs only on the low-slope roof areas, with no equipment located closer than 10' to a roof edge. No permanent

				edges (A-504), but this is not shown at the edge of the P995 roof. Please confirm that no permanent fall protection systems are required for P995.	guardrails nor anchorage points are required. Bid as specified.
313		07 52 00, 07 61 14	1.8.1, 1.7	Specification section 07 52 00 paragraph 1.8.1 and specification section 07 61 14 paragraph 1.7 on P995 mention to provide a 30-year manufacturer NDL warranty. The roofing UFC caps this manufacturer's warranty period out at 20 years. Additionally, P993 only requires a 20-year manufacturer's warranty for the modified bitumen and standing seam roofing systems. Please confirm that these manufacturer roofing warranties for P995 can be changed to 20 years in duration.	PENDING RESPONSE
314		13 21 16		Please clarify if the walk-in freezer must meet a class 1 or div 1 hazardous rating.	PENDING RESPONSE
315		Attachm ent F Price Proposal Form		OPTION 12 for P995: Electronic Security System (ESS) states contractor to provide a price per the drawings and specifications. No drawings or specifications for Electronic Security Systems for P995 are provided aside from infrastructure. Please provide drawings and specifications.	PENDING RESPONSE
316		41 22 14	1.3.1.1	Please confirm if the bridge crane in the sanding, paint, and x-ray booth are be supplied and installed by paint, and sanding and x-ray subcontractors per specification 41 22 14 paragraph 1.3.1.1.	Specification section 41 22 14 BOOTH BRIDGE CRANES, OVERHEAD PNEUMATIC, UNDER RUNNING TROLLEY, Paragraph 1.3.1.1 confirms that pneumatic cranes for paint, sanding and X-Ray booths are included as part of the delegated design for each. Sheet A-703 "SANDING & PAINT BOOTH GENERAL NOTES" Note 2 confirms that cranes are "PROVIDED BY THE BOOTH MANUFACTURER AS PART OF THE OVERALL DELEGATED DESIGN FOR SUCH." The X-Ray booth is included under specification section 45 52 00 AEROSPACE X-RAY TESTING EQUIPMENT.

					"Internal Bridge Crane" is included under requirements listed in paragraph 3.4 Aerospace x-ray Testing Equipment. Confirmed. Bid as specified.
317		Division 1		Offerors need to understand if P995 has its own division 1 specifications or if all of P993's specifications, which are currently listed as CUI, apply to P995. Note this is important for various reasons, for instance the required people on the project for P993 are those doubled for P995 per Division 1 or all that is required to managed both projects, i.e. One QC Manager for both sites?	PENDING RESPONSE
318	28 10 05	TY001, and TY500s		The Government has provided specification section 28 10 05 for Electronic Security Systems ESS. TY001 identifies the ESS equipment as GFGI. Please confirm this specification is provided for reference only and the Government will Furnish and Install the ESS equipment and contractors are only required to install the ESS infrastructure (pathway backbone) that the Government will utilize for installation of ESS equipment and wires.	The contract is limited to providing pathways that support Government Furnished Government Installed devices and cabling. The security devices and cabling will be provided under a separate contract.
319		EP601 Keynote 10		Per EP601 keynote 10, "THE EXISTING CIRCUIT 5 FROM SW1 TO SW2 IS 1#350 PER PHASE PLUS GND. AN ADDITIONAL #350 PER PHASE PLUS GND TO BE ADDED AND THE THREE MANHOLES TO BE INSTALLED TO REPLACE THE CTC'S AS SHOWN IN EXISTING 4-WAY DUCT BANK. CONNECT EXISTING CABLES IN MAN HOLES." Please confirm that switchgear 2 can be without power for several weeks. If switchgear 2 cannot be without power, we recommend that a new duct bank is installed between switchgear 1 and switchgear 2 (approximately 1100') with the new manholes and pull in 2 new sets of 350'S with grounds to feed switchgear 2. This will reduce the shutdown time to a single weekend. This will result in an increased cost but will prevent the extended outage to Switchgear 2 and	The power distribution to switchgear 2 is looped with source feeds from switchgear 1 and switchgear 6. Switchgear 2 can be fed from switchgear 6 when addition 350 is being installed between switchgear 1 and switchgear 2.

				limit the amount of splices in the manholes.	
320	L-102			Please confirm if the Insignia signs shown on L-102 shall be included in the base bid for P-993.	Yes, they should be included in the base bid.
321	00 21 00			Factor 6, Small Business Utilization and Participation paragraph (i.) Submittal Requirements reads that for Historic Small Business Utilization, Offerors are to submit the required information for three projects of their choice. Please confirm that projects shown can be in progress but have completed ISRs which demonstrate the projects current SB utilization and projected SB utilization.	PENDING RESPONSE
322				Please clarify if we are to provide all PV canopies as shown, or if we can provide fewer canopies if we have more efficient PV panels.	Provide all PV canopies as shown in the contract drawings. The canopy count and layout are a fixed scope requirement and cannot be reduced due to module efficiency. Any panel substitutions that require design or layout changes are the Contractor's responsibility and must be approved by the Government. Bidders may provide optional pricing for higher efficiency PV modules as a voluntary alternate, provided the alternate bid includes all PV canopies as shown.
323				Please confirm there are no stainless steel computer kiosks required for the Apron Sunshades as none are shown or specified.	Confirmed, no stainless steel computer kiosks required for Apron sunshades.
324	I-101/102	10 44 16		As noted on I-101/102 the FF&E scope, fire extinguishers are included. FF&E is apart of HAR 23. Please clarify if we must supply the fire extinguisher cabinets for these fire extinguishers, or if these cabinets are included in the FF&E package HAR 23.	Fire extinguishers are provided in FFE as noted, cabinets are not included in FFE. Fire Extinguisher Cabinets must be provided by KTR: locations are shown on drawing sheet GI101 "LIFE SAFETY COMPREHENSIVE FLOOR PLAN" and they are specified under specification section 10 44 16 FIRE EXTINGUISHERS.
325				Please address differing electrical loads from the design for specialty equipment such as paint booths, autoclaves, and X-Ray equipment. The panels schedules have a demand factor of 65% for industrial loads. If	The industrial load diversity shown on the panel schedules are limited to the various L5,L6, and L8 receptacles, with a quantity intended to cover various locations and

				the final equipment loads are higher than this for the delegated designed equipment, how will this be addressed?	expecting only a few to be in use at a time. The sanding and paint booths are currently calculated at 100% demand for the switchboard calcs, and slightly higher final loads should be acceptable for the switchboard sizing.
326		SF1442		Partial BOD P995 - Duration for both P993 & P995 is noted to be 1,461 calendar days. Please confirm if the contractor completes P995 ahead of 1,461 CDs, the government will take BOD of the facility ahead of the completion of P993.	PENDING RESPONSE
327		41 34 23		Please clarify if the rooms in the paint booths are required, since paint booths are considered a classified area and inside the booth needs to be clear and free.	Confirmed: the indicated rooms, identified on the drawings as 'blowoff chambers' and revised to be referred to as 'vacuum chambers' in amendment 2, are required. Bid as specified.
328		41 34 23		Please clarify if the dust collection system attached to the paint booth is required. It is not recommended to pull air from the paint booth to the dust collector as it will clog the collection system if it picks up paint particulates.	Confirmed: dust collection systems as shown and described are required for each paint and/or sanding booth. Bid as specified.
329		41 34 23		Please confirm that the dust analysis for the paint booths is required. How does this analysis get performed?	Confirmed; Dust analysis is required as specified, and procedures are outlined in NFPA 652, Chapter 7 as specified. Bid as specified.
330				What is the substantial and final completion?	PENDING RESPONSE
331	BB101			We are going to need a geotechnical report here. It is called out multiple times in the plans and specs, but I did not see it anywhere. The only thing I saw was the boring logs in the drawings.	Geotech report will not be released in its entirety.
332				What are the liquidated damages for this project?	See Amendment 0001.
333				Will any fencing be required?	Bid as shown.
334				What size is the overflow pipe?	12-inch diameter
335				What is the construction easement for the site during tank construction?	Owner owns property so no easement is required. Prime contractor and tank manufacturer are responsible for sequencing and laydown areas.
336				Can we work 7 days a week?	PENDING RESPONSE
337				What is the budget for this project?	PENDING RESPONSE

338				Is this project subject to AIS OR BABA requirements?	PENDING RESPONSE
339				Is this project exempt from state or local taxes?	PENDING RESPONSE
340				Will there be any third-party inspections on the tank?	Coating Inspection Company provided by Contractor per Specification 09 97 13.27 Part 1.4.6.2. Radiographic inspection of welded tank shell provided by Contractor per Specification 33 16 15 Part 3.6.3. Owner reserves right to provide own inspector.
341	5	33	2.1.2	In this paragraph you have stated a "double ellipsoidal type double-cone type or as approved." In tanks over 150,000 we go with the torris bottom (TB) style tank. Will the torris bottom be acceptable moving forward with the tank design?	Yes.
342	9	33	2.4.1	There was a safety cage called out in the spec, and we always recommend a ladder gate. There are many safety and costs implicated with the safety cage. Will the ladder gate be an acceptable alternate?	PENDING RESPONSE
343				What is the construction sequence this project?	PENDING RESPONSE
344	2	div_09	97 13.16	Remove SSPC QS 1 from tank spec.	PENDING RESPONSE
345	3	div_09	97 13.16	Remove "qualifications of certified industrial hygienist (CIH)" from tank spec	PENDING RESPONSE
346	6	div_09	97 13.16	Remove "Qualifications of Coating Contractors" from tank spec. With this removed there will be sufficient cost savings and an improved schedule of completion.	PENDING RESPONSE
347	DWG EA001 FOR P-993 PROJECT			REFERENCING PROJECT P-993. GENERAL NOTE 13 STATES THE EXISTING ALCMS SYSTEM WAS DOCUMENTED AS MANUFACTURED BY EDGECON SYSTEMS. EDGECON/SPAWARS/NIWC DOES NOT MANUFACTURE NOR SUPPORT NAVY MARINE CORP. ALCMS ANY MORE. PLEASE CONFIRM THERE ARE SPARE CONTACTORS IN THE EXISTING EDGECON ALCMS.	PENDING RESPONSE
348				Can you confirm that a PLA will not be required for this project?	Confirmed

(End Summary of Changes)