

STATEMENT OF WORK
Service
Replace Insulation on Lower Raceway Building

1. General:

1.1 Ennis National Fish Hatchery (NFH), 180 Fish Hatchery Road, Ennis, MT 59729-9113.
Service, Replace Insulation on Lower Raceway Building.

1.2 Purpose/End Application: This project is to provide safe and energy efficient insulation in the Lower fish production building. Currently, the batt insulation and vinyl protective covering have become severely degraded from decades exposure to consistent water condensation, freeze/thaw, and icicle development. The insulation and vinyl covering is separating from the building, falling, and degrading into small particles, making work in the buildings unsafe for both humans and fish. The insulation and vinyl cover needs to be removed and replaced with closed cell spray foam.

1.3 Contractor Qualifications: The contractor shall be appropriately licensed, accredited, and certified within the state of Montana for the removal and installation insulation.

1.4 Other: The contractor shall follow all associated regulations and laws including Federal, State, and County.

2. Place of Performance and Period of Performance

2.1 Work is to be performed on The Lower Raceway Building at Ennis National Fish Hatchery (NFH), 180 Fish Hatchery Road, Ennis, MT 59729-911.

2.2 Period of Performance July 1, 2026 - August 31, 2026.

2.3 Normal duty hours Monday thru Friday 07:30 a.m. – 03:30 p.m. In the event of emergencies, Contractor shall provide contact information.

2.4 Non-duty hours include weeknights, weekends, and Government holidays (New Year's Day, Martin Luther King JR's Birthday, Memorial Day, Juneteenth, Independence Day, Labor Day, Columbus Day, Veteran's Day, Thanksgiving Day, Christmas Day).

3. Scope

3.1 The contractor shall remove the current batt insulation and associate vinyl covering within multiple designated workspaces and dispose of materials according to all applicable local, state, and federal laws. Once the insulation is removed, the contractor shall install closed cell spray foam in the areas where the batt insulation and vinyl coverings were previously located.

3.1.1 The contractor shall coordinate with designated U.S. Fish and Wildlife Service representative at least one day prior to conducting work. Hatchery operations within the building occur concurrently with the insulation demolition and replacement, thus work within segmented workspaces within the building, including fish raceways, will need to be completed from demolition to installation of foam in segments. This is because the fish will need to be moved around by the hatchery staff as the work continues.

3.1.1.1 Contractor shall confine workspace to the area determined through coordination with the designated U.S. Fish and Wildlife Service representative at least one day prior. The station will need to relocate fish each time the designated workspace is changed.

3.1.2 The contractor shall take all protective measures to confine and prevent particles from the insulation and vinyl removal, and from the installation of the closed cell spray foam drifting past the specified work area; to include all safety equipment required for contractor's workers within the workspace.

3.1.3 The contractor shall remove the current batt insulation and associated vinyl covering from the ceiling and walls within the designated workspaces and lawfully dispose in qualified disposal sites: landfills, transfer stations, etc.

3.1.4 The contractor shall install closed cell spray foam in the spaces where the batt insulation and vinyl coverings were previously located.

- A. Exterior Walls: Closed-cell, high-lift spray foam insulation, R-14 IV HFO WIN HI, 2 nominal inches minimum.
- B. Roof: Closed-cell, high-lift spray foam insulation, R-21 IV HFO WIN HI, 3 nominal inches minimum.
- C. Overhead Doors: Closed-cell, high-lift spray foam insulation, R-14 IV HFO WIN HI, 2 nominal inches minimum.

3.2 The contractor shall be responsible for verifying the dimensions for the Lower Raceway Building that require the work to be completed.

3.3 The contractor is strongly encouraged to conduct a site visit prior to submitting a bid for this project. Necessary information and/or potential issues missed by the contractor that could have been observed from a site visit shall be solely the responsibility of the contractor, financially or otherwise.

4. Deliverables and/or Delivery Schedule: (for extended list a bid schedule and/or use of line-item detail on the PR is recommended)

4.1 The contractor shall provide all necessary equipment and supplies required for the safe

removal and disposal of the current batt insulation and associate vinyl covering, such as but not limited to:

- A. Dumpster(s)
- B. Safety equipment/materials (masks, eye protection, gloves, plastic sheets to enclose the work area, etc.)
- C. Lifting equipment to perform work.
- D. Platforms to cover concrete fish raceways when necessary.

4.2 The contractor shall provide all materials and equipment necessary to install closed cell spray foam, to include, but not limited to:-

- A. Exterior Walls: Closed-cell, high-lift spray foam insulation, R-14 IV HFO WIN HI, 2 nominal inches minimum.
- B. Roof: Closed-cell, high-lift spray foam insulation, R-21 IV HFO WIN HI, 3 nominal inches minimum.
- C. Overhead Doors: Closed-cell, high-lift spray foam insulation, R-14 IV HFO WIN HI, 2 nominal inches minimum.
- D. Safety equipment/materials (masks, eye protection, gloves, plastic sheets to enclose the work area, etc.) – same as with 4.1 if work will be done concurrently.

5. Data Management Plan (DMP) N/A

6. Government-Furnished Equipment (GFE) / Government-Furnished Information (GFI)

6.1 Ennis NFH will provide restrooms, electricity, and water for the contractor to use while the contracted work is being completed.

6.2 No government furnished equipment will be used for this project.

7. Acceptance

7.1 Government acceptance is contingent upon: designated U.S. Fish and Wildlife Service representative(s) determining the work to be acceptable based on the contract agreement and in good working order.

8. Quality Control/Quality Assurance:

8.1 For commercial supplies reference clauses for inspection and acceptance. Where appropriate, QC will be maintained according to industry standards and made available to the agency with the contractor's proposal.

8.2 Quality Control/Quality Assurance can be performed by any designated U.S. Fish and Wildlife Service representative(s) at any time. These representatives may stop work at anytime for safety concerns.

9. Technical Coordinators:

9.1 Primary

Ron Hopper

Hatchery Manager

180 Fish Hatchery Road

Ennis, MT 59729-9113

Office: (406) 682-4847

Cell: (406) 548-4859

ron_hopper@fws.gov

9.2 Secondary

Kristopher “Kris” Johnson

Facility Management Coordinator (FMC)

Asset Management Coordinator (AMC)

U.S. Fish and Wildlife Service

Fish and Aquatic Conservation (FAC)

1380 South 2350 West

Vernal, UT 84078

Cell: 435-299-5150

Office: 435-789-0351 ext. 16

kristopher_b_johnson@fws.gov